



HAL
open science

Regional analysis of public capital expenditure: to which regions is public capital expenditure channelled - to "rich" or to "poor" ones?

Jiří Blažek, Marie Macešková

► To cite this version:

Jiří Blažek, Marie Macešková. Regional analysis of public capital expenditure: to which regions is public capital expenditure channelled - to "rich" or to "poor" ones?. *Regional Studies*, 2010, 44 (06), pp.679-696. 10.1080/00343400903002713. hal-00600455

HAL Id: hal-00600455

<https://hal.science/hal-00600455>

Submitted on 15 Jun 2011

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.



Regional analysis of public capital expenditure: to which regions is public capital expenditure channelled – to “rich” or to “poor” ones?

Journal:	<i>Regional Studies</i>
Manuscript ID:	CRES-2008-0070.R2
Manuscript Type:	Main Section
JEL codes:	E61 - Policy Objectives; Policy Designs, Consistency, Coordination < E6 - Macro Policy Formation, Macro Public Finance, Macro Policy, etc < E - Macroeconomics and Monetary Economics, H5 - National Government Expenditures and Related Policies < H - Public Economics, R11 - Regional Economic Activity: Growth, Development, and Changes < R1 - General Regional Economics < R - Urban, Rural, and Regional Economics, R58 - Regional Development Policy < R5 - Regional Government Analysis < R - Urban, Rural, and Regional Economics
Keywords:	regional impact of non-regional policies, sectoral policies, territorial impact assessment, regional policy, public investment, Czech Republic

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60



For Peer Review Only

1
2
3 Regional analysis of public capital expenditure: to which regions is public
4
5
6 capital expenditure channelled – to "rich" or to "poor" ones?
7
8
9
10
11
12
13
14
15
16
17
18
19
20

21 Jiří Blažek, Charles University in Prague, Faculty of Science, Department of Social
22 Geography and Regional Development, Albertov 6, Praha 2, 128 43, Czech Republic. Email:
23 blazek@natur.cuni.cz
24
25

26
27 Marie Macešková, Charles University in Prague, Faculty of Science, Department of Social
28 Geography and Regional Development, Albertov 6, Praha 2, 128 43, Czech Republic. Email:
29
30 marie.maceskova@gmail.com
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

Received March 2008; in revised form October 2008

Abstract

The paper aims to contribute to the debate on the regional dimension of sectoral (i.e. non-regional) policies and to empirically demonstrate the huge discrepancy between both the volume and the regional pattern of sectoral public capital expenditure policies on the one hand, and official regional policy on the other. The analyses were based on a unique database of public investment in the Czech Republic covering the years 1995–2005. Their results show significant conflicts in policy objectives and thus represent a clear argument in favour of pursuing territorial impact assessment (TIA) of sectoral policies.

Key words: regional impact of non-regional policies, sectoral policies, territorial impact assessment, regional policy, public investments, Czech Republic

Une analyse des dépenses en capital publiques: vers quelles régions les dépenses en capital publiques sont-elles canalisées – vers les régions riches ou les régions pauvres?

Cet article cherche à contribuer au débat sur la dimension régionale des politiques sectorielles (c'est-à-dire, qui ne sont pas à but régional) et à démontrer de façon empirique l'écart sensible entre le volume et la distribution régionale des politiques sectorielles pour ce qui concerne les dépenses en capital publiques d'un côté, et la politique régionale officielle de l'autre côté. Les analyses sont fondées sur une base de données unique sur l'investissement public en République tchèque de 1995 à 2005. Il s'avère d'importants conflits entre les objectifs de politique, et les résultats représentent donc un argument clair en faveur de la poursuite d'une étude de l'impact territorial des politiques sectorielles.

Impact régional des politiques qui ne sont pas à but régional / Politiques sectorielles / Etude de l'impact territorial / Politique régionale / Dépenses publiques en capital / République tchèque

Regionalanalyse öffentlicher Investitionen: In welche Regionen werden öffentliche Investitionen gelenkt – in 'reiche' oder 'arme'?

Mit diesem Artikel möchten wir zur Debatte über die regionale Dimension sektoraler (d. h. nicht-regionaler) Politiken beitragen und empirisch nachweisen, dass zwischen dem Volumen und regionalen Muster sektoraler öffentlicher Investitionspolitiken einerseits und der offiziellen Regionalpolitik andererseits eine gewaltige Diskrepanz besteht. Die Analysen stützten sich auf eine einzelne Datenbank öffentlicher Investitionen in der Tschechischen Republik in den Jahren von 1995 bis 2005. Die Ergebnisse lassen auf signifikante Konflikte hinsichtlich der politischen Ziele schließen und stellen somit ein klares Argument für eine Untersuchung der territorialen Auswirkungen sektoraler Politiken dar.

Key words:

1
2
3 Regionale Auswirkungen nicht-regionaler Politiken Sektorale Politiken
4 Untersuchung territorialer Auswirkungen Regionalpolitik Öffentliche Investitionen
5 Tschechische Republik
6
7
8
9

10
11 **Análisis regional de inversión de capital público: ¿A qué regiones se canaliza la**
12 **inversión de capital público: a las ‘ricas’ o a las ‘pobres’?**
13

14
15
16 **Abstract**

17 El objetivo de este artículo es contribuir al debate sobre la dimensión regional de
18 políticas sectoriales (es decir, no regionales) y demostrar empíricamente las
19 enormes discrepancias entre el volumen y el modelo regional de las políticas de
20 inversión de capital público sectorial, por una parte, y la política regional oficial, por
21 otra. Los análisis se han fundamentado en una única base de datos de la inversión
22 pública de la República Checa que abarca los años 1995–2005. Sus resultados
23 muestran conflictos significativos en objetivos políticos y, por tanto, representan un
24 claro argumento a favor de obrar con arreglo a una evaluación del impacto territorial
25 de las políticas sectoriales.
26
27

28
29 **Key words:**

30 Impacto regional de políticas no regionales Políticas sectoriales Evaluación del
31 impacto territorial Política regional Inversiones públicas República Checa
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

JEL classifications: H5, E61, R 11, R 58

1. Introduction

The aim of the paper is to contribute to the debate on the regional dimension and the regional impact of sectoral public capital expenditure policies. This debate started decades ago (e.g. SHORT, 1978; BENNETT, 1980; MARTHUR and STEIN, 1980; MOLLE and CAPPELLIN, 1988) but recently received a significant impetus in the form of a discussion on the regional impact of sectoral policies and the possibilities of their “regionalization” (e.g. DG RESEARCH, 1991; MARTIN, 1999; ROBERT *et al.*, 2001; MOLLE, 2007). The “regionalization” of sectoral policies can be understood as the fine-tuning of sectoral public expenditure according to the needs and circumstances of specific regions.¹ One of the important results of this discussion was the gradual development of the methodology of the territorial impact assessment of large projects and later, also of programmes and policies – SCHINDEGGER and TATZBERGER, 2003; CAMAGNI, 2006). The increasing attention being paid to the regional dimension of public expenditure policies stemmed originally from the effort to learn how to improve or - more precisely - how to ensure the coordination of the territorial impact of the EU policy of economic and social cohesion (ESC) and of other European policies (e.g. CEC, 1996; SHOUT and JORDAN, 2007). Moreover, at the same time, there was a significant research endeavour to discover to what extent the regional impact of ESC policy has been in compliance with the spatial effects of numerous national public policies of the EU Member States (CEC, 2004).

¹ Such fine-tuning can take many different forms, for example differentiation of the form and the rate of public support or the involvement of regional self-government or other regional bodies in decision-making procedures, although in practice such an approach is rather rarely applied.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

Nevertheless, the number of existing analyses of the regional impact of sectoral policies is still relatively limited (for exceptions see e.g. HEALD, 1994; AUTERI and COSTANTINI, 2004; KATAOKA, 2005; MACEŠKOVÁ, 2007), mostly due to the severe data limitations in most countries. Therefore, the main aim of this article is an attempt to perform an analysis of the regional dimension of public capital expenditure in one of the new Member States (the Czech Republic) at the level of the NUTS 3 and 4 regions. This analysis is based on a unique data set of capital public expenditure covering investment projects supported during 1995–2005.

The analyses undertaken here are aimed at answering several research questions. Firstly, the relation between the level of the socio-economic development of the regions and the amount of invested public capital expenditure will be investigated. It is assumed that public investments are highly concentrated in the most socio-economically developed regions. Such a regional allocation of this type of public funds would be in accordance with the principles of a strategic regional policy (for more on strategic regional policy see e.g. GORZELAK, 1992). In other words, given the many deficiencies in the sphere of the technical and other infrastructures inherited from the communist period, it is supposed that public investment was primarily focused on the enhancement of the infrastructure in major cities and namely in Prague to strengthen the gateway effect (DRBOHLAV and SÝKORA, 1997) and to enhance the competitiveness of the national metropolis on the international scene.

Moreover, another reason for the anticipated concentration of public investment in core regions is the assumed higher efficiency of investment in these regions (e.g. CAMINAL, 2004; DE LA FLUENTE, 2004). Therefore, a positive correlation between the level of socio-economic development and the amount of public capital invested (relative per capita) is expected. However, it should be stressed that such a regional pattern of public investment contradicts the objectives of the Czech national strategy for regional development and of

1
2
3 regional policy aiming at decreasing regional disparities and being in compliance with the
4
5 “insurance” type of regional policy (MRD, 2006; GORZELAK, 1992). As a result, it can be
6
7 argued that there is an immense policy conflict between goals of explicit regional policy and
8
9 mostly unintended spatial impacts of much more vigorous non-regional governmental
10
11 policies. Therefore, our analyses might also serve as empirical support for the importance of
12
13 pursuing territorial impact assessment (TIA), both for major public capital projects and for
14
15 sectoral policies as a whole.
16
17

18
19
20 Secondly, a replication of the traditional East-West gradient of socio-economic
21
22 development by the regional structure of capital expenditure is also expected (for more on the
23
24 East-West gradient, see BLAŽEK and CSANK, 2007).
25
26

27
28 Obviously, given the fact that public capital expenditure is highly “visible”, the
29
30 allocation is inevitably subject to challenge in the political arena, and a significant role of
31
32 subjective and “soft” factors in the regional allocation of this expenditure is envisaged.
33
34 Despite the fact that the available data does not allow for a thorough explanation of the
35
36 obtained result, the potentially most important explanatory factors are identified.
37
38

39
40 Finally, it is believed that a detailed scrutiny of the regional structure of public
41
42 expenditure significantly helps our understanding of regional development.
43
44

45
46 The paper is structured as follows. Firstly, the theoretical debate and the most
47
48 important findings of previous studies are summarized. Next, the data and the methodology
49
50 are described. Thirdly, the main findings of the empirical analyses of public capital
51
52 expenditure on the NUTS 3 and NUTS 4 levels are provided and discussed. Finally,
53
54 conclusions and policy implications are drawn.
55
56

57 58 2. Regional impact of government policy and its sectoral policies 59 60

1
2
3 The subject of public finance and fiscal policy is an important and traditional sphere of
4 research for economists (e.g. MUSGRAVE and MUSGRAVE, 1973; ATKINSON and STIGLITZ,
5 1980), nevertheless, geographers have also been interested in this sphere for several decades
6 (e.g. BENNET, 1980; HEALD, 1994; BLAŽEK, 1995). While economists often build models of
7 public sector spending and frequently deal with the issue of the efficiency of public sector
8 spending, geographers tend to derive the implications of public finance for regional
9 development (e.g. BLAŽEK, 1995; PORTEOUS, 1995; MARTIN, 2005).

10
11
12
13
14
15
16
17
18
19
20 Obviously, fiscal policy as a whole has a huge regional impact, depending on the
21 design of both the revenue and expenditure sides of the state budget. However, the regional
22 patterns of both revenue and expenditure are unknown in most countries. Generally, it can be
23 expected that a system of progressive taxation reduces revenues in more affluent regions
24 while social benefits tend to flow into the less well off regions, representing an important
25 mechanism for interregional redistribution (PRUDHOMME, 1993; WISHLADE *et al.*, 1996). The
26 regional redistribution of financial resources via governmental policies is one of the important
27 factors contributing to the economic growth of the respective regions (LEFEBER, 1964;
28 GUIŚÁN and CANCELO, 1996) and helps the social stabilization and internal cohesion of the
29 country in question (DE LA FLUENTE, 2004). Nevertheless, in the case of the regional
30 allocation of capital expenditure, there is even less certainty about the actual regional pattern
31 of this expenditure than in the case of current expenditure.

32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48 Authors focusing on analyses of the impact of governmental policy on the growth of
49 particular regions arrive at the conclusion that public investments are having measurable
50 positive effects on the respective regions (e.g. MARTHUR and STEIN, 1980; FÓLSTER and
51 HENREKSON, 2001; AUTERI and COSTANTINI, 2004). Other studies are devoted to the
52 investigation of efficiency issues (e.g. GUIŚÁN and CANCELO, 1996; DE LA FLUENTE, 2004).
53
54
55
56
57
58
59
60 Other authors point to the problem of the insufficient coordination of different public policies

1
2
3 and activities, as their goals and effects can be overlapping or even contradictory (e.g.
4
5 WISHLADE *et al.*, 1996; MARTIN, 2005; SHOUT and JORDAN, 2007). In addition, some other
6
7 studies have dealt with issues of social justice or equity within the sphere of public finance
8
9 (e.g. BOYN and POWELL, 1995).

10
11
12 One country where the allocation of public money attracts considerable attention from
13
14 both politicians and analysts is the UK. However, the main rationale for these studies is
15
16 mainly the issue of the distribution of public expenditure between England, Wales, Scotland
17
18 and Northern Ireland in the context of devolution (e.g. SHORT, 1978; HEALD, 1994; HEALD
19
20 and SHORT, 2002; MIDWINTER, 2004). In Japan, KATAOKA (2005) assessed the regional
21
22 distribution of public investments between 47 prefectures in the post-war period. Kataoka
23
24 noticed that periods of high national economic growth are positively correlated with the
25
26 concentration of public investment into economically strong regions while in periods of low
27
28 growth, a more balanced distribution of public capital expenditure has been observed.
29
30
31 WILSON and WISE (1986) studied the regional implications of public investment in a
32
33 developing country – Peru – over the period 1968–1983. They showed a high concentration of
34
35 public investment into the rich coastal regions during three subsequent time periods, while a
36
37 shift in favour of the poorer inland regions was observed in the second half of the period
38
39 studied. However, according to these authors, this shift is mainly attributable to the huge
40
41 investments in the mining industries in the inland regions.
42
43
44
45
46
47
48
49

50 51 3. Sectoral policies and regional policy

52
53 There have already been voices among experts suggesting that the regional impact of
54
55 vigorously pursued sectoral policies is much more profound than the regional impact of
56
57 regional policy itself (e.g. ROBERT *et al.*, 2001; MARTIN, 2005). Therefore, within this
58
59 context, some authors distinguish regional policy in a “narrow” and “broad” sense, while
60

1
2
3 other authors prefer the terms “explicit” and “implicit” regional policy (e.g. ARMSTRONG and
4 TAYLOR, 1985; CUADRADO, DE LA DEHESA and PRECEDO, 1993). While it can be agreed that
5 regional policy in a “narrow” sense is synonym with explicit regional policy, the difference
6 between implicit regional policy and a regional policy in a “broad” sense should be stressed.
7
8 Implicit regional policy encompasses public policies which have been to a certain extent
9 “regionalized” (i.e. there has been some sort of adjustments of an overall design of sectoral or
10 non-regional policy in question to meet specific regional conditions and needs). Regional
11 policy in a “broad” sense, on the other hand, comprises of all public policies or actions
12 executed by the public sector which have important regional impacts and this importance is to
13 some extent recognized (e.g. agricultural policy, transport policy, energy policy, competition
14 policy, science and technology policy). Despite the fact that these policies often lack an
15 explicit definition of regional goals, they are clearly having a specific impact on different
16 regions (e.g. CUADRADO, DE LA DEHESA and PRECEDO, 1993; EUROPEAN COMMISSION, 1998,
17 2004; HILL and LOWE, 2007). Examples of public policies that reflect at least some specific
18 regional characteristics or which react to specific regional conditions are the policy aimed at
19 attracting large investors to the Czech Republic (UHLÍŘ, 2004) or the R&D policy in Germany
20 (see KOSCHATZKY, 2001). Considerable attention has been paid to the regional impact of
21 sectoral policies and analogous policies at EU level in studies undertaken within the ESPON
22 programme (e.g. THE ESPON MONITORING COMMITTEE, 2005).

23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
BLAŽEK (2005a) argues that one key component of fiscal policy that has an enormous
regional impact is the way the decentralized public administration bodies (municipalities and
regions) are financed. For example, in 2007, within the state budget of the Czech Republic
only CZK 1.5 bln was allocated to explicit regional policy (which represents only 0,06 % of
Czech GDP), while in the same year the state distributed more than CZK 160 bln to
municipalities and regions via a strictly egalitarian tax-sharing formula (this volume amounts

1
2
3 7,7% of Czech GDP). It is clear that the principles upon which the applied model of financing
4
5 local and regional government in particular countries rests are of tremendous importance and
6
7 consequently, due to the vast amount of money concerned, the system of local government
8
9 financing has a much more profound regional impact than official “explicit” regional policy.
10
11

12
13 Moreover, important regional impacts can be attributable even to non-spending
14
15 policies, for example to an anti-monopoly policy. WISHLADE *et al.* (1996) consider the spatial
16
17 impact of non-spending policies as “blind spots” of regional analyses.
18
19

20 21 22 23 4. The budgetary scheme of the Czech Republic

24
25 The budgetary scheme of the Czech Republic consists of two prime components – public
26
27 budgets and extra-budgetary funds created for specific investment purposes such as transport
28
29 infrastructure, and expenditure on environmental projects. (see Figure 1).
30
31

32 33 34 35 Figure 1: Simplified budgetary scheme of the Czech Republic

36
37 Source: modified on the basis of PEKOVÁ (2002), p. 79

38
39 (about here).
40
41

42
43 Nevertheless, due to the focus of this paper on the identification of spatial patterns in the
44
45 allocation of public capital expenditure, the analysis was limited to a regional analysis (at the
46
47 level of the NUTS 3 and NUTS 4 regions) of capital investment allocated from central
48
49 sources, i.e. from the state budget and from state extra-budgetary funds. The Czech state
50
51 budget operates with the dominant part of public finance assigned to public budgets, but as
52
53 Table 1 illustrates, the share of state budget allocated to capital expenditure is rather small.
54
55 This fact can be partly explained by the key role of state extra-budgetary funds in the case of
56
57 such expenditure (see Table 2), as they are designed to function as a vehicle allowing the
58
59
60

1
2
3 implementation of multi-annual projects, while the state budget in principle provides the
4 financial framework for one year only. In addition, a noteworthy volume of public capital
5 expenditure flows through decentralized public budgets, and especially via municipal budgets
6 (on average in 2000–2005 the capital expenditure of decentralized public budgets accounted
7 for CZK 74.2 bln per year, which represents 28.5 % of the total decentralized public budgets
8 on average per year). Nonetheless, in line with our research focus the analysis presented
9 below concentrates only on the capital expenditure allocated from the central level.
10
11
12
13
14
15
16
17
18
19
20
21

22 Table 1: Expenditure of the Czech state budget in 1995–2005 (current prices, in billion
23 CZK, in %)
24
25

26 Source: Statistical Yearbook of the Czech Republic 1997, 1999, 2001, 2002, 2004, 2006.
27

28 Note: In December 2007, the exchange rate was approx. 1 EUR = 27 CZK.
29

30 (about here)
31
32

33 Table 2: Expenditure from selected state extra-budgetary funds in 2000–2005 (current prices,
34 in billion CZK)
35
36

37 Source: Statistical Yearbook of the Czech Republic 2000–2006.
38

39 (about here)
40
41
42
43
44
45

46 5. Data and Methodology

47
48 The prime source for this regional analysis of the capital expenditure of the state budget of the
49 Czech Republic is the ISPROFIN (Information System of Programming Funding from the
50 State Budget) database, which comprises data regarding investment spending from the state
51 budget, in our case for the years 1995–2005. ISPROFIN is managed by the Ministry of
52
53
54
55
56
57
58
59
60

1
2
3 Finance of the Czech Republic and has been operational since 1995.² The structure of the
4 entries into ISPROFIN allows a regional break-down of capital expenditure at the level of the
5 NUTS 3 and 4 regions. However, several methodological problems arose during the analysis
6 of this data, and consequently a number of projects and programmes (and the corresponding
7 financial volume of capital expenditure) had to be excluded from the analysis. The following
8 criteria for omitting particular projects or programmes were applied: i) the regional allocation
9 of the investment incentives was not given or investment was implemented abroad; ii) the
10 project or programme was predominately for current expenditure; iii) the project was of an
11 “extraordinary” nature (i.e. expenditure devoted to the recovery of the territories affected by
12 the 1997 and 2002 floods or devoted to the restitution to former owners of private property
13 that was nationalized during the communist period).
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32

33 ² Except for the programmes set by a special act such as state support to the national cultural
34 heritage or agriculture.
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

1
2
3 An overview of the financial amounts included (and excluded) from the regional analysis of
4 public capital expenditure is given in Table 3. Another methodological challenge was
5 represented by projects which benefited the whole country, but in ISPROFIN were assigned
6 to one region only. This was especially the case for the purchase of jet fighter aircraft which
7 were also excluded from the analysis.
8
9
10
11
12
13
14

15
16
17 This problem relates to the fundamental methodological question of which principle
18 investment expenditure should be attributed to a certain region. For instance, SHORT (1978)
19 has explicitly distinguished two types of regional expenditure: “regionally relevant” and “total
20 expenditure” allocated to the region. According to Short, “regionally relevant” expenditure
21 benefits only the region in which the particular public money was allocated. Alternatively,
22 WISHLADE *et al.*, (1996) and also CAMINAL (2004) differentiated between the “flow” and
23 “benefit” approaches to the analysis of the regional distribution of public expenditure. The
24 “flow” approach assigns expenditure to regions regardless of whether or not the region in
25 question is an “end user”, while the “benefit” approach concentrates on the final beneficiaries
26 of the public money spent, or more precisely on the final beneficiary regions. Consequently,
27 in our analysis, the flow approach has been applied as it would be impossible to judge each of
28 the approximately 40,000 investment projects of ISPROFIN included in the analysis on the
29 basis of the benefit approach.
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49

50 Table 3: Financial resources of ISPROFIN 1995–2005 (in billion CZK, current prices, in %)

51 Source: ISPROFIN (Internal material of the Ministry of Finance of the Czech Republic),
52 authors` calculations.
53
54
55

56 (about here)
57
58
59
60

1
2
3 In addition to ISPROFIN, which covers capital expenditure financed from the state budget,
4
5 the two most relevant extra-budgetary funds were incorporated into our analysis. These two
6
7 funds are: The State Fund for Transport Infrastructure (SFTI) and the State Environmental
8
9 Fund (SEF). The data on the individual projects supported by these funds were obtained from
10
11 the responsible institutions. In the case of the State Fund for Transport Infrastructure, the
12
13 capital expenditure for 2001–2005 has been analysed at the level of NUTS 3 regions.
14
15 Investment projects to a total value of CZK 222.3 billion were included in the analysis. The
16
17 State Environmental Fund is represented by the data concerning expenditure during the years
18
19 1999–2005, which amounted to CZK 13 billion. Therefore, this analysis covers capital
20
21 expenditure from the state budget and from two extra-budgetary funds to a total value of CZK
22
23 617 bln. The analysis was structured into six parts, covering the most relevant thematic
24
25 spheres of public capital expenditure (see Table 4).
26
27
28
29
30
31
32
33

34 Table 4: Overview of the analyzed data for the period 1995-2005 (in billion CZK, current
35
36 prices)
37

38 Source: ISPROFIN (Internal material of the Ministry of Finance of the Czech Republic),
39
40 Internal materials of the State Fund for Transport Infrastructure (SFTI) and the State
41
42 Environmental Fund (SEF), authors` calculations.
43
44

45 (about here)
46
47
48
49
50

51 6. Results

52
53 In this section, the main results of the regional analysis of capital expenditure committed
54
55 within the sectoral governmental policies in the Czech Republic will be presented (Table 4
56
57 provides an overview of the financial volumes analysed). First, attention is paid to an analysis
58
59 of the distribution of all capital expenditure, that is an analysis of investment projects financed
60

1
2
3 from the state budget and from relevant state extra-budgetary funds. In view of the fact that
4
5 the overall nature of regional differentiation of investment allocation is considerably
6
7 influenced by investments in the transport infrastructure, in the next stage such investments
8
9 are excluded from the analysis and analysed separately. Next, the regional allocation of
10
11 investments in other relevant sectors is considered, namely the territorial allocation of
12
13 investments within explicit regional policy, investments in universities and the R&D sector,
14
15 and finally investment assigned to the environmental sector.
16
17
18
19
20
21

22 6.1. Regional analysis of total capital expenditure

23
24 The regional analysis of total capital expenditure financed from the central level (i.e. from the
25
26 state budget and from both state extra-budgetary funds) in the period 1995–2005, includes
27
28 nearly CZK 617 billion after the data has been ‘cleaned’ by the above described procedure.
29
30 The nature of the capital expenditure determined that such invested funds were used primarily
31
32 for development activities, and allocation of such investments has an undoubted dynamic
33
34 effect on the relevant regions (e.g. SHORT, 1981; AUTERI and COSTANTINI, 2004).
35
36
37
38
39
40

41 The overall spatial pattern of the regional distribution of the analysed funds can be considered
42
43 as significantly unbalanced. In the period studied, over one quarter of the analysed
44
45 investments (which in absolute terms represents approximately CZK 168 billion) were
46
47 allocated from the national level into the capital city of Prague, socio-economically the most
48
49 advanced region of the Czech Republic (for regional GDP per capita see Figure 2). The
50
51 dominance of Prague is also proved by relative indicators, i.e. investments per inhabitant
52
53 (approximately CZK 142 thousand per inhabitant, which is 237% of the average for the Czech
54
55 Republic - see Table 5). With respect to economic performance indicators, i.e. after putting
56
57 capital expenditure in relation to the regional GDP level, it was 116% of the average
58
59
60

1
2
3 allocation of the Czech Republic and in relation to the economic aggregate it was 123% of the
4 national average. The term economic aggregate was defined by HAMPL (2005) as the product
5 of the number of jobs (the number of jobs is determined as the number of economically active
6 persons after deducting the unemployed and adding the commuting balance calculated on the
7 basis of the 2001 Census) and the average wage in the region in question. The Plzeňský and
8 Olomoucký regions achieved an even higher investment allocation than Prague with respect
9 to GDP (136%, resp. 137% - see Table 5), and the same order applies when the allocated
10 investment volume is related to the economic aggregate.
11
12
13
14
15
16
17
18
19
20
21
22
23

24 Table 5: Capital expenditure per capita and per regional GDP (1995–2005, in %)

25 Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech
26 Republic 2001, authors` calculations.
27
28
29

30 (about here)
31
32
33
34
35

36 6.2. Regional analysis of total capital expenditure after exclusion of transport investment

37 Since the extraordinary volume of investment devoted to transport infrastructure (CZK 222
38 billion from the state budget and from the State Fund for Transport Infrastructure – see Table
39 4) which undoubtedly influences the overall picture of the regional allocation of investment,
40 such expenditure was excluded from the analysis in the following stage. The remaining
41 investment projects thus represent approximately CZK 395 billion for the period of 1995–
42 2005 again.
43
44
45
46
47
48
49
50
51
52
53

54 After the exclusion of projects in the transport infrastructure sector, the position of Prague is
55 even higher (see Table 5). In absolute terms, its share of public capital expenditure in the
56 Czech Republic actually increased to 37.5%, while in per capita terms the investment
57
58
59
60

1
2
3 allocation to Prague was 326% of the average value for the Czech Republic. No other NUTS
4
5
6 3 region received an above-average allocation per inhabitant. Even when the allocated
7
8 investment projects are related to the regional GDP, the Prague region is still above the
9
10 national average (see Table 5). Investments in Prague were directed particularly to the state
11
12 administration (approximately CZK 55 billion), state defence (CZK 24 billion), health service
13
14 (CZK 18.1 billion), infrastructure development (CZK 18.9 billion) as well as public city
15
16 transport (4.8 billion CZK), R&D (CZK 6.9 billion) and education (CZK 8.7 billion).
17
18

19
20
21
22 As all data except for that on transport infrastructure projects was territorially identified up to
23
24 NUTS 4 level, a detailed analysis of the regional distribution of capital expenditure, after
25
26 exclusion of transport expenditure, could be carried out on the NUTS 4 level regions. At this
27
28 hierarchical level, Prague dominates absolutely. The district of Kutná Hora achieved the
29
30 second highest allocation per inhabitant and the highest allocation per economic aggregate,
31
32 but this was thanks to extraordinary investments in the military air force base in Čáslav. The
33
34 district of Brno–město (after Prague the second most important economic centre of the Czech
35
36 Republic) is in third position with 162% of the average allocation per inhabitant. Brno also
37
38 achieved the second highest share of 6%. The districts of Ostrava–město (2.2%), Olomouc
39
40 (2.6%) and Plzeň–město (2.2%) also received significant shares. Other districts received only
41
42 minor allocations.
43
44
45
46
47
48
49

50
51 Where capital expenditure was considered per inhabitant, above-average investments
52
53 compared to the average for the Czech Republic were allocated to only 11 out of 77 districts,
54
55 and 22 districts did not even achieve 50%. The regions receiving significantly below-average
56
57 investment funds per inhabitant include the majority of districts in North-Western Bohemia
58
59 and Northern Moravia (which, however, are mostly among the regions supported within
60

1
2
3 Czech regional policy – see Figure 2), the internal periphery, as well as a large area of
4
5 Southern, Western, Northern and Eastern Bohemia and the Czech-Slovak borderland (see
6
7 Figure 3).
8
9

10
11
12
13 Figure 2: Assisted regions supported within Czech explicit regional policy

14
15 Source: Ministry for Regional Development.

16
17 (about here)
18
19
20
21

22 Figure 3: Capital expenditure per capita after exclusion of transport infrastructure in NUTS 4
23
24 regions, 1995–2005, Czech Rep. = 100 % (in %).

25
26 Source: ISPROFIN, SEF, Statistical Yearbook of the Czech Republic 2001, authors`
27
28 calculations.
29

30
31 (about here)
32
33

34 Due to the unavailability of GDP data for NUTS 4 regions and the limited reliability of this
35
36 indicator on the NUTS 3 regions, GDP was replaced by an economic aggregate. At regional
37
38 level, this indicator achieves a very high correlation with regional GDP (0.998). After putting
39
40 the allocated investment funds in relation to the economic aggregate (see Figure 4), Prague
41
42 achieved 169% of the average for the Czech Republic (the highest allocations went to the
43
44 districts of Kutná Hora - 257% and Prostějov - 170%, in both cases thanks to extraordinary
45
46 investments in the defence sector). Highly uneven distribution of this expenditure illustrates
47
48 well the fact that above-average values were achieved by only 13 districts, among which was
49
50 also the second largest city (district Brno-město - 119 %).
51
52
53
54
55
56

57 Figure 4: Capital expenditure per economic aggregate after exclusion of transport

58
59 infrastructure investments in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %).
60

1
2
3 Source: ISPROFIN, SEF, Statistical Yearbook of the Czech Republic 2001, HAMPL (2005),
4
5 authors` calculations.
6

7
8 (about here)
9

10 11 12 6.3. Capital expenditure in the transport sector 13

14
15 The extraordinary importance of investment devoted to the transport infrastructure is given by
16
17 their very high volume (CZK 222 billion), which represents approximately 36% of the
18
19 volume of the investment observed in this study. In addition, it is obvious that the regional
20
21 formula of transport constructions, often linear in nature, may significantly differ from the
22
23 spatial formula of other investment projects. For this reason, the transport sector was chosen
24
25 for a separate regional analysis (i.e. investment in construction of motorways, expressways,
26
27 railway corridors, and the underground in Prague). Despite a number of methodological
28
29 constraints, it was possible to unite the two most important sources of funds for this sector:
30
31 the state budget (i.e. ISPROFIN) and the State Fund for Transport Infrastructure. The total
32
33 analysed investment volume of 1995–2005 exceeds CZK 222.3 billion (ISPROFIN – CZK
34
35 96.7 billion, the State Fund for Transport Infrastructure – CZK 125.5 billion), and the data are
36
37 available only for NUTS 3 regions.
38
39
40
41
42
43
44
45

46 Figure 5 illustrates the considerably above-average allocation of investment in transport in
47
48 Western Bohemia, which corresponds to the hypothesis of allocation of investment along a
49
50 traditional west-east gradient in the level of socio-economic development. In transport
51
52 investment, this gradient is raised by the effort to ensure transport connections for the Czech
53
54 Republic or its capital of Prague with nearby economic centres in Germany (Munich,
55
56 Frankfurt, Berlin). Although the area of Northern Moravia is a structurally affected region, as
57
58 is North-Western Bohemia, transport investment has flowed more to Northern Bohemia in
59
60

1
2
3 recent years, because the transport connection with Poland was of less priority than
4
5 connections to Germany or Western Europe.
6
7
8
9

10 Figure 5: Transport infrastructure investment per capita in NUTS 3 regions, 1995–2005,
11
12 Czech Rep. = 100 % (in %)

13 Source: ISPROFIN, SFTI, Statistical Yearbook of the Czech Republic 2001, authors`
14
15 calculations.
16
17

18
19 (about here)
20
21
22
23

24 The spatial formula for the allocation of per capita investment in transport is very similar to
25
26 the case where transport investment is related to GDP (the correlation coefficient is 0.954). In
27
28 both indicators the position of Prague is well below national average (78%, resp. 38% of the
29
30 Czech Republic average). On the contrary, Plzeňský, Olomoucký, Ústecký and Karlovarský
31
32 regions achieved significantly above-average allocations. However, in evaluating the regional
33
34 distribution of transport infrastructure investments (and of general investments as well) it is
35
36 necessary to consider the time aspect in the sense that if a significantly higher amount of
37
38 funds is granted to a region in a certain time range, it may mean that the necessary
39
40 infrastructure had not previously been constructed in the region in question and it is being
41
42 built behind schedule or out of needs arising from the different geopolitical orientation of the
43
44 Czech Republic after the fall of the Iron Curtain. For example, as early as the communist era,
45
46 the D1 motorway was completed between Prague and Brno, leading across the Vysočina
47
48 region, so this region records a significantly below-average allocation, while in the districts of
49
50 Tachov and Plzeň-jih districts, the D5 connecting Prague and Bavaria was built during the
51
52 period considered here.
53
54
55
56
57
58
59
60

1
2
3 The regional distribution of capital expenditure after the exclusion of transport infrastructure
4 investments when related to the economic level of the region (GDP) shows that transport
5 investments are what “aid” economically weaker regions to reach above-average values. If
6
7
8
9
10 transport investments are not considered, Prague is quite clearly the region that gains most
11
12 from redistribution of public investment both in per capita terms and in relation to GDP
13
14 (116 %, or 159 % of the Czech Republic average - see Table 5).
15
16
17
18
19

20 6.4. Capital expenditure allocated within explicit regional policy 21

22 Since one of the aims of this article is to show a significant discrepancy between the regional
23 formula for the allocation of public investment funds within non-regional policies and
24 regional policy, this is presented by Figure 6 which shows investments granted to explicit
25 regional policy from the state budget. Strikingly, the funds allocated within regional policy
26
27 are spread widely across the whole territory of the Czech Republic. This is in sharp contrast
28
29 with the very conception of regional policy as a policy which supports only selected regions.
30
31 This finding cannot be justified by changes of assisted areas over the investigated period as
32
33 there was considerable stability of both the regional pattern of lagging and leading regions
34
35 and consequently also of assisted areas delineated for the sake of regional policy (BLAŽEK,
36
37 2005b). On the other hand, the pattern of investment within regional policy does confirm that
38
39 a certain priority was given to the assisted areas. Namely, the Moravian districts, especially
40
41 the southern and, to some extent, northern ones ranked among the largest recipients of such
42
43 investments (together with North-Western Bohemia they rank among the regions supported
44
45 within Czech explicit regional policy, as does Northern Bohemia to some degree).
46
47 Nevertheless, it is necessary to mention a paradox as a statistically highly significant positive
48
49 relation of regional policy investment to regional GDP and to the economic aggregate was
50
51 demonstrated for NUTS 3 regions (in both cases excluding Prague - see Table 6a). The same
52
53
54
55
56
57
58
59
60

1
2
3 applies also to the level of NUTS 4 regions (see Table 6b) where a statistically significant
4
5 positive relation was found between the regional policy capital expenditure and the level of
6
7 economic development measured by the economic aggregate as a proxy for regional GDP. At
8
9 the same time, a larger part of Moravia ranks, with other regions supported within explicit
10
11 regional policy, as an area significantly underfinanced with respect to the total investment
12
13 from the state budget after the exclusion of transport. In simple terms, districts supported
14
15 within the explicit regional policy in the Czech Republic received only a very limited volume
16
17 of investment from the national level (after the exclusion of transport constructions) (compare
18
19 Figures 2, 3 and 4). On the other hand, support within Czech regional policy was significantly
20
21 concentrated into these regions (see Figure 6). However, a huge difference in the financial
22
23 sums invested has to be stressed again: CZK 7.2 billion for regional policy versus the total
24
25 volume of the analysed funds amounting to CZK 617 billion. Nevertheless, although the
26
27 volume of investments for regional policy at the national level is nearly negligible, its
28
29 importance is significantly higher for the supported regions.
30
31
32
33
34
35
36
37
38

39 Figure 6: Capital expenditure per capita from the state budget devoted to explicit regional
40
41 policy in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %).
42

43 Source: ISPROFIN, Statistical Yearbook of the Czech Republic 2001, authors` calculations.

44
45 (about here)
46
47
48
49

50 Table 6a: Correlation of selected indicators for NUTS 3 regions (n=13 – Prague excluded)

51
52 Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech
53
54 Republic 2001, HAMPL (2005), authors` calculations.
55
56

57
58
59 Table 6b: Correlation of selected indicators for NUTS 4 regions (n=76 – Prague excluded)
60

1
2
3 Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech
4
5 Republic 2001, HAMPL (2005), authors` calculations.
6

7
8 (about here)
9

10 11 12 6.5. Capital expenditure for higher education, R&D and the environmental sector 13

14
15 Within the regional analysis of capital expenditure from the state budget of the Czech
16
17 Republic, sectoral analyses were also carried out. As an example, Figure 7 shows investment
18
19 from the state budget in the infrastructure of universities and colleges and other R&D
20
21 institutions amounting to approximately CZK 25 billion. The expected regional distribution of
22
23 such expenditure into economically more developed regions (Prague, Brno) and to regions
24
25 where a public college is located, or to regions with headquarters of important research
26
27 institutes (the Prague hinterland) was demonstrated (similar regional pattern of public R&D
28
29 expenditure was shown by WISHLADE *et al.* 1996 or THE ESPON MONITORING COMMITTEE
30
31 2005). Nevertheless, it is necessary to point out that it is not only capital expenditure from the
32
33 central level that is devoted to this sector. For example, it was not possible to obtain data on
34
35 the regional allocation of financial support for R&D projects allocated by the Grant Agency
36
37 of the Czech Republic. In addition, it is necessary to take into account a frequent
38
39 methodological problem, when some analysed data are allocated according to the
40
41 headquarters of the institution in question, although such funds may then be invested in
42
43 branches of the institution in a different region. It is thus probable that in fact investment in
44
45 higher education and R&D is less concentrated than the data analysed shows.
46
47
48
49
50
51
52
53
54

55 Figure 7: Capital expenditure per capita of the state budget devoted to universities and for
56
57 R&D institutions in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %)
58

59 Source: ISPROFIN, Statistical Yearbook of the Czech Republic 2001, authors` calculations.
60

1
2
3 (about here)
4
5
6
7

8 Figure 8 shows investment in the environment sector amounting to CZK 25.6 billion
9 allocated both from the state budget and the State Environmental Fund. Although no clear
10 relation between the distribution of funds and environmental quality has been shown, we may
11 confirm to some extent that investment was allocated to regions in which it is necessary to
12 solve a specific problem with respect to the environment (e.g. support of mining reduction,
13 revitalising the river system, pond reconstructions).
14
15
16
17
18
19
20
21

22
23
24 A surprisingly high allocation of investment to border districts in South-Western Bohemia
25 relates to investment in the territorially largest national park in the Czech Republic (The
26 Šumava National Park). Figure 8 provides, however, a surprising finding, that investment
27 projects in the environment sector are not greatly concentrated in the structurally handicapped
28 regions in Northern Bohemia and in Northern Moravia where the environment is seriously
29 damaged. There is one exception with high investment - the Česká Lípa district - where the
30 running down of the uranium industry and subsequent cultivation of the area are jointly in
31 progress.
32
33
34
35
36
37
38
39
40
41
42
43
44
45

46 Figure 8: Environmentally related capital expenditure per capita of the state budget in 1995–
47 2005 and of the State Environmental Fund in 1999–2005 in NUTS 4 regions, Czech Rep.
48
49 =100 % (in %)
50
51

52 Source: ISPROFIN, SEF, Statistical Yearbook of the Czech Republic 2001, authors`
53 calculations.
54
55

56
57 (about here)
58
59
60

6.6. Relation of capital expenditures to selected socio-economic variables

1
2
3 On the basis of correlation coefficients for selected indicators for NUTS 3 regions (Table 6a)
4 we can demonstrate a statistically significant relation between all regional allocations of
5 investment via all analysed categories of investment (i.e. total investment, total investment
6 after exclusion of transport investment, transport investment, investment into R&D and
7 universities and regional policy investment, and their economic performance expressed by the
8 GDP and the economic aggregate. The same finding counts for correlation coefficients for
9 NUTS 4 regions (Table 6b), however, due to data limitations only the correlation between 3
10 investment categories and the economic aggregate could be calculated. It is important to stress
11 again that with respect to the declared objectives of Czech regional policy, the correlation
12 between the share of investment allocated within explicit regional policy and economic
13 performance should be negative. However, on both NUTS 3 and NUTS 4 level regions
14 positive and even statistically significant values were obtained indicating that even allocation
15 of investment within regional policy is not in line with its own strategic objective.
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33

34
35 The identification and detailed assessment of factors behind these observed patterns goes
36 beyond the focus of this paper, however at least a brief discussion should be included. In
37 countries like the Czech Republic which are lacking instruments for the systematic evaluation
38 of the effectiveness and efficiency of planned public investment, a relatively important role
39 can be assumed for subjective factors. The decision making process on public investment
40 committed from the central level basically proceeds at two levels. Firstly, on the basis of a
41 proposal of the Ministry of Finance, the Government and Parliament decide about financial
42 allocations to particular sectors that come under the responsibility of particular ministries.
43 Secondly, there is a process of selection of priorities by a particular ministry. In this case,
44 three main factors influencing the decision making process on public investments might be
45 identified: i) the adopted strategy for a specific sector (inevitably even these strategic
46 documents can to some extent reflect subjective factors), ii) the interests of (esp. high-
47
48
49
50
51
52
53
54
55
56
57
58
59
60

1
2
3 ranking) public servants and iii) the interests of politicians. On the basis of our experience of
4 more than 10 years of contractual cooperation by one of the authors with one central
5 administration body we can draw two preliminary conclusions. First, the relevance of these
6 three types of factors differs widely among different sectoral policies. Second, in some cases
7 each of the three above mentioned factors can be decisive. This, therefore, makes a clear case
8 for the introduction of some instruments (including TIA) that would be able to “objectivise”
9 the need for public investment.
10
11
12
13
14
15
16
17
18
19
20

21 7. Conclusions and policy implications

22
23 The article aims to contribute to the debate on the regional dimension of sectoral (non-
24 regional) governmental policies and to empirically demonstrate the huge discrepancy between
25 both the volume and regional pattern of public capital expenditure committed within the
26 national sectoral policies on the one hand and the official regional policy on the other. The
27 performed analyses focused “only” on the public capital expenditures allocated by the
28 Government of the Czech Republic, but it can be claimed that public capital investments have
29 the most important implications for the development of particular regions (SHORT, 1981;
30 YAMANO and OHKAWARA, 2000). Obviously, the financial volume of the total public capital
31 expenditure is incomparably higher than the financial volume allocated to explicit regional
32 policy.
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49

50 The regional analyses performed were based on the dataset of public capital expenditure in
51 the Czech Republic covering the years 1995–2005 and demonstrated uneven regional
52 distribution of these investments in favour of the most economically developed region of the
53 Czech Republic – the capital city of Prague. Such a regional pattern for the distribution of
54 public investment supports the hypothesis that there exists a contradiction between the
55 regional impact of sectoral policies on the one hand, and the goals of explicit regional policy
56
57
58
59
60

1
2
3 on the other. The discrepancy between these two is particularly striking as assisted regions
4 delineated for the sake of national regional policy were to a large extent left aside by
5 decisions regarding the allocation of public capital expenditure (with the exception of
6 expenditure on transport infrastructure). Moreover, a surprising pattern was identified even in
7 the case of investment committed within explicit regional policy (see Fig. 6) which is not
8 coinciding well with the map of assisted areas (see Fig. 2). Clearly, the allocation of regional
9 policy investments is not respecting fully the objectives of regional policy itself.

10
11
12
13
14
15
16
17
18
19
20
21
22 Consequently, there is a clear conflict between the goals of explicit regional policy aiming at
23 the support of less well-off regions and mostly unintended regional impacts of much more
24 vigorous non-regional governmental policies generally supporting the most developed
25 regions. These findings are in line with research performed by e.g. WILSON and WISE (1986)
26 but in contrast with results of YAMANO and OHKAWARA (2000).

27
28
29
30
31
32
33
34
35
36 However, it is necessary to stress that from the point of view of the entire expenditure side of
37 the governmental policies comprising both capital and current expenditure, the region of
38 Prague is very likely the most important net payer into the system of public finance due to its
39 buoyant tax base and to its relatively low share of persons receiving social benefits (see
40 OUŘEDNÍČEK and NOVÁK, 2006). Nevertheless, it is clear that the uneven distribution of
41 public capital expenditure, generally favouring more developed regions, is one of the most
42 important mechanisms of regional differentiation and is, moreover, cumulative in nature.

43
44
45
46
47
48
49
50
51
52
53
54 The expectation of a replication of the traditional East-West gradient in the level of socio-
55 economic development by the regional structure of total capital expenditure has not been
56 experienced. However, the evidence supporting this expectation can be observed in the case
57 of the capital expenditure allocated to transport infrastructure. The greater support of transport
58
59
60

1
2
3 infrastructure projects in the Western part of the Czech Republic is a reflection of the priority
4 assigned to connecting the Czech Republic to Western European structures.
5
6

7
8
9 Key implications deriving from the conducted regional analysis relate in particular to the
10 necessity of developing a sound methodology for the territorial impact assessment of public
11 policies and programmes. In other words, it is essential to develop a procedure evaluating not
12 only the regional impact of incentives carried out within explicit regional policy (which is
13 already becoming common practice in the most developed countries) but also the impact of
14 public interventions which do not explicitly incorporate a regional dimension but where
15 implementation might have a significant regional impact. Such an evaluative instrument is
16 essential for tackling of regional development issues and problems more effectively by
17 achieving synergies and eliminating contradictions between different policies (SCHÄFFER,
18 2005; CEC, 2006a, 2006b). Nevertheless, this approach is a real challenge due to the fact that
19 public policies in most advanced countries are traditionally being implemented via sectorally
20 structured public administration at central governmental level while the relevance of sectoral
21 policies for development of particular regions has been clearly underestimated (ROBERT *et al.*,
22 2001; MACEŠKOVÁ, 2007).
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44

45 Despite the effort that has been put into developing TIA methodology, no comprehensive and
46 satisfactory tool for regional impact assessment has yet been developed. Therefore, as also
47 documented by our empirical results, which showed both an uneven spatial pattern of the
48 allocation of public capital expenditure and a huge mismatch between the regional pattern of
49 this expenditure and the assisted regions, the development of a suitable instrument for
50 territorial/regional impact assessment and its application at least to the most relevant sectoral
51 policies remains a critical challenge for both researchers and decision-makers.
52
53
54
55
56
57
58
59
60

1
2
3
4
5
6 Acknowledgements
7

8 This paper received financial support from Research Programme No. MSM 0021620831 and
9
10 from project 2D06012 "Socio-Spatial Differentiation of Population and its Impact on Quality
11
12 of Life in Cities and Communities in the Czech Republic" both sponsored by the Czech
13
14 Ministry of Education, Youth and Sport. The authors would also like to thank to two
15
16 anonymous referees for their helpful comments.
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

Table 1: Expenditure of the Czech state budget in 1995-2005 (current prices, in billion CZK, in %)

	1995	1996	1997	1998	1999
Total expenditure of the state budget	432.7	484.4	524.7	566.7	596.9
of which capital expenditures of the state budget	44.1	46.4	50.6	50.5	59.0
share of capital expenditures of the total expenditure of the state budget (%)	10,2	9,6	9,6	8,9	9,9

Source: Statistical Yearbook of the Czech Republic 1997, 1999, 2001, 2002, 2004, 2006.

Note: In December 2007, the exchange rate was approx. 1 EUR = 27 CZK.

Table 1 continued

	2000	2001	2002	2003	2004	2005
Total expenditure of the state budget	632.3	693.9	750.8	808.7	862.9	923.0
of which capital expenditures of the state budget	60.9	49.6	49.7	56.9	66.7	79.0
share of capital expenditures of the total expenditure of the state budget (%)	9,6	7,1	6,6	7,4	7,7	8,3

Source: Statistical Yearbook of the Czech Republic 1997, 1999, 2001, 2002, 2004, 2006.

Table 2: Expenditure from selected state extra-budgetary funds in 2000-2005 (current prices, in billion CZK)

	2000	2001	2002	2003	2004	2005
Total expenditure of the State Environmental Fund of the Czech Republic	2.9	3.8	4.2	4.8	4.2	3.4
of which capital expenditure of the State Environmental Fund of the Czech Republic	2.6	3.5	3.7	4.2	3.7	3.0
share of capital expenditure of the entire expenditure of the State Environmental Fund of the Czech Republic	89.7	92.1	88.1	87.5	88.1	88.2
Total expenditure of the State Fund for Transport Infrastructure	8.5	30.6	40.2	41.3	52.1	48.5
of which the capital expenditure of the State Fund for Transport Infrastructure	5.0	13.9	24.1	25.1	34.6	37.8
share of capital expenditure of the entire expenditure of the State Fund for Transport Infrastructure	58.8	45.4	60.0	60.8	66.4	77.9

Source: Statistical Yearbook of the Czech Republic 2000 - 2006.

Table 3: Financial resources of ISPROFIN 1995-2005 (in billion CZK, current prices, in %)

ISPROFIN	billion CZK	share of the total sum of ISPROFIN (in %)
Total	658.9	100.0
Included into analysis	478.5	72.6
Totally excluded from the analysis	180.3	27.4
<i>of which</i> regional allocation unknown	81.7	12.5
allocation abroad	6.1	0.9
current expenditures	37.7	5.7
extraordinary expenditures	14.7	2.3
other specific capital expenditures - e.g. purchase of fighter aircraft	39.5	6.0

Source: ISPROFIN, authors' calculations.

Table 4: Overview of the analyzed data for the period 1995-2005 (in billion CZK, current prices)

Thematic sphere of capital expenditure	Financial volume	Source	Level
Total capital expenditure	617.2	State budget (ISPROFIN), SFTI, SEF	NUTS 3
Capital expenditure excluding transport infrastructure investments	394.9	State budget (ISPROFIN), SEF	NUTS 3 NUTS 4
Transport infrastructure investments	222.3	SFTI, State budget (ISPROFIN)	NUTS 3
Explicit regional policy and regional development	7.2	State budget (ISPROFIN)	NUTS 4
Environmental capital expenditure	25.6	SEF, State budget (ISPROFIN)	NUTS 4
Capital expenditure devoted to universities and R&D	25.4	State budget (ISPROFIN)	NUTS 4

Source: ISPROFIN (Internal material of the Ministry of Finance of the Czech Republic), Internal materials of the State Fund for Transport Infrastructure (SFTI) and the State Environmental Fund (SEF), authors` calculation.

Table 5: Capital expenditure per capita and related to regional GDP (1995-2005, in %)

Region	Total investments in bln CZK	Total investments per capita Czech Rep. = 100 %	Total investments excluded of transport infrastructure investments per capita, Czech Rep. = 100 %	GDP per capita, Czech Rep. = 100 %	Total investments per GDP, Czech Rep. = 100 %	Total investments excluded of transport infrastructure investments per GDP, Czech Rep. = 100 %	Transport infrastructure investments per GDP, Czech Rep. = 100 %
Prague	168.3	237	326	206	116	159	38
Central Bohemia region	55.9	84	76	95	86	78	100
South Bohemia region	29.2	78	66	89	87	74	109
Plzeňský region	42.3	128	89	94	136	95	209
Karlovarský region	13.1	71	44	80	89	55	150
Ústecký region	45.3	91	53	82	111	64	194
Liberecký region	21.9	85	85	83	102	103	102
Královehradecký region	22.6	68	78	90	76	86	57
Pardubický region	23.6	77	66	84	92	78	116
Vysočina region	18.8	60	67	87	69	78	54
South Moravia region	61.6	90	93	93	98	101	93
Olomoucký region	40.9	106	87	77	137	113	181
Zlínský region	19.9	55	57	82	68	71	64
Moravskoslezský region	53.9	70	51	80	89	65	131
Czech Republic	617.2	100	100	100	100	100	100

Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech Republic 2001, authors' calculations.

Table 6a: Correlation of selected indicators for NUTS 3 regions (n=13 - Prague excluded)

	Regional share of GDP	Regional share of economic aggregate	Regional unemployment rate	Regional share of total investment	Regional share of transport investment	Regional share of investment excluding transport	Regional share of investment in universities and R&D
Regional share of economic aggregate	0,993						
Regional unemployment rate	0,304	0,357					
Regional share of total investment	0,906	0,910	0,399				
Regional share of transport investment	0,717	0,741	0,634	0,892			
Regional share of investment excluding transport	0,905	0,890	0,097	0,903	0,612		
Regional share of investment in universities and R&D	0,583	0,592	-0,001	0,618	0,323	0,775	
Regional share of expenditure on regional policy	0,782	0,818	0,547	0,710	0,573	0,698	0,617

1
2
3 Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech Republic 2001, HAMPL (2005), authors`
4
5 calculations.
6

7
8 Note: Critical value of correlation coefficient for 95% level of significance is 0,497.
9

10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

For Peer Review Only

Table 6b: Correlation of selected indicators for NUTS 4 regions (n=76 - Prague excluded)


	Regional share of economic aggregate	Regional unemployment rate	Regional share of investment excluding transport	Regional share of investment in universities and R&D
Regional unemployment rate	0,111			
Regional share of investment excluding transport	0,851	-0,009		
Regional share of investment in universities and R&D	0,822	-0,039	0,915	
Regional share of expenditure on regional policy	0,320	0,404	0,228	0,122

Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech Republic 2001, HAMPL (2005), authors' calculations.

Note: Critical value of correlation coefficient for 95% level of significance is 0,200.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60


Figure 1: Simplified budgetary scheme of the Czech Republic



Source: modified on the basis of PEKOVÁ (2002), p. 79


Peer Review Only

Figure 2: Assisted regions supported within Czech explicit regional policy



Source: Ministry for Regional Development.


Figure 3: Capital expenditure per capita after exclusion of transport infrastructure in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %).



Source: ISPROFIN, SEF, Statistical Yearbook of the Czech Republic 2001, authors' calculations.


Review Only

Figure 4: Capital expenditure per economic aggregate after exclusion of transport infrastructure investments in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %).



Source: ISPROFIN, SEF, Statistical Yearbook of the Czech Republic 2001, HAMPL (2005), authors` calculations.


Figure 5: Transport infrastructure investment per capita in NUTS 3 regions, 1995–2005,
Czech Rep. = 100 % (in %)



Source: ISPROFIN, SFTI, Statistical Yearbook of the Czech Republic 2001, authors' calculations.


Review Only

1
2
3 Figure 6: Capital expenditure per capita from the state budget devoted to explicit regional
4 policy in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %).
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32




33 Source: ISPROFIN, Statistical Yearbook of the Czech Republic 2001, authors` calculations.
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

Figure 7: Capital expenditure per capita of the state budget devoted to universities and for R&D institutions in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %)



Source: ISPROFIN, Statistical Yearbook of the Czech Republic 2001, authors` calculations.

1
2
3 Figure 8: Environmentally related capital expenditure per capita of the state budget in 1995–
4
5 2005 and of the State Environmental Fund in 1999–2005 in NUTS 4 regions, Czech Rep.
6
7
8 =100 % (in %)
9



34
35 Source: ISPROFIN, SEF, Statistical Yearbook of the Czech Republic 2001, authors`
36
37 calculations.
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

1
2
3 ARMSTRONG H. and TAYLOR J. (1985) *Regional Economics and Policy*. Philip Allan,
4
5 Hertfordshire.
6
7

8
9
10 AUTERI M. and COSTANTINI M. (2004) Fiscal Policy and Economic Growth: The Case of
11
12 the Italian Regions, *The Review of Regional Studies* **34**, 72-94.
13
14

15
16
17 BENNET R. J. (1980) *The Geography of Public Finance*. Methuen, London.
18
19

20
21
22 BLAŽEK J. (1995) Le nouveau système de financement des administratios locales en
23
24 République tchèque et ses incidences è Í échelle régionale, Cahiers du CEFRES, No.9f,
25
26 Prague.
27
28

29
30
31
32 BLAŽEK J. (2005a) Financing of Local Government in the Czech Republic: A Never Ending
33
34 Reform Process? (Part III), in *New Modes of Governance. The Evolution of Regional*
35
36 *Development Regimes in CEE - The Czech Republic* (available at: [http://www.eu-](http://www.eu-newgov.org/database/DELIV/D15D02c_Regional_Development_Regimes_CzechR.pdf)
37
38 [newgov.org/database/DELIV/D15D02c_Regional_Development_Regimes_CzechR.pdf](http://www.eu-newgov.org/database/DELIV/D15D02c_Regional_Development_Regimes_CzechR.pdf)).
39
40

41
42
43 BLAŽEK, J. (2005b) Trends to Regional Disparities in the Czech Republic in Pre-Accession
44
45 Period in the European Context, *Geographia Polonica* **78.2**, p. 91-106.
46
47

48
49
50
51 BLAŽEK J. and CSANK P. (2007) The West-East gradient and regional development: The
52
53 case of The Czech Republic, *Acta Universitatis Carolinae - Geographica* **1-2**, 89-108.
54
55

56
57
58 CAMINAL R. (2004) Personal redistribution and the regional allocation of public
59
60 investment, *Regional Science and Urban Economics* **34**, 55-69.

1
2
3
4
5
6 CAMAGNI R. (2006) Territorial Impact Assessment – TIA: a methodological proposal,
7
8 *Scienze Regionali – Italian Journal of Regional Science* **5**, 135-146.
9

10
11
12
13 CEC (1996) First Report on Economic and Social Cohesion. Brussels (available at:
14
15 http://ec.europa.eu/regional_policy/sources/docoffic/official/reports/repc_en.htm).
16
17

18
19
20 CEC (2004) DG REGIO – The Impact of Member State Policies on Cohesion (Final report)
21
22 (available at:
23
24 [http://europa.eu.int/comm/regional_policy/sources/docgener/studies/pdf/3cr/impact_member.](http://europa.eu.int/comm/regional_policy/sources/docgener/studies/pdf/3cr/impact_member.pdf)
25
26 pdf).
27
28

29
30
31 CEC (2006a) Territorial Impact Assessment. In CEC: *European Territorial Research in*
32
33 *Progress*, pp. 67-132. Conference Proceedings of the 1st ESPON Scientific Conference,
34
35 ESPON Programme, Luxembourg.
36
37

38
39
40 CEC (2006b) *Applied Territorial Research. Building a Scientific Platform for*
41
42 *Competitiveness and Cohesion*. ESPON Scientific Report II, ESPON Programme,
43
44 Luxembourg.
45
46
47
48
49

50
51 CUADRADO J.R., DE LA DEHESA G. and PRECEDO, A. (1993) Regional imbalances and
52
53 government compensatory financial flows: the case of Spain, in Giovannini A. (Ed.) *Finance*
54
55 *and Development: Issues and Experience*, pp. 261-300. Cambridge University Press,
56
57 Cambridge.
58
59
60

1
2
3 DG RESEARCH (1991) *The Regional Impact of Community Policies*. Research and
4
5 Documentation Papers. Regional policy and transport, series 17., Office for Official
6
7 Publications of the European Communities, Luxembourg.
8
9

10
11
12 DRBOHLAV D. and SÝKORA L. (1997) Gateway cities in the process of regional integration
13
14 in Central and Eastern Europe: the case of Prague, in Biffi G. *Migration, Free Trade and*
15
16 *Regional Integration in Central and Eastern Europe*, pp. 215-237. Verlag Österreich, Wien.
17
18
19

20
21
22 EUROPEAN COMMISSION (1998) *Economic and social cohesion in the European Union:*
23
24 *The impact of Member States' own policies*. Office for Official Publications of the European
25
26 Communities, Luxembourg.
27
28

29
30
31 EUROPEAN COMMISSION (2004) *A new partnership for cohesion. Convergence,*
32
33 *Competitiveness, Cooperation. Third Report on Economic and Social Cohesion*. Office for
34
35 Official Publications of the European Communities, Luxembourg.
36
37

38
39
40 FLUENTE A. de la (2004) Second-best redistribution through public investment: a
41
42 characterization, an empirical test and an application to the case of Spain, *Regional Science*
43
44 *and Urban Economics* **34**, 489-503.
45
46
47

48
49
50 HAMPL M. (2005) *Geografická organizace společnosti v České republice: transformační*
51
52 *procesy a jejich obecný kontext*. Faculty of Science, Charles University in Prague, Prague.
53
54
55

56
57
58 HEALD D. (1994) Territorial public expenditure in the United Kingdom, *Public*
59
60 *Administration* **72**, 147-175.

1
2
3 HEALD D. and SHORT J. (2002) The regional dimension of public expenditure in England.
4
5
6 *Regional Studies* **36**, 743-755.
7

8
9
10 HILL E. and LOWE J. (2007) Regional impact assessment: an Australian example, *Impact*
11
12 *Assessment and Project Appraisal* **25**, 189-197.
13

14
15
16
17 GORZELAK G. (1992) Dilemmas of Polish regional policies during transition, in Gorzelak
18
19 G. and Kuklinski A. *Dilemmas of regional policies in Eastern and Central Europe*, pp. 18-
20
21 38. University of Warsaw, Warsaw.
22
23

24
25
26
27 GUIÁN M.C. and CANELO M.T. (1996) Territorial Public Expenditure and Revenue:
28
29 Economic Impact in the European Regional Growth, Euro-American Association of
30
31 Economic Development, Working Paper no. 8, Series Economic Development, University of
32
33 Santiago de Compostela (available at: <http://ideas.uqam.ca/ideas/data/eaecodev.html>).
34
35

36
37
38 KATAOKA M. (2005) Effect of Public Investment on the Regional Economies in Postwar
39
40 Japan, *Review of Urban & Regional Development Studies* **17**, 115-139.
41
42

43
44
45
46 KOSHATZKY K. (2001) The regionalisation of Innovation Policy in Germany - Theoretical
47
48 Foundations and Recent Experience. Working Papers Firms and Region No. R1/2000,
49
50 Institute for Systems and Innovation Research, Fraunhofer.
51
52

53
54
55 LEFEBER L. (1964) Regional Allocation of resources in India, in Alonso W. and Friedmann
56
57 J. *Regional Development and Planning, A Reader*, pp. 642-653. The M.I.T. Press, Cambridge,
58
59 Massachusetts.
60

1
2
3 MACEŠKOVÁ M. (2007) Regionální dimenze fiskální politiky na příkladě veřejných
4 investičních výdajů v Česku (Regional dimension of fiscal policy – an example of public
5 capital expenditure in the Czech Republic), *Geografie-Sborník ČGS* **112**, 17-32.
6
7
8
9

10
11
12 MARTHUR V.K. and STEIN S. (1980) Regional Impact of Monetary and Fiscal Policy: An
13 Investigation into the Reduced Form Approach, *Journal of Regional Science* **20**, 343-351.
14
15
16
17

18
19
20 MARTIN R. (1999) *The Regional Dimension in European Public Policy: Convergence or*
21 *Divergence?*. Palgrave Publisher, New York.
22
23
24

25
26
27 MARTIN R. (2005) Venture Capital Programmes in the UK and Germany: In What Sense
28 Regional Policies?, *Regional Studies* **39**, 255-273.
29
30
31

32
33
34 MIDWINTER A. (2004) The Changing Distribution of Territorial Public Expenditure in the
35 UK, *Regional and Federal Studies* **14**, 499-512.
36
37
38

39
40
41 MOLLE W. and CAPPELLIN R. (1988) (Eds) *Regional Impact of Community Policies in*
42 *Europe*. Aldershot, Avebury.
43
44
45

46
47
48 MOLLE W. (2007) *European Cohesion Policy*. Routledge, London.
49
50
51

52
53
54 MRD (2006) *Strategie regionálního rozvoje*. Ministry for Regional Development of the
55 Czech Republic, Prague.
56
57
58
59
60

1
2
3 MUSGRAVE A.R. and MUSGRAVE B.P. (1973) *Public Finance in Theory and Practice*.
4
5 McGraw-Hill Kogakusha, Tokyo.
6
7

8
9
10 OUŘEDNIČEK M. and NOVÁK J (2007) Kvantitativní analýza stavu a vývoje
11 segregace/separace obyvatelstva, in Sýkora L. *et al Segregace v*
12 *České republice (Segregation in the Czech Republic)*, pp 9-28.
13
14 Ministry for Regional Development, Prague.
15
16
17
18
19

20
21
22 PEKOVÁ J. (2002) *Veřejné finance - úvod do problematiky*. ASPI Publishig, Praha.
23
24
25

26
27 PORTEOUS D.J. (1995) *The Geography of Finance*. Aldershot, Avebury.
28
29
30

31
32 PRUD'HOMME R. (1993) The Potential role of the EC budget in the reduction of spatial
33 disparities in a European economic and monetary union, in Commission of the European
34 Communities *The Economics of Community Public Finance*, pp. 321-351. Reports and
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
Studies. Directorate-General for Economic and Financial Affairs, European Economy no. 5.
Luxembourg.

ROBERT J. *et al* (2001) *Spatial Impacts of Community Policies and Costs of Non-co-*
ordination. European Commission, Brussels.

SHORT J. (1978) The regional distribution of public expenditure in Great Britain, 1967/70 –
1973/74', *Regional Studies* **12**, 499-510.

1
2
3 SHORT J. (1981) *Public Expenditure and Taxation in the UK Regions*. Gower Publishing
4 Co. Ltd, Hampshire (England).
5
6
7

8
9
10 SHOUT J.A. and JORDAN A.J. (2007) From Cohesion to Territorial Policy Integration
11 (TPI): Exploring the Governance Challenges in the European Union, *European Planning*
12 *Studies* **15**, 835-851.
13
14
15

16
17
18 SCHÄFFER N. (2005) Coordination of European spatial development: Whose
19 responsibility?, *The Town Planning Review* **76**, 14-57.
20
21
22
23

24
25
26 SCHINDEGGER F. and TATZBERGER G. (2003) TIA minimum requirements – a
27 Guidance for Policy Impact Projects of ESPON. Austrian Institute for Regional Studies and
28 Spatial Planning (available at:
29
30
31
32
33
34 http://www.espon.lu/online/documentation/projects/cross_thematic/816/2.ir-3.1.pdf).

35
36
37
38 THE ESPON MONITORING COMMITTEE (2005) ESPON 2.1.2 Territorial Effects of EU
39 Research and Development Policies (Final report) (available at:
40
41
42
43 http://www.espon.eu/mmp/online/website/content/projects/243/266/file_399/fr-
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
2.1.1_final.pdf).

61
62
63 UHLÍŘ D. (2004) Regional versus National Development: What sort of Policy for new
64 Czech Regions?, in Drbohlav D., Kalvoda J. and Voženílek V. (Eds) *Czech Geography at the*
65 *Dawn of the Millenium*, pp. 269-277. Palacky University in Olomouc, Olomouc.
66

1
2
3 WILSON P.A. and WISE C. (1986) The Regional Implications of Public Investment in Peru,
4
5 1968-1983, *Latin American Research Review* **21**, 93-116.
6
7
8
9

10 WISHLADE F., YUILL D., TAYLOR S., DAVEZIES L., NICOT B.H. and PRUD`HOMME R. (1996):
11
12 Economic and Social Cohesion in the European Union: The Impact of Member States`Own
13
14 Policies. Final report for the European Commission. European Policies Research Centre,
15
16 University of Strathclyde, Glasgow.
17
18
19
20
21

22 YAMANO N. and OHKAWARA T. (2000) The Regional Allocation of Public Investment:
23
24 Efficiency or Equity, *Journal of Regional Science* **40**, 205-229.
25
26
27
28
29
30
31

32 Other sources 33 34 35 36

37 ISPROFIN – Internal Material of Ministry of Finance of the Czech Republic
38

39 Internal Material of State Fund for Transport Infrastructure of the Czech Republic
40

41 Internal Material of State Environmental Fund of the Czech Republic
42

43 Statistical Yearbooks of the Czech Republic 1997-2006 – Czech Statistical Office
44
45

46 Regional accounts – Czech Statistical Office
47
48
49
50
51
52
53
54
55
56
57
58
59
60

Regional analysis of public capital expenditure: to which regions is public capital expenditure channelled – to “rich” or to “poor” ones?

Abstract

The paper aims to contribute to the debate on the regional dimension of sectoral (i.e. non-regional) policies and to empirically demonstrate the huge discrepancy between both the volume and the regional pattern of sectoral public capital expenditure policies on the one hand, and official regional policy on the other. The analyses were based on a unique database of public investment in the Czech Republic covering the years 1995–2005. Their results show significant conflicts in policy objectives and thus represent a clear argument in favour of pursuing territorial impact assessment (TIA) of sectoral policies.

Key words: regional impact of non-regional policies, sectoral policies, territorial impact assessment, regional policy, public investments, Czech Republic

JEL classifications: H5, E61, R 11, R 58

Acknowledgements

This paper received financial support from Research Programme No. MSM 0021620831 sponsored by the Czech Ministry of Education, Youth and Sport. The authors would like to thank to two anonymous referees for their helpful comments.

1. Introduction

The aim of the paper is to contribute to the debate on the regional dimension and the regional impact of sectoral public capital expenditure policies. This debate started decades ago (e.g. SHORT, 1978; BENNETT, 1980; MARTHUR and STEIN, 1980; MOLLE and CAPPELLIN,

1
2
3 1988) but recently received a significant impetus in the form of a discussion on the regional
4 impact of sectoral policies and the possibilities of their “regionalization” (e.g. DG RESEARCH,
5 1991; MARTIN, 1999; ROBERT *et al.*, 2001; MOLLE, 2007). The “regionalization” of sectoral
6 policies can be understood as the fine-tuning of sectoral public expenditure according to the
7 needs and circumstances of specific regions.ⁱ One of the important results of this discussion
8 was the gradual development of the methodology of the territorial impact assessment of large
9 projects and later, also of programmes and policies – SCHINDEGGER and TATZBERGER, 2003;
10 CAMAGNI, 2006). The increasing attention being paid to the regional dimension of public
11 expenditure policies stemmed originally from the effort to learn how to improve or - more
12 precisely - how to ensure the coordination of the territorial impact of the EU policy of
13 economic and social cohesion (ESC) and of other European policies (e.g. CEC, 1996; SHOUT
14 and JORDAN, 2007). Moreover, at the same time, there was a significant research endeavour to
15 discover to what extent the regional impact of ESC policy has been in compliance with the
16 spatial effects of numerous national public policies of the EU Member States (CEC, 2004).

17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36 Nevertheless, the number of existing analyses of the regional impact of sectoral
37 policies is still relatively limited (for exceptions see e.g. HEALD, 1994; AUTERI and
38 COSTANTINI, 2004; KATAOKA, 2005; MACEŠKOVÁ, 2007), mostly due to the severe data
39 limitations in most countries. Therefore, the main aim of this article is an attempt to perform
40 an analysis of the regional dimension of public capital expenditure in one of the new Member
41 States (the Czech Republic) at the level of the NUTS 3 and 4 regions. This analysis is based
42 on a unique data set of capital public expenditure covering investment projects supported
43 during 1995–2005.

44
45
46
47
48
49
50
51
52
53
54
55 The analyses undertaken here are aimed at answering several research questions.
56 Firstly, the relation between the level of the socio-economic development of the regions and
57 the amount of invested public capital expenditure will be investigated. It is assumed that
58
59
60

1
2
3 public investments are highly concentrated in the most socio-economically developed regions.
4
5 Such a regional allocation of this type of public funds would be in accordance with the
6
7 principles of a strategic regional policy (for more on strategic regional policy see e.g.
8
9 GORZELAK, 1992). In other words, given the many deficiencies in the sphere of the technical
10
11 and other infrastructures inherited from the communist period, it is supposed that public
12
13 investment was primarily focused on the enhancement of the infrastructure in major cities and
14
15 namely in Prague to strengthen the gateway effect (DRBOHLAV and SÝKORA, 1997) and to
16
17 enhance the competitiveness of the national metropolis on the international scene.
18
19
20
21

22
23 Moreover, another reason for the anticipated concentration of public investment in
24
25 core regions is the assumed the higher efficiency of investment in these regions (e.g.
26
27 CAMINAL, 2004; DE LA FLUENTE, 2004). Therefore, a positive correlation between the level of
28
29 socio-economic development and the amount of public capital invested (relative per capita) is
30
31 expected. However, it should be stressed that such a regional pattern of public investment
32
33 contradicts the objectives of the Czech national strategy for regional development and of
34
35 regional policy aiming at decreasing regional disparities and being in compliance with the
36
37 “insurance” type of regional policy (MRD, 2006; GORZELAK, 1992). As a result, it can be
38
39 argued that there is an immense policy conflict between goals of explicit regional policy and
40
41 mostly unintended spatial impacts of much more vigorous non-regional governmental
42
43 policies. Therefore, our analyses might also serve as empirical support for the importance of
44
45 pursuing territorial impact assessment (TIA), both for major public capital projects and for
46
47 sectoral policies as a whole.
48
49
50
51

52
53 Secondly, a replication of the traditional East-West gradient of socio-economic
54
55 development by the regional structure of capital expenditure is also expected (for more on the
56
57 East-West gradient, see BLAŽEK and CSANK, 2007).
58
59
60

1
2
3 Obviously, given the fact that public capital expenditure is highly “visible”, the
4 allocation is inevitably subject to challenge in the political arena, and a significant role of
5 subjective and “soft” factors in the regional allocation of this expenditure is envisaged.
6
7 Despite the fact that the available data does not allow for a thorough explanation of the
8 obtained result, the potentially most important explanatory factors are identified.
9
10
11
12

13
14
15 Finally, it is believed that a detailed scrutiny of the regional structure of public
16 expenditure significantly helps our understanding of regional development.
17
18

19
20 The paper is structured as follows. Firstly, the theoretical debate and the most
21 important findings of previous studies are summarized. Next, the data and the methodology
22 are described. Thirdly, the main findings of the empirical analyses of public capital
23 expenditure on the NUTS 3 and NUTS 4 levels are provided and discussed. Finally,
24 conclusions and policy implications are drawn.
25
26
27
28
29
30
31
32
33

34 **2. Regional impact of fiscal policy and its sectoral policies**

35
36 The subject of public finance and fiscal policy is an important and traditional sphere of
37 research for economists (e.g. MUSGRAVE and MUSGRAVE, 1973; ATKINSON and STIGLITZ,
38 1980), nevertheless, geographers have also been interested in this sphere for several decades
39 (for example BENNET, 1980; HEALD, 1994; BLAŽEK, 1995). While economists often build
40 models of public sector spending and frequently deal with the issue of the efficiency of public
41 sector spending, geographers tend to derive the implications of public finance for regional
42 development (for example BLAŽEK, 1995; PORTEOUS, 1995).
43
44
45
46
47
48
49
50
51
52

53 Obviously, fiscal policy as a whole has a huge regional impact, depending on the
54 design of both the revenue and expenditure sides of the state budget. However, the regional
55 patterns of both revenue and expenditure are unknown in most countries. Generally, it can be
56 expected that a system of progressive taxation reduces revenues in more affluent regions
57
58
59
60

1
2
3 while social benefits tend to flow into the less well off regions, representing an important
4 mechanism for interregional redistribution (PRUDHOMME, 1993; WISHLADE *et al.*, 1996). The
5 regional redistribution of financial resources via fiscal policy is one of the important factors
6 contributing to the economic growth of the respective regions (LEFEBER, 1964; GUIÁN and
7 CANCELO, 1996) and helps the social stabilization and internal cohesion of the country in
8 question (DE LA FLUENTE, 2004). Nevertheless, in the case of the regional allocation of capital
9 expenditure, there is even less certainty about the actual regional pattern of this expenditure
10 than in the case of current expenditure.
11
12
13
14
15
16
17
18
19
20
21

22 Authors focusing on analyses of the impact of fiscal policy on the growth of particular
23 regions arrive at the conclusion that public investments are having measurable positive effects
24 on the respective regions (e.g. MARTHUR and STEIN, 1980; FÖLSTER and HENREKSON, 2001;
25 AUTERI and COSTANTINI, 2004). Other studies are devoted to the investigation of efficiency
26 issues (for example GUIÁN and CANCELO, 1996; DE LA FLUENTE, 2004). Other authors point
27 to the problem of the insufficient coordination of different public policies and activities, as
28 their goals and effects can be overlapping or even contradictory (e.g. WISHLADE *et al.*, 1996;
29 MARTIN, 2005; SHOUT and JORDAN, 2007). In addition, some other studies have dealt with
30 issues of social justice or equity within the sphere of public finance (e.g. BOYN and POWELL,
31 1995).
32
33
34
35
36
37
38
39
40
41
42
43
44

45 One country where the allocation of public money attracts considerable attention from
46 both politicians and analysts is the UK. However, the main rationale for these studies is
47 mainly the issue of the distribution of public expenditure between England, Wales, Scotland
48 and Northern Ireland in the context of devolution (e.g. SHORT, 1978; HEALD, 1994; HEALD
49 and SHORT, 2002; MIDWINTER, 2004). In Japan, KATAOKA (2005) assessed the regional
50 distribution of public investments between 47 prefectures in the post-war period. Kataoka
51 noticed that periods of high national economic growth are positively correlated with the
52
53
54
55
56
57
58
59
60

1
2
3 concentration of public investment into economically strong regions while in periods of low
4 growth, a more balanced distribution of public capital expenditure has been observed.
5
6
7
8 WILSON and WISE (1986) studied the regional implications of public investment in a
9
10 developing country – Peru – over the period 1968–1983. They showed a high concentration of
11
12 public investment into the rich coastal regions during three subsequent time periods, while a
13
14 shift in favour of the poorer inland regions was observed in the second half of the period
15
16 studied. However, according to these authors, this shift is mainly attributable to the huge
17
18 investments in the mining industries in the inland regions.
19
20
21
22
23
24

25 **3. Sectoral policies and regional policy**

26
27 There have already been voices among experts suggesting that the regional impact of
28
29 vigorously pursued sectoral policies is much more profound than the regional impact of
30
31 regional policy itself (e.g. ROBERT *et al.*, 2001; MARTIN, 2005). Therefore, within this
32
33 context, some authors distinguish regional policy in a “narrow” and “broad” sense, while
34
35 other authors prefer the terms “explicit” and “implicit” regional policy (e.g. ARMSTRONG and
36
37 TAYLOR, 1985; CUADRADO, DE LA DEHESA and PRECEDO, 1993). While it can be agreed that
38
39 regional policy in a “narrow” sense is synonym with explicit regional policy, the difference
40
41 between implicit regional policy and a regional policy in a “broad” sense should be stressed.
42
43 Implicit regional policy encompasses public policies which have been to a certain extent
44
45 “regionalized” (i.e. there has been some sort of adjustments of an overall design of sectoral or
46
47 non-regional policy in question to meet specific regional conditions and needs). Regional
48
49 policy in a “broad” sense, on the other hand, comprises of all public policies or actions
50
51 executed by the public sector which have important regional impacts and this importance is to
52
53 some extent recognized (e.g. agricultural policy, transport policy, energy policy, competition
54
55 policy, science and technology policy). Despite the fact that these policies often lack an
56
57
58
59
60

1
2
3 explicit definition of regional goals, they are clearly having a specific impact on different
4 regions (e.g. CUADRADO, DE LA DEHESA and PRECEDO, 1993; EUROPEAN COMMISSION, 1998,
5 2004; HILL and LOWE, 2007). Examples of public policies that reflect at least some specific
6 regional characteristics or which react to specific regional conditions are the policy aimed at
7 attracting large investors to the Czech Republic (UHLÍŘ, 2004) or the R&D policy in Germany
8 (see KOSCHATZKY, 2001). Considerable attention has been paid to the regional impact of
9 sectoral policies and analogous policies at EU level in studies undertaken within the ESPON
10 programme (e.g. THE ESPON MONITORING COMMITTEE 2005).

11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

BLAŽEK (2005a) argues that one key component of fiscal policy that has an enormous regional impact is the way the decentralized public administration bodies (municipalities and regions) are financed. For example, in 2007, within the state budget of the Czech Republic only CZK 1.5 bln was allocated to explicit regional policy (which represents only 0,06 % of Czech GDP), while in the same year the state distributed more than CZK 160 bln to municipalities and regions via a strictly egalitarian tax-sharing formula (this volume amounts 7,7% of Czech GDP). It is clear that the principles upon which the applied model of financing local and regional government in particular countries rests are of tremendous importance and consequently, due to the vast amount of money concerned, the system of local government financing has a much more profound regional impact than official “explicit” regional policy.

Moreover, important regional impacts can be attributable even to non-spending policies, for example to an anti-monopoly policy. WISHLADE *et al.*, (1996) consider the spatial impact of non-spending policies as “blind spots” of regional analyses.

4. The budgetary scheme of the Czech Republic

1
2
3 The budgetary scheme of the Czech Republic consists of two prime components – public
4 budgets and extra-budgetary funds created for specific investment purposes such as transport
5 infrastructure, and expenditure on environmental projects. (see Figure 1).
6
7
8
9

10
11
12 **Figure 1: Simplified budgetary scheme of the Czech Republic**
13

14
15 Source: modified on the basis of PEKOVÁ (2002), p. 79

16
17 (about here).
18
19
20

21 Nevertheless, due to the focus of this paper on the identification of spatial patterns in the
22 allocation of public capital expenditure, the analysis was limited to a regional analysis (at the
23 level of the NUTS 3 and NUTS 4 regions) of capital investment allocated from central
24 sources, i.e. from the state budget and from state extra-budgetary funds. The Czech state
25 budget operates with the dominant part of public finance assigned to public budgets, but as
26 Table 1 illustrates, the share of state budget allocated to capital expenditure is rather small.
27 This fact can be partly explained by the key role of state extra-budgetary funds in the case of
28 such expenditure (see Table 2), as they are designed to function as a vehicle allowing the
29 implementation of multi-annual projects, while the state budget in principle provides the
30 financial framework for one year only. In addition, a noteworthy volume of public capital
31 expenditure flows through decentralized public budgets, and especially via municipal budgets
32 (on average in 2000–2005 the capital expenditure of decentralized public budgets accounted
33 for CZK 74.2 bln per year, which represents 28.5 % of the total decentralized public budgets
34 on average per year). Nonetheless, in line with our research focus the analysis presented
35 below concentrates only on the capital expenditure allocated from the central level.
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58

59 **Table 1: Expenditure of the Czech state budget in 1995–2005 (current prices, in billion**
60 **CZK, in %)**

1
2
3 Source: Statistical Yearbook of the Czech Republic 1997, 1999, 2001, 2002, 2004, 2006.
4

5 Note: In December 2007, the exchange rate was approx. 1 EUR = 27 CZK.
6

7 (about here)
8

9
10 ***Table 2: Expenditure from selected state extra-budgetary funds in 2000–2005 (current***
11 ***prices, in billion CZK)***
12

13
14 Source: Statistical Yearbook of the Czech Republic 2000–2006.
15

16 (about here)
17
18
19

20 **5. Data and Methodology**
21

22
23 The prime source for this regional analysis of the capital expenditure of the state budget of the
24 Czech Republic is the ISPROFIN (Information System of Programming Funding from the
25 State Budget) database, which comprises data regarding investment spending from the state
26 budget, in our case for the years 1995–2005. ISPROFIN is managed by the Ministry of
27 Finance of the Czech Republic and has been operational since 1995.ⁱⁱ The structure of the
28 entries into ISPROFIN allows a regional break-down of capital expenditure at the level of the
29 NUTS 3 and 4 regions. However, several methodological problems arose during the analysis
30 of this data, and consequently a number of projects and programmes (and the corresponding
31 financial volume of capital expenditure) had to be excluded from the analysis. The following
32 criteria for omitting particular projects or programmes were applied: i) the regional allocation
33 of the investment incentives was not given or investment was implemented abroad; ii) the
34 project or programme was predominately for current expenditure; iii) the project was of an
35 “extraordinary” nature (i.e. expenditure devoted to the recovery of the territories affected by
36 the 1997 and 2002 floods or devoted to the restitution to former owners of private property
37 that was nationalized during the communist period).
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

1
2
3 An overview of the financial amounts included (and excluded) from the regional analysis of
4 public capital expenditure is given in Table 3. Another methodological challenge was
5 represented by projects which benefited the whole country, but in ISPROFIN were assigned
6 to one region only. This was especially the case for the purchase of jet fighter aircraft which
7 were also excluded from the analysis.
8
9

10
11
12
13
14
15
16
17 This problem relates to the fundamental methodological question of which principle
18 investment expenditure should be attributed to a certain region. For instance, SHORT (1978)
19 has explicitly distinguished two types of regional expenditure: “regionally relevant” and “total
20 expenditure” allocated to the region. According to Short, “regionally relevant” expenditure
21 benefits only the region in which the particular public money was allocated. Alternatively,
22 WISHLADE *et al.*, (1996) and also CAMINAL (2004) differentiated between the “flow” and
23 “benefit” approaches to the analysis of the regional distribution of public expenditure. The
24 “flow” approach assigns expenditure to regions regardless of whether or not the region in
25 question is an “end user”, while the “benefit” approach concentrates on the end users of the
26 public money spent, or more precisely on the final beneficiary regions. Consequently, in our
27 analysis, the flow approach has been applied as it would be impossible to judge each of the
28 approximately 40,000 investment projects of ISPROFIN included in the analysis on the basis
29 of the benefit approach.
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50

51 **Table 3: Financial resources of ISPROFIN 1995–2005 (in billion CZK, current prices, in**
52 **%)**

53
54
55 Source: ISPROFIN (Internal material of the Ministry of Finance of the Czech Republic), authors` calculations.

56
57 (about here)
58
59
60

1
2
3 In addition to ISPROFIN, which covers capital expenditure financed from the state budget,
4
5 the two most relevant extra-budgetary funds were incorporated into our analysis. These two
6
7 funds are: The State Fund for Transport Infrastructure (SFTI) and the State Environmental
8
9 Fund (SEF). The data on the individual projects supported by these funds were obtained from
10
11 the responsible institutions. In the case of the State Fund for Transport Infrastructure, the
12
13 capital expenditure for 2001–2005 has been analysed at the level of NUTS 3 regions.
14
15 Investment projects to a total value of CZK 222.3 billion were included in the analysis. The
16
17 State Environmental Fund is represented by the data concerning expenditure during the years
18
19 1999–2005, which amounted to CZK 13 billion. Therefore, this analysis covers capital
20
21 expenditure from the state budget and from two extra-budgetary funds to a total value of CZK
22
23 617 bln. The analysis was structured into six parts, covering the most relevant thematic
24
25 spheres of public capital expenditure (see Table 4).
26
27
28
29
30
31
32
33

34 ***Table 4: Overview of the analyzed data for the period 1995-2005 (in billion CZK, current***
35 ***prices)***
36
37

38 Source: ISPROFIN (Internal material of the Ministry of Finance of the Czech Republic), Internal materials of
39 the State Fund for Transport Infrastructure (SFTI) and the State Environmental Fund (SEF), authors`
40
41 calculations.
42
43

44 (about here)
45
46
47
48

49 **6. Results**

50
51 In this section, the main results of the regional analysis of capital expenditure committed
52
53 within the sectoral governmental policies in the Czech Republic will be presented (Table 4
54
55 provides an overview of the financial volumes analysed). First, attention is paid to an analysis
56
57 of the distribution of all capital expenditure, that is an analysis of investment projects financed
58
59 from the state budget and from relevant state extra-budgetary funds. In view of the fact that
60

1
2
3 the overall nature of regional differentiation of investment allocation is considerably
4 influenced by investments in the transport infrastructure, in the next stage such investments
5 are excluded from the analysis and analysed separately. Next, the regional allocation of
6 investments in other relevant sectors is considered, namely the territorial allocation of
7 investments within explicit regional policy, investments in universities and the R&D sector,
8 and finally investment assigned to the environmental sector.
9
10
11
12
13
14
15
16
17
18
19

20 **6.1. Regional analysis of total capital expenditure**

21
22 The regional analysis of total capital expenditure financed from the central level (i.e. from the
23 state budget and from both state extra-budgetary funds) in the period 1995–2005, includes
24 nearly CZK 617 billion after the data has been ‘cleaned’ by the above described procedure.
25
26 The nature of the capital expenditure determined that such invested funds were used primarily
27 for development activities, and allocation of such investments has an undoubted dynamic
28 effect on the relevant regions (e.g. SHORT, 1981; AUTERI and COSTANTINI, 2004).
29
30
31
32
33
34
35
36
37
38

39 The overall spatial pattern of the regional distribution of the analysed funds can be considered
40 as significantly unbalanced. In the period studied, over one quarter of the analysed
41 investments (which in absolute terms represents approximately CZK 168 billion) were
42 allocated from the national level into the capital city of Prague, socio-economically the most
43 advanced region of the Czech Republic (for regional GDP per capita see Figure 2). The
44 dominance of Prague is also proved by relative indicators, i.e. investments per inhabitant
45 (approximately CZK 142 thousand per inhabitant, which is 237% of the average for the Czech
46 Republic - see Table 5). With respect to economic performance indicators, i.e. after putting
47 capital expenditure in relation to the regional GDP level, it was 116% of the average
48 allocation of the Czech Republic and in relation to the economic aggregate it was 123% of the
49
50
51
52
53
54
55
56
57
58
59
60

1
2
3 national average. The term economic aggregate was defined by HAMPL (2005) as the product
4
5 of the number of jobs (the number of jobs is determined as the number of economically active
6
7 persons after deducting the unemployed and adding the commuting balance calculated on the
8
9 basis of the 2001 Census) and the average wage in the region in question. The Plzeňský and
10
11 Olomoucký regions achieved an even higher investment allocation than Prague with respect
12
13 to GDP (136%, resp. 137% - see Table 5), and the same order applies when the allocated
14
15 investment volume is related to the economic aggregate.
16
17
18
19
20
21

22 ***Table 5: Capital expenditure per capita and per regional GDP (1995–2005, in %)***
23

24 Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech Republic 2001,
25 authors` calculations.
26
27

28 (about here)
29
30
31
32

33 ***6.2. Regional analysis of total capital expenditure after exclusion of transport investment***
34

35 Since the extraordinary volume of investment devoted to transport infrastructure (CZK 222
36
37 billion from the state budget and from the State Fund for Transport Infrastructure – see Table
38
39 4) which undoubtedly influences the overall picture of the regional allocation of investment,
40
41 such expenditure was excluded from the analysis in the following stage. The remaining
42
43 investment projects thus represent approximately CZK 395 billion for the period of 1995–
44
45 2005 again.
46
47
48
49
50
51

52 After the exclusion of projects in the transport infrastructure sector, the position of Prague is
53
54 even higher (see Table 5). In absolute terms, its share of public capital expenditure in the
55
56 Czech Republic actually increased to 37.5%, while in per capita terms the investment
57
58 allocation to Prague was 326% of the average value for the Czech Republic. No other NUTS
59
60 3 region received an above-average allocation per inhabitant. Even when the allocated

1
2
3 investment projects are related to the regional GDP, the Prague region is still above the
4 national average (see Table 5). Investments in Prague were directed particularly to the state
5 administration (approximately CZK 55 billion), state defence (CZK 24 billion), health service
6 (CZK 18.1 billion), infrastructure development (CZK 18.9 billion) as well as public city
7 transport (4.8 billion CZK), R&D (CZK 6.9 billion) and education (CZK 8.7 billion).
8
9

10
11
12
13
14
15
16
17 As all data except for that on transport infrastructure projects was territorially identified up to
18 NUTS 4 level, a detailed analysis of the regional distribution of capital expenditure, after
19 exclusion of transport expenditure, could be carried out on the NUTS 4 level regions. At this
20 hierarchical level, Prague dominates absolutely. The district of Kutná Hora achieved the
21 second highest allocation per inhabitant and the highest allocation per economic aggregate,
22 but this was thanks to extraordinary investments in the military air force base in Čáslav. The
23 district of Brno–město (after Prague the second most important economic centre of the Czech
24 Republic) is in third position with 162% of the average allocation per inhabitant. Brno also
25 achieved the second highest share of 6%. The districts of Ostrava–město (2.2%), Olomouc
26 (2.6%) and Plzeň–město (2.2%) also received significant shares. Other districts received only
27 minor allocations.
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45

46 Where capital expenditure was considered per inhabitant, above-average investments
47 compared to the average for the Czech Republic were allocated to only 11 out of 77 districts,
48 and 22 districts did not even achieve 50%. The regions receiving significantly below-average
49 investment funds per inhabitant include the majority of districts in North-Western Bohemia
50 and Northern Moravia (which, however, are mostly among the regions supported within
51 Czech regional policy – see Figure 2), the internal periphery, as well as a large area of
52
53
54
55
56
57
58
59
60

1
2
3 Southern, Western, Northern and Eastern Bohemia and the Czech-Slovak borderland (see
4
5 Figure 3).
6
7
8
9

10 ***Figure 2: Assisted regions supported within Czech explicit regional policy***

11
12 Source: Ministry for Regional Development.

13
14 (about here)
15
16
17
18

19 ***Figure 3: Capital expenditure per capita after exclusion of transport infrastructure in***

20
21 ***NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %).***

22
23 Source: ISPROFIN, SEF, Statistical Yearbook of the Czech Republic 2001, authors` calculations.

24
25
26 (about here)
27

28 Due to the unavailability of GDP data for NUTS 4 regions and the limited reliability of this
29 indicator on the NUTS 3 regions, GDP was replaced by an economic aggregate. At regional
30 level, this indicator achieves a very high correlation with regional GDP (0.998). After putting
31 the allocated investment funds in relation to the economic aggregate (see Figure 4), Prague
32 achieved 169% of the average for the Czech Republic (the highest allocations went to the
33 districts of Kutná Hora - 257% and Prostějov - 170%, in both cases thanks to extraordinary
34 investments in the defence sector). Highly uneven distribution of this expenditure illustrates
35 well the fact that above-average values were achieved by only 13 districts, among which was
36 also the second largest city (district Brno-město - 119 %).
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51

52 ***Figure 4: Capital expenditure per economic aggregate after exclusion of transport***

53
54 ***infrastructure investments in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %).***

55
56 Source: ISPROFIN, SEF, Statistical Yearbook of the Czech Republic 2001, HAMPL (2005), authors` calculations.

57
58 (about here)
59
60

6.3. *Capital expenditure in the transport sector*

The extraordinary importance of investment devoted to the transport infrastructure is given by their very high volume (CZK 222 billion), which represents approximately 36% of the volume of the investment observed in this study. In addition, it is obvious that the regional formula of transport constructions, often linear in nature, may significantly differ from the spatial formula of other investment projects. For this reason, the transport sector was chosen for a separate regional analysis (i.e. investment in construction of motorways, expressways, railway corridors, and the underground in Prague). Despite a number of methodological constraints, it was possible to unite the two most important sources of funds for this sector: the state budget (i.e. ISPROFIN) and the State Fund for Transport Infrastructure. The total analysed investment volume of 1995–2005 exceeds CZK 222.3 billion (ISPROFIN – CZK 96.7 billion, the State Fund for Transport Infrastructure – CZK 125.5 billion), and the data are available only for NUTS 3 regions.

Figure 5 illustrates the considerably above-average allocation of investment in transport in Western Bohemia, which corresponds to the hypothesis of allocation of investment along a traditional west-east gradient in the level of socio-economic development. In transport investment, this gradient is raised by the effort to ensure transport connections for the Czech Republic or its capital of Prague with nearby economic centres in Germany (Munich, Frankfurt, Berlin). Although the area of Northern Moravia is a structurally affected region, as is North-Western Bohemia, transport investment has flowed more to Northern Bohemia in recent years, because the transport connection with Poland was of less priority than connections to Germany or Western Europe.

1
2
3 **Figure 5: Transport infrastructure investment per capita in NUTS 3 regions, 1995–2005,**
4
5 **Czech Rep. = 100 % (in %)**
6

7
8 Source: ISPROFIN, SFTI, Statistical Yearbook of the Czech Republic 2001, authors` calculations.
9

10 (about here)
11
12

13
14
15 The spatial formula for the allocation of per capita investment in transport is very similar to
16 the case where transport investment is related to GDP (the correlation coefficient is 0.954). In
17 both indicators the position of Prague is well below national average (78%, resp. 38% of the
18 Czech Republic average). On the contrary, Plzeňský, Olomoucký, Ústecký and Karlovarský
19 regions achieved significantly above-average allocations. However, in evaluating the regional
20 distribution of transport infrastructure investments (and of general investments as well) it is
21 necessary to consider the time aspect in the sense that if a significantly higher amount of
22 funds is granted to a region in a certain time range, it may mean that the necessary
23 infrastructure had not previously been constructed in the region in question and it is being
24 built behind schedule or out of needs arising from the different geopolitical orientation of the
25 Czech Republic after the fall of the Iron Curtain. For example, as early as the communist era,
26 the D1 motorway was completed between Prague and Brno, leading across the Vysočina
27 region, so this region records a significantly below-average allocation, while in the districts of
28 Tachov and Plzeň-jih districts, the D5 connecting Prague and Bavaria was built during the
29 period considered here.
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50

51
52 The regional distribution of capital expenditure after the exclusion of transport infrastructure
53 investments when related to the economic level of the region (GDP) shows that transport
54 investments are what “aid” economically weaker regions to reach above-average values. If
55 transport investments are not considered, Prague is quite clearly the region that gains most
56
57
58
59
60

1
2
3 from redistribution of public investment both in per capita terms and in relation to GDP
4
5 (116 %, or 159 % of the Czech Republic average - see Table 5).
6
7
8
9

10 **6.4. Capital expenditure allocated within explicit regional policy**

11
12 Since one of the aims of this article is to show a significant discrepancy between the regional
13 formula for the allocation of public investment funds within non-regional policies and
14 regional policy, this is presented by Figure 6 which shows investments granted to explicit
15 regional policy from the state budget. Strikingly, the funds allocated within regional policy
16 are spread widely across the whole territory of the Czech Republic. This is in sharp contrast
17 with the very conception of regional policy as a policy which supports only selected regions.
18 This finding cannot be justified by changes of assisted areas over the investigated period as
19 there was considerable stability of both the regional pattern of lagging and leading regions
20 and consequently also of assisted areas delineated for the sake of regional policy (BLAŽEK,
21 2005b). On the other hand, the pattern of investment within regional policy does confirm that
22 a certain priority was given to the assisted areas. Namely, the Moravian districts, especially
23 the southern and, to some extent, northern ones ranked among the largest recipients of such
24 investments (together with North-Western Bohemia they rank among the regions supported
25 within Czech explicit regional policy, as does Northern Bohemia to some degree).
26 Nevertheless, it is necessary to mention a paradox as a statistically highly significant positive
27 relation of regional policy investment to regional GDP and to the economic aggregate was
28 demonstrated for NUTS 3 regions (in both cases excluding Prague - see Table 6a). The same
29 applies also to the level of NUTS 4 regions (see Table 6b) where a statistically significant
30 positive relation was found between the regional policy capital expenditure and the level of
31 economic development measured by the economic aggregate as a proxy for regional GDP. At
32 the same time, a larger part of Moravia ranks, with other regions supported within explicit
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

1
2
3 regional policy, as an area significantly underfinanced with respect to the total investment
4 from the state budget after the exclusion of transport. In simple terms, districts supported
5 within the explicit regional policy in the Czech Republic received only a very limited volume
6 of investment from the national level (after the exclusion of transport constructions) (compare
7 Figures 2, 3 and 4). On the other hand, support within Czech regional policy was significantly
8 concentrated into these regions (see Figure 6). However, a huge difference in the financial
9 sums invested has to be stressed again: CZK 7.2 billion for regional policy versus the total
10 volume of the analysed funds amounting to CZK 617 billion. Nevertheless, although the
11 volume of investments for regional policy at the national level is nearly negligible, its
12 importance is significantly higher for the supported regions.
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28

29 ***Figure 6: Capital expenditure per capita from the state budget devoted to explicit regional***
30 ***policy in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %).***
31
32

33 Source: ISPROFIN, Statistical Yearbook of the Czech Republic 2001, authors` calculations.
34

35 (about here)
36
37
38
39
40

41 ***Table 6a: Correlation of selected indicators for NUTS 3 regions (n=13 – Prague excluded)***
42

43 Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech Republic 2001,
44 HAMPL (2005), authors` calculations.
45
46

47 ***Table 6b: Correlation of selected indicators for NUTS 4 regions (n=76 – Prague excluded)***
48

49 Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech Republic 2001,
50 HAMPL (2005), authors` calculations.
51
52

53 (about here)
54
55
56

57 ***6.5. Capital expenditure for higher education, R&D and the environmental sector***

58 Within the regional analysis of capital expenditure from the state budget of the Czech
59 Republic, sectoral analyses were also carried out. As an example, Figure 7 shows investment
60

1
2
3 from the state budget in the infrastructure of universities and colleges and other R&D
4
5 institutions amounting to approximately CZK 25 billion. The expected regional distribution of
6
7 such expenditure into economically more developed regions (Prague, Brno) and to regions
8
9 where a public college is located, or to regions with headquarters of important research
10
11 institutes (the Prague hinterland) was demonstrated (similar regional pattern of public R&D
12
13 expenditure was shown by WISHLADE *et al.* 1996 or THE ESPON MONITORING COMMITTEE
14
15 2005). Nevertheless, it is necessary to point out that it is not only capital expenditure from the
16
17 central level that is devoted to this sector. For example, it was not possible to obtain data on
18
19 the regional allocation of financial support for R&D projects allocated by the Grant Agency
20
21 of the Czech Republic. In addition, it is necessary to take into account a frequent
22
23 methodological problem, when some analysed data are allocated according to the
24
25 headquarters of the institution in question, although such funds may then be invested in
26
27 branches of the institution in a different region. It is thus probable that in fact investment in
28
29 higher education and R&D is less concentrated than the data analysed shows.
30
31
32
33
34
35
36
37
38

39 ***Figure 7: Capital expenditure per capita of the state budget devoted to universities and for***
40 ***R&D institutions in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %)***

41
42
43 Source: ISPROFIN, Statistical Yearbook of the Czech Republic 2001, authors' calculations.

44
45 (about here)
46
47
48
49

50
51 Figure 8 shows investment in the environment sector amounting to CZK 25.6 billion
52
53 allocated both from the state budget and the State Environmental Fund. Although no clear
54
55 relation between the distribution of funds and environmental quality has been shown, we may
56
57 confirm to some extent that investment was allocated to regions in which it is necessary to
58
59 solve a specific problem with respect to the environment (e.g. support of mining reduction,
60
revitalising the river system, pond reconstructions).

1
2
3
4
5
6 A surprisingly high allocation of investment to border districts in South-Western Bohemia
7
8 relates to investment in the territorially largest national park in the Czech Republic (The
9
10 Šumava National Park). Figure 8 provides, however, a surprising finding, that investment
11
12 projects in the environment sector are not greatly concentrated in the structurally handicapped
13
14 regions in Northern Bohemia and in Northern Moravia where the environment is seriously
15
16 damaged. There is one exception with high investment - the Česká Lípa district - where the
17
18 running down of the uranium industry and subsequent cultivation of the area are jointly in
19
20 progress.
21
22
23
24
25
26

27 ***Figure 8: Environmentally related capital expenditure per capita of the state budget in***
28 ***1995–2005 and of the State Environmental Fund in 1999–2005 in NUTS 4 regions, Czech***
29 ***Rep. =100 % (in %)***
30
31
32

33 Source: ISPROFIN, SEF, Statistical Yearbook of the Czech Republic 2001, authors' calculations.

34
35
36 (about here)
37
38

39 ***6.6. Relation of capital expenditures to selected socio-economic variables***

40
41
42

43 On the basis of correlation coefficients for selected indicators for NUTS 3 regions (Table 6a)
44
45 we can demonstrate a statistically significant relation between all regional allocations of
46
47 investment via all analysed categories of investment (i.e. total investment, total investment
48
49 after exclusion of transport investment, transport investment, investment into R&D and
50
51 universities and regional policy investment, and their economic performance expressed by the
52
53 GDP and the economic aggregate. The same finding counts for correlation coefficients for
54
55 NUTS 4 regions (Table 6b), however, due to data limitations only the correlation between 3
56
57 investment categories and the economic aggregate could be calculated. It is important to stress
58
59 again that with respect to the declared objectives of Czech regional policy, the correlation
60

1
2
3 between the share of investment allocated within explicit regional policy and economic
4 performance should be negative. However, on both NUTS 3 and NUTS 4 level regions
5
6 positive and even statistically significant values were obtained indicating that even allocation
7
8 of investment within regional policy is not in line with its own strategic objective.
9
10
11

12
13 The identification and detailed assessment of factors behind these observed patterns goes
14 beyond the focus of this paper, however at least a brief discussion should be included. In
15 countries like the Czech Republic which are lacking instruments for the systematic evaluation
16 of the effectiveness and efficiency of planned public investment, a relatively important role
17 can be assumed for subjective factors. The decision making process on public investment
18 committed from the central level basically proceeds at two levels. Firstly, on the basis of a
19 proposal of the Ministry of Finance, the Government and Parliament decide about financial
20 allocations to particular sectors that come under the responsibility of particular ministries.
21 Secondly, there is a process of selection of priorities by a particular ministry. In this case,
22 three main factors influencing the decision making process on public investments might be
23 identified: i) the adopted strategy for a specific sector (inevitably even these strategic
24 documents can to some extent reflect subjective factors), ii) the interests of (esp. high-
25 ranking) public servants and iii) the interests of politicians. On the basis of our experience of
26 more than 10 years of contractual cooperation by one of the authors with one central
27 administration body we can draw two preliminary conclusions. First, the relevance of these
28 three types of factors differs widely among different sectoral policies. Second, in some cases
29 each of the three above mentioned factors can be decisive. This, therefore, makes a clear case
30 for the introduction of some instruments (including TIA) that would be able to “objectivise”
31 the need for public investment.
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

7. Conclusions and policy implications

The article aims to contribute to the debate on the regional dimension of sectoral (non-regional) governmental policies and to empirically demonstrate the huge discrepancy between both the volume and regional pattern of public capital expenditure committed within the national sectoral policies on the one hand and the official regional policy on the other. The performed analyses focused “only” on the public capital expenditures allocated by the Government of the Czech Republic, but it can be claimed that public capital investments have the most important implications for the development of particular regions (SHORT, 1981; YAMANO and OHKAWARA, 2000). Obviously, the financial volume of the total public capital expenditure is incomparably higher than the financial volume allocated to explicit regional policy.

The regional analyses performed were based on the dataset of public capital expenditure in the Czech Republic covering the years 1995–2005 and demonstrated uneven regional distribution of these investments in favour of the most economically developed region of the Czech Republic – the capital city of Prague. Such a regional pattern for the distribution of public investment supports the hypothesis that there exists a contradiction between the regional impact of sectoral policies on the one hand, and the goals of explicit regional policy on the other. The discrepancy between these two is particularly striking as assisted regions delineated for the sake of national regional policy were to a large extent left aside by decisions regarding the allocation of public capital expenditure (with the exception of expenditure on transport infrastructure). Moreover, a surprising pattern was identified even in the case of investment committed within explicit regional policy (Fig. 6) which is not coinciding well with the map of assisted areas (Fig. 2). Clearly, the allocation of regional policy investments is not respecting fully the objectives of regional policy itself.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

Consequently, there is a clear conflict between the goals of explicit regional policy aiming at the support of less well-off regions and mostly unintended regional impacts of much more vigorous non-regional governmental policies generally supporting the most developed regions. These findings are in line with research performed by e.g. WILSON and WISE (1986) but in contrast with results of YAMANO and OHKAWARA (2000).

However, it is necessary to stress that from the point of view of the entire expenditure side of the governmental policies comprising both capital and current expenditure, the region of Prague is very likely the most important net payer into the system of public finance due to its buoyant tax base and to its relatively low share of persons receiving social benefits (see OUŘEDNÍČEK and NOVÁK, 2006). Nevertheless, it is clear that the uneven distribution of public capital expenditure, generally favouring more developed regions, is one of the most important mechanisms of regional differentiation and is, moreover, cumulative in nature.

The expectation of a replication of the traditional East-West gradient in the level of socio-economic development by the regional structure of total capital expenditure has not been experienced. However, the evidence supporting this expectation can be observed in the case of the capital expenditure allocated to transport infrastructure. The greater support of transport infrastructure projects in the Western part of the Czech Republic is a reflection of the priority assigned to connecting the Czech Republic to Western European structures.

Key implications deriving from the conducted regional analysis relate in particular to the necessity of developing a sound methodology for the territorial impact assessment of public policies and programmes. In other words, it is essential to develop a procedure evaluating not only the regional impact of incentives carried out within explicit regional policy (which is

1
2
3 already becoming common practice in the most developed countries) but also the impact of
4 public interventions which do not explicitly incorporate a regional dimension but where
5 implementation might have a significant regional impact. Such an evaluative instrument is
6
7
8 essential for tackling of regional development issues and problems more effectively by
9
10 achieving synergies and eliminating contradictions between different policies (SCHÄFFER,
11
12 2005; CEC, 2006a, 2006b). Nevertheless, this approach is a real challenge due to the fact that
13
14 public policies in most advanced countries are traditionally being implemented via sectorally
15
16 structured public administration at central governmental level while the relevance of sectoral
17
18 policies for development of particular regions has been clearly underestimated (ROBERT *et al.*,
19
20 2001; MACEŠKOVÁ, 2007).
21
22
23
24
25
26
27
28

29 Despite the effort that has been put into developing TIA methodology, no comprehensive and
30
31 satisfactory tool for regional impact assessment has yet been developed. Therefore, as also
32
33 documented by our empirical results, which showed both an uneven spatial pattern of the
34
35 allocation of public capital expenditure and a huge mismatch between the regional pattern of
36
37 this expenditure and the assisted regions, the development of a suitable instrument for
38
39 territorial/regional impact assessment and its application at least to the most relevant sectoral
40
41 policies remains a critical challenge for both researchers and decision-makers.
42
43
44
45
46
47

48 ⁱ Such fine-tuning can take many different forms, for example differentiation of the form and
49
50 the rate of public support or the involvement of regional self-government or other regional
51
52 bodies in decision-making procedures, although in practice such an approach is rather rarely
53
54 applied.
55
56

57
58 ⁱⁱ Except for the programmes set by a special act such as state support to the national cultural
59
60 heritage or agriculture.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

For Peer Review Only

Regional analysis of public capital expenditure: to which regions is public capital expenditure channelled – to “rich” or to “poor” ones?

Abstract

The paper aims to contribute to the debate on the regional dimension of sectoral (i.e. non-regional) policies and to empirically demonstrate the huge discrepancy between both the volume and the regional pattern of sectoral public capital expenditure, policies on the one hand, and official regional policy on the other. The analyses were based on a unique database of public investment in the Czech Republic covering the years 1995–2005. Their results show significant conflicts in policy objectives and thus represent a clear argument in favour of pursuing territorial impact assessment (TIA) of sectoral policies.

Deleted: committed within sectoral

Deleted: policies

Deleted: 11

Deleted: period (

Deleted:)

Deleted: and t

Deleted: proved

Key words: regional impact of non-regional policies, sectoral policies, territorial impact assessment, regional policy, public investments, Czech Republic

JEL classifications: H5, E61, R 11, R 58

Acknowledgements

This paper received financial support from Research Programme No. MSM 0021620831 sponsored by the Czech Ministry of Education, Youth and Sport. The authors would like to thank to two anonymous referees for their helpful comments.

Deleted: was elaborated with

Deleted: o

Deleted: ¶

1. Introduction

The aim of the paper is to contribute to the debate on the regional dimension and the regional impact of sectral public capital expenditure, policies. This debate started decades ago (e.g. SHORT, 1978; BENNETT, 1980; MARTHUR and STEIN, 1980; MOLLE and CAPPELLIN,

Deleted: committed within sectoral

1
2 1988) but recently received a significant impetus in the form of a discussion on the regional
3
4 impact of sectoral policies and the possibilities of their “regionalization” (e.g. DG RESEARCH,
5
6 1991; MARTIN, 1999; ROBERT *et al.*, 2001; MOLLE, 2007). The “regionalization” of sectoral
7
8 policies can be understood as the fine-tuning of sectoral public expenditure according to the
9
10 needs and circumstances of specific regions.¹ One of the important results of this discussion
11
12 was the gradual development of the methodology of the territorial impact assessment of large
13
14 projects and later, also of programmes and policies – SCHINDEGGER and TATZBERGER, 2003;
15
16 CAMAGNI, 2006). The increasing attention being paid to the regional dimension of public
17
18 expenditure policies stemmed originally from the effort to learn how to improve or - more
19
20 precisely - how to ensure the coordination of the territorial impact of the EU policy of
21
22 economic and social cohesion (ESC) and of other European policies (e.g. CEC, 1996; SHOUT
23
24 and JORDAN, 2007). Moreover, at the same time, there was a significant research endeavour to
25
26 discover to what extent the regional impact of ESC policy has been in compliance with the
27
28 spatial effects of numerous national public policies of the EU Member States (CEC, 2004).

29
30 Nevertheless, the number of existing analyses of the regional impact of sectoral
31
32 policies is still relatively limited (for exceptions see e.g. HEALD, 1994; AUTERI and
33
34 COSTANTINI, 2004; KATAOKA, 2005; MACEŠKOVÁ, 2007), mostly due to the severe data
35
36 limitations in most countries. Therefore, the main aim of this article is an attempt to perform
37
38 an analysis of the regional dimension of public capital expenditure in one of the new Member
39
40 States (the Czech Republic) at the level of the NUTS 3 and 4 regions. This analysis is based
41
42 on a unique data set of capital public expenditure covering investment projects supported
43
44 during 1995–2005.

45
46 The analyses undertaken here are aimed at answering several research questions.
47
48 Firstly, the relation between the level of the socio-economic development of the regions and
49
50 the amount of invested public capital expenditure will be investigated. It is assumed that
51
52
53
54
55
56
57
58
59
60

Deleted: policies

Deleted: in

Deleted: reason for the

Deleted: and

Deleted: on the data available

Deleted: within the 11 year period

1 public investments are highly concentrated in the most socio-economically developed regions.

Deleted: o

2 Such a regional allocation of this type of public funds would be in accordance with the

Deleted: , which is contrary to current public expenditure.

3 principles of a strategic regional policy (for more on strategic regional policy see e.g.

4 GORZELAK, 1992). In other words, given the many deficiencies in the sphere of the technical

5 and other infrastructures inherited from the communist period, it is supposed that public

6 investment was primarily focused on the enhancement of the infrastructure in major cities and

7 namely in Prague to strengthen the gateway effect (DRBOHLAV and SÝKORA, 1997) and to

8 enhance the competitiveness of the national metropolis on the international scene.

9 Moreover, another reason for the anticipated concentration of public investment in

Deleted: to

10 core regions is the assumed the higher efficiency of investment in these regions (e.g.

Deleted: areas

Deleted: rgument of

Deleted: the

11 CAMINAL, 2004; DE LA FLUENTE, 2004). Therefore, a positive correlation between the level of

12 socio-economic development and the amount of public capital invested (relative per capita) is

13 expected. However, it should be stressed that such a regional pattern of public investment

Deleted: nature of

14 contradicts the objectives of the Czech national strategy for regional development and of

Deleted: would be in contradiction to

15 regional policy aiming at decreasing regional disparities and being in compliance with the

16 "insurance" type of regional policy (MRD, 2006; GORZELAK, 1992). As a result, it can be

17 argued that there is an immense policy conflict between goals of explicit regional policy and

18 mostly unintended spatial impacts of much more vigorous non-regional governmental

19 policies. Therefore, our analyses might also serve as empirical support for the importance of

Deleted: ,

Deleted: an

Deleted: ly

Deleted: proved argument

Deleted: essential

Deleted: the

Deleted: on the level of

Deleted: on the level of

Deleted:

Deleted: on the level of

Deleted: foreseen

20 pursuing territorial impact assessment (TIA), both for major public capital projects and for

21 sectoral policies as a whole.

22 Secondly, a replication of the traditional East-West gradient of socio-economic

23 development by the regional structure of capital expenditure is also expected (for more on the

24 East-West gradient, see BLAŽEK and CSANK, 2007).

Obviously, given the fact that public capital expenditure is highly “visible”, the allocation is inevitably subject to challenge in the political arena, and a significant role of subjective and “soft” factors in the regional allocation of this expenditure is envisaged.

Despite the fact that the available data does not allow for a thorough explanation of the obtained result, the potentially most important explanatory factors are identified.

Deleted: data

Deleted: yielded

Deleted: s

Deleted: presented.

Finally, it is believed that a detailed scrutiny of the regional structure of public expenditure significantly helps our understanding of regional development.

The paper is structured as follows. Firstly, the theoretical debate and the most important findings of previous studies are summarized. Next, the data and the methodology are described. Thirdly, the main findings of the empirical analyses of public capital expenditure on the NUTS 3 and NUTS 4 levels are provided and discussed. Finally, conclusions and policy implications are drawn.

Deleted: applied

2. Regional impact of fiscal policy and its sectoral policies

The subject of public finance and fiscal policy is an important and traditional sphere of research for economists (e.g. MUSGRAVE and MUSGRAVE, 1973; ATKINSON and STIGLITZ, 1980), nevertheless, geographers have also been interested in this sphere for several decades (for example BENNET, 1980; HEALD, 1994; BLAŽEK, 1995). While economists often build models of public sector spending and frequently deal with the issue of the efficiency of public sector spending, geographers tend to derive the implications of public finance for regional development (for example BLAŽEK, 1995; PORTEOUS, 1995).

Deleted: various

Obviously, fiscal policy as a whole has a huge regional impact, depending on the design of both the revenue and expenditure sides of the state budget. However, the regional patterns of both revenue and expenditure are unknown in most countries. Generally, it can be expected that a system of progressive taxation reduces revenues in more affluent regions

1
2 while social benefits tend to flow into the less well off regions, representing an important
3
4 mechanism for interregional redistribution (PRUDHOMME, 1993; WISHLADE *et al.*, 1996). The
5
6 regional redistribution of financial resources via fiscal policy is one of the important factors
7
8 contributing to the economic growth of the respective regions (LEFEBER, 1964; GUIŚÁN and
9
10 CANCELO, 1996) and helps the social stabilization and internal cohesion of the country in
11
12 question (DE LA FLUENTE, 2004). Nevertheless, in the case of the regional allocation of capital
13
14 expenditure, there is even less certainty about the actual regional pattern of this expenditure
15
16 than in the case of current expenditure.

17
18 Authors focusing on analyses of the impact of fiscal policy on the growth of particular
19
20 regions arrive at the conclusion that public investments are having measurable positive effects
21
22 on the respective regions (e.g. MARTHUR and STEIN, 1980; FÖLSTER and HENREKSON, 2001;
23
24 AUTERI and COSTANTINI, 2004). Other studies are devoted to the investigation of efficiency
25
26 issues (for example GUIŚÁN and CANCELO, 1996; DE LA FLUENTE, 2004). Other authors point
27
28 to the problem of the insufficient coordination of different public policies and activities, as
29
30 their goals and effects can be overlapping or even contradictory (e.g. WISHLADE *et al.*, 1996;
31
32 MARTIN, 2005; SHOUT and JORDAN, 2007). In addition, some other studies have dealt with
33
34 issues of social justice or equity within the sphere of public finance (e.g. BOYN and POWELL,
35
36 1995).

37
38 One country where the allocation of public money attracts considerable attention from
39
40 both politicians and analysts is the UK. However, the main rationale for these studies is
41
42 mainly the issue of the distribution of public expenditure between England, Wales, Scotland
43
44 and Northern Ireland in the context of devolution (e.g. SHORT, 1978; HEALD, 1994; HEALD
45
46 and SHORT, 2002; MIDWINTER, 2004). In Japan, KATAOKA (2005) assessed the regional
47
48 distribution of public investments between 47 prefectures in the post-war period. Kataoka
49
50 noticed that periods of high national economic growth are positively correlated with the
51
52
53
54
55
56
57
58
59
60

Deleted: The a

Deleted: ed

Deleted: d

Deleted: experts

1
2 concentration of public investment into economically strong regions while in periods of low
3 growth, a more balanced distribution of public capital expenditure has been observed.

Deleted: was

4
5
6 WILSON and WISE (1986) studied the regional implications of public investment in a
7
8 developing country – Peru – over the period 1968–1983. They showed a high concentration of
9
10 public investment into the rich coastal regions during three subsequent time periods, while a
11
12 shift in favour of the poorer inland regions was observed in the second half of the period
13
14 studied. However, according to these authors, this shift is mainly attributable to the huge
15
16 investments in the mining industries in the inland regions.

17 18 19 20 3. Sectoral policies and regional policy

21
22 There have already been voices among experts suggesting that the regional impact of
23
24 vigorously pursued sectoral policies is much more profound than the regional impact of
25
26 regional policy itself (e.g. ROBERT *et al.*, 2001; MARTIN, 2005). Therefore, within this
27
28 context, some authors distinguish regional policy in a “narrow” and “broad” sense, while
29
30 other authors prefer the terms “explicit” and “implicit” regional policy (e.g. ARMSTRONG and
31
32 TAYLOR, 1985; CUADRADO, DE LA DEHESA and PRECEDO, 1993). While it can be agreed that
33
34 regional policy in a “narrow” sense is synonym with explicit regional policy, the difference
35
36 between implicit regional policy and a regional policy in a “broad” sense should be stressed.

Deleted: with

Deleted: being

Deleted: for

37
38 Implicit regional policy encompasses public policies which have been to a certain extent
39
40 “regionalized” (i.e. there has been some sort of adjustments of an overall design of sectoral or
41
42 non-regional policy in question to meet specific regional conditions and needs). Regional
43
44 policy in a “broad” sense, on the other hand, comprises of all public policies or actions

Deleted:

45
46 executed by the public sector which have important regional impacts and this importance is to
47
48 some extent recognized (e.g. agricultural policy, transport policy, energy policy, competition
49
50 policy, science and technology policy). Despite the fact that these policies often lack an

Deleted: committed within

Deleted: do

Deleted: at least

Deleted: a certain

1
2 explicit definition of regional goals, they are clearly having a specific impact on different
3 regions (e.g. CUADRADO, DE LA DEHESA and PRECEDO, 1993; EUROPEAN COMMISSION, 1998,
4 2004; HILL and LOWE, 2007). Examples of public policies that reflect at least some specific
5 regional characteristics or which react to specific regional conditions are the policy aimed at
6 attracting large investors to the Czech Republic (UHLÍŘ, 2004) or the R&D policy in Germany
7 (see KOSCHATZKY, 2001). Considerable attention has been paid to the regional impact of
8 sectoral policies and analogous policies at EU level in studies undertaken within the ESPON
9 programme (e.g. THE ESPON MONITORING COMMITTEE 2005).

Deleted: the

Deleted: the

Deleted: performed

17
18 BLAŽEK (2005a) argues that one key component of fiscal policy that has an enormous
19 regional impact is the way the decentralized public administration bodies (municipalities and
20 regions) are financed. For example, in 2007, within the state budget of the Czech Republic
21 only CZK 1.5 bln was allocated to explicit regional policy (which represents only 0,06 % of
22 Czech GDP), while in the same year the state distributed more than CZK 160 bln to
23 municipalities and regions via a strictly egalitarian tax-sharing formula (this volume amounts
24 7,7% of Czech GDP). It is clear that the principles upon which the applied model of financing
25 local and regional government in particular countries rests are of tremendous importance and
26 consequently, due to the vast amount of money concerned, the system of local government
27 financing has a much more profound regional impact than official "explicit" regional policy.

Deleted: approx.

Deleted: the

Deleted: of the Czech Republic

30
31 Moreover, important regional impacts can be attributable even to non-spending
32 policies, for example to an anti-monopoly policy. WISHLADE *et al.*, (1996) consider the spatial
33 impact of non-spending policies as "blind spots" of regional analyses.

Deleted: an

Formatted: Indent: First line: 0 pt

46 4. The budgetary scheme of the Czech Republic

The budgetary scheme of the Czech Republic consists of two prime components – public budgets and extra-budgetary funds created for specific investment purposes such as transport infrastructure, and expenditure on environmental projects, (see Figure 1).

Deleted: environment etc

Figure 1: Simplified budgetary scheme of the Czech Republic

Source: modified on the basis of PEKOVÁ (2002), p. 79

(about here).

Nevertheless, due to the focus of this paper on the identification of spatial patterns in the allocation of public capital expenditure, the analysis was limited to a regional analysis (at the level of the NUTS 3 and NUTS 4 regions) of capital investment allocated from central sources, i.e. from the state budget and from state extra-budgetary funds. The Czech state budget operates with the dominant part of public finance assigned to public budgets, but, as Table 1 illustrates, the share of state budget allocated to capital expenditure is rather small.

Deleted: ,

This fact can be partly explained by the key role of state extra-budgetary funds in the case of such expenditure (see Table 2), as they are designed to function as a vehicle allowing the implementation of multi-annual projects, while the state budget in principle provides the financial framework for one year only. In addition, a noteworthy volume of public capital expenditure flows through decentralized public budgets, and especially via municipal budgets (on average in 2000–2005 the capital expenditure of decentralized public budgets accounted for CZK 74.2 bln per year, which represents 28.5 % of the total decentralized public budgets on average per year). Nonetheless, in line with our research focus the analysis presented below concentrates only on the capital expenditure allocated from the central level.

Deleted: a

Table 1: Expenditure of the Czech state budget in 1995–2005 (current prices, in billion CZK, in %)

Source: Statistical Yearbook of the Czech Republic 1997, 1999, 2001, 2002, 2004, 2006.

Note: In December 2007, the exchange rate was approx. 1 EUR = 27 CZK.

(about here)

Table 2: Expenditure from selected state extra-budgetary funds in 2000–2005 (current prices, in billion CZK)

Source: Statistical Yearbook of the Czech Republic 2000–2006.

(about here)

5. Data and Methodology

The prime source for this regional analysis of the capital expenditure of the state budget of the Czech Republic is the ISPROFIN (Information System of Programming Funding from the State Budget) database, which comprises data regarding investment spending from the state budget, in our case for the years 1995–2005. ISPROFIN is managed by the Ministry of Finance of the Czech Republic and has been operational since 1995.ⁱⁱ The structure of the entries into ISPROFIN allows a regional break-down of capital expenditure at the level of the NUTS 3 and 4 regions. However, several methodological problems arose during the analysis of this data, and consequently, a number of projects and programmes (and the corresponding financial volume of capital expenditure) had to be excluded from the analysis. The following criteria for omitting particular projects or programmes were applied: i) the regional allocation of the investment incentives was not given or investment was implemented abroad; ii) the project or programme was predominately for current expenditure; iii) the project was of an “extraordinary” nature (i.e. expenditure devoted to the recovery of the territories affected by the 1997 and 2002 floods or devoted to the restitution to former owners of private property that was nationalized during the communist period).

Deleted: elaboration

Deleted: ,

Deleted: o

Deleted: s

Deleted: the

1
2 An overview of the financial amounts included (and excluded) from the regional analysis of
3 public capital expenditure is given in Table 3. Another methodological challenge was
4 represented by projects which benefited the whole country, but in ISPROFIN were assigned
5
6 to one region only. This was especially the case for the purchase of jet fighter aircraft, which
7
8 were also excluded from the analysis.
9
10
11
12

Deleted: o

Deleted: s

Deleted: consequently

Formatted: Indent: First line: 0 pt

13
14 This problem relates to the fundamental methodological question of which principle
15 investment expenditure should be attributed to a certain region. For instance, SHORT (1978)
16 has explicitly distinguished two types of regional expenditure: “regionally relevant” and “total
17 expenditure” allocated to the region. According to Short, “regionally relevant” expenditure
18 benefits only the region in which the particular public money was allocated. Alternatively,
19
20 WISHLADE *et al.*, (1996) and also CAMINAL (2004) differentiated between the “flow” and
21
22 “benefit” approaches to the analysis of the regional distribution of public expenditure. The
23
24 “flow” approach assigns expenditure to regions regardless of whether or not the region in
25
26 question is an “end user”, while the “benefit” approach concentrates on the end users of the
27
28 public money spent, or more precisely on the final beneficiary regions. Consequently, in our
29
30 analysis, the flow approach has been applied as it would be impossible to judge each of the
31
32 approximately 40,000 investment projects of ISPROFIN included in the analysis on the basis
33
34 of the benefit approach.
35
36
37
38
39
40

Deleted: the

41 **Table 3: Financial resources of ISPROFIN 1995–2005 (in billion CZK, current prices, in**
42 **%)**
43

44 Source: ISPROFIN (Internal material of the Ministry of Finance of the Czech Republic), authors` calculations.
45

46 (about here)
47
48
49
50
51
52
53
54
55
56
57
58
59
60

1
2 In addition to ISPROFIN, which covers capital expenditure financed from the state budget,
3
4 the two most relevant extra-budgetary funds were incorporated into our analysis. These two
5
6 funds are: The State Fund for Transport Infrastructure (SFTI) and the State Environmental
7
8 Fund (SEF). The data on the individual projects supported by these funds were obtained from
9
10 the responsible institutions. In the case of the State Fund for Transport Infrastructure, the
11
12 capital expenditure for 2001–2005 has been analysed at the level of NUTS 3 regions.
13
14 Investment projects to a total value of CZK 222.3 billion were included in the analysis. The
15
16 State Environmental Fund is represented by the data concerning expenditure during the years
17
18 1999–2005, which amounted to CZK 13 billion. Therefore, this analysis covers capital
19
20 expenditure from the state budget and from two extra-budgetary funds to a total value of CZK
21
22 617 bln. The analysis was structured into six parts, covering the most relevant thematic
23
24 spheres of public capital expenditure (see Table 4).
25
26
27

Deleted: ¶

Deleted: of

28 **Table 4: Overview of the analyzed data for the period 1995-2005 (in billion CZK, current**
29
30 **prices)**

31 Source: ISPROFIN (Internal material of the Ministry of Finance of the Czech Republic), Internal materials of
32
33 the State Fund for Transport Infrastructure (SFTI) and the State Environmental Fund (SEF), authors'
34
35 calculations.

36 (about here)
37
38
39

40 **6. Results**

41 In this section, the main results of the regional analysis of capital expenditure committed
42
43 within the sectoral governmental policies in the Czech Republic will be presented (Table 4
44
45 provides an overview of the financial volumes analysed). First, attention is paid to an analysis
46
47 of the distribution of all capital expenditure, that is an analysis of investment projects financed
48
49 from the state budget and from relevant state extra-budgetary funds. In view of the fact that
50
51

Deleted: analysed

Deleted: i.e.

Deleted: both

1
2 the overall nature of regional differentiation of investment allocation is considerably
3
4 influenced by investments in the transport infrastructure, in the next stage such investments
5
6 are excluded from the analysis and analysed separately. Next, the regional allocation of
7
8 investments in other relevant sectors is considered, namely the territorial allocation of
9
10 investments within explicit regional policy, investments in universities and the R&D sector,
11
12 and finally investment assigned to the environmental sector.

Deleted: i.e. besides the already mentioned transport sector,

Deleted: s

Deleted: in

Deleted: are examined as well.

16 6.1. Regional analysis of total capital expenditure

17
18 The regional analysis of total capital expenditure financed from the central level (i.e. from the
19
20 state budget and from both state extra-budgetary funds) in the period 1995–2005, includes
21
22 nearly CZK 617 billion after the data has been ‘cleaned’ by the above described procedure.
23
24 The nature of the capital expenditure determined that such invested funds were used primarily
25
26 for development activities, and allocation of such investments has an undoubted dynamic
27
28 effect on the relevant regions (e.g. SHORT, 1981; AUTERI and COSTANTINI, 2004).

29
30
31 The overall spatial pattern of the regional distribution of the analysed funds can be considered
32
33 as significantly unbalanced. In the period studied, over one quarter of the analysed
34
35 investments (which in absolute terms represents approximately CZK 168 billion) were
36
37 allocated from the national level into the capital city of Prague, socio-economically the most
38
39 advanced region of the Czech Republic (for regional GDP per capita see Figure 2). The
40
41 dominance of Prague is also proved by relative indicators, i.e. investments per inhabitant
42
43 (approximately CZK 142 thousand per inhabitant, which is 237% of the average for the Czech
44
45 Republic - see Table 5). With respect to economic performance indicators, i.e. after putting
46
47 capital expenditure in relation to the regional GDP level, it was 116% of the average
48
49 allocation of the Czech Republic and in relation to the economic aggregate it was 123% of the

Deleted:

Deleted:) (

Deleted:

Deleted:

national average. The term economic aggregate was defined by HAMPL (2005) as the product of the number of jobs (the number of jobs is determined as the number of economically active persons after deducting the unemployed and adding the commuting balance calculated on the basis of the 2001 Census) and the average wage in the region in question. The Plzeňský and Olomoucký regions achieved an even higher investment allocation than Prague with respect to GDP (136%, resp. 137% - see Table 5), and the same order applies when the allocated investment volume is related to the economic aggregate.

Deleted: E

Deleted: a

Deleted:

Deleted:

Deleted:) (

Table 5: Capital expenditure per capita and per regional GDP (1995–2005, in %)

Deleted: related to regional

Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech Republic 2001, authors' calculations.
(about here)

6.2. Regional analysis of total capital expenditure after exclusion of transport investment

Deleted: s

Since the extraordinary volume of investment devoted to transport infrastructure (CZK 222 billion from the state budget and from the State Fund for Transport Infrastructure – see Table 4), which undoubtedly influences the overall picture of the regional allocation of investment, such expenditure was excluded from the analysis in the following stage. The remaining investment projects thus represent approximately CZK 395 billion for the period of 1995–2005 again.

Deleted: Due to

Deleted: the

Deleted: ,

Deleted: differentiation of

Deleted: allocation

After the exclusion of projects in the transport infrastructure sector, the position of Prague is even higher (see Table 5). In absolute terms, its share of public capital expenditure in the Czech Republic actually increased to 37.5%, while in per capita terms the investment allocation to Prague was 326% of the average value for the Czech Republic. No other NUTS 3 region received an above-average allocation per inhabitant. Even when the allocated

Deleted: n

Deleted:

Deleted:

1
2 investment projects are related to the regional GDP, the Prague region is still above the
3 national average (see Table 5). Investments in Prague were directed particularly to the state
4
5 administration (approximately CZK 55 billion), state defence (CZK 24 billion), health service
6
7 (CZK 18.1 billion), infrastructure development (CZK 18.9 billion) as well as public city
8
9 transport (4.8 billion CZK), R&D (CZK 6.9 billion) and education (CZK 8.7 billion).
10
11

Deleted: "subsidized" by the other regions

12
13
14 As all data except for that on transport infrastructure projects was territorially identified up to
15
16 NUTS 4 level, a detailed analysis of the regional distribution of capital expenditure, after
17
18 exclusion of transport expenditure, could be carried out on the NUTS 4 level regions. At this
19
20 hierarchical level, Prague dominates absolutely. The district of Kutná Hora achieved the
21
22 second highest allocation per inhabitant and the highest allocation per economic aggregate,
23
24 but this was thanks to extraordinary investments in the military air force base in Čáslav. The
25
26 district of Brno–město (after Prague the second most important economic centre of the Czech
27
28 Republic) is in third position with 162% of the average allocation per inhabitant. Brno also
29
30 achieved the second highest share of 6%. The districts of Ostrava–město (2.2%), Olomouc
31
32 (2.6%) and Plzeň–město (2.2%) also received significant shares. Other districts received only
33
34 minor allocations.
35
36

Deleted:

Deleted:

Deleted:

Deleted:

Deleted:

37
38 Where capital expenditure was considered per inhabitant, above-average investments
39
40 compared to the average for the Czech Republic were allocated to only 11 out of 77 districts,
41
42 and 22 districts did not even achieve 50%. The regions receiving significantly below-average
43
44 investment funds per inhabitant include the majority of districts in North-Western Bohemia
45
46 and Northern Moravia (which, however, are mostly among the regions supported within
47
48 Czech regional policy – see Figure 2), the internal periphery, as well as a large area of
49
50
51
52
53
54
55
56
57
58
59
60

Deleted:

Deleted: that have

Deleted: ed

Deleted: the

Southern, Western, Northern and Eastern Bohemia and the Czech-Slovak borderland (see Figure 3).

Figure 2: Assisted regions supported within Czech explicit regional policy

Source: Ministry for Regional Development.

(about here)

Deleted: the

Figure 3: Capital expenditure per capita after exclusion of transport infrastructure in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %).

Source: ISPROFIN, SEF, Statistical Yearbook of the Czech Republic 2001, authors` calculations.

(about here)

Deleted: per capita

Due to the unavailability of GDP data for NUTS 4 regions and the limited reliability of this indicator on the NUTS 3 regions, GDP was replaced by an economic aggregate. At regional level, this indicator achieves a very high correlation with regional GDP (0.998). After putting the allocated investment funds in relation to the economic aggregate (see Figure 4), Prague achieved 169% of the average for the Czech Republic (the highest allocations went to the districts of Kutná Hora - 257% and Prostějov - 170%, in both cases thanks to extraordinary investments in the defence sector). Highly uneven distribution of this expenditure illustrates well the fact that above-average values were achieved by only 13 districts, among which was also the second largest city (district Brno-město - 119 %).

Deleted: on GDP on the

Deleted: level

Deleted: level

Deleted: the

Deleted: On the

Deleted:

Deleted:

Deleted:

Figure 4: Capital expenditure per economic aggregate after exclusion of transport infrastructure investments in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %).

Source: ISPROFIN, SEF, Statistical Yearbook of the Czech Republic 2001, HAMPL (2005), authors` calculations.

(about here)

Deleted: per economic aggregate

6.3. Capital expenditure in the transport sector

The extraordinary importance of investment devoted to the transport infrastructure is given by their very high volume (CZK 222 billion), which represents approximately 36% of the volume of the investment observed in this study. In addition, it is obvious that the regional formula of transport constructions, often linear in nature, may significantly differ from the spatial formula of other investment projects. For this reason, the transport sector was chosen for a separate regional analysis (i.e. investment in construction of motorways, expressways, railway corridors, and the underground in Prague). Despite a number of methodological constraints, it was possible to unite the two most important sources of funds for this sector: the state budget (i.e. ISPROFIN) and the State Fund for Transport Infrastructure. The total analysed investment volume of 1995–2005 exceeds CZK 222.3 billion (ISPROFIN – CZK 96.7 billion, the State Fund for Transport Infrastructure – CZK 125.5 billion), and the data are available only for NUTS 3 regions.

Deleted: s

Deleted:

Deleted: s

Deleted: to that

Deleted: s

Deleted: at the

Deleted: level

Figure 5 illustrates the considerably above-average allocation of investment in transport in Western Bohemia, which corresponds to the hypothesis of allocation of investment along a traditional west-east gradient in the level of socio-economic development. In transport investment, this gradient is raised by the effort to ensure transport connections for the Czech Republic or its capital of Prague with nearby economic centres in Germany (Munich, Frankfurt, Berlin). Although the area of Northern Moravia is a structurally affected region, as is North-Western Bohemia, transport investment has flowed more to Northern Bohemia in recent years, because the transport connection with Poland was of less priority than connections to Germany or Western Europe.

Deleted: s

Deleted: s

Deleted: s

Deleted: s

Deleted: ve

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

Figure 5: Transport infrastructure investment per capita in NUTS 3 regions, 1995–2005,

Czech Rep. = 100 % (in %)

Source: ISPROFIN, SFTI, Statistical Yearbook of the Czech Republic 2001, authors' calculations.

(about here)

The spatial formula for the allocation of per capita investment in transport is very similar to the case where transport investment is related to GDP (the correlation coefficient is 0.954). In both indicators the position of Prague is well below national average (78%, resp. 38% of the Czech Republic average). On the contrary, Plzeňský, Olomoucký, Ústecký and Karlovarský regions achieved significantly above-average allocations. However, in evaluating the regional distribution of transport infrastructure investments (and of general investments as well) it is necessary to consider the time aspect in the sense that if a significantly higher amount of funds is granted to a region in a certain time range, it may mean that the necessary infrastructure had not previously been constructed in the region in question and it is being built behind schedule or out of needs arising from the different geopolitical orientation of the Czech Republic after the fall of the Iron Curtain. For example, as early as the communist era, the D1 motorway was completed between Prague and Brno, leading across the Vysočina region, so this region records a significantly below-average allocation, while in the districts of Tachov and Plzeň-jih districts, the D5 connecting Prague and Bavaria was built during the period considered here.

The regional distribution of capital expenditure after the exclusion of transport infrastructure investments when related to the economic level of the region (GDP) shows that transport investments are what "aid" economically weaker regions to reach above-average values. If transport investments are not considered, Prague is quite clearly the region that gains most

Deleted: s

Deleted: s

Deleted: s

Deleted: are

Deleted:) (see Table 5 and 6a

Formatted: Not Highlight

Deleted: , only with the difference

Formatted: Not Highlight

Deleted: that in both

Formatted: Not Highlight

Deleted:

Formatted: Not Highlight

Deleted: , or

Deleted: in

1
2 from redistribution of public investment, both in per capita terms and in relation to GDP
3
4 (116 %, or 159 % of the Czech Republic average - see Table 5).
5
6
7

Deleted: s

Deleted:) (

8 **6.4. Capital expenditure allocated within explicit regional policy**

Deleted: the

9
10 Since one of the aims of this article is to show a significant discrepancy between the regional
11 formula for the allocation of public investment funds within non-regional policies and
12 regional policy, this is presented by Figure 6 which shows investments granted to explicit
13 regional policy from the state budget. Strikingly, the funds allocated within regional policy
14 are spread widely across the whole territory of the Czech Republic. This is in sharp contrast
15 with the very conception of regional policy as a policy which supports only selected regions.
16
17
18
19
20

Deleted: empirically

Deleted: the

21
22 This finding cannot be justified by changes of assisted areas over the investigated period as
23 there was considerable stability of both the regional pattern of lagging and leading regions
24 and consequently also of assisted areas delineated for the sake of regional policy (BLAŽEK,
25 2005b). On the other hand, the pattern of investment within regional policy does confirm that
26 a certain priority was given to the assisted areas. Namely, the Moravian districts, especially
27 the southern and, to some extent, northern ones ranked among the largest recipients of such
28 investments (together with North-Western Bohemia they rank among the regions supported
29 within Czech explicit regional policy, as does Northern Bohemia to some degree).
30 Nevertheless, it is necessary to mention a paradox as a statistically highly significant positive
31 relation of regional policy investment to regional GDP and to the economic aggregate was
32 demonstrated for NUTS 3 regions (in both cases excluding Prague - see Table 6a). The same
33 applies also to the level of NUTS 4 regions (see Table 6b) where a statistically significant
34 positive relation was found between the regional policy capital expenditure and the level of
35 economic development measured by the economic aggregate as a proxy for regional GDP. At
36 the same time, a larger part of Moravia ranks, with other regions supported within explicit
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

Deleted:

Deleted:) (

Deleted: s

Deleted: the Czech

1 regional policy, as an area significantly underfinanced with respect to the total investment
 2 from the state budget after the exclusion of transport. In simple terms, districts supported
 3 within the explicit regional policy in the Czech Republic received only a very limited volume
 4 of investment from the national level (after the exclusion of transport constructions) (compare
 5 Figures 2, 3 and 4). On the other hand, support within Czech regional policy was significantly
 6 concentrated into these regions (see Figure 6). However, a huge difference in the financial
 7 sums invested has to be stressed again: CZK 7.2 billion for regional policy versus the total
 8 volume of the analysed funds amounting to CZK 617 billion. Nevertheless, although the
 9 volume of investments for regional policy at the national level is nearly negligible, its
 10 importance is significantly higher for the supported regions.

Deleted: s

Deleted: very

Deleted: s

Deleted: cfr.

Deleted: and

Deleted: or

Deleted: the state

21
 22
 23
 24 **Figure 6: Capital expenditure per capita from the state budget devoted to explicit regional
 25 policy in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %).**

Deleted: devoted

Deleted: per capita

26 Source: ISPROFIN, Statistical Yearbook of the Czech Republic 2001, authors` calculations.

27 (about here)

28
 29
 30
 31
 32
 33 **Table 6a: Correlation of selected indicators for NUTS 3 regions (n=13 – Prague excluded)**

34 Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech Republic 2001,
 35 HAMPL (2005), authors` calculations.

36
 37
 38
 39 **Table 6b: Correlation of selected indicators for NUTS 4 regions (n=76 – Prague excluded)**

40 Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech Republic 2001,
 41 HAMPL (2005), authors` calculations.

42 (about here)

43 44 45 46 **6.5. Capital expenditure for higher education, R&D and the environmental sector**

47 Within the regional analysis of capital expenditure from the state budget of the Czech
 48 Republic, sectoral analyses were also carried out. As an example, Figure 7 shows investment
 49
 50

Deleted: also according to sectoral classification

Deleted: s

1
2 from the state budget in the infrastructure of universities and colleges and other R&D
3
4 institutions amounting to approximately CZK 25 billion. The expected regional distribution of
5
6 such expenditure into economically more developed regions (Prague, Brno) and to regions
7
8 where a public college is located, or to regions with headquarters of important research
9
10 institutes (the Prague hinterland) was demonstrated (similar regional pattern of public R&D
11
12 expenditure was shown by WISHLADE *et al.* 1996 or THE ESPON MONITORING COMMITTEE
13
14 2005). Nevertheless, it is necessary to point out that it is not only capital expenditure from the
15
16 central level that is devoted to this sector. For example, it was not possible to obtain data on
17
18 the regional allocation of financial support for R&D projects allocated by the Grant Agency
19
20 of the Czech Republic. In addition, it is necessary to take into account a frequent
21
22 methodological problem, when some analysed data are allocated according to the
23
24 headquarters of the institution in question, although such funds may then be invested in
25
26 branches of the institution in a different region. It is thus probable that in fact investment in
27
28 higher education and R&D is less concentrated than the data analysed shows.

Deleted: s

Deleted: are quite

31
32 **Figure 7: Capital expenditure per capita of the state budget devoted to universities and for**
33
34 **R&D institutions in NUTS 4 regions, 1995–2005, Czech Rep. = 100 % (in %)**

Deleted: per capita

35 Source: ISPROFIN, Statistical Yearbook of the Czech Republic 2001, authors' calculations.

36
37 (about here)

38
39
40
41 Figure 8 shows investment in the environment sector amounting to CZK 25.6 billion,
42
43 allocated both from the state budget and the State Environmental Fund. Although no clear
44
45 relation between the distribution of funds and environmental quality has been shown, we may
46
47 confirm to some extent that investment was allocated to regions in which it is necessary to
48
49 solve a specific problem with respect to the environment (e.g. support of mining reduction,
50
51 revitalising the river system, pond reconstructions).

Deleted: s

Deleted: al

Deleted: that were

Deleted: was/

1
2
3
4 A surprisingly high allocation of investment to border districts in South-Western Bohemia
5
6 relates to investment in the territorially largest national park in the Czech Republic (The
7
8 Šumava National Park). Figure 8 provides, however, a surprising finding, that investment
9
10 projects in the environment sector are not greatly concentrated in the structurally handicapped
11
12 regions in Northern Bohemia and in Northern Moravia where the environment is seriously
13
14 damaged. There is one exception with high investment - the Česká Lípa district - where the
15
16 running down of the uranium industry and subsequent cultivation of the area are jointly in
17
18 progress.

Deleted: s

Deleted: al

Deleted: s

19
20
21
22 **Figure 8: Environmentally related capital expenditure *per capita* of the state budget in**
23
24 **1995–2005 and of the State Environmental Fund in 1999–2005 in NUTS 4 regions, Czech**

Deleted: per capita

25
26 **Rep. =100 % (in %)**

27 Source: ISPROFIN, SEF, Statistical Yearbook of the Czech Republic 2001, authors' calculations.

28
29 (about here)

30 31 32 **6.6. Relation of capital expenditures to selected socio-economic variables**

33
34
35 On the basis of correlation coefficients for selected indicators for NUTS 3 regions (Table 6a)

36 we can demonstrate a statistically significant relation between all regional allocations of
37
38 investment via all analysed categories of investment (i.e. total investment, total investment
39
40 after exclusion of transport investment, transport investment, investment into R&D and
41
42 universities and regional policy investment, and their economic performance expressed by the
43
44 GDP and the economic aggregate. The same finding counts for correlation coefficients for
45
46 NUTS 4 regions (Table 6b), however, due to data limitations only the correlation between 3
47
48 investment categories and the economic aggregate could be calculated. It is important to stress
49
50 again that with respect to the declared objectives of Czech regional policy, the correlation
51
52

Deleted: s'

Deleted: s

Deleted: s

Deleted: s

Deleted: s

Deleted: s

Deleted: (

Deleted:)

Deleted: on

Deleted: values of the

Deleted: coefficients

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

between the share of investment allocated within explicit regional policy and economic performance should be negative. However, on both NUTS 3 and NUTS 4 level regions positive and even statistically significant values were obtained indicating that even allocation of investment within regional policy is not in line with its own strategic objective.

Deleted: s

Deleted: while

Deleted: III

Deleted: IV

Deleted: s

Deleted: representative

Deleted: .

Deleted: There is also the interesting fact that if Prague is considered with the NUTS 3 units, the shares of regions in capital expenditure allocated within the regional policy and regional development support do not correlate closely with indicators of the level of economic development.

The identification and detailed assessment of factors behind these observed patterns goes beyond the focus of this paper, however at least a brief discussion should be included. In countries like the Czech Republic which are lacking instruments for the systematic evaluation of the effectiveness and efficiency of planned public investment, a relatively important role can be assumed for subjective factors. The decision making process on public investment committed from the central level basically proceeds at two levels. Firstly, on the basis of a proposal of the Ministry of Finance, the Government and Parliament decide about financial allocations to particular sectors that come under the responsibility of particular ministries. Secondly, there is a process of selection of priorities by a particular ministry. In this case, three main factors influencing the decision making process on public investments might be identified: i) the adopted strategy for a specific sector (inevitably even these strategic documents can to some extent reflect subjective factors), ii) the interests of (esp. high-ranking) public servants and iii) the interests of politicians. On the basis of our experience of more than 10 years of contractual cooperation by one of the authors with one central administration body we can draw two preliminary conclusions. First, the relevance of these three types of factors differs widely among different sectoral policies. Second, in some cases each of the three above mentioned factors can be decisive. This, therefore, makes a clear case for the introduction of some instruments (including TIA) that would be able to "objectivise" the need for public investment.

Deleted: on

Deleted: the

Deleted: line

Deleted: line

Deleted: o

Deleted: particular

Deleted: , s

7. Conclusions and policy implications

The article aims to contribute to the debate on the regional dimension of sectoral (non-regional) governmental policies and to empirically demonstrate the huge discrepancy between both the volume and regional pattern of public capital expenditure committed within the national sectoral policies on the one hand and the official regional policy on the other. The performed analyses focused “only” on the public capital expenditures allocated by the Government of the Czech Republic, but it can be claimed that public capital investments have the most important implications for the development of particular regions (SHORT, 1981; YAMANO and OHKAWARA, 2000). Obviously, the financial volume of the total public capital expenditure is incomparably higher than the financial volume allocated to explicit regional policy.

The regional analyses performed were based on the dataset of public capital expenditure in the Czech Republic covering the years 1995–2005 and demonstrated uneven regional distribution of these investments in favour of the most economically developed region of the Czech Republic – the capital city of Prague. Such a regional pattern for the distribution of public investment supports the hypothesis that there exists a contradiction between the regional impact of sectoral policies on the one hand, and the goals of explicit regional policy on the other. The discrepancy between these two is particularly striking as assisted regions delineated for the sake of national regional policy were to a large extent left aside by decisions regarding the allocation of public capital expenditure (with the exception of expenditure on transport infrastructure). Moreover, a surprising pattern was identified even in the case of investment committed within explicit regional policy (Fig. 6) which is not coinciding well with the map of assisted areas (Fig. 2). Clearly, the allocation of regional policy investments is not respecting fully the objectives of regional policy itself.

Deleted: the extremely

Deleted: socio-

Deleted: of the

Deleted: virtually

Deleted: the

Deleted: s

Deleted: the

Deleted: the

1
2
3
4 Consequently, there is a clear conflict between the goals of explicit regional policy aiming at
5
6 the support of less well-off regions and mostly unintended regional impacts of much more
7
8 vigorous non-regional governmental policies generally supporting the most developed
9
10 regions. These findings are in line with research performed by e.g. WILSON and WISE (1986)
11
12 but in contrast with results of YAMANO and OHKAWARA (2000).
13

14
15
16 However, it is necessary to stress that from the point of view of the entire expenditure side of
17
18 the governmental policies comprising both capital and current expenditure, the region of
19
20 Prague is very likely the most important net payer into the system of public finance due to its
21
22 buoyant tax base and to its relatively low share of persons receiving social benefits (see
23
24 OUŘEDNÍČEK and NOVÁK, 2006). Nevertheless, it is clear that the uneven distribution of
25
26 public capital expenditure, generally favouring more developed regions, is one of the most
27
28 important mechanisms of regional differentiation and is, moreover, cumulative in nature.
29

30
31 The expectation of a replication of the traditional East-West gradient in the level of socio-
32
33 economic development by the regional structure of total capital expenditure has not been
34
35 experienced. However, the evidence supporting this expectation can be observed in the case
36
37 of the capital expenditure allocated to transport infrastructure. The greater support of transport
38
39 infrastructure projects in the Western part of the Czech Republic is a reflection of the priority
40
41 assigned to connecting the Czech Republic to Western European structures.
42

43
44 Key implications deriving from the conducted regional analysis relate in particular to the
45
46 necessity of developing a sound methodology for the territorial impact assessment of public
47
48 policies and programmes. In other words, it is essential to develop a procedure evaluating not
49
50 only the regional impact of incentives carried out within explicit regional policy (which is
51
52
53
54
55
56
57
58
59
60

Deleted: underline

Deleted: hypothesis expecting

Deleted: proven.

Deleted: assumption

1
2 already becoming common practice in the most developed countries) but also the impact of
3
4 public interventions which do not explicitly incorporate a regional dimension but where
5
6 implementation might have a significant regional impact. Such an evaluative instrument is
7
8 essential for tackling of regional development issues and problems more effectively by
9
10 achieving synergies and eliminating contradictions between different policies (SCHÄFFER,
11
12 2005; CEC, 2006a, 2006b). Nevertheless, this approach is a real challenge due to the fact that
13
14 public policies in most advanced countries are traditionally being implemented via sectorally
15
16 structured public administration at central governmental level while the relevance of sectoral
17
18 policies for development of particular regions has been clearly underestimated (ROBERT *et al.*,
19
20 2001; MACEŠKOVÁ, 2007).
21
22
23

Deleted: a more effective

Deleted: on

24 Despite the effort that has been put into developing TIA methodology, no comprehensive and
25
26 satisfactory tool for regional impact assessment has yet been developed. Therefore, as also
27
28 documented by our empirical results, which showed both an uneven spatial pattern of the
29
30 allocation of public capital expenditure and a huge mismatch between the regional pattern of
31
32 this expenditure and the assisted regions, the development of a suitable instrument for
33
34 territorial/regional impact assessment and its application at least to the most relevant sectoral
35
36 policies remains a critical challenge for both researchers and decision-makers.
37
38

Deleted: spatial

Deleted: s

Deleted: highly

Deleted: on

39
40 ⁱ Such fine-tuning can take many different forms, for example differentiation of the form and
41
42 the rate of public support or the involvement of regional self-government or other regional
43
44 bodies in decision-making procedures, although in practice such an approach is rather rarely
45
46 applied.
47

48
49 ⁱⁱ Except for the programmes set by a special act such as state support to the national cultural
50
51 heritage or agriculture.
52
53
54
55
56
57
58
59
60

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

For Peer Review Only

1
2
3 ARMSTRONG H. and TAYLOR J. (1985) *Regional Economics and Policy*. Philip Allan,
4
5 Hertfordshire.
6
7

8
9
10 AUTERI M. and COSTANTINI M. (2004) Fiscal Policy and Economic Growth: The Case of
11
12 the Italian Regions, *The Review of Regional Studies* **34**, 72-94.
13
14

15
16
17 BENNET R. J. (1980) *The Geography of Public Finance*. Methuen, London.
18
19

20
21
22 BLAŽEK J. (1995) Le nouveau système de financement des administratios locales en
23
24 République tchèque et ses incidences è l' échelle régionale, Cahiers du CEFRES, No.9f,
25
26 Prague.
27
28

29
30
31
32 BLAŽEK J. (2005a) Financing of Local Government in the Czech Republic: A Never Ending
33
34 Reform Process? (Part III), in *New Modes of Governance. The Evolution of Regional*
35
36 *Development Regimes in CEE - The Czech Republic* (available at: [http://www.eu-](http://www.eu-newgov.org/database/DELIV/D15D02c_Regional_Development_Regimes_CzechR.pdf)
37
38 [newgov.org/database/DELIV/D15D02c_Regional_Development_Regimes_CzechR.pdf](http://www.eu-newgov.org/database/DELIV/D15D02c_Regional_Development_Regimes_CzechR.pdf)).
39
40

41
42
43 BLAŽEK, J. (2005b) Trends to Regional Disparities in the Czech Republic in Pre-Accession
44
45 Period in the European Context, *Geographia Polonica* **78.2**, p. 91-106.
46
47

48
49
50
51 BLAŽEK J. and CSANK P. (2007) The West-East gradient and regional development: The
52
53 case of The Czech Republic, *Acta Universitatis Carolinae - Geographica* **1-2**, 89-108.
54
55

56
57
58 CAMINAL R. (2004) Personal redistribution and the regional allocation of public
59
60 investment, *Regional Science and Urban Economics* **34**, 55-69.

1
2
3
4
5
6 CAMAGNI R. (2006) Territorial Impact Assessment – TIA: a methodological proposal,
7
8 *Scienze Regionali – Italian Journal of Regional Science* **5**, 135-146.
9

10
11
12 CEC (1996) First Report on Economic and Social Cohesion. Brussels (available at:
13
14 http://ec.europa.eu/regional_policy/sources/docoffic/official/reports/repc_en.htm).
15
16

17
18
19 CEC (2004) DG REGIO – The Impact of Member State Policies on Cohesion (Final report)
20
21 (available at:
22
23 [http://europa.eu.int/comm/regional_policy/sources/docgener/studies/pdf/3cr/impact_member.](http://europa.eu.int/comm/regional_policy/sources/docgener/studies/pdf/3cr/impact_member.pdf)
24
25 [pdf](http://europa.eu.int/comm/regional_policy/sources/docgener/studies/pdf/3cr/impact_member.pdf)).
26
27
28

29
30
31 CEC (2006a) Territorial Impact Assessment. In CEC: *European Territorial Research in*
32
33 *Progress*, pp. 67-132. Conference Proceedings of the 1st ESPON Scientific Conference,
34
35 ESPON Programme, Luxembourg.
36
37

38
39
40 CEC (2006b) *Applied Territorial Research. Building a Scientific Platform for*
41
42 *Competitiveness and Cohesion*. ESPON Scientific Report II, ESPON Programme,
43
44 Luxembourg.
45
46
47

48
49
50 CUADRADO J.R., DE LA DEHESA G. and PRECEDO, A. (1993) Regional imbalances and
51
52 government compensatory financial flows: the case of Spain, in Giovannini A. (Ed.) *Finance*
53
54 *and Development: Issues and Experience*, pp. 261-300. Cambridge University Press,
55
56
57
58
59
60 Cambridge.

1
2
3 DG RESEARCH (1991) *The Regional Impact of Community Policies*. Research and
4
5 Documentation Papers. Regional policy and transport, series 17., Office for Official
6
7 Publications of the European Communities, Luxembourg.
8
9

10
11
12 DRBOHLAV D. and SÝKORA L. (1997) Gateway cities in the process of regional integration
13
14 in Central and Eastern Europe: the case of Prague, in Biffi G. *Migration, Free Trade and*
15
16 *Regional Integration in Central and Eastern Europe*, pp. 215-237. Verlag Österreich, Wien.
17
18
19

20
21
22 EUROPEAN COMMISSION (1998) *Economic and social cohesion in the European Union:*
23
24 *The impact of Member States' own policies*. Office for Official Publications of the European
25
26 Communities, Luxembourg.
27
28

29
30
31 EUROPEAN COMMISSION (2004) *A new partnership for cohesion. Convergence,*
32
33 *Competitiveness, Cooperation. Third Report on Economic and Social Cohesion*. Office for
34
35 Official Publications of the European Communities, Luxembourg.
36
37
38

39
40
41 FLUENTE A. de la (2004) Second-best redistribution through public investment: a
42
43 characterization, an empirical test and an application to the case of Spain, *Regional Science*
44
45 *and Urban Economics* **34**, 489-503.
46
47
48

49
50
51 HAMPL M. (2005) *Geografická organizace společnosti v České republice: transformační*
52
53 *procesy a jejich obecný kontext*. Faculty of Science, Charles University in Prague, Prague.
54
55

56
57
58 HEALD D. (1994) Territorial public expenditure in the United Kingdom, *Public*
59
60 *Administration* **72**, 147-175.

1
2
3 HEALD D. and SHORT J. (2002) The regional dimension of public expenditure in England.
4
5
6 *Regional Studies* **36**, 743-755.
7

8
9
10 HILL E. and LOWE J. (2007) Regional impact assessment: an Australian example, *Impact*
11
12 *Assessment and Project Appraisal* **25**, 189-197.
13

14
15
16
17 GORZELAK G. (1992) Dilemmas of Polish regional policies during transition, in Gorzelak
18
19 G. and Kuklinski A. *Dilemmas of regional policies in Eastern and Central Europe*, pp. 18-
20
21 38. University of Warsaw, Warsaw.
22
23

24
25
26
27 GUIÁN M.C. and CANELO M.T. (1996) Territorial Public Expenditure and Revenue:
28
29 Economic Impact in the European Regional Growth, Euro-American Association of
30
31 Economic Development, Working Paper no. 8, Series Economic Development, University of
32
33 Santiago de Compostela (available at: <http://ideas.uqam.ca/ideas/data/eaecodev.html>).
34
35

36
37
38
39 KATAOKA M. (2005) Effect of Public Investment on the Regional Economies in Postwar
40
41 Japan, *Review of Urban & Regional Development Studies* **17**, 115-139.
42
43

44
45
46 KOSHATZKY K. (2001) The regionalisation of Innovation Policy in Germany - Theoretical
47
48 Foundations and Recent Experience. Working Papers Firms and Region No. R1/2000,
49
50 Institute for Systems and Innovation Research, Fraunhofer.
51
52

53
54
55 LEFEBER L. (1964) Regional Allocation of resources in India, in Alonso W. and Friedmann
56
57 J. *Regional Development and Planning, A Reader*, pp. 642-653. The M.I.T. Press, Cambridge,
58
59
60 Massachusetts.

1
2
3
4
5 MACEŠKOVÁ M. (2007) Regionální dimenze fiskální politiky na příkladě veřejných
6 investičních výdajů v Česku (Regional dimension of fiscal policy – an example of public
7 capital expenditure in the Czech Republic), *Geografie-Sborník ČGS* **112**, 17-32.
8
9

10
11
12
13
14
15 MARTHUR V.K. and STEIN S. (1980) Regional Impact of Monetary and Fiscal Policy: An
16 Investigation into the Reduced Form Approach, *Journal of Regional Science* **20**, 343-351.
17
18

19
20
21
22 MARTIN R. (1999) *The Regional Dimension in European Public Policy: Convergence or*
23 *Divergence?*. Palgrave Publisher, New York.
24
25

26
27
28
29 MARTIN R. (2005) Venture Capital Programmes in the UK and Germany: In What Sense
30 Regional Policies?, *Regional Studies* **39**, 255-273.
31
32

33
34
35
36 MIDWINTER A. (2004) The Changing Distribution of Territorial Public Expenditure in the
37 UK, *Regional and Federal Studies* **14**, 499-512.
38
39

40
41
42
43 MOLLE W. and CAPPELLIN R. (1988) (Eds) *Regional Impact of Community Policies in*
44 *Europe*. Aldershot, Avebury.
45
46

47
48
49
50 MOLLE W. (2007) *European Cohesion Policy*. Routledge, London.
51
52

53
54
55
56 MRD (2006) *Strategie regionálního rozvoje*. Ministry for Regional Development of the
57 Czech Republic, Prague.
58
59
60

1
2
3 MUSGRAVE A.R. and MUSGRAVE B.P. (1973) *Public Finance in Theory and Practice*.
4
5 McGraw-Hill Kogakusha, Tokyo.
6
7

8
9
10 OUŘEDNIČEK M. and NOVÁK J (2007) Kvantitativní analýza stavu a vývoje
11 segregace/separace obyvatelstva, in Sýkora L. *et al Segregace v*
12 *České republice (Segregation in the Czech Republic)*, pp 9-28.
13
14 Ministry for Regional Development, Prague.
15
16
17

18
19
20
21
22 PEKOVÁ J. (2002) *Veřejné finance - úvod do problematiky*. ASPI Publishig, Praha.
23
24
25

26
27 PORTEOUS D.J. (1995) *The Geography of Finance*. Aldershot, Avebury.
28
29
30

31
32 PRUD`HOMME R. (1993) The Potential role of the EC budget in the reduction of spatial
33 disparities in a European economic and monetary union, in Commission of the European
34 Communities *The Economics of Community Public Finance*, pp. 321-351. Reports and
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
Studies. Directorate-General for Economic and Financial Affairs, European Economy no. 5.
Luxembourg.

ROBERT J. *et al* (2001) *Spatial Impacts of Community Policies and Costs of Non-co-*
ordination. European Commission, Brussels.

SHORT J. (1978) The regional distribution of public expenditure in Great Britain, 1967/70 –
1973/74', *Regional Studies* **12**, 499-510.

1
2
3 SHORT J. (1981) *Public Expenditure and Taxation in the UK Regions*. Gower Publishing
4 Co. Ltd, Hampshire (England).
5
6
7

8
9
10 SHOUT J.A. and JORDAN A.J. (2007) From Cohesion to Territorial Policy Integration
11 (TPI): Exploring the Governance Challenges in the European Union, *European Planning*
12 *Studies* **15**, 835-851.
13
14
15

16
17
18 SCHÄFFER N. (2005) Coordination of European spatial development: Whose
19 responsibility?, *The Town Planning Review* **76**, 14-57.
20
21
22
23

24
25
26 SCHINDEGGER F. and TATZBERGER G. (2003) TIA minimum requirements – a
27 Guidance for Policy Impact Projects of ESPON. Austrian Institute for Regional Studies and
28 Spatial Planning (available at:
29 http://www.espon.lu/online/documentation/projects/cross_thematic/816/2.ir-3.1.pdf).
30
31
32
33

34
35
36
37
38 THE ESPON MONITORING COMMITTEE (2005) ESPON 2.1.2 Territorial Effects of EU
39 Research and Development Policies (Final report) (available at:
40 [http://www.espon.eu/mmp/online/website/content/projects/243/266/file_399/fr-](http://www.espon.eu/mmp/online/website/content/projects/243/266/file_399/fr-2.1.1_final.pdf)
41 [2.1.1_final.pdf](http://www.espon.eu/mmp/online/website/content/projects/243/266/file_399/fr-2.1.1_final.pdf)).
42
43
44
45
46
47

48
49
50 UHLÍŘ D. (2004) Regional versus National Development: What sort of Policy for new
51 Czech Regions?, in Drbohlav D., Kalvoda J. and Voženílek V. (Eds) *Czech Geography at the*
52 *Dawn of the Millenium*, pp. 269-277. Palacky University in Olomouc, Olomouc.
53
54
55
56
57
58
59
60

1
2
3 WILSON P.A. and WISE C. (1986) The Regional Implications of Public Investment in Peru,
4
5 1968-1983, *Latin American Research Review* **21**, 93-116.
6
7
8

9
10 WISHLADE F., YUILL D., TAYLOR S., DAVEZIES L., NICOT B.H. and PRUD`HOMME R. (1996):
11
12 Economic and Social Cohesion in the European Union: The Impact of Member States`Own
13
14 Policies. Final report for the European Commission. European Policies Research Centre,
15
16 University of Strathclyde, Glasgow.
17
18
19

20
21
22 YAMANO N. and OHKAWARA T. (2000) The Regional Allocation of Public Investment:
23
24 Efficiency or Equity, *Journal of Regional Science* **40**, 205-229.
25
26
27
28
29

30
31
32 Other sources
33
34
35

36 ISPROFIN – Internal Material of Ministry of Finance of the Czech Republic

37
38 Internal Material of State Fund for Transport Infrastructure of the Czech Republic

39
40 Internal Material of State Environmental of the Czech Republic

41
42 Statistical Yearbooks of the Czech Republic 1997-2006 – Czech Statistical Office

43
44
45 Regional accounts – Czech Statistical Office
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

236x87mm (300 x 300 DPI)

158x98mm (500 x 500 DPI)

175x98mm (300 x 300 DPI)

158x97mm (300 x 300 DPI)

159x98mm (300 x 300 DPI)

160x97mm (300 x 300 DPI)

For Peer Review Only

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60

163x97mm (300 x 300 DPI)

161x97mm (300 x 300 DPI)

For Peer Review Only

Table 1: Expenditure of the Czech state budget in 1995-2005 (current prices, in billion CZK, in %)

	1995	1996	1997	1998	1999
Total expenditure of the state budget	432.7	484.4	524.7	566.7	596.9
of which capital expenditures of the state budget	44.1	46.4	50.6	50.5	59.0
share of capital expenditures of the total expenditure of the state budget (%)	10,2	9,6	9,6	8,9	9,9

Source: Statistical Yearbook of the Czech Republic 1997, 1999, 2001, 2002, 2004, 2006.

Note: In December 2007, the exchange rate was approx. 1 EUR = 27 CZK.

Table 1 continued

	2000	2001	2002	2003	2004	2005
Total expenditure of the state budget	632.3	693.9	750.8	808.7	862.9	843.8
of which capital expenditures of the state budget	60.9	49.6	49.7	56.9	66.7	79.0
share of capital expenditures of the total expenditure of the state budget (%)	9,6	7,1	6,6	7,4	7,7	9,4

Source: Statistical Yearbook of the Czech Republic 1997, 1999, 2001, 2002, 2004, 2006.

Table 2: Expenditure from selected state extra-budgetary funds in 2000-2005 (current prices, in billion CZK)

	2000	2001	2002	2003	2004	2005
Total expenditure of the State Environmental Fund of the Czech Republic	2.9	3.8	4.2	4.8	4.2	3.4
of which capital expenditure of the State Environmental Fund of the Czech Republic	2.6	3.5	3.7	4.2	3.7	3.0
share of capital expenditure of the entire expenditure of the State Environmental Fund of the Czech Republic	89.7	92.1	88.1	87.5	88.1	88.2
Total expenditure of the State Fund for Transport Infrastructure	8.5	30.6	40.2	41.3	52.1	48.5
of which the capital expenditure of the State Fund for Transport Infrastructure	5.0	13.9	24.1	25.1	34.6	37.8
share of capital expenditure of the entire expenditure of the State Fund for Transport Infrastructure	58.8	45.4	60.0	60.8	66.4	77.9

Source: Statistical Yearbook of the Czech Republic 2000 - 2006.

Table 3: Financial resources of ISPROFIN 1995-2005 (in billion CZK, current prices in %)

ISPROFIN	billion CZK	share of the total sum of ISPROFIN (in %)
Total	658.9	100.0
Included into analysis	478.5	72.6
Totally excluded from the analysis	180.3	27.4
<i>of which</i> regional allocation unknown	81.7	12.5
allocation abroad	6.1	0.9
current expenditures	37.7	5.7
extraordinary expenditures	14.7	2.3
other specific capital expenditures - e.g. purchase of fighter aircraft	39.5	6.0

Source: ISPROFIN, authors' calculations.

Table 4: Overview of the analyzed data for the period 1995-2005 (in billion CZK, current prices)

Thematic sphere of capital expenditure	Financial volume	Source	Level
Total capital expenditure	617.2	State budget (ISPROFIN), SFTI, SEF	NUTS 3
Capital expenditure excluding transport infrastructure investments	394.9	State budget (ISPROFIN), SEF	NUTS 3 NUTS 4
Transport infrastructure investments	222.3	SFTI, State budget (ISPROFIN)	NUTS 3
Explicit regional policy and regional development	7.2	State budget (ISPROFIN)	NUTS 4
Environmental capital expenditure	25.6	SEF, State budget (ISPROFIN)	NUTS 4
Capital expenditure devoted to universities and R&D	25.4	State budget (ISPROFIN)	NUTS 4

Source: ISPROFIN (Internal material of the Ministry of Finance of the Czech Republic), Internal materials of the State Fund for Transport Infrastructure (SFTI) and the State Environmental Fund (SEF), authors' calculation.

Table 5: Capital expenditure per capita and related to regional GDP (1995-2005, in %)

Region	Total investments in bln CZK	Total investments per capita Czech Rep. = 100 %	Total investments excluded of transport infrastructure investments per capita, Czech Rep. = 100 %	GDP per capita, Czech Rep. = 100 %	Total investments per GDP, Czech Rep. = 100 %	Total investments excluded of transport infrastructure investments per GDP, Czech Rep. = 100 %	Transport infrastructure investments per GDP, Czech Rep. = 100 %
Prague	168.3	237	326	206	116	159	38
Central Bohemia region	55.9	84	76	95	86	78	100
South Bohemia region	29.2	78	66	89	87	74	109
Plzeňský region	42.3	128	89	94	136	95	209
Karlovarský region	13.1	71	44	80	89	55	150
Ústecký region	45.3	91	53	82	111	64	194
Liberecký region	21.9	85	85	83	102	103	102
Královeský region	22.6	68	78	90	76	86	57
Pardubický region	23.6	77	66	84	92	78	116
Vysočina region	18.8	60	67	87	69	78	54
South Moravia region	61.6	90	93	93	98	101	93
Olomoucký region	40.9	106	87	77	137	113	181
Zlínský region	19.9	55	57	82	68	71	64
Moravskoslezský region	53.9	70	51	80	89	65	131
Czech Republic	617.2	100	100	100	100	100	100

Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech Republic 2001, authors' calculations.

Table 6a: Correlation of selected indicators for NUTS 3 regions (n=13 - Prague excluded)

	Regional share of GDP	Regional share of economic aggregate	Regional unemployment rate	Regional share of total investment	Regional share of transport investment	Regional share of investment excluding transport	Regional share of investment in universities and R&D
Regional share of economic aggregate	0,993						
Regional unemployment rate	0,304	0,357					
Regional share of total investment	0,906	0,910	0,399				
Regional share of transport investment	0,717	0,741	0,634	0,892			
Regional share of investment excluding transport	0,905	0,890	0,097	0,903	0,612		
Regional share of investment in universities and R&D	0,583	0,592	-0,001	0,618	0,323	0,775	
Regional share of expenditure on regional policy	0,782	0,818	0,547	0,710	0,573	0,698	0,617

Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech Republic 2001, HAMPL (2005), authors' calculations.

Note: Critical value of correlation coefficient for 95% level of significance is 0,497.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

Table 6b: Correlation of selected indicators for NUTS 4 regions (n=76 - Prague excluded)

	Regional share of economic aggregate	Regional unemployment rate	Regional share of investment excluding transport	Regional share of investment in universities and R&D
Regional unemployment rate	0,111			
Regional share of investment excluding transport	0,851	-0,009		
Regional share of investment in universities and R&D	0,822	-0,039	0,915	
Regional share of expenditure on regional policy	0,320	0,404	0,228	0,122

Source: ISPROFIN, SFTI, SEF, Czech Statistical Office, Statistical Yearbook of the Czech Republic 2001, HAMPL (2005), authors` calculations.

Note: Critical value of correlation coefficient for 95% level of significance is 0,200.