

The flexible stem hypothesis: evidence from genetic data Jean-Michel Gibert

▶ To cite this version:

Jean-Michel Gibert. The flexible stem hypothesis: evidence from genetic data. Development Genes and Evolution, 2017, 227 (5), pp.297-307. 10.1007/s00427-017-0589-0. hal-01628015

HAL Id: hal-01628015

https://hal.science/hal-01628015

Submitted on 2 Nov 2017

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

The flexible stem hypothesis: evidence from genetic data Jean-Michel Gibert Sorbonne Universités, UPMC Univ Paris 06, CNRS, Biologie du Développement Paris Seine, Institut de Biologie Paris Seine (LBD-IBPS), 75005 Paris, France. e-mail: jean-michl.gibert@upmc.fr tel: 00 33 1 44 27 58 42 Orcid number: 0000-0002-1579-0266 Acknowledgments: I thank Sophie Gournet for the drawings illustrating this review. I thank Frédérique Peronnet, Emmanuèle Mouchel-Vielh and Virginie Courtier-Orgogozo for critical reading of the manuscript and stimulating discussions. I thank the two anonymous reviewers for comments that significantly enriched the manuscript.

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

Abstract: Phenotypic plasticity, the ability of a given genotype to produce different phenotypes in response to distinct environmental conditions, is widely observed in the wild. It is believed to facilitate evolution and, under the "flexible stem hypothesis", it is thought that an ancestral plastic species can be at the origin of sister lineages with divergent phenotypes fixed by genetic assimilation of alternative morphs. We review here the genetic mechanisms underlying such phenomenon. We show several examples in which the same gene shows transcriptional plasticity in response to environmental factors and divergence of expression within or between species. Thus, the same gene is involved both in the plasticity of a trait and in the evolution of that trait. In a few cases, it can be traced down to cisregulatory variation in this gene and, in one case, in the very same regulatory sequence whose activity is modulated by the environment. These data are compatible with the "flexible stem hypothesis" and also suggest that the evolution of the plasticity of a trait and the evolution of the trait are not completely uncoupled as they often involve the same locus. Furthermore, the "flexible stem hypothesis" implies that it is possible to canalize initially plastic phenotypes. Several studies have shown that it was possible through modification of chromatin regulation or hormonal signalling/response. Further studies of phenotypic plasticity in an evolutionary framework are needed to see how much the findings described in this review can be generalized.

43

44

42

Key words: Phenotypic plasticity, Evolution, Gene expression, Review

47

48

49

50

51

52

53

54

55

56

57

58

59

60

61

62

63

64

65

66

67

68

69

In developmental biology, the environment has long been thought to fulfil essentially a permissive role, simply providing the required conditions for normal development to occur. Thus, most developmental biology laboratories still use standardized environmental conditions and focus on genetic factors to dissect developmental mechanisms. However, in many cases the environment has an instructive role, directing the development to particular alternative path (Gilbert 2001). Phenotypic plasticity is a major concept which describes "the property of a given genotype to produce different phenotypes in response to distinct environmental conditions" (Pigliucci 2001). It is widely observed in the wild, and this concept was formulated by Bradshaw in the sixties (Bradshaw 1965). Phenotypic plasticity can be an adaptation to fluctuating environments such as seasonal variations, presence/absence of predators, or population density. It can also be non adaptive and Schmalhausen used the term "morphose" to describe aberrant phenotypes induced by extreme environmental conditions (Schmalhausen 1949). A major tool to illustrate phenotypic plasticity is the reaction norm, first drawn by Woltereck in 1909 (Woltereck 1909), which represents the value of a quantitative phenotype produced by a given genotype in function of an environmental parameter. Note that "genotype" and "phenotype" were defined only shortly after by Johannsen (1911) who reinterpreted the reaction norms of Woltereck (Johannsen 1911). Indeed, Woltereck observed that different pure lines could produce different morphologies in a given environment but the same morphology in another environment. He interpreted this as inconsistent with the existence of constant differences between the genotypes. Because he did not distinguish between genotypes and phenotypes,

he thought that the different pure lines had the same genotype in a given environment (when they had the same phenotype) and different genotypes in another environment (when they had different phenotypes). When phenotypic plasticity leads to discrete morphs, these morphs are called polyphenisms. Phenotypic plasticity can generate, within a single species, morphological differences of a magnitude usually observed between distantly related species. As selection operates on phenotypes, this direct input of the environment on the expression of the genotype must be taken into account to understand evolutionary processes. This was clearly formulated by Schmalhausen (1949) (Schmalhausen 1949): "Darwin has previously noted the fundamental importance of inherited variability (mutations) for the evolution of organisms. However, mutations have different expressions under diverse conditions. If natural selection is the basic factor in evolution, then the concrete expression of individual characteristics under given environmental conditions is of decisive importance in this process ». Thus, the role of phenotypic plasticity in evolution has been actively discussed (Pfennig et al. 2010; Moczek et al. 2011; Laland et al. 2014, 2015; Schneider and Meyer 2017). The issue is complex and certain empirical results suggest that it is important to distinguish between adaptive and nonadaptive plasticity as they may have opposite effects on genetic divergence (Ghalambor et al. 2015). The idea that an ancestral plastic species could have been at the origin of divergent lineages with pronounced phenotypic differences has been proposed by Mary-Jane West-Eberhard as the "flexible stem hypothesis" (West-Eberhard 2003). It is intimately linked to the process of genetic assimilation discovered by Conrad Waddington more than 50 years ago (Waddington 1952, 1956, 1959). In

70

71

72

73

74

75

76

77

78

79

80

81

82

83

84

85

86

87

88

89

90

91

92

93

his experiments on *Drosophila*, Waddington showed that a phenotype initially induced by the environment can be fixed by selection and become constitutively expressed even in the absence of the initial environmental factor. Most of these experiments were based on developmental defects induced by stressors such as heatshock (crossveinless phenotypes on wings) (Waddington 1952) or ether vapour (bithorax phenocopies) (Waddington 1956). However, they could be generalized to adaptive phenotypes and had therefore major evolutionary implications. Indeed, in another Waddington experiment, the morphological change induced by the environment, *i.e.* size increase of the anal papilla of larvae in response to high salt concentration, was likely adaptive and was also genetically assimilated (Waddington 1959). Importantly, genetic assimilation is a genuine evolutionary process based on selection of genetic variation existing in the population submitted to environmental changes. Indeed, Waddington experiments were later repeated by Bateman on outbred or isogenized stocks and it was shown that genetic assimilation did not happen in the absence of genetic variation in the population (Dworkin 2005). This genetic variation is cryptic in the original environment in which it accumulates as it has no phenotypic consequences. This genetic variation translates into phenotypic variation in the new environment, which allows genetic assimilation by selection. Thus, a lineage characterized by a constitutively expressed morph could evolve from a plastic ancestor by genetic assimilation of a phenotype initially induced by environmental change. This has lead Mary Jane West-Eberhard to propose that genes act more as followers than as leaders during evolution (West-Eberhard 2005). Although very stimulating, this idea cannot be generalized to the evolution of all traits. Indeed,

95

96

97

98

99

100

101

102

103

104

105

106

107

108

109

110

111

112

113

114

115

116

117

118

in many examples, genetic polymorphisms have played a major role in the origin of a phenotype later fixed during evolution (Schwander and Leimar 2011). For example, a particular allele of the pigmentation gene tan leading to lighter pigmentation is segregating in Drosophila americana and has been fixed in its sister species *Drosophila novamexicana* which has a derived pale phenotype (Wittkopp et al. 2009). However, although the "plasticity first hypothesis" does not apply to all traits, it is worth investigating it empirically. The flexible stem model of adaptive radiation predicts that the pattern of phenotypic divergence between derived lineages should mirror the pattern of developmental plasticity in their common ancestor (Wund et al. 2008). Several studies have provided empirical morphological data strongly suggesting that it could occur in nature (Wund et al. 2008). For example, the pharyngeal jaws of midas cichlids show a morphological plasticity in response to the hardness of the diet which parallels the morphological diversity observed between specialised species (Muschick et al. 2011). Similarly, stress-induced changes in mandible shape in *Sorex* shrews correspond to traits showing divergence between species (Badyaev and Foresman 2000). What we would like to review and discuss in this article is the underlying genetic bases of the flexible stem hypothesis. Indeed, under this hypothesis, it is expected that the genetic mechanisms that generate the plastic phenotypes should be the same as those that generate the phenotypic divergence. The idea that phenotypic plasticity is under genetic control was initially developed by Bradshaw (Bradshaw 1965) and a recurrent question was the existence and the nature of "plasticity genes" (Via et al. 1995). However, Via considered that modifications of reaction norms was an indirect consequence of the selection on

120

121

122

123

124

125

126

127

128

129

130

131

132

133

134

135

136

137

138

139

140

141

142

143

the mean phenotype in each separate environment and that no plasticity genes were required (Via 1993). Scheiner, Schlichting and Pigliucci objected to Via that the plasticity of a trait could evolve independently of the mean of the trait because the plasticity and the mean of the trait are under the control of different genes (Scheiner 1993; Schlichting and Pigliucci 1993). This debate settled down in the mid nineties in favour of the existence of plasticity genes. Two kinds of genetic mechanisms involved in phenotypic plasticity were proposed (Via et al. 1995). The first one, "allelic sensitivity", refers to alleles expressed differently in distinct environment. This could correspond to a single gene showing transcriptional plasticity or to an enzyme active in only some environmental conditions for example. The second genetic mechanism, "gene regulation", corresponds to a regulatory switch under environmental control, which would lead to the activation of a panel of target genes depending on the environment. Obviously, the two mechanisms may blur as the regulatory *locus* influences the amount of products of its targets, thus mediating allelic sensitivity (Via et al. 1995). Clearly, a great deal of information could be gained by genetic dissection of phenotypic plasticity in a variety of organisms. A few empirical studies have identified genes involved in the phenotypic plasticity of particular traits and in several cases, data are available regarding genes involved in the variation within or between species of the traits of interest. Thus, it is possible to analyse the genetic changes that underlie genetic assimilation of initially plastic traits. Furthermore, several studies have dissected the mechanisms involved in phenotypic plasticity and environmental canalization. The typical questions we would like to address are the following: What are the relationships between genes involved in phenotypic plasticity of a

145

146

147

148

149

150

151

152

153

154

155

156

157

158

159

160

161

162

163

164

165

166

167

168

trait and genes involved in the evolution of this trait? What kind of mutations are selected during the evolution of these traits? Are they regulatory or coding mutations? Do they target *cis*-regulatory sequences of a modulated gene or *trans*-acting factors? How is it possible to make independent of the environment an initially plastic trait? We present here several examples of phenotypic plasticity, chosen in animals or plants, whose genetic bases have been addressed through candidate gene approach or global transcriptome analyses. Most of these analyses are performed in an evolutionary context (either artificial or natural) or can be complemented by other studies on the evolution of the particular traits of interest in closely related species. Furthermore, we describe studies dissecting the mechanisms involved in phenotypic plasticity and environmental canalisation. Modulation of such mechanisms must be involved in the environmental canalization of initially plastic traits involved in the flexible stem hypothesis.

Ether-induced *Ultrabithorax* phenocopies in *Drosophila*

Treatment of *Drosophila* embryos with ether vapor leads to phenocopies of the *bithorax* mutant in adults (Waddington 1956). This corresponds to partial homeotic transformation of the third thoracic segment into the second thoracic segment. In *Drosophila*, like in all dipterans, the dorsal appendages of the third thoracic segments are not wings but little round structures named halteres. In *bithorax* phenocopies, halteres are partially transformed into wings and the postnotum is partially transformed into an additional mesonotum (Figure 1). Waddington showed that this ether-induced phenotype can be genetically assimilated (Waddington 1956). By selection after ether treatment at each

generation, he could progressively increase the proportion of individual showing the *bithorax* phenocopy. At the eighth generation, this phenotype was observed in some individuals even in the absence of ether treatment (Figure 1). The *bithorax* phenotype was therefore genetically assimilated. Waddington experiments were repeated by Gibson and Hogness (Gibson and Hogness 1996). They analysed the expression of the homeotic gene *Ultrabithorax* (*Ubx*) which is expressed in haltere but not wing imaginal disc and is responsible for the different identities of these organs. They showed that ether-induced *bithorax* phenocopies are caused by clonal loss of expression of *Ubx* in the haltere imaginal disc. Furthermore, using polymorphism in *Ubx*, they could show that the frequency of particular alleles of *Ubx* increased during genetic assimilation of the *bithorax* phenotype. The *Ubx* polymorphism was not the only source of genetic variation affecting sensitivity to ether, but it had a major effect. Thus, *Ubx* expression is sensitive to ether and during genetic assimilation of this phenotype, artificial selection targeted the *Ubx* locus itself.

Transcriptional response to osmotic challenge in killifish:

The Atlantic killifish (*Fundulus heteroclitus*) can be found along a steep salinity gradient in Atlantic coast estuaries and can quickly adjust to extremes in environmental salinity (Figure 2). Thus, this species is able to occupy an extremely wide osmotic niche. Hypo-osmotic challenge induces a change of cellular morphology of the apical surface of the gill epithelium (Whitehead et al. 2011) (Figure 2). In sea water, the apical surface of the gill epithelium is made of pavement cells interspersed with mitochondrion-rich cells possessing apical crypt with small surface area (Whitehead et al. 2011). Exposure to fresh water

leads to enlargement of the apical surface of mitochondrion-rich cells. This modification occurs within a few days, but its speed and the precise morphology of the gill epithelium differs between populations originating from different point of the salinity gradient. Analysis of the transcriptome of gills in fish submitted to hypo-osmotic challenge allowed to identify sets of genes whose expression was modulated by salinity (Whitehead et al. 2011). It was found that genes showing transcriptional plasticity during osmotic challenge are more likely to show divergence of expression between populations living in different environment (Whitehead et al. 2011, 2012). Indeed, many of the genes modulated during hypo-osmotic challenge show adaptive divergence in expression in populations living exclusively in freshwater habitat. Among these genes, many have a well known role in osmotic regulation, for example Aquaporin 3 (AQP3), the sodium/potassium transporting ATPAse ATP1A1 or versican (VCAN) (Whitehead et al. 2012).

Plasticity of wing eyespots in the butterfly Bicyclus anynana

The African satyrine butterfly *Bicyclus anynana* shows seasonal polyphenisms. In the wet season morph, conspicuous eyespots made of concentric rings of differently pigmented scales are observed on the ventral wings. In the dry season morph, the ventral eyespots are absent. Only a reduced version of the white spot in the centre of the eyespot is visible. The wet and dry season morphs can be produced in the laboratory by rearing the larvae at 27°C or 17°C respectively (Brakefield et al. 1996) (Figure 3).

Many developmental regulatory genes are expressed in developing eyespots of *Bicyclus anynana*, among which *Distal-less (Dll)* which is expressed in the future

centre of the eyespot (Brakefield et al. 1996; Shirai et al. 2012). This is not simply a correlation as it was recently shown by gain and loss of function experiments using transgenic Bicyclus anynana that Dll is involved in eyespot formation (Monteiro et al. 2013). Indeed, overexpression of *Dll* increases eyespot size and induces ectopic eyespots. Conversely, decreasing *Dll* expression reduces eyespot size. Furthermore, the expression of *Dll* in presumptive eyespots is modulated by temperature: it is stronger and wider in pupae grown at 27°C that will produce the wet season morph (Brakefield et al. 1996). Thus, Dll is one of the genes involved in eyespot plasticity. It is possible to fix alternative morphs by artificial selection performed at intermediate temperature. This lead to a LOW line and a HIGH line showing almost non plastic dry season and wet season phenotypes, respectively (Brakefield et al. 1996) (Figure 3). Thus, the wet or dry season morphs can be genetically assimilated and become virtually independent of the rearing temperature. This correlates with a modification of *Dll* expression, which is stronger and wider in pupae of the HIGH line than in pupae of the LOW line grown in the same environmental conditions. Thus, genetic assimilation of the alternative seasonal morphs has involved modulation of *Dll* expression. Whether this genetic assimilation was caused by selection at the Dll locus itself (cis variation) or by trans-acting factors was not tested in this experiment. However, another selection experiment targeting the size of dorsal eyespots (which however are not plastic), showed that natural genetic variation in *Dll* was linked to eyespot size variation in Bicyclus anynana (Beldade et al. 2002). Thus, variation at the Dll locus with significant impact on eyespot patterning exists in Bicyclus anynana.

245

246

247

248

249

250

251

252

253

254

255

256

257

258

259

260

261

262

263

264

265

266

267

268

272

273

274

275

276

277

278

279

280

281

282

283

284

285

286

287

288

289

290

291

292

293

294

Polyphenism of cuticular teeth in diplogastrid nematods

The diplogastrid nematod *Pristionchus pacificus* displays two alternative tooth morphs, stenostomatous (St) or eurystomatous (Eu), that are produced after an irreversible decision during larval development (Bento et al. 2010) (Figure 4). Eu morph is adapted to predation on other nematods, whereas St morph is adapted to bacterial diet. The ratio of individuals with St or Eu teeth varies between strains but is also influenced by environmental factors such as crowding and starvation (Bento et al. 2010; Ragsdale et al. 2013). The high expression of the gene eud-1, encoding a sulfatase, is necessary and sufficient to produce the Eu phenotype in *Pristionchus pacificus* (Ragsdale et al. 2013). Loss of function mutations of *eud-1* are dominant and lead to the St phenotype. Difference of the Eu/St ratio between wild isolates of Pristonchus pacificus correlates with difference in eud-1 expression. Furthermore, eud-1 overexpression of is sufficient to transform high St strains into Eu ones. The role of eud-1 in tooth dimorphism extends to the other diplogastrid species *Pristionchus* exspectacus (Ragsdale et al. 2013). Indeed, through hybrid crosses between various P. pacificus lines and a P. exspectacus St line, it was shown that the St phenotype of the *P. exspectatus* line was caused by a low expression of *eud-1*. As transformation of P. pacificus eud-1 mutant with the eud-1 allele of the P. exspectatus St line leads to a Eu phenotype, the eud-1 allele of P. exspectacus is functional and differences of eud-1 expression between P. pacificus and P. exspectacus are caused by differences in trans-acting factors. Thus, divergence in the ratio of tooth morphs might have involved several components of the eud-1 network.

It is thought that the stem species in diplogastrid nematods was polyphenic (Kiontke and Fitch 2010). Many descendant species such as *Pristionchus pacificus* have kept both morphs, but others have become exclusively Eu or St. Interestingly, recent morphometric analysis of diplogastrid mouth structures in a more global evolutionary framework revealed a rapid process of diversification associated with developmental plasticity (Susoy et al. 2015): The gain of dimorphic mouth structures was associated with an increase rate of evolution and the appearance of numerous new species with diversified mouth parts.

Modulation of leaf margin dissection by temperature in Capsella

The two brassicaceae sister species *Capsella rubella* and *Capsella grandiflora* show differences in leaf margin dissection (Sicard et al. 2014). Leaf margin dissection is more pronounced in *Capsella rubella* and is increased at low temperature (16°C *versus* 22°C). It was shown that the major locus responsible for the difference in leaf margin dissection between *C. rubella* and *C. grandiflora* is the homeobox gene *RCO-A* which is expressed in sinuses between growing lobes of developing leaves in *C. rubella* (Sicard et al. 2014). This difference of expression level is caused by insertions in the *C. rubella RCO-A* promoter. The effect of the *RCO-A* region on leaf margin dissection is visible in nearly isogenic lines differing only in the region of *RCO-A*, *NILgg* (carrying the *RCO-A* allele of *C. grandiflora*) and *NILrr* (carrying the *RCO-A* allele of *C. rubella*) (Figure 5). In addition, *RCO-A* expression is strongly modulated by temperature. Expression of the *C. grandiflora RCO-A* allele is extremely weak at 22°C and the leaves show no dissection. This allele is up-regulated more than 150 folds at 16°C compared to 22°C, which leads to leaf margin dissection. The *C. rubella RCO-A* allele is more

expressed than the *C. grandiflora one* at 22°C and is upregulated less than 5 folds between 22°C and 16°C. Consequently, it leads to leaf margin dissection at both temperatures in *C. rubella*.

In another brassicae species, *Arabidopsis thaliana*, the *RCO-A* locus is deleted and there is no leaf margin dissection. Insertion of transgenes carrying *Capsella rubella RCO-A* gene in *Arabidopsis thaliana* is sufficient to induce leaf margin dissection (Sicard et al. 2014).

Thus, the same *locus* is directly involved in phenotypic plasticity and species divergence regarding leaf margin dissection. However, as the activity of the regulatory sequences of *RCO-A* responsible for the difference of expression between the two *Capsella* species was not studied with a reporter gene in transgenic lines grown at different temperatures, it is not known whether they

Thermal plasticity of abdominal pigmentation in *Drosophila melanogaster*

also mediate the effect of the environment.

females

Cold induces melanism in many insects (Gibert et al. 2000; Michie et al. 2010; Fedorka et al. 2013). This is thought to be beneficial as dark pigmentation increases body temperature. However, pigmentation is highly pleiotropic and is also correlated to many other traits such as longevity, fecundity or immunity (Wittkopp and Beldade 2009; Fedorka et al. 2013; Kutch et al. 2014; Rajpurohit et al. 2016). In *Drosophila melanogaster* females, abdominal pigmentation is strongly modulated by temperature (Figure 6). This is particularly pronounced in the more posterior segments (A5, A6 and A7) (Gibert et al. 2000). Correspondingly, the expression of several genes encoding the enzymes of the

cuticular pigment synthesis pathway in the abdominal epidermes of late pupae and young adults is modulated by temperature (Gibert et al. 2016, 2017). However, among them, the gene tan stands out, being expressed seven times more in the abdominal epidermis of young females grown at 18°C than 29°C. The activity of tan increases melanin production and genetic experiments showed that temperature modulation of *tan* expression plays an essential role in thermal plasticity of female abdominal pigmentation (Gibert et al. 2016). Furthermore, temperature modulates the activity of the tan abdominal enhancer (t_MSE) and the level of the active histone mark H3K4me3 on tan promoter. Interestingly, tan is well known for its involvement in pigmentation variation and divergence in the Drosophila melanogaster species subgroup. In Drosophila melanogaster, independent genome wide association studies performed on European, African and American populations have identified single nucleotide polymorphisms in the *t_MSE* involved in variation of female abdominal pigmentation (Bastide et al. 2013; Dembeck et al. 2015; Endler et al. 2015). In Drosophila erecta, female dimorphic pigmentation is caused by genetic variation in the t MSE maintained by balancing selection (Yassin et al. 2016). In Drosophila santomea, several independent loss of function mutations located in the *t_MSE* have lead to the light phenotype of this species, whereas in the sister species Drosophila yakuba a functional *t-MSE* enhancer is associated with dark abdominal pigmentation (Jeong et al. 2008). Thus, in the *Drosophila melanogaster* species subgroup, plasticity and variation between species of abdominal pigmentation work through modulation of the same gene and involves genetic changes in the very same regulatory sequence, *t_MSE*, that also mediates the effect of temperature on tan expression in *Drosophila melanogaster*.

345

346

347

348

349

350

351

352

353

354

355

356

357

358

359

360

361

362

363

364

365

366

367

368

372

373

374

375

376

377

378

379

380

381

382

383

384

385

386

387

388

389

390

391

392

393

394

Discussion

These examples demonstrate that several genes showing transcriptional plasticity in response to environmental changes are differentially expressed within and/or between species and contribute to phenotypic variation and/or divergence. Thus, the same genes respond to the environment and are involved in evolution. It might seem predictable that the same genes are involved in the plasticity of a trait and the variation/evolution of this trait. However, this is not so obvious. Indeed, the same phenotypes can sometimes be produced by different mechanisms. For example, *Drosophila* wing size can be modulated by both temperature and clinal genetic variation. However, this occurs through distinct mechanisms: temperature modulates cell size (Azevedo et al. 2002), whereas clinal genetic variation primarily affects cell number (James et al. 1995). Similar pigmentation phenotypes can be produced by modulating the expression of different pigmentation genes (Wittkopp et al. 2003). For example, melanin production can be increased by up-regulating tan or down-regulating ebony, that encode enzymes with antagonist activities (True et al. 2005). In the case of RCO-A and tan, the variation or divergence in expression is caused by mutations in the *cis*-regulatory sequences of the genes. This is also likely the case for *Ubx* during genetic assimilation of the *bithorax* phenotype. Remarkably, for tan, the same cis-regulatory sequence mediates, at least partly, the effect of temperature. It is generally thought that cis-regulatory mutations are less pleiotropic than mutations in *trans*-acting factors (Prud'homme et al. 2007). Thus, targeting tan, a gene encoding a pigmentation enzyme, or RCO-A, whose expression is limited to the sinuses between growing leaf lobes, limit potential

deleterious effects. The recurrent involvement of *RCO-A* and *tan* in evolution lead to their characterization as evolutionary hotspots (Martin and Orgogozo 2013; Sicard et al. 2014). Why are these two genes targets of recurrent evolution? For a given allele, temperature sensitivity of RCO-A and tan expression leads to different phenotypes in different environments. Reciprocally, different alleles will induce different phenotypes in the same environment. It follows that only some genotypes will produce an optimal phenotype in a given environment. This may lead to selection of different alleles of these genes in different environments to reach an optimal phenotype. This is in particular the case if the phenotype produced by the plastic response is not well adjusted to the environment. Genetic variation will be selected to reduce or to increase the effect of the environment. As the environment fluctuates spatially and temporally, adjusting selection increases genetic variation with functional consequences at these *loci*. This higher genetic variation facilitates the involvement of those loci in evolution. In the other cases presented in this review, the respective contributions of *cis* and trans variations are not known (eud-1 in P. pacificus, genes modulated by osmotic challenge in Fundulus, Dll in Bicyclus anynana) but the recent identification of trans-regulators of eud-1 is a step towards answering this question (Serobyan et al. 2016). However, what is clear is that evolution has targeted components of the gene networks regulating the transcriptionally plastic genes if not these genes themself. In most cases described in this review, the gene showing transcriptional plasticity also exhibits genetic variation that provides substrate for evolution through selection or simply drift. The fact that the same networks, or even the same genes, are involved in plasticity and

395

396

397

398

399

400

401

402

403

404

405

406

407

408

409

410

411

412

413

414

415

416

417

418

evolution contradicts somehow Scheiner's ideas on the decoupling of the genetic processes controlling the plasticity and the mean of a trait (Scheiner 1993). In addition, the "flexible stem hypothesis" implies that it is mechanistically possible for a trait initially plastic to undergo environmental canalization and become independent of the environment. Several studies have dissected the mechanisms behind phenotypic plasticity and environmental canalization. Two major mechanisms have been identified: regulation of chromatin structure and hormonal signalling/response. It is known that environmental conditions can modulate DNA methylation (Kucharski et al. 2008), histone post-translational modifications (Simola et al. 2016; Gibert et al. 2016) or chromatin compaction (Leung et al. 2014). Thus, stabilization of chromatin structure in an initially plastic species, could lead to production of a constant phenotype independent of the environment. For example, artificial down-regulation of DNA methylation in honey-bees lead to the production of a queen phenotype from larvae that should have developed as workers because on the diet they fed on (Kucharski et al. 2008). Some alleles might carry variation in their *cis*-regulatory sequences that promotes the formation of a particular chromatin structure independently of the environment. This might be the case for tan or Ubx and selection on this variation might contribute to modify the sensitivity of their expression to the environment. Regarding, hormonal regulation, it is known that differences of plasticity between genotypes could be linked to differences of hormonal signalling or response (Suzuki and Nijhout 2006). In Manduca sexta larvae, artificial selection on temperature induced pigmentation variation lead to the production of a polyphenic and a monophenic lines differing by their juvenile hormone titer and response (Suzuki and Nijhout 2006). Interestingly a similar

420

421

422

423

424

425

426

427

428

429

430

431

432

433

434

435

436

437

438

439

440

441

442

443

process applies to differences of plasticity between organs. In Drosophila, the size of late larval brain and adult male genitalia is buffered against nutrient restriction, whereas the size of other organs decreases under these conditions. The buffering of genitalia size is caused by repression of *FOXO* expression in the genital disc which makes it insensitive to the nutritional information provided by insulin signalling (Tang et al. 2011). The buffering of late larval brain size is caused by cell-type specific expression of Alk and its ligand Jelly Belly which renders neuroblasts insensitive to amino acid and insulin sensing (Cheng et al. 2011). Thus, by modifying the expression of key genes involved in hormonal signalling or response it is possible to reduce or even abolish the influence of the environment on a given trait. These studies illustrate what kind of mechanisms might be involved in the genetic assimilation taking place during the formation of a monophenic lineage under the "flexible stem hypothesis". The examples described in this review are compatible with the "flexible stem hypothesis" (West-Eberhard 2003), which postulate ancestral plasticity followed by genetic assimilation of alternative morphs in derived lineages. Analysis of phenotypic plasticity of nematod feeding structures in an evolutionary framework supports indeed that plasticity was ancestral and that one morph was stabilized (genetically assimilated) in particular lineages whereas others have kept plasticity (Kiontke and Fitch 2010). A definite demonstration of the "flexible stem hypothesis" would be to follow allelic frequencies during genetic assimilation of a phenotype of interest. This was done in only one of the examples, but for a deleterious phenotype normally not observed in the wild, i.e. the bithorax phenocopies (Gibson and Hogness 1996). Thus, more studies on the genetic bases of phenotypic plasticity in an evolutionary conceptual framework

445

446

447

448

449

450

451

452

453

454

455

456

457

458

459

460

461

462

463

464

465

466

467

468

470	are needed. In particular, it would be interesting to know whether the example
471	of tan and its t_MSE is just a particular case or whether it is predictive of a more
472	systematic involvement of the same regulatory sequences in phenotypic
473	plasticity and species variation and divergence.
474	
475	
476	
477	References:
478 479 480	Azevedo RBR, French V, Partridge L (2002) Temperature modulates epidermal cell size in Drosophila melanogaster. J Insect Physiol 48:231–237.
481 482 483 484	Badyaev AV, Foresman KR (2000) Extreme environmental change and evolution: stress-induced morphological variation is strongly concordant with patterns of evolutionary divergence in shrew mandibles. Proc Biol Sci 267:371–7.
485 486 487	Bastide H, Betancourt A, Nolte V, et al (2013) A Genome-Wide, Fine-Scale Map of Natural Pigmentation Variation in Drosophila melanogaster. PLoS Genet 9:e1003534. doi: 10.1371/journal.pgen.1003534
488 489 490	Beldade P, Brakefield PM, Long AD (2002) Contribution of Distal-less to quantitative variation in butterfly eyespots. Nature 415:315–318. doi: 10.1038/415315a
491 492 493	Bento G, Ogawa A, Sommer RJ (2010) Co-option of the hormone-signalling module dafachronic acid-DAF-12 in nematode evolution. Nature 466:494–497. doi: 10.1038/nature09164
494 495 496	Bradshaw AD (1965) Evolutionary Significance of Phenotypic Plasticity in Plants. In: Thoday EWC and JM (ed) Advances in Genetics. Academic Press, pp 115–155
497 498	Brakefield PM, Gates J, Keys D, et al (1996) Development, plasticity and evolution of butterfly eyespot patterns. Nature 384:236–42.
499 500 501	Cheng LY, Bailey AP, Leevers SJ, et al (2011) Anaplastic lymphoma kinase spares organ growth during nutrient restriction in Drosophila. Cell 146:435–447 doi: 10.1016/j.cell.2011.06.040

502 503 504	Dembeck LM, Huang W, Magwire MM, et al (2015) Genetic Architecture of Abdominal Pigmentation in Drosophila melanogaster. PLoS Genet 11:e1005163. doi: 10.1371/journal.pgen.1005163
505 506 507	Dworkin I (2005) Towards a genetic architecture of cryptic genetic variation and genetic assimilation: the contribution of K. G. Bateman. J Genet 84:223–226.
508 509 510 511	Endler L, Betancourt AJ, Nolte V, Schlötterer C (2015) Reconciling Differences in Pool-GWAS between Populations: A Case Study of Female Abdominal Pigmentation in Drosophila melanogaster. Genetics. doi: 10.1534/genetics.115.183376
512 513 514 515	Fedorka KM, Copeland EK, Winterhalter WE (2013) Seasonality influences cuticle melanization and immune defense in a cricket: support for a temperature-dependent immune investment hypothesis in insects. J Exp Biol 216:4005–10. doi: 10.1242/jeb.091538
516 517 518	Ghalambor CK, Hoke KL, Ruell EW, et al (2015) Non-adaptive plasticity potentiates rapid adaptive evolution of gene expression in nature. Nature 525:372–375. doi: 10.1038/nature15256
519 520 521 522	Gibert J-M, Mouchel-Vielh E, De Castro S, Peronnet F (2016) Phenotypic Plasticity through Transcriptional Regulation of the Evolutionary Hotspot Gene tan in Drosophila melanogaster. PLoS Genet 12:e1006218. doi: 10.1371/journal.pgen.1006218
523 524 525	Gibert J-M, Mouchel-Vielh E, Peronnet F (2017) Modulation of yellow expression contributes to thermal plasticity of female abdominal pigmentation in Drosophila melanogaster. Sci Rep 7:43370. doi: 10.1038/srep43370
526 527 528	Gibert P, Moreteau B, David JR (2000) Developmental constraints on an adaptive plasticity: reaction norms of pigmentation in adult segments of Drosophila melanogaster. Evol Dev 2:249–60.
529 530	Gibson G, Hogness DS (1996) Effect of polymorphism in the Drosophila regulatory gene Ultrabithorax on homeotic stability. Science 271:200–3.
531 532	Gilbert SF (2001) Ecological developmental biology: developmental biology meets the real world. Dev Biol 233:1–12. doi: 10.1006/dbio.2001.0210
533 534	James AC, Azevedo RB, Partridge L (1995) Cellular basis and developmental timing in a size cline of Drosophila melanogaster. Genetics 140:659–66.
535 536 537	Jeong S, Rebeiz M, Andolfatto P, et al (2008) The evolution of gene regulation underlies a morphological difference between two Drosophila sister species. Cell 132:783–93.
538	Johannsen W (1911) The genotype conception of heredity. Am Nat XLV:129–159.

539 540	Kiontke K, Fitch DHA (2010) Phenotypic plasticity: different teeth for different feasts. Curr Biol CB 20:R710-712. doi: 10.1016/j.cub.2010.07.009
541 542 543	Kucharski R, Maleszka J, Foret S, Maleszka R (2008) Nutritional control of reproductive status in honeybees via DNA methylation. Science 319:1827–30.
544 545 546	Kutch IC, Sevgili H, Wittman T, Fedorka KM (2014) Thermoregulatory strategy may shape immune investment in Drosophila melanogaster. J Exp Biol 217:3664–9. doi: 10.1242/jeb.106294
547 548	Laland K, Uller T, Feldman M, et al (2014) Does evolutionary theory need a rethink? Nature 514:161–164. doi: 10.1038/514161a
549 550 551	Laland KN, Uller T, Feldman MW, et al (2015) The extended evolutionary synthesis: its structure, assumptions and predictions. Proc Biol Sci 282:20151019. doi: 10.1098/rspb.2015.1019
552 553 554	Leung A, Parks BW, Du J, et al (2014) Open chromatin profiling in mice livers reveals unique chromatin variations induced by high fat diet. J Biol Chem. doi: 10.1074/jbc.M114.581439
555 556 557	Martin A, Orgogozo V (2013) The Loci of repeated evolution: a catalog of genetic hotspots of phenotypic variation. Evolution 67:1235–50. doi: 10.1111/evo.12081
558 559 560 561	Michie LJ, Mallard F, Majerus ME, Jiggins FM (2010) Melanic through nature or nurture: genetic polymorphism and phenotypic plasticity in Harmonia axyridis. J Evol Biol 23:1699–707. doi: 10.1111/j.1420-9101.2010.02043.x
562 563	Moczek AP, Sultan S, Foster S, et al (2011) The role of developmental plasticity in evolutionary innovation. Proc Biol Sci. doi: 10.1098/rspb.2011.0971
564 565 566	Monteiro A, Chen B, Ramos DM, et al (2013) Distal-less regulates eyespot patterns and melanization in Bicyclus butterflies. J Exp Zoolog B Mol Dev Evol 320:321–331. doi: 10.1002/jez.b.22503
567 568 569 570	Muschick M, Barluenga M, Salzburger W, Meyer A (2011) Adaptive phenotypic plasticity in the Midas cichlid fish pharyngeal jaw and its relevance in adaptive radiation. BMC Evol Biol 11:116. doi: 10.1186/1471-2148-11-116
571 572	Pfennig DW, Wund MA, Snell-Rood EC, et al (2010) Phenotypic plasticity's impacts on diversification and speciation.
573 574	Pigliucci M (2001) Phenotypic Plasticity, Beyond Nature and Nurture. Baltimore and London
575 576	Prud'homme B, Gompel N, Carroll SB (2007) Emerging principles of regulatory evolution. Proc Natl Acad Sci U A 104 Suppl 1:8605–12.

577 578 579	Ragsdale EJ, Müller MR, Rödelsperger C, Sommer RJ (2013) A developmental switch coupled to the evolution of plasticity acts through a sulfatase. Cell 155:922–933. doi: 10.1016/j.cell.2013.09.054
580 581 582	Rajpurohit S, Richardson R, Dean J, et al (2016) Pigmentation and fitness trade- offs through the lens of artificial selection. Biol Lett. doi: 10.1098/rsbl.2016.0625
583 584	Scheiner SM (1993) Plasticity as a Selectable Trait: Reply to Via. Am Nat 142:371–373.
585 586	Schlichting CD, Pigliucci M (1993) Control of phenotypic plasticity via regulatory genes. Am Nat 142:366–370. doi: 10.1086/285543
587 588	Schmalhausen II (1949) Factors of Evolution, The Theory of Stabilizing Selection The University of Chicago Press, Chicago and London
589 590 591	Schneider RF, Meyer A (2017) How plasticity, genetic assimilation and cryptic genetic variation may contribute to adaptive radiations. Mol Ecol 26:330–350. doi: 10.1111/mec.13880
592 593	Schwander T, Leimar O (2011) Genes as leaders and followers in evolution. Trends Ecol Evol 26:143–151. doi: 10.1016/j.tree.2010.12.010
594 595 596 597	Serobyan V, Xiao H, Namdeo S, et al (2016) Chromatin remodelling and antisense-mediated up-regulation of the developmental switch gene eud-1 control predatory feeding plasticity. Nat Commun 7:12337. doi: 10.1038/ncomms12337
598 599 600 601	Shirai LT, Saenko SV, Keller RA, et al (2012) Evolutionary history of the recruitment of conserved developmental genes in association to the formation and diversification of a novel trait. BMC Evol Biol 12:21. doi: 10.1186/1471-2148-12-21
602 603 604	Sicard A, Thamm A, Marona C, et al (2014) Repeated evolutionary changes of leaf morphology caused by mutations to a homeobox gene. Curr Biol 24:1880-6. doi: 10.1016/j.cub.2014.06.061
605 606 607	Simola DF, Graham RJ, Brady CM, et al (2016) Epigenetic (re)programming of caste-specific behavior in the ant Camponotus floridanus. Science. doi: 10.1126/science.aac6633
608 609 610	Susoy V, Ragsdale EJ, Kanzaki N, Sommer RJ (2015) Rapid diversification associated with a macroevolutionary pulse of developmental plasticity. eLife. doi: 10.7554/eLife.05463
611 612	Suzuki Y, Nijhout HF (2006) Evolution of a polyphenism by genetic accommodation. Science 311:650–2.

513 514 515	specific phenotypic plasticity in Drosophila. PLoS Genet 7:e1002373. doi: 10.1371/journal.pgen.1002373
616 617	True JR, Yeh SD, Hovemann BT, et al (2005) Drosophila tan Encodes a Novel Hydrolase Required in Pigmentation and Vision. PLoS Genet 1:e63.
618 619	Via S (1993) Adaptive phenotypic plasticity: target or by-product of selection in a variable environment? Am Nat 142:352–365. doi: 10.1086/285542
620 621	Via S, Gomulkievicz R, de Jong G, et al (1995) Adaptive phenotypic plasticity: consensus and controversy. TREE 10:212–217.
622 623	Waddington CH (1952) Selection of the genetic basis for an acquired character. Nature 169:278.
624 625	Waddington CH (1956) Genetic Assimilation of the Bithorax Phenotype. Evolution 10:1–13. doi: 10.2307/2406091
626 627	Waddington CH (1959) Canalization of development and genetic assimilation of acquired characters. Nature 183:1654–5.
628 629	West-Eberhard MJ (2003) Developmental plasticity and evolution. Oxford University Press, New York
630 631	West-Eberhard MJ (2005) Developmental plasticity and the origin of species differences. Proc Natl Acad Sci U A 102 Suppl 1:6543–9.
632 633 634 635	Whitehead A, Roach JL, Zhang S, Galvez F (2011) Genomic mechanisms of evolved physiological plasticity in killifish distributed along an environmental salinity gradient. Proc Natl Acad Sci U A 108:6193–8. doi: 10.1073/pnas.1017542108
636 637 638 639	Whitehead A, Roach JL, Zhang S, Galvez F (2012) Salinity- and population-dependent genome regulatory response during osmotic acclimation in the killifish (Fundulus heteroclitus) gill. J Exp Biol 215:1293–1305. doi: 10.1242/jeb.062075
640 641 642	Wittkopp PJ, Beldade P (2009) Development and evolution of insect pigmentation: genetic mechanisms and the potential consequences of pleiotropy. Semin Cell Dev Biol 20:65–71.
643 644 645	Wittkopp PJ, Stewart EE, Arnold LL, et al (2009) Intraspecific polymorphism to interspecific divergence: genetics of pigmentation in Drosophila. Science 326:540–4. doi: 10.1126/science.1176980
646 647 648	Wittkopp PJ, Williams BL, Selegue JE, Carroll SB (2003) Drosophila pigmentation evolution: divergent genotypes underlying convergent phenotypes. Proc Natl Acad Sci U A 100:1808–13.

649 650 651	Woltereck R (1909) Weitere experimentelle unters "uchungen "uber artver anderung, speziell "uber das wesen quantitativer artunterschiede bei daphniden. Verhandlungen Dtsch. Zooligischen Ges. 110–172.
652 653 654 655	Wund MA, Baker JA, Clancy B, et al (2008) A test of the "flexible stem" model of evolution: ancestral plasticity, genetic accommodation, and morphological divergence in the threespine stickleback radiation. Am Nat 172:449–462. doi: 10.1086/590966
656 657 658	Yassin A, Bastide H, Chung H, et al (2016) Ancient balancing selection at tan underlies female colour dimorphism in Drosophila erecta. Nat Commun 7:10400. doi: 10.1038/ncomms10400
559	

Figure legends:

Figure 1: Above: wild-type *Drosophila melanogaster* female. Bellow: female *Drosophila* showing a *bithorax* phenotype obtained after genetic assimilation of the *bithorax* phenocopy initially induced by ether treatment of the embryo (modified after (Waddington 1956)). The post-notum is replaced by an additional meso-notum and halteres are replaced by rudimentary wings.

Figure 2: Left: the network of rivers flowing into the Chesapeake-bay, in northeast America, constitutes a range of water habitat with different salinity going from pure sea water (dark blue) to pure fresh water (red), modified after (Whitehead et al. 2011). Top right, populations of Atlantic killifish (Fundulus heteroclitus) are locally adapted to particular salinities but are also able to quickly adjust to osmotic challenges. Bottom right: modification of gill epithelium after transfer form sea water to fresh water (after (Whitehead et al. 2012)). In sea water (32 ppt), the apical surface of the gill epithelium is made of pavement cells (red asterisk) interspersed with mitochondrion-rich cells possessing apical crypt with small surface area (green arrowhead). Exposure to fresh water (0.1 ppt) leads to an enlargement of the apical surface of mitochondrion-rich cells (green arrowhead).


Figure 3: Top: natural populations of the satyrine butterfly *Bicyclus anynana* show two seasonal morphs, the dry season morph (left) and the wet season morph (right) that can be produced in the lab by rearing the larvae at 17°C or 27°C, respectively. Middle and bottom: the dry season and the wet season


morphs can be fixed by artificial selection leading to a LOW line (middle) or a HIGH line (bottom) with very limited plasticity (after (Brakefield et al. 1996)).


Figure 4: The diplogastrid nematod *Pristionchus pacificus* displays two alternative tooth morphs: a wide one, eurystomatous (Eu, left) or a narrow one stenostomatous (St, right), that are produced after an irreversible decision during larval development (after (Kiontke and Fitch 2010)). The ratio of these two morphs is variable between strains and is modulated by environmental factors such as crowding and starvation.


Figure 5: Capsella grandiflora and Capsella rubella differ regarding the dissection of their leaf margins. This difference was mapped to the RCO-A locus. Above nearly isogenic lines (NIL) differing only in the RCO-A locus region. The line with the C. grandiflora allele (NILgg) (left) does not show any leaf margin dissection at 22°C contrary to the line with the C. rubella allele (NILrr) (right). Lower temperature (16°C) induces (NILgg) or increases (NILrr) leaf margin dissection.


Figure 6: Abdominal cuticles of females *Drosophila melanogaster* from an inbred line (w^{1118}) grown at 18°C (left) or 29°C (right). Female abdominal pigmentation is sensitive to temperature during development in particular in the most posterior segments (A5, A6 and A7). Anterior is up, ventral is left (after (Gibert et al. 2016)).











714 Eurystomatous (Eu)

Stenostomatous (St)

