



HAL
open science

Highly-ionized metals as probes of the circumburst gas in the natal regions of gamma-ray bursts

K.E. Heintz, D. Watson, P. Jakobsson, J.P. U. Fynbo, J. Bolmer, M.
Arabsalmani, Z. Cano, S. Covino, V. d'Elia, A. Gomboc, et al.

► **To cite this version:**

K.E. Heintz, D. Watson, P. Jakobsson, J.P. U. Fynbo, J. Bolmer, et al.. Highly-ionized metals as probes of the circumburst gas in the natal regions of gamma-ray bursts. *Monthly Notices of the Royal Astronomical Society*, 2018, 479 (3), pp.3456-3476. 10.1093/mnras/sty1447 . hal-01853902

HAL Id: hal-01853902

<https://hal.science/hal-01853902>

Submitted on 4 May 2023

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

Highly ionized metals as probes of the circumburst gas in the natal regions of gamma-ray bursts

K. E. Heintz,^{1,2,3★} D. Watson,^{2,3} P. Jakobsson,¹ J. P. U. Fynbo,^{2,3} J. Bolmer,⁴
M. Arabsalmani,^{5,6} Z. Cano,⁷ S. Covino,⁸ V. D’Elia,⁹ A. Gomboc,¹⁰ J. Japelj,¹¹
L. Kaper,¹² J.-K. Krogager,^{13,3} G. Pugliese,¹¹ R. Sánchez-Ramírez,¹⁴ J. Selsing,³
M. Sparre,¹⁵ N. R. Tanvir,¹⁶ C. C. Thöne,⁷ A. de Ugarte Postigo^{7,3} and S. D. Vergani⁶

¹Centre for Astrophysics and Cosmology, Science Institute, University of Iceland, Dunhagi 5, 107 Reykjavík, Iceland

²Cosmic Dawn Center, Niels Bohr Institute, University of Copenhagen, Juliane Maries Vej 30, DK-2100 Copenhagen Ø, Denmark

³Dark Cosmology Centre, Niels Bohr Institute, University of Copenhagen, Juliane Maries Vej 30, DK-2100 Copenhagen Ø, Denmark

⁴European Southern Observatory, Alonso de Córdova 3107, Vitacura, Casilla 19001, Santiago 19, Chile

⁵IRFU, CEA, Université Paris-Saclay, F-91191 Gif-sur-Yvette, France

⁶GEPI, Observatoire de Paris, PSL Research University, CNRS, Place Jules Janssen, F-92190 Meudon, France

⁷Instituto de Astrofísica de Andalucía (IAA-CSIC), Glorieta de la Astronomía s/n, E-18008 Granada, Spain

⁸INAF – Osservatorio Astronomico di Brera, Via E. Bianchi 46, I-23807 Merate (LC), Italy

⁹Space Science Data Center - Agenzia Spaziale Italiana, via del Politecnico, s.n.c., I-00133 Roma, Italy

¹⁰Centre for Astrophysics and Cosmology, University of Nova Gorica, Vipavska 11c, 5270 Ajdovščina, Slovenia

¹¹Anton Pannekoek Institute for Astronomy, University of Amsterdam, Science Park 904, NL-1098 XH Amsterdam, the Netherlands

¹²Astronomical Institute Anton Pannekoek, University of Amsterdam, PO Box 94249, NL-1090 GE Amsterdam, the Netherlands

¹³Institut d’Astrophysique de Paris, CNRS-UPMC, UMR7095, 98bis bd Arago, F-75014 Paris, France

¹⁴INAF, Istituto Astrofisica e Planetologia Spaziali, Via Fosso del Cavaliere 100, I-00133 Roma, Italy

¹⁵Institut für Physik und Astronomie, Universität Potsdam, Karl-Liebknecht-Str. 24/25, D-14476 Golm, Germany

¹⁶Department of Physics and Astronomy and Leicester Institute of Space and Earth Observation, University of Leicester, University Road, Leicester LE1 7RH, UK

Accepted 2018 May 29. Received 2018 May 25; in original form 2018 February 21

ABSTRACT

We present here a survey of high-ionization absorption lines in the afterglow spectra of long-duration gamma-ray bursts (GRBs) obtained with the VLT/X-shooter spectrograph. Our main goal is to investigate the circumburst medium in the natal regions of GRBs. Our primary focus is on the N v $\lambda\lambda$ 1238, 1242 line transitions, but we also discuss other high-ionization lines such as O vi, C iv, and Si iv. We find no correlation between the column density of N v and the neutral gas properties such as metallicity, H I column density, and dust depletion; however, the relative velocity of N v, typically a blueshift with respect to the neutral gas, is found to be correlated with the column density of H I. This may be explained if the N v gas is part of an H II region hosting the GRB, where the region’s expansion is confined by dense, neutral gas in the GRB’s host galaxy. We find tentative evidence (at 2σ significance) that the X-ray derived column density, $N_{\text{H}, \text{X}}$, may be correlated with the column density of N v, which would indicate that both measurements are sensitive to the column density of the gas located in the vicinity of the GRB. We investigate the scenario where N v (and also O vi) is produced by recombination after the corresponding atoms have been stripped entirely of their electrons by the initial prompt emission, in contrast to previous models where highly ionized gas is produced by photoionization from the GRB afterglow.

Key words: gamma-ray bursts: general – ISM: abundances.

1 INTRODUCTION

Cosmic lighthouses such as gamma-ray bursts (GRBs) allow the interstellar medium (ISM) of their host galaxies and foreground absorbers to be studied in great detail (e.g. Jakobsson et al. 2004) up to high redshifts. In particular, they enable investigations of the ISM

* E-mail: keh14@hi.is

in terms of chemical abundances (Fynbo et al. 2006; Prochaska et al. 2007; Cucchiara et al. 2015), dust content (Savaglio, Fall & Fiore 2003; Schady et al. 2010; Zafar et al. 2011; Zafar & Watson 2013), kinematics (Prochaska et al. 2008a; Arabalmani et al. 2015, 2018), and the very local circumburst medium (Møller et al. 2002; Prochaska, Chen & Bloom 2006; Fox et al. 2008; Prochaska et al. 2008b; Castro-Tirado et al. 2010; Schady et al. 2011). The large majority of GRB afterglow spectra show damped Lyman- α (DLA) absorption, i.e. a neutral hydrogen column density of $N(\text{H I}) > 2 \times 10^{20} \text{ cm}^{-2}$ (Vreeswijk et al. 2004; Jakobsson et al. 2006; Fynbo et al. 2009; Cucchiara et al. 2015, and Tanvir et al., submitted), typically with higher H I column densities than seen in DLAs towards quasars (e.g. Noterdaeme et al. 2009; Sánchez-Ramírez et al. 2016). This is consistent with the scenario where the GRB explodes in the inner region, or in a dense, star-forming cloud, within its host galaxy (Bloom, Kulkarni & Djorgovski 2002; Fruchter et al. 2006; Prochaska et al. 2007; Vreeswijk et al. 2007, 2011; Fynbo et al. 2008; Svensson et al. 2010; Lyman et al. 2017).

While the neutral gas-phase ISM in the host galaxy can be studied in great detail with GRBs, it is much more difficult to examine their immediate environments. Due to the hardness of the prompt emission and the extreme luminosity across all wavelengths, GRBs are expected to destroy dust and fully or at least partly ionize the circumburst gas, out to a few tens of pc (Waxman & Draine 2000; Fruchter, Krolik & Rhoads 2001; Perna, Lazzati & Fiore 2003; Watson et al. 2006, 2013). This can potentially erase any traces of the physical conditions of the circumburst material from their optical afterglow spectra. Highly ionized absorption features or X-ray observations of the GRBs might therefore be the only spectroscopically way to probe the circumburst medium. The observed soft X-ray absorption column density is typically larger than that of the neutral gas in GRB host galaxies (Galama & Wijers 2001; Watson et al. 2007; Campana et al. 2010; Schady et al. 2011), which could indicate that the X-ray absorption probes a significant column of hot, ionized metals that is transparent to UV photons. Another plausible scenario is that the He in the natal H II region of the GRB is responsible for most of the soft X-ray absorption (Krongold & Prochaska 2013; Watson et al. 2013). The absorption is likely due to the much larger population of He atoms, and since the abundance of He saturates the He-ionizing UV continuum out to about 10 pc from the GRB, it can remain in a neutral or singly ionized state. This scenario also supports previous models where dust is destroyed and metals are stripped of all their electrons by the GRB out to distances of tens to hundreds of pc (Waxman & Draine 2000; Fruchter et al. 2001; Perna et al. 2003; Watson et al. 2006, 2013).

Since the relative location of the absorbing gas cannot be resolved in X-ray spectroscopy, the observed column density probes the total gas column along the line of sight. For this reason the soft X-ray absorption might originate in the intergalactic medium (IGM) or in intervening absorbers. This was argued to be the cause for the observed correlation between the X-ray absorbing column density and redshift (Behar et al. 2011; Arcodia, Campana & Salvaterra 2016). However, Watson & Jakobsson (2012) and Watson et al. (2013) showed that this trend is largely a consequence of the higher gas column density in GRB hosts at high redshifts (similar to what is observed for main-sequence galaxies, e.g. Magdis et al. 2012) and that at low- z , the dust bias (excluding high X-ray absorbing column density GRBs) is more severe than at high- z . Only at the highest redshifts ($z \gtrsim 4$) is it plausible that a significant component of absorption from intervening matter could be present (Starling et al. 2013).

The long-standing problem of the origin of the soft X-ray absorption could therefore be solved by comparing the high-ionization absorption features seen in optical GRB afterglows to the X-ray derived column density. If a correlation is found between these two quantities, it may be possible to robustly relate the X-ray absorption to the immediate environment of the GRB. In this paper we compile a list of all high-redshift ($z \gtrsim 1.7$), long-duration GRBs with good-quality X-shooter spectra to investigate the high-ionization absorption features in GRB afterglows. Such highly ionized absorption lines, in particular N V, have already been studied with high-resolution data though only in small samples (Fox et al. 2008; Prochaska et al. 2008b). Our sample is three times as large as those previously published, and by combining the individual samples we are now able to study the high-ionization absorption features with better statistics.

The paper is structured as follows. In Section 2 we present our sample, discuss the imposed selection criteria, and evaluate the neutral gas properties (such as z_{GRB} , H I column density, metallicity, and dust depletion) of the GRBs in our sample. In Section 3 we present our results, with a specific focus on N V which is the best constrained high-ionization absorption line. We provide a discussion of our data in Section 4, where we also propose a new scenario for the origin of highly ionized metals in the vicinity of GRBs. Finally, we conclude on our work in Section 5.

Throughout the paper we assume a standard, flat cosmology with $H_0 = 67.8 \text{ km s}^{-1} \text{ Mpc}^{-1}$, $\Omega_m = 0.308$, and $\Omega_\Lambda = 0.692$ (Planck Collaboration XIII 2016). Abundances are expressed relative to solar, i.e. $[X/H] = \log N(X)/N(H) - \log N(X)_\odot/N(H)_\odot$, using solar abundances from Asplund et al. (2009).

2 THE GRB SAMPLE

The sample of GRB afterglows studied here was built by extracting all long-duration GRBs at $z \gtrsim 1.7$ from the VLT/X-shooter GRB (XS-GRB) legacy survey (Selsing et al., in preparation). Table 1 compiles the information of each of the GRBs in our study, including the time of the observation, the spectroscopic sequence, observing programme, spectral resolution, and references for the high-energy detection and X-shooter follow-up. After examining each individual spectrum we imposed additional observational selection criteria to exclude bursts with poor S/N or insufficient coverage of the high-ionization lines (see Section 2.2). In Section 2.3 we report the low-ionization properties of the sample such as the systemic redshift, H I column density, gas-phase metallicity, and dust depletion.

2.1 Observations and data reduction

The majority of GRBs observed with the VLT/X-shooter spectrograph in our sample were detected by the Burst Alert Telescope (BAT) onboard the *Niel Gehrels Swift Observatory* satellite (Gehrels et al. 2004). The three exceptions are the GRBs 090926A, 141028A, and 161023A, where the first two were detected by *Fermi*-LAT/GBM (Atwood et al. 2009; Meegan et al. 2009) onboard the *Fermi* Gamma-Ray Space Telescope and the last was detected by the *INTEGRAL* satellite (Winkler et al. 2003).

The localization of each burst was distributed within a few minutes through the GCN which allowed for quick follow-up observations with VLT. Three of the 18 GRB afterglows in our sample (GRBs 120909A, 151021A and 160203A) were observed with the rapid-response mode (RRM; Vreeswijk et al. 2010) available at the ESO/VLT. All bursts were observed within 24 h after trigger (see also below).

Table 1. X-shooter GRB sample and log of observations. GCN circulars that reported the GRB detection and the subsequent X-shooter afterglow follow-up observations (if available). ^aTime of spectroscopic follow-up after GRB trigger; ^bSpectral resolution in the UVB and VIS arm. **References.** (1) Markwardt et al. (2009); (2) Malesani et al. (2009a); (3) Bissaldi et al. (2009); (4) Malesani et al. (2009b); (7) Saxton et al. (2011); (8) Wiersema et al. (2011); (9) Beardmore et al. (2012); (10) Sbarufatti et al. (2012); (11) Kruehler et al. (2012); (12) Pagani et al. (2012a); (13) Malesani et al. (2012); (14) Immler et al. (2012); (15) Hartoog et al. (2012); (16) Pagani et al. (2012b); (17) Tanvir et al. (2012b); (18) Lien et al. (2013); (19) Hjorth et al. (2013); (20) Ukwatta et al. (2013); (21) Xu et al. (2013); (22) Bissaldi et al. (2014); (23) Xu et al. (2014a); (24) D’Avanzo et al. (2014); (25) Xu et al. (2014b); (26) Lien et al. (2015); (27) Pugliese et al. (2015); (28) Melandri et al. (2015); (29) de Ugarte Postigo, Malesani & Xu (2015); (30) Ukwatta et al. (2015); (31) Xu et al. (2015); (32) D’Avanzo et al. (2016); (33) Pugliese et al. (2016); (34) Mereghetti et al. (2016); (35) Tanvir et al. (2016).

GRB	Trigger (UT) (hh:mm:ss)	Δt^a (h)	Mag _{AB} (Acq.)	Exp. time (s)	ESO prog. ID	$\mathcal{R}_{\text{UVB/VIS}}^b$ (km s ⁻¹)	Notes and refs.
090809	17:31:14	10.2	21.0	4 × 1800	60.A-9427(A)	53.6/31.3	(1,2)
090926A	21:55:48	22.0	17.9	4 × 600	60.A-9427(A)	49.2/28.6	(3,4)
100425A	02:50:45	4.00	20.6	4 × 600	85.A-0009(B)	52.5/30.0	(5,6)
111008A	22:12:58	8.50	21.0	4 × 2400	88.A-0051(B)	46.2/26.5	(7,8)
120119A	04:04:30	1.40	17.0	4 × 600	88.A-0051(B)	39.5/22.7	(9)
120327A	02:55:16	2.10	18.8	4 × 600	88.A-0051(B)	33.3/19.4	(10,11)
120815A	03:55:21	1.69	18.9	4 × 600	89.A-0067(B)	44.1/25.4	(12,13)
120909A	01:42:03	1.70	21.0	2 × 600	89.A-0067(B)	56.6/33.0	RRM, (14,15)
121024A	02:56:12	1.80	20.0	4 × 600	90.A-0088(B)	41.7/24.0	(16,17)
130408A	21:51:38	1.90	20.0	2 × 600	91.C-0934(C)	39.5/22.7	(18,19)
130606A	21:04:39	7.10	19.0	7 × 600	91.C-0934(C)	37.0/21.4	(20,21)
141028A	10:54:46	15.4	20.0	4 × 600	94.A-0134(A)	53.6/30.9	(22,23)
141109A	05:49:55	1.90	19.2	2 × 1200	94.A-0134(A)	41.7/24.2	(24,25)
150403A	21:54:16	10.8	19.1	4 × 600	95.A-0045(A)	44.8/26.1	(26,27)
151021A	01:29:12	0.75	18.2	7 × 600	96.A-0079(B)	50.0/29.1	RRM, (28,29)
151027B	22:40:40	5.00	20.5	4 × 600	96.A-0079(A)	55.6/32.3	(30,31)
160203A	02:13:10	0.30	18.0	11 × 600	96.A-0079(A)	37.5/21.7	RRM, (32,33)
161023A	22:39:24	3.00	17.5	2 × 600	98.A-0055(A)	46.2/26.5	(34,35)

The VLT/X-shooter spectrograph covers the spectral wavelength range from 3000 to 24 800 Å, divided into three spectroscopic arms (Vernet et al. 2011). The UVB arm covers 3000–5500 Å, the VIS arm 5500–10200 Å, and the NIR arm 10 200–24 800 Å. In the large majority of cases, the spectra were obtained following an ABBA nodding pattern, the slits were aligned with the parallactic angle, selecting slit widths of 1'0, 0'9, and 0'9 for the three arms, respectively. For this set-up the nominal instrumental resolutions in the UVB, VIS, and NIR arms are 70, 40, and 55 km s⁻¹, respectively. If the seeing on the night of observation is smaller than the slit width projected on the sky, the delivered resolution is enhanced. In the VIS and NIR arms the resolution is determined by fitting a range of telluric absorption lines and extracting the full width at half-maximum (FWHM). Since no tellurics fall in the UVB arm from which we can measure the resolution directly, we extrapolated the ratio of the observed-to-nominal resolution in the VIS arm and assume the same ratio for the observed-to-nominal resolution in the UVB arm. For each burst we list the delivered resolution in the UVB and VIS arms in Table 1.

All the science spectra were reduced in a consistent manner for the XS-GRB legacy sample. The exact procedure is described in Selsing et al. (in preparation), so in the following we will only briefly summarize the data reduction strategy. First, the raw spectra were processed through a cosmic-ray removal algorithm (van Dokkum 2001). Then, each of the exposures was separately reduced using the VLT/X-shooter pipeline, version 2.7.1 or newer (Goldoni et al. 2006; Modigliani et al. 2010), and was subsequently combined in the post-processing. The pipeline produces a flat-fielded, rectified and wavelength-calibrated 2D spectrum for every frame in the UVB, VIS, and NIR arms. To extract the final 1D spectra from the combined 2D frames we model the trace using a running Voigt profile fit. All wavelengths reported throughout the paper are in vacuum and are shifted to the heliocentric velocity. Finally, the spectra were

corrected for the Galactic extinction in the line of sight using the dust maps of Schlegel, Finkbeiner & Davis (1998) from the most recent update (Schlafly & Finkbeiner 2011).

2.2 Selection criteria

After examining the individual quality of all the spectra we imposed additional observational and brightness constraints to remove bursts with poor signal-to-noise (S/N) ratios (effectively eliminating the majority of sources for which the mean $S/N \lesssim 3$ per wavelength element). The criteria we imposed for the GRB follow-up observations are: (i) that the GRB was observed with X-shooter within 24 h after the GRB trigger, (ii) the brightness measured from the X-shooter acquisition image is brighter than 21.0 mag, and (iii) there is spectral coverage of the Ly α profile and at least the Nv doublet of the high-ionization transitions, effectively requiring that the galaxies hosting the bursts are located at $z \gtrsim 1.7$. In total, 18 GRBs observed with the VLT/X-shooter fulfil these criteria, see Table 1 (for the observational details) and Section 2.3 and Table 2 (for the low-ionization properties of each).

The Nv transition is of particular interest to us since it has been shown that the majority of this highly ionized gas must be located within approximately 1 kpc of the GRB explosion site (Prochaska et al. 2006) or perhaps even within $\lesssim 10$ pc (Prochaska et al. 2008b). Studying these events, together with the low-ionization properties of the host galaxy, allows us to constrain the physical properties of their circumburst medium. Moreover, this line is located in the red wing of the absorption trough of the Ly α line and is easily detected compared to the majority of the high-ionization species that are located in the Ly α forest. The final sample of GRBs observed with VLT/X-shooter presented here is three times the size of previous surveys for Nv absorption in GRB afterglows (Fox et al. 2008; Prochaska et al. 2008b) and extends the redshift range out to $z \sim$

Table 2. Low-ionization properties and Nv detection summary. **References.** (1) Cucchiara et al. (2015); (2) D’Elia et al. (2010); (3) Sparre et al. (2014); (4) Wiseman et al. (2017); (5) D’Elia et al. (2014); (6) Krühler et al. (2013); (7) Friis et al. (2015); (8) Hartoog et al. (2015); (9) Tanvir et al. (submitted); (10) Thöne et al. (in preparation); (11) Pugliese et al. (in preparation); (12) de Ugarte Postigo et al. (in preparation).

GRB	z_{GRB}	$\log N(\text{H I})$ (cm^{-2})	[X/H]	[X/Fe]	Ion	$\log N(\text{N v})$ (cm^{-2})	δv (km s^{-1})	Refs.
090809	2.737 06	21.70 ± 0.20	-0.57 ± 0.10	0.30 ± 0.31	Si	< 14.43	–	(1)
090926A	2.106 94	21.60 ± 0.07	-1.85 ± 0.10	0.34 ± 0.13	S	14.30 ± 0.19	4 ± 2	(2)
100425A	1.756 40	21.05 ± 0.10	-0.96 ± 0.42	–	Fe	< 14.63	–	(1)
111008A	4.991 46	22.30 ± 0.06	-1.70 ± 0.10	0.05 ± 0.13	S	> 14.00	8 ± 10	(3)
120119A	1.728 83	22.70 ± 0.20	-0.79 ± 0.42	0.36 ± 0.28	Si	< 15.15	–	(4)
120327A	2.814 82	22.01 ± 0.09	-1.17 ± 0.11	0.56 ± 0.15	Zn	13.56 ± 0.03	0 ± 1	(5)
120815A	2.358 20	21.95 ± 0.10	-1.15 ± 0.12	1.01 ± 0.10	Zn	14.60 ± 0.18	-6 ± 7	(6)
120909A	3.928 82	21.70 ± 0.10	-0.66 ± 0.11	0.88 ± 0.16	S	14.75 ± 0.11	-14 ± 4	(1)
121024A	2.302 44	21.88 ± 0.10	-0.40 ± 0.12	0.85 ± 0.04	Zn	< 14.35	–	(7)
130408A	3.757 92	21.80 ± 0.10	-1.24 ± 0.12	0.11 ± 0.26	S	14.44 ± 0.07	-16 ± 2	(1)
130606A	5.912 78	19.91 ± 0.02	-1.30 ± 0.08	0.79 ± 0.13	Si	14.50 ± 0.04	-83 ± 1	(8)
141028A	2.333 27	20.60 ± 0.15	-0.50 ± 0.38	0.57 ± 0.21	Si	14.28 ± 0.10	-104 ± 20	(4)
141109A	2.994 38	22.10 ± 0.20	-1.40 ± 0.22	0.84 ± 0.37	Zn	$\gtrsim 14.85$	13 ± 15	(9,10)
150403A	2.057 07	21.80 ± 0.20	-0.80 ± 0.35	1.31 ± 0.43	S	14.73 ± 0.14	-32 ± 3	(9,10)
151021A	2.329 75	22.20 ± 0.20	-1.11 ± 0.20	1.15 ± 0.28	Si	14.80 ± 0.46	34 ± 5	(9,10)
151027B	4.064 69	20.50 ± 0.20	-1.62 ± 0.24	0.34 ± 0.28	Si	< 13.98	–	(9,10)
160203A	3.518 71	21.75 ± 0.10	-1.26 ± 0.11	0.59 ± 0.25	S	< 13.58	–	(9,11)
161023A	2.710 67	20.96 ± 0.05	-1.24 ± 0.09	0.45 ± 0.11	Si	13.66 ± 0.08	-114 ± 6	(12)

6. These former two surveys found a high detection rate of N v in 6/7 GRB afterglows, however, five bursts were common to both samples. From our sample here we can independently assess the detection rate.

For completeness, we also survey the high-ionization species of N v λ 1238, 1242, O vi λ 1031, 1037, C iv λ 1548, 1550, Si iv λ 1393, 1402, S iv λ 1062, and S vi λ 933, 944. The ionization potentials to create these ions are 77.5, 113.9, 47.9, 33.5, 34.8, and 72.6 eV (see also Table 3). In addition to these, we also look for P v λ 1117, 1128, which to our knowledge have not been observed in GRB afterglow spectra before. Furthermore, we include absorption lines that trace the neutral gas, typically Si ii or Fe ii to (1) determine the systemic redshifts, z_{GRB} , and (2) to measure the gas-phase metallicity of the galaxy hosting the GRB (see below). In the Appendix we provide notes on all the individual GRBs in our sample and the detected high-ionization lines.

2.3 Low-ionization properties

For each burst, the systemic redshift, z_{GRB} , is defined by the position of the peak optical depth in the low-ionization lines (typically Fe ii or Si ii). We searched for high-ionization absorption features within $z_{\text{GRB}} \pm 500 \text{ km s}^{-1}$, representing the low-velocity components. We did not look for high-velocity components ($500\text{--}5000 \text{ km s}^{-1}$ relative to z_{GRB}), which likely trace outflows that can be driven to high velocities by the burst progenitor (see e.g. Fox et al. 2008; Castro-Tirado et al. 2010), since we are only interested in the immediate environment around the GRB. We list the measured z_{GRB} for each burst in the second column of Table 2. In the third column, the neutral hydrogen (H i) column density is reported for each GRB where we adopt the values reported in the single papers that examined the individual bursts (see references in the table) or those from the extensive compilation of GRB afterglow H i column densities by Tanvir et al. (submitted, and references therein).

Except for GRBs 141109A, 150403A, 151021A, 151027B, 160203A, and 161023A (de Ugarte Postigo et al., in preparation), we adopt the gas-phase metallicities reported in the literature (see

the references in Table 2), listed as [X/H], where the ion X is one of the volatile species, Si, S, or Zn. In all cases, the dust depletion of the ion X relative to iron, [X/Fe], is also reported. For the remaining six bursts in our sample we use our own fitting tool to derive column densities and gas-phase metallicities of the low-ionization absorption features by performing a series of Voigt profile fits to the absorption line profiles (the full set of absorption line fits to the XS-GRB sample will be published in Thöne et al., in preparation).

The code is developed in Python and is described in detail in Krogager (2018). Simply, the software takes as input the instrumental resolution, the zero-point redshift, and the H i column density and returns the redshift of the different velocity components (z), line width (b), and column density ($\log N$) for each species. The derived metallicities and depletion patterns are summarized in Table 2 and are reported in detail for each burst in the Appendix. We follow the same procedure to derive the column densities of the high-ionization absorption features by fitting the various components and ionization species in each GRB afterglow spectrum independently. Since the N v λ 1238, 1242 doublet is located in the red wing of the Ly α absorption trough in bursts with large H i column densities ($\log N(\text{H I}) \gtrsim 21$), the continuum flux in this region will be underestimated. To measure the column density of N v we therefore fit the N v and Ly α lines simultaneously, using a prior estimate of the H i column density from the already published values. This approach is shown in Fig. 1 for GRB 090926A (with an H i column density of $\log N(\text{H I}) \gtrsim 21.60$), where it is also clearly demonstrated how the Ly α absorption affects the continuum level in the region around the N v doublet. For the non-detections of N v, 3σ upper limits were calculated using $N(\text{N v}) = 1.13 \times 10^{20} W_{\text{lim}}/\lambda_0^2 f$ where W_{lim} is the 3σ upper limit on the rest-frame equivalent width in \AA and $N(\text{N v})$ is in cm^{-2} .

3 RESULTS

The results of the Voigt profile fits for each burst are shown in the Appendix (Tables B1–B16 and Figs. B1–B16) together with notes on all the GRB afterglows in our sample. We report the best-




Figure 1. VLT/X-shooter spectrum of GRB 090926A. In the bottom panel, the black solid line shows the normalized UVB arm spectrum centred on $\text{Ly}\alpha$ at $z \approx 2.107$ with the associated error spectrum shown in blue. The best-fitting Voigt profiles to the $\text{Ly}\alpha$ line and the $\text{Nv}\lambda\lambda$ 1238, 1242 doublet are shown as the solid red line. In the upper panel we show a zoomed-in region of the Nv transitions and the same combined Voigt profile fit.

fitting Voigt profile parameters in individual tables and show the corresponding fit in the figures belonging to each burst. In each of the figures, an example of one of the low-ionization absorption lines is included, where the peak optical depth of this line represents z_{GRB} . In Table 3 we list the results of the Voigt profile fits and show the corresponding best-fitting combined line profiles in velocity-space in Fig. 2 for one of the bursts, GRB 161023A, as an example (but see also de Ugarte Postigo et al., in preparation).

In the majority of cases, the high-ionization species O VI , S IV , S VI , and P V are blended with the $\text{Ly}\alpha$ forest. Si IV and C IV are detected in all of the GRB afterglow spectra but are both heavily saturated. In this section we therefore focus mainly on the N v doublet that has the advantage of not being saturated (in most cases) compared to some of the other high-ionization lines, and is located in the red wing of the $\text{Ly}\alpha$ absorption trough. The medium resolution of the X-shooter spectrograph also ensures that the Nv doublet is well resolved. Due to the varying quality of the spectra and since the $\text{Ly}\alpha$ absorption line and Nv doublet lie in the bluest part of the UVB arm for redshifts $z \approx 1.7$, the detection limit varies from approximately $\log N(\text{Nv}) = 13.5$ to 15.2. The results of the Nv column densities and 3σ upper limits are summarized in Table 2, where we also list the relative velocity to z_{GRB} . For the GRBs with Nv detections we find average and median values of $\log N(\text{Nv})_{\text{avg}} = 14.36$ and $\log N(\text{Nv})_{\text{med}} = 14.50$, respectively. We obtain robust fits to all the Nv lines, and we find that blending or line saturation is not an issue in the majority of cases (although see the individual tables for the few exceptions). As mentioned above, the column densities for Nv are fitted simultaneously with the $\text{Ly}\alpha$ line and those values are reported in Table 2 and in the individual tables in the Appendix. The measured column densities using this approach are, however, mostly consistent (within the 1σ errors) to the values obtained by fitting only the Nv lines.

As the large ionization potential of N IV (as well as O V and S V) well exceeds the integrated galactic ionizing radiation from O and




Figure 2. GRB161023A: Normalized high-ionization absorption-line profiles on a velocity scale relative to z_{GRB} . Voigt profile fits are shown in red (solid line) with the centre of each velocity component marked with dotted or dashed lines. The part of the spectrum shown in grey is masked out in the fit. The residual spectrum to the best fit is shown at the top of each panel.

Table 3. Voigt profile fits for GRB 161023A at $z = 2.71067$. The ionization potential (IP) for each transition is also listed.

Ion	IP eV	v_0 (km s^{-1})	b (km s^{-1})	$\log N$ (N in cm^{-2})	$\log N_{\text{total}}$ (N in cm^{-2})
N v	77.5	-114 ± 6	30 ± 10	13.66 ± 0.08	13.66 ± 0.08
O VI	113.9	-118 ± 6	78 ± 9	14.59 ± 0.04	14.59 ± 0.04
C IV	47.9	-130 ± 2	44 ± 3	14.91 ± 0.07	14.93 ± 0.07
		-8 ± 4	22 ± 7	13.60 ± 0.04	–
Si IV	33.5	-117 ± 4	26 ± 7	14.47 ± 0.18	14.50 ± 0.17
		-27 ± 13	44 ± 17	13.30 ± 0.13	–
		-168 ± 65	47 ± 41	13.56 ± 0.75	–
S IV	34.8	-104 ± 8	58 ± 12	14.66 ± 0.07	14.66 ± 0.07
S VI	72.6	-121 ± 6	52 ± 8	14.17 ± 0.06	14.17 ± 0.06
P V	65.0	-39 ± 6	49 ± 9	13.54 ± 0.06	13.54 ± 0.06

B stars that drop strongly above 54 eV due to the He II ionization edge (Bregman & Harrington 1986), an additional intense radiation source is required to produce N v . Furthermore, Prochaska et al. (2008b) demonstrated that GRB afterglows can photoionize nitrogen up to N v if the gas is closer than ≈ 10 pc. This, together with the fact that the relative velocities of the Nv lines in general are coincident with the UV-pumped fine-structure lines of Si II and Fe II

(Prochaska et al. 2008b), implies that the observed N v absorption features are related to the material close to the GRB or its progenitor. The following sections are dedicated to investigate the relation between the characteristics of the N v gas and the physical properties of the GRB host galaxy, such as GRB redshift, ISM gas-phase metallicity, dust and metal column density, and internal kinematics.

3.1 Detection rates

We detect at least two of the surveyed high-ionization absorption features within a few hundred km s^{-1} of z_{GRB} in all 18 GRB spectra. The detection rates are N v (seen in 12/18 cases), O vi (3/18), C iv (18/18), Si iv (18/18), S iv (5/18), S vi (6/18), and P v (4/18). The detection rates of the high-ionization lines that originate in the Ly α forest are to be treated as lower limits since they are, in the majority of cases, heavily blended or located in a spectral region with a poor S/N. Compared to earlier studies of high-ionization lines in GRB afterglows (e.g. Fox et al. 2008; Prochaska et al. 2008b), the detection rate of N v is lower in our sample. Both of the previous samples found that N v was detected in 6/7 GRB afterglow spectra. The single burst, GRB 060607, with a non-detection of N v down to $\log N(\text{N v}) < 12.61$, common to both samples, is unique in the sense that it has a very low H i column density. The physical properties of the line of sight to this GRB are therefore most likely significantly different.

While our sample shows six non-detections of Nv, the limits in the individual GRB afterglow spectra are almost at the same order as the derived N v column densities. To understand why N v is only observed in 12/18 GRB afterglow spectra, our first approach is to examine whether the detection rate is caused by observational constraints. In Fig. 3 we show the derived column density of N v as a function of hours post-burst at the time of observation and the measured acquisition magnitude (values taken from Selsing et al., in preparation). There appears to be no correlation between any of these parameters. We note, however, that four out of the six bursts with non-detections of Nv were faint in the acquisition images at the time of observation, which would suggest that the cause of the non-detections is of observational origin.

Another scenario could be that the luminosity of the afterglow itself is not intense enough to produce highly ionized metals. To test this scenario we examine the gamma-ray luminosity, $L_{\gamma, \text{int}}$ (erg s^{-1}), of each burst and compare it to the N v column density. We extract the gamma-ray fluence, $F_{\gamma, \text{obs}}$ (erg cm^{-2}), from the *Swift*/BAT data base in the observer frame energy band 15–150 keV. To convert this value to an intrinsic property we calculate $L_{\gamma, \text{int}} = F_{\gamma, \text{obs}} 4\pi d_L^2 (1+z)^{-1}$ (similar to Lien et al. 2016), where d_L is the luminosity distance. We caution that this is a simple approximation, and that a k -correction in principle also should be applied to account for the spectral shape. The results are shown in Fig. 4. It is clear that the non-detections all belong to intrinsically faint GRBs (as already noted above from the acquisition images) except for GRB 120119A for which we are, however, only able to put a poorly constrained upper limit on N v. For reference, GRB 060607 (with a non-detection reported for N v) has an intrinsic gamma-ray fluence of $\log L_{\gamma, \text{int}} = 52.71$. This value is around the median for the GRBs in our sample, suggesting that the non-detection in this case is likely due to the different nature of the galaxy hosting this GRB. For comparison we detect two cases with one and two orders of magnitudes higher N v column densities ($\log N(\text{N v}) = 13.5$ – 14.5) with the same intrinsic gamma-ray luminosity, $\log L_{\gamma, \text{int}} \approx 52.7$, as GRB 060607.




Figure 3. Detection of N v as a function of time of observation post-burst (upper panel) and acquisition magnitude of the afterglow (bottom panel). Blue dots denote bursts where N v is detected and a column density measured. Light blue triangles are non-detections and the corresponding 3σ upper limit is instead shown.

Since the total isotropic gamma-ray energy is correlated with the X-ray and optical afterglow brightness (Nysewander, Fruchter & Pe’er 2009), it is reasonable to expect that the production of highly ionized metals should be correlated with the radiation field from the GRB itself and the following afterglow radiation. The fact that the strength of N v depends on the intrinsic gamma-ray energy of the GRB then supports a scenario where N v traces the circumburst medium of the GRB. We will return to this issue in Section 3.4 where we provide further evidence that N v is a good probe of the metals in the molecular cloud or H ii region surrounding the GRB.

3.2 Dependence of N v on neutral gas properties

To explore the different factors that might influence the production of N v, we plot the measured N v column densities as a function of redshift in Fig. 5 and as a function of metallicity, H i column density, and dust depletion in Fig. 6. We include the GRBs from the two previous surveys for N v and high-ionization absorption (Fox et al.




Figure 4. Detection of N v as a function of the intrinsic gamma-ray luminosity, $L_{\gamma,\text{int}} = F_{\gamma,\text{obs}} 4\pi d_L^2 (1+z)^{-1}$, where $F_{\gamma,\text{obs}}$ is the observed BAT fluence in the 15–150 keV band. The full sample is shown except for GRBs 090926A, 141028A, and 161023A since these were not detected by *Swift*/BAT. The same symbols are used as in Fig. 3.




Figure 5. The column density of N v as a function of redshift. In the bottom panel, the same symbols are again used as in Figs. 3 and 4 for GRBs in our sample. We have included N v detections from two previous GRB surveys (Fox et al. 2008; Prochaska et al. 2008b), shown here as the green squares and upward facing triangles (lower limits). In the upper panel we show the redshift distribution of the GRBs in our sample with (blue filled) and without (solid line) N v detections as histograms. The full sample spans a large redshift range of $1.7 < z < 6$. In addition, the distribution of the included GRBs with N v detections from previous surveys is shown as the green filled histogram.

2008; Prochaska et al. 2008b) in both figures. Our sample spans a redshift range of $1.7 < z < 6$ and N v column densities of $13.5 \lesssim \log N(\text{N v}) \lesssim 15.0$ (not including non-detections). The probability and strength of N v detection are not dependent on redshift, but we note that the two GRBs at $z > 4$ have higher than average N v column densities.

Comparing the probability and strength of the N v detection to the physical properties related to the neutral gas of the GRB hosts reveals that N v is not dependent on the H I column density and

metallicity (see the computed linear Pearson correlation coefficients in each of the panels in the figure), consistent with previous conclusions. We note, however, that there is a tentative correlation with dust depletion at the 1σ level and that strong N v absorption is predominantly seen at high values of $N(\text{H I})$. Our sample spans metallicities of $-1.9 < [\text{X}/\text{H}] < -0.4$, neutral hydrogen column densities of $19.9 < \log N(\text{H I}) < 22.7$, and dust depletion ratios of $0.1 < [\text{X}/\text{Fe}] < 1.3$. We can therefore provide further evidence that the highly ionized gas in GRBs is not directly related to the properties of the neutral ISM. This is in contrast to what is observed for QSO-DLAs with N v detections, where the detection probability is found to be dependent on metallicity (Fox et al. 2009). Absorbing galaxies towards quasars are not expected to contain intense non-stellar radiation (like GRBs), so the high-ionization absorption in quasar DLAs likely originates in the ISM or in the halo gas [which also explains the lower mean value of $\log N(\text{N v}) = 13.78$, and the large percentage (≈ 87 per cent) of non-detections; Fox et al. 2009].

3.3 Velocity offset of N v

A crucial piece of information about the circumburst medium can be obtained if we can localize the GRB in the host galaxy and derive its immediate physical conditions. However, deep, resolved imaging of GRB host galaxies is required to accurately locate the GRB explosion sites and to investigate the physical properties of their surrounding medium. Such maps are very challenging to obtain for GRB hosts at high redshifts [Tanvir et al. 2012a, although see e.g. McGuire et al. (2016) where *HST* imaging was sufficient to resolve the location of the GRB 130606A close to the centre of its host]. Instead, we can examine the relative velocity of the main component of high-ionization absorption, assuming that it represents discrete clouds in the host galaxy, to see how it coincides with the low-ionization components tracing the neutral ISM gas. Detailed studies of the velocity components of high-ionization lines can also potentially reveal the scales of which the intervening gas absorbs the photons from the GRB afterglow, shown e.g. for GRB 021004 (Møller et al. 2002; Castro-Tirado et al. 2010).

We compare the relative velocity of the strongest N v component to z_{GRB} as a function of metallicity and H I column density in Fig. 7. If the strongest, high-ionization components are aligned with the peak optical depth of the low-ionization profiles, they likely originate in the same cloud. If GRBs preferably occur in metal-poor environments it is reasonable to expect that the metal-rich GRB host galaxies would show high-ionization components separated from the strongest low-ionization metal components. We do not find any statistically significant correlation between the relative velocity of the high-ionization components to z_{GRB} as a function of metallicity. We do note, however, that at higher metallicities the scatter around z_{GRB} increases. This is likely due to a mass–metallicity scaling relation, where the more metal-rich GRBs are consistently more massive (and thus physically larger; Ledoux et al. 2006; Arabalmani et al. 2018). This allows for a greater range of internal velocities of possible star-forming clouds.

We find that the relative velocity of N v to z_{GRB} depends on the H I column density of the GRB. While an approximate linear function could describe the relation between the two quantities quite well (see the r and p values in the bottom panel of Fig. 7), an alternative is that the data instead show two populations: One with large H I column densities ($\log N(\text{H I}) > 21.5$) for which N v is aligned with z_{GRB} and one with low H I column densities ($\log N(\text{H I}) < 21.0$) for which the N v component is separated by $\approx 80\text{--}120 \text{ km s}^{-1}$ relative to the peak optical depth of the low-ionization profiles. While we




Figure 6. The column density of N v compared to low-ionization properties. We show the detection of N v in our sample, and the detections from the previous two GRB surveys for N v, as a function of metallicity (left-hand panel), H I column density (middle panel), and dust depletion (right-hand panel). In each panel the computed r and p values are shown. The same symbols are used as in Fig. 5.

do not find any correlation between N v and H I column densities, such that the immediate environment of the GRB is directly related to the H I column density, we argue that the data instead show a confinement effect. We propose a scenario where the pressure of dense ($\log N(\text{H I}) > 21.5$) clouds confines the H II region or molecular cloud, in which the GRB exploded, to the part of the galaxy with the largest amount of neutral gas. In more diffuse clouds ($\log N(\text{H I}) < 21.0$) the star-forming region is not as confined by the gas pressure. From the lower panel of Fig. 7 it can also be seen that only blueshifts of high-ionization components are measured with a relative velocity of $\approx -100 \text{ km s}^{-1}$. This would also be explained by the confinement scenario where the diffuse H I gas is not dense enough to counterbalance the effect of stellar winds originating from massive stars in the H II region. Stellar winds causing the expansion of the H II region are also of the order of $\approx 100 \text{ km s}^{-1}$ (Dyson 1977), which would explain why we only observe the blueshifted component: the absorbing material is expanding and thus moves towards us in the line of sight to the GRB explosion site. If this scenario is true, then we would also expect that the relative velocities of the fine-structure lines are slightly less blueshifted compared to N v, since they are typically measured to be at distances around a few hundred pc from the GRB. Only one of the GRBs in all three high-ionization line samples has a simultaneous measurement of N v (at $\delta v \approx -80 \text{ km s}^{-1}$) and a fine-structure line (GRB 130606A Hartoog et al. 2015), which shows a slightly smaller blueshift of Si II* at $\delta v \approx -50 \text{ km s}^{-1}$. For more of such cases, the relative velocity of the fine-structure and high-ionization lines would be valuable to examine.

3.4 The circumburst gas

The majority of GRB afterglows observed with *Swift*/XRT show soft X-ray absorption in excess of Galactic (e.g. Galama & Wijers 2001; Watson et al. 2002). While the X-ray absorption is believed to be dominated by metals, its origin has yet to be fully understood. Some authors claim that it traces the IGM along the line of sight (e.g. Behar et al. 2011; Campana et al. 2015) due to the increasing soft X-ray column density with redshift, however, no such trend has been observed, e.g. towards quasars (Eitan & Behar 2013). Since the Galactic X-ray absorption is also well accounted for (Willingale

et al. 2013), this indicates that the observed excess X-ray derived absorption column density is likely located at the GRB redshift. Furthermore, the derived X-ray absorption is typically found to be larger than the column density of neutral hydrogen (Watson et al. 2007, 2013; Campana et al. 2010) and the metal column density of the neutral gas (Galama & Wijers 2001; Schady et al. 2010; Greiner et al. 2011; Zafar et al. 2011) related to the dust extinction, A_V , of the ISM (Zafar & Watson 2013). This is also demonstrated in the upper panel of Fig. 8 where we compare the X-ray derived column density and the optically derived metal column density of the neutral ISM ($\log N(\text{H I}) + [\text{X}/\text{H}]$) for the bursts with N v detections from our sample and the two previous samples of Prochaska et al. (2008b) and Fox et al. (2008). The X-ray column densities are either adapted from the literature (e.g. Campana et al. 2010, but see the notes in the Appendix) or from the *Swift*/XRT repository.¹ We confirm the trend of significantly larger X-ray derived metal column densities and observe no correlation with the optically derived metal column density. This indicates that the soft X-ray absorption is not dominated by the neutral gas of the ISM in GRB host galaxies.

This suggests that the large X-ray absorption originates in a much smaller region, possibly close to the GRB. The main difficulty in studying the circumburst medium of GRBs is that they are so energetic that they are expected to destroy dust and ionize gas to very large distances from the burst, thereby largely removing this circumburst gas from tracers in the optical afterglow spectra. Previously, it has been postulated that the majority of the X-ray absorption might originate from highly ionized gas (Schady et al. 2011) or from helium (Watson et al. 2013) in the immediate, circumburst environment of the GRB, constituting the H II region. Therefore, the most viable tool to study the circumburst material is likely from hot gas signatures or to observe the gas at X-ray wavelengths. No strong correlations are yet observed, however, thereby constraining the use of the soft X-ray absorption as a diagnostic tool to study the circumburst medium of GRBs.

Prochaska et al. (2008b) suggest that both the N v column density and the X-ray absorption should be sensitive to the metals in the vicinity of the GRB. If N v is produced by photoionization from the GRB afterglow, and the X-ray photons are absorbed at the same

¹http://www.swift.ac.uk/xrt_spectra/




Figure 7. The relative velocity of the strongest component of N v compared to z_{GRB} as a function of metallicity (upper panel) and H I column density (lower panel). The dots (our sample) and squares (bursts from the previous samples) representing the GRBs are colour-coded as a function of redshift. In both panels the computed r and p values are shown. The dashed line intercepts the GRBs for which the position of the strongest high-ionization absorption component is consistent with the strongest low-ionization absorption component in relative velocity space.

approximate distance, we would expect a correlation between the two measurements. In the lower panel of Fig. 8 we demonstrate for the first time that there is indeed evidence for such a correlation. Combining our sample with the two previous samples, we find that computing the linear Pearson correlation coefficients for the N v column density as a function of the X-ray derived absorption column density yields $r = 0.62$ and $p = 0.04$ (excluding upper limits), i.e. the null hypothesis is rejected at more than 2σ . GRB 141028A is located outside the plotting region with an upper limit on $\log N_{\text{H,X}}$ of < 23 to better illustrate the linear correlation. Subtracting the optically derived metal column density from the X-ray absorption column yields a similar result, indicating that the metals in the neutral gas-phase in the ISM provide a negligible contribution to the X-ray absorption. The fact that there is marginal evidence for a correlation between N v and the X-ray absorption also suggests that the majority of the X-ray derived column density originates in




Figure 8. The *Swift*/XRT soft X-ray derived metal column density, $N_{\text{H,X}}$, as a function of the UV/optical metal column density, $\log N(\text{H I}) + [\text{X}/\text{H}]$, (upper panel), and the N v column density (bottom panel). In both panels the computed r and p values are shown. In the upper panel the 1:1 ratio between the two distinct metal column densities is represented as the dashed line. Only the GRBs from our sample and the two previous samples with N v detections are plotted in both panels. Open triangles denote GRBs with upper limits on $N_{\text{H,X}}$.

the host galaxies of GRBs and not, e.g. in the IGM or intervening systems. The scenario where the X-ray absorption traces the H I region or (former) molecular cloud in which the GRB exploded is also supported by the observed correlation between the X-ray column density and the surface luminosity (Lyman et al. 2017) since both are expected to be related to a region of intense star formation.

4 DISCUSSION

4.1 Highly ionized gas from recombination

While it has previously been shown by Prochaska et al. (2008b) that N v can be produced by photoionization from the GRB afterglow, their model relies on no prior ionization of the circumburst gas, e.g. by the initial prompt emission from the GRB. Based on the cor-

relation between N v and the X-ray derived metal column density, $N_{\text{H},\text{X}}$, we infer that the relative abundance of nitrogen is related to the total metal column density inferred from X-ray absorption. In the following we examine whether N v absorption could be dominated by the recombination of nitrogen stripped of electrons by the prompt emission (as suggested by, e.g. Watson et al. 2013) out to a few pc. We demonstrate that the observed column density of N v (and also O vi for a few cases) can be reproduced by the recombination of nitrogen (and oxygen) atoms using simple approximations. However, the temporal evolution of the column densities of these ions should be quite pronounced.

The recombination rate for a given transition is $R = \alpha n_e n_i$, where α is the recombination rate for the specific atom. The recombination time is therefore of the order of $t_{\text{rec}} \propto 1/(\alpha n_e)$. For the gas temperature ($T \approx 10^4$ K) and density ($n_e = 4 \times 10^3 \text{ cm}^{-3}$) in a typical H II region, and assuming that the total recombination coefficient $\alpha = 3 \times 10^{-9}$ for N v (Goshu 2017, though this value is two orders of magnitude higher than the sum of the radiative and dielectronic recombination rate coefficients), this yields a recombination time of $t_{\text{rec}} \approx 10^5$ s (i.e. about a day). Then, assuming the relative solar abundance of N to H is 6.7×10^{-5} (Asplund et al. 2009), we find that an absorber with 10^{22} cm^{-2} (typically observed in X-rays) yields 6.7×10^{17} nitrogen atoms cm^{-2} . Assuming all the nitrogen of interest is completely stripped of electrons immediately following the burst, and every other source of N iv ionizing photons is negligible, the fraction of nitrogen in the N v state can be determined following the recombination series and assuming the electron density remains approximately constant over this time. Under the order of magnitude assumption that the recombination coefficients of N v–N viii are the same, the general equation for the expected column density of N v can be written as $N(\text{N v}) = \frac{1}{6} N(\text{N}) \times (\alpha n_e \Delta t_{\text{rest}})^3 e^{-\alpha n_e \Delta t_{\text{rest}}}$, where $N(\text{N}) = N_{\text{H},\text{X}} \times (\text{N}/\text{H})_{\odot}$, e.g. $N(\text{N}) = 6.7 \times 10^{17} \text{ cm}^{-2}$ for an X-ray absorber with 10^{22} cm^{-2} . At the typical time of observation, a somewhat high density of $\sim 2 \times 10^4 \text{ cm}^{-3}$ is required so that $\sim 10^{-3}$ of the nitrogen atoms will have recombined from N viii to N v to give a value of $\log N(\text{N v})/\text{cm}^{-2} \sim 14.6$, consistent with the linear correlation between $N_{\text{H},\text{X}}$ and N v found in Section 3.4. In the above we have assumed the recombination rate from Goshu (2017) for N v and that this is the same for N v to N viii. If the recombination rate is an order of magnitude lower or higher this would then yield electron densities of 2×10^5 and $2 \times 10^3 \text{ cm}^{-3}$ instead, respectively.

Since O vi is expected to be produced by recombination in this scenario as well, we would expect the relative abundance of N v to O vi to be consistent with the solar ratio. This must be the case since the recombination rate is roughly the same for both ions and since N v and O vi are both lithium-like atoms with three electrons. In the recombination scenario, both atoms are therefore populated on the same time-scales from fully ionized to N v and O vi, respectively. From the five bursts with robust measurements of both N v and O vi in our sample, and from Fox et al. (2008), we find that the ratios are in the range $N(\text{N v})/N(\text{O vi}) = 0.08\text{--}0.38$ (with a mean and median ratio of ≈ 0.19), which is of the same order as the solar abundance ratio $[(\text{N}/\text{O})_{\odot} \approx 0.13]$; Asplund et al. 2009]. The observed relative abundance ratio is more difficult to explain in the photoionization scenario, since O vi has a much higher ionization potential (≈ 115 eV) than N v (≈ 77 eV). We note that the [N/O] abundance ratios in low-metallicity systems are typically sub-solar (Pettini et al. 2008), exacerbating this inconsistency further.

However, in the pure recombination scenario sketched roughly above, the column density of N v should be very sensitive to the electron density and should be very time-dependent, with a value that initially rises very quickly in the first several hours after the

burst and then drops exponentially at about a day, depending on the density and recombination rate coefficients. We cannot entirely exclude this simple scenario based on the current data. GRB 120327A is the only GRB in our sample with two time-separated measurements of N v and shows no significant variability from 2 to 30 h (1σ difference is 26 per cent of the first measurement). In most scenarios, we would expect a change of two orders of magnitude over this time. However, since that GRB has only upper limits to the X-ray column density it cannot be excluded that the points straddle a rise and fall centred around 1 d. In addition, our current data do not show a strong correlation with time taking the bursts as an ensemble. Time-series observations of N v in the future would be very valuable to completely rule out the simple recombination-dominated hypothesis, since for most reasonable H II region electron densities, we would expect the column density of N v to rise strongly with time, such that a substantial fraction of nitrogen atoms are recombined at 10^5 s (≈ 1 d) compared to 10^4 s, easily ruling out (or confirming) a recombination-dominant scenario. The recombination outlined above excludes a contribution to the high-ionization column densities from photoionization by the GRB afterglow as suggested by Prochaska et al. (2008b). This effect almost certainly needs to be considered to properly model the time-variation of the column density in the high-ionization lines. As it is, neither the recombination or the photoionization scenarios are in agreement with the observed non-varying N v abundance and more time-resolved data are required to resolve this issue in both models.

4.2 Hot gas in GRB host galaxy haloes

There is now positive evidence that the N v (and likely also O vi) absorption features seen in GRB afterglows originate in the circumburst medium of GRBs. We note, however, that these ions are also observed in the Galactic halo² (Savage, Sembach & Lu 1997; Sembach et al. 2003; Wakker et al. 2012) but rarely with column densities as large as that observed for the GRB sample. Prochaska et al. (2008b) use this argument, together with theoretical predictions, to exclude the galactic halo gas as the origin of N v and O vi absorption in GRB afterglows. The presence of N v and O vi absorption (though rare) in DLAs and sub-DLAs in the line of sight towards quasars (Fox et al. 2007a, 2009), however, likely originates from their galactic haloes. Similar low column densities, as in the local Galactic halo, are observed for these samples. Moreover, the column density of N v in these quasar absorbers is found to be correlated with the column density and velocity width of C iv (Fox et al. 2009) which supports a circumgalactic origin.

The fact that the velocity width of C iv is generally more extended than the neutral gas profiles (e.g. Ledoux et al. 1998; Wolfe & Prochaska 2000; Fox et al. 2007b) is in good agreement with a model where C iv originates in the hot gas constituting the galactic haloes (Maller et al. 2003). That the same is true for C iv and Si iv absorption observed in GRB afterglows was motivated by, e.g. Fox et al. (2008), who found that the velocity widths of these ions are similar to those observed for DLAs towards quasars (Fox et al. 2007b), with multiple components in a velocity range of several hundred km s^{-1} around z_{GRB} (although still with a larger average C iv column density).

With the advent of space-borne UV spectroscopy, interstellar absorption lines of highly ionized species (C iv, Si iv, N v, and O vi)

²Here we use the term Galactic halo to distinguish the hot gas surrounding the host from the neutral ISM of the galaxy.

have also been detected in several Galactic sight lines towards OB-type stars (e.g. Black et al. 1980). These detections demonstrate the presence of highly ionized ‘coronal’ gas in the disc (and halo) of the Milky Way as well as in other nearby galaxies (Lehner et al. 2011). The absorption by C IV and Si IV exhibits broad and narrow components, while only broad components are seen in N V and O VI. The narrow components are associated with the vicinities of O-type stars and their surrounding supershells. The broad components trace collisionally ionized gas ($T > 10^5$ K) in the hot ISM.

It is not possible to robustly measure the column densities of C IV and Si IV for the GRBs in our sample due to heavy saturation. We confirm, however, that the velocity widths of these ions are generally much larger than the line profiles of the low-ionization lines and N V. Moreover, the peak optical depth of C IV and Si IV is not aligned with N V, except in a few cases where all three ions are aligned with z_{GRB} . In conclusion, while C IV and Si IV absorption likely originates in the galactic haloes of DLAs and sub-DLAs towards quasars and surrounding GRB hosts, N V and O VI absorption is caused by gas at two distinct regions in the two cases; one from the hot halo gas around DLA and sub-DLAs towards quasars and the other from the gas in the vicinity of the GRB explosion site (though also with a possible small contribution from the hot halo gas).

5 CONCLUDING REMARKS

We have performed a survey for high-ionization absorption in 18 afterglow spectra of long-duration GRBs at $z \approx 1.7$ –6 observed with VLT/X-shooter. We surveyed the high-ionization species of N V, O VI, C IV, Si IV, S IV, S VI, and P V, but focus on N V since it is the least saturated and blended of these ions. Out of the 18 bursts, we detect N V in 12 of the cases, all having large column densities for which we found average and median values of $\log N(\text{N V})_{\text{avg}} = 14.36$ and $\log N(\text{N V})_{\text{med}} = 14.50$, respectively. We place 3σ upper limits on N V for the remaining six bursts and show that the non-detections are likely either related to the intrinsic or observed faintness of the GRBs, resulting in poor signal-to-noise ratios at the spectral region covering the N V doublet.

By comparing the strength of N V to the neutral gas properties in individual bursts such as metallicity, H I column density, and dust depletion, both from our sample and previous samples from the literature, we found no correlation between any of these measurements. This suggests that the gas responsible for the N V absorption is unrelated to the properties of the neutral gas in the GRB host galaxy ISM. We found, however, that for GRBs with H I column densities below $\approx 10^{21} \text{ cm}^{-2}$, the line profile of N V is offset by $\delta v \approx -100 \text{ km s}^{-1}$ relative to z_{GRB} , whereas for higher H I column densities the N V gas is kinematically ‘cold’, where $|\delta v| \lesssim 30 \text{ km s}^{-1}$. This suggests a scenario where the natal H II region of the GRB containing the N V gas is confined by the pressure from the surrounding neutral gas in the ISM.

It has been argued that since we observe soft X-ray absorption in excess of Galactic in the majority of GRB afterglows, there must be a significant column density of highly ionized gas within GRB host galaxies. Based on our sample and two previous samples from the literature we found that the X-ray derived metal column density, $N_{\text{H,X}}$, is positively correlated (at 2σ significance) with the column density of N V. Since the line profiles of N V are also found to be coincident in velocity with the UV-pumped fine-structure absorption lines, we affirm that both measurements likely trace the column density of metals in the circumburst medium of the GRB. We then demonstrate that a simple model, where the initial prompt emission from the GRB has stripped the electrons from the surrounding gas

entirely, can reproduce the observed column densities of N V and O VI via recombination. We here assumed that the gas is fully ionized out to ≈ 10 pc within the first few seconds after the GRB, and that the gas has $T = 10^4$ K and an electron density of $n_e = 2 \times 10^4 \text{ cm}^{-3}$ typical for H II regions.

We would like to encourage future and more detailed modelling of the proposed recombination scenario. Such a model would also have to include the later contribution from photoionization by the afterglow to the observed column densities. A complementary approach would be to measure variations in the column density of N V as a function of time in GRB afterglow spectra. We searched for such a temporal variation in the first and second epoch VLT/X-shooter spectra of GRB 120327A (obtained at $\Delta t_{\text{obs}} \approx 2.1$ and 30.6 h), but the equivalent width of N V is not observed to vary with statistical significance. A similar result was found by Prochaska et al. (2008b) for GRBs 050730 and 050820. Finally, if the recombination scenario proposed here is true we would expect to observe strong emission features from the transitions of, e.g. N VII to N VI and N VI to N V. These line emissions might be possible to observe for low- z GRBs but will require a telescope that is sensitive in the near- and far-ultraviolet.

ACKNOWLEDGEMENTS

We would like to thank the referee for a clear and thorough report, which greatly improved the presentation of the results in the paper. We also wish to thank K. Wiersema and P. Møller for enlightening discussions. KEH and PJ acknowledge support by a Project Grant (162948–051) from The Icelandic Research Fund. JK acknowledges financial support from the Danish Council for Independent Research (EU-FP7 under the Marie-Curie grant agreement no. 600207) with reference DFF–MOBILEX–5051–00115. JJ acknowledges support from NOVA and NWO-FAPESP grant for advanced instrumentation in astronomy. AG acknowledges the financial support from the Slovenian Research Agency (research core funding no. P1-0031 and project grant no. J1-8136). AdUP, CCT, and ZC acknowledge support from the Spanish Ministry of Economy and Competitiveness under grant number AYA 2014-58381-P. AdUP and CCT acknowledge support from Ramon y Cajal fellowships (RyC-2012-09975 and RyC-2012-09984). AdUP acknowledges support from a grant from the BBVA foundation for researchers and cultural creators. ZC acknowledges support from the Juan de la Cierva Incorporación fellowship IJCI-2014-21669 and from the Spanish research project AYA 2014-58381-P. RS-R acknowledges support from ASI (Italian Space Agency) through the contract no. 2015-046-R.0 and from European Union Horizon 2020 Programme under the AHEAD project (grant agreement no. 654215).

REFERENCES

- Arabsalmani M. et al., 2018, *MNRAS*, 473, 3312
- Arabsalmani M., Møller P., Fynbo J. P. U., Christensen L., Freudling W., Savaglio S., Zafar T., 2015, *MNRAS*, 446, 990
- Arcodia R., Campana S., Salvaterra R., 2016, *A&A*, 590, A82
- Asplund M., Grevesse N., Sauval A. J., Scott P., 2009, *ARA&A*, 47, 481
- Atwood W. B. et al., 2009, *ApJ*, 697, 1071
- Beardmore A. P. et al., 2012, GCN Circ. (GRB Coordinates Network), #1, 12859
- Behar E., Dado S., Dar A., Laor A., 2011, *ApJ*, 734, 26
- Bissaldi E., Briggs M. S., Piron F., Takahashi H., Uehara T., 2009, GCN Circ. (GRB Coordinates Network), 9972
- Bissaldi E., Racusin J. L., Longo F., Kocevski D., Vianello G., Arimoto M., 2014, GCN Circ. (GRB Coordinates Network), #1, 16969

- Black J. H., Hartmann L. W., Raymond J. C., Dupree A. K., 1980, *ApJ*, 239, 502
- Bloom J. S., Kulkarni S. R., Djorgovski S. G., 2002, *AJ*, 123, 1111
- Bregman J. N., Harrington J. P., 1986, *ApJ*, 309, 833
- Campana S., Thöne C. C., de Ugarte Postigo A., Tagliaferri G., Moretti A., Covino S., 2010, *MNRAS*, 402, 2429
- Campana S., Salvaterra R., Ferrara A., Pallottini A., 2015, *A&A*, 575, A43
- Castro-Tirado A. J. et al., 2010, *A&A*, 517, A61
- Cucchiara A., Fumagalli M., Rafelski M., Kocevski D., Prochaska J. X., Cooke R. J., Becker G. D., 2015, *ApJ*, 804, 51
- D'Avanzo P., Barthelmy S. D., Bernardini M. G., Chester M. M., Melandri A., Palmer D. M., Siegel M. H., 2014, GCN Circ. (GRB Coordinates Network), #1, 17037
- D'Avanzo P., Barthelmy S. D., Burrows D. N., Marshall F. E., Melandri A., Palmer D. M., Sbarufatti B., Siegel M. H., 2016, GCN Circ. (GRB Coordinates Network), #1, 18979
- D'Elia V. et al., 2010, *A&A*, 523, A36
- D'Elia V. et al., 2014, *A&A*, 564, A38
- de Ugarte Postigo A., Malesani D., Xu D., 2015, GCN Circ. (GRB Coordinates Network), #1, 18426
- Dyson J. E., 1977, *A&A*, 59, 161
- Eitan A., Behar E., 2013, *ApJ*, 774, 29
- Fox A. J., Petitjean P., Ledoux C., Srianand R., 2007a, *A&A*, 465, 171
- Fox A. J., Ledoux C., Petitjean P., Srianand R., 2007b, *A&A*, 473, 791
- Fox A. J., Ledoux C., Vreeswijk P. M., Smette A., Jaunsen A. O., 2008, *A&A*, 491, 189
- Fox A. J., Prochaska J. X., Ledoux C., Petitjean P., Wolfe A. M., Srianand R., 2009, *A&A*, 503, 731
- Friis M. et al., 2015, *MNRAS*, 451, 167
- Fruchter A. S. et al., 2006, *Nature*, 441, 463
- Fruchter A., Krolik J. H., Rhoads J. E., 2001, *ApJ*, 563, 597
- Fynbo J. P. U. et al., 2006, *A&A*, 451, L47
- Fynbo J. P. U. et al., 2009, *ApJS*, 185, 526
- Fynbo J. P. U., Prochaska J. X., Sommer-Larsen J., Dessauges-Zavadsky M., Møller P., 2008, *ApJ*, 683, 321
- Galama T. J., Wijers R. A. M. J., 2001, *ApJ*, 549, L209
- Gehrels N. et al., 2004, *ApJ*, 611, 1005
- Goldoni P., Royer F., François P., Horrobin M., Blanc G., Vernet J., Modigliani A., Larsen J., 2006, Proc. SPIE Conf. Ser. Vol., SPIE, Bellingham, p. 62692K
- Goshu B. S., 2017, *Am. J. Astron. Astrophys.*, 5, 42
- Greiner J. et al., 2011, *A&A*, 526, A30
- Hartoog O. E. et al., 2015, *A&A*, 580, A139
- Hartoog O. E., Malesani D., Wiersema K., Kruehler T., Schulze S., de Ugarte Postigo A., D'Elia V., Fynbo J. P. U., 2012, GCN Circ. (GRB Coordinates Network), #1, 13730
- Hjorth J., Melandri A., Malesani D., Kruehler T., Xu D., 2013, GCN Circ. (GRB Coordinates Network), #1, 14365
- Immler S. et al., 2012, GCN Circ. (GRB Coordinates Network), #1, 13727
- Jakobsson P. et al., 2004, *A&A*, 427, 785
- Jakobsson P. et al., 2006, *A&A*, 460, L13
- Krogager J.-K., 2018, preprint ([arXiv:1803.01187](https://arxiv.org/abs/1803.01187))
- Krongold Y., Prochaska J. X., 2013, *ApJ*, 774, 115
- Kruehler T., Fynbo J. P. U., Milvang-Jensen B., Tanvir N., Jakobsson P., 2012, GCN Circ. (GRB Coordinates Network), #1, 13134
- Krühler T. et al., 2013, *A&A*, 557, A18
- Ledoux C., Petitjean P., Bergeron J., Wampler E. J., Srianand R., 1998, *A&A*, 337, 51
- Ledoux C., Petitjean P., Fynbo J. P. U., Møller P., Srianand R., 2006, *A&A*, 457, 71
- Lehner N., Zech W. F., Howk J. C., Savage B. D., 2011, *ApJ*, 727, 46
- Lien A. Y. et al., 2013, GCN Circ. (GRB Coordinates Network), #1, 14361
- Lien A. et al., 2016, *ApJ*, 829, 7
- Lien A. Y., Barthelmy S. D., D'Elia V., Gehrels N., Kennea J. A., Marshall F. E., Page K. L., Sbarufatti B., 2015, GCN Circ. (GRB Coordinates Network), #1, 17665
- Lyman J. D. et al., 2017, *MNRAS*, 467, 1795
- Magdis G. E. et al., 2012, *ApJ*, 760, 6
- Malesani D. et al., 2009b, GCN Circ. (GRB Coordinates Network), 9942
- Malesani D., Fynbo J. P. U., Christensen L., de Ugarte Postigo A., Milvang-Jensen B., Covino S., 2009a, GCN Circ. (GRB Coordinates Network), 9761
- Malesani D., Schulze S., de Ugarte Postigo A., Xu D., D'Elia V., Fynbo J. P. U., Tanvir N. R., 2012, GCN Circ. (GRB Coordinates Network), #1, 13649
- Maller A. H., Prochaska J. X., Somerville R. S., Primack J. R., 2003, *MNRAS*, 343, 268
- Markwardt C. B. et al., 2009, GCN Circ. (GRB Coordinates Network), 9754
- McGuire J. T. W. et al., 2016, *ApJ*, 825, 135
- Meegan C. et al., 2009, *ApJ*, 702, 791
- Melandri A., Barthelmy S. D., D'Avanzo P., Krimm H. A., Kuin N. P. M., Palmer D. M., Sbarufatti B., 2015, GCN Circ. (GRB Coordinates Network), #1, 18425
- Mereghetti S., Gotz D., Ferrigno C., Fotopoulou S., Borkowski J., 2016, GCN Circ. (GRB Coordinates Network), #1, 20103
- Modigliani A. et al., 2010, Proc. SPIE Conf. Ser. Vol., Observatory Operations: Strategies, Processes, and Systems III. SPIE, Bellingham, p. 773728
- Møller P. et al., 2002, *A&A*, 396, L21
- Noterdaeme P., Petitjean P., Ledoux C., Srianand R., 2009, *A&A*, 505, 1087
- Nysewander M., Fruchter A. S., Pe'er A., 2009, *ApJ*, 701, 824
- Pagani C. et al., 2012b, GCN Circ. (GRB Coordinates Network), #1, 13886
- Pagani C., Barthelmy S. D., Gehrels N., Marshall F. E., Page K. L., Palmer D. M., Stamatikos M., 2012a, GCN Circ. (GRB Coordinates Network), #1, 13645
- Perna R., Lazzati D., Fiore F., 2003, *ApJ*, 585, 775
- Pettini M., Zych B. J., Steidel C. C., Chaffee F. H., 2008, *MNRAS*, 385, 2011
- Planck Collaboration et al., 2016, *A&A*, 594, A13
- Prochaska J. X., Chen H.-W., Bloom J. S., 2006, *ApJ*, 648, 95
- Prochaska J. X., Chen H.-W., Dessauges-Zavadsky M., Bloom J. S., 2007, *ApJ*, 666, 267
- Prochaska J. X., Chen H.-W., Wolfe A. M., Dessauges-Zavadsky M., Bloom J. S., 2008a, *ApJ*, 672, 59
- Prochaska J. X., Dessauges-Zavadsky M., Ramirez-Ruiz E., Chen H.-W., 2008b, *ApJ*, 685, 344
- Pugliese V., Xu D., Tanvir N. R., Wiersema K., Fynbo J. P. U., Milvang-Jensen B., D'Elia V., 2015, GCN Circ. (GRB Coordinates Network), #1, 17672
- Pugliese G., Covino S., Kruehler T., Xu D., Tanvir N. R., 2016, GCN Circ. (GRB Coordinates Network), #1, 18982
- Sánchez-Ramírez R. et al., 2016, *MNRAS*, 456, 4488
- Savage B. D., Sembach K. R., Lu L., 1997, *AJ*, 113, 2158
- Savaglio S., Fall S. M., Fiore F., 2003, *ApJ*, 585, 638
- Saxton C. J. et al., 2011, GCN Circ. (GRB Coordinates Network), 12423
- Sbarufatti B. et al., 2012, GCN Circ. (GRB Coordinates Network), #1, 13123
- Schady P. et al., 2010, *MNRAS*, 401, 2773
- Schady P., Savaglio S., Krühler T., Greiner J., Rau A., 2011, *A&A*, 525, A113
- Schlafly E. F., Finkbeiner D. P., 2011, *ApJ*, 737, 103
- Schlegel D. J., Finkbeiner D. P., Davis M., 1998, *ApJ*, 500, 525
- Sembach K. R. et al., 2003, *ApJS*, 146, 165
- Sparre R. et al., 2014, *ApJ*, 785, 150
- Starling R. L. C., Willingale R., Tanvir N. R., Scott A. E., Wiersema K., O'Brien P. T., Levan A. J., Stewart G. C., 2013, *MNRAS*, 431, 3159
- Svensson K. M., Levan A. J., Tanvir N. R., Fruchter A. S., Strolger L.-G., 2010, *MNRAS*, 405, 57
- Tanvir N. R. et al., 2012a, *ApJ*, 754, 46
- Tanvir N. R., Fynbo J. P. U., Melandri A., Levan A. J., Xu D., D'Elia V., 2012b, GCN Circ. (GRB Coordinates Network), #1, 13890
- Tanvir N. R., Kruehler T., De Cia A., Wiersema K., Xu D., Malesani D., 2016, GCN Circ. (GRB Coordinates Network), #1, 20104
- Ukwatta T. N. et al., 2013, GCN Circ. (GRB Coordinates Network), #1, 14781

- Ukwatta T. N. et al., 2015, GCN Circ. (GRB Coordinates Network), #1, 18499
- van Dokkum P. G., 2001, *PASP*, 113, 1420
- Vernet J. et al., 2011, *A&A*, 536, A105
- Vreeswijk P. M. et al., 2004, *A&A*, 419, 927
- Vreeswijk P. M. et al., 2007, *A&A*, 468, 83
- Vreeswijk P. M. et al., 2011, *A&A*, 532, C3
- Vreeswijk P. M., Kaufer A., Spyromilio J., Schmutzer R., Ledoux C., Smette A., De Cia A., 2010, Proc. SPIE Conf. Ser. Vol., Observatory Operations: Strategies, Processes, and Systems III. SPIE, Bellingham, p. 77370M
- Wakker B. P., Savage B. D., Fox A. J., Benjamin R. A., Shapiro P. R., 2012, *ApJ*, 749, 157
- Watson D. et al., 2006, *ApJ*, 652, 1011
- Watson D. et al., 2013, *ApJ*, 768, 23
- Watson D., Jakobsson P., 2012, *ApJ*, 754, 89
- Watson D., Reeves J. N., Osborne J., O'Brien P. T., Pounds K. A., Tedds J. A., Santos-Lleó M., Ehle M., 2002, *A&A*, 393, L1
- Watson D., Hjorth J., Fynbo J. P. U., Jakobsson P., Foley S., Sollerman J., Wijers R. A. M. J., 2007, *ApJ*, 660, L101
- Waxman E., Draine B. T., 2000, *ApJ*, 537, 796
- Wiersema K. et al., 2011, GCN Circ. (GRB Coordinates Network), 12431
- Willingale R., Starling R. L. C., Beardmore A. P., Tanvir N. R., O'Brien P. T., 2013, *MNRAS*, 431, 394
- Winkler C. et al., 2003, *A&A*, 411, L1
- Wiseman P., Schady P., Bolmer J., Krühler T., Yates R. M., Greiner J., Fynbo J. P. U., 2017, *A&A*, 599, A24
- Wolfe A. M., Prochaska J. X., 2000, *ApJ*, 545, 591
- Xu D. et al., 2013, GCN Circ. (GRB Coordinates Network), #1, 14816
- Xu D., Levan A. J., Fynbo J. P. U., Tanvir N. R., D'Elia V., Malesani D., 2014a, GCN Circ. (GRB Coordinates Network), #1, 16983
- Xu D., Vreeswijk P. M., Fynbo J. P. U., D'Elia V., Wiersema K., Tanvir N. R., de Ugarte Postigo A., Covino S., 2014b, GCN Circ. (GRB Coordinates Network), #1, 17040
- Xu D., Tanvir N. R., Malesani D., Fynbo J., 2015, GCN Circ. (GRB Coordinates Network), #1, 18505
- Zafar T., Watson D., 2013, *A&A*, 560, A
- Zafar T., Watson D., Fynbo J. P. U., Malesani D., Jakobsson P., de Ugarte Postigo A., 2011, *A&A*, 532, A143

APPENDIX A: NOTES ON INDIVIDUAL GRBS

A1 GRB 090809 at $z = 2.737\ 06$

The spectrum of GRB 090809A was secured 10.2 h after trigger with an acquisition magnitude of 21.0 mag. The H α column density is adopted from Tanvir et al. (submitted) and was used for the determination of the metallicity. From the fit to Si λ 1808, Thöne et al. (in preparation) find $[\text{Si}/\text{H}] = -0.76 \pm 0.20$. We detect high-ionization absorption features from C IV and Si IV and measure an upper limit for N V of $\log N(\text{N}\text{V}) < 14.43$ (see Fig. B1). The spectral data have low S/N at the location of the other surveyed high-ionization species. The detected high-ionization features are consistent with a single velocity component at $\approx z_{\text{GRB}}$. The X-ray derived metal column density used in Section 3.4 for this burst is from the *Swift*/XRT data base.³

A2 GRB 090926A at $z = 2.106\ 94$

The spectrum of GRB 090926A was secured 22.0 h after trigger with an acquisition magnitude of 17.9 mag. The H α column density and metallicity are adopted from D'Elia et al. (2010). We detect high-ionization absorption features from N V , C IV , Si IV , S IV , and




Figure B1. GRB090809.

O VI (see Fig. B2). The absorption lines from S $\text{VI}\lambda\lambda$ 933, 944 are located outside the spectral coverage of the UVB arm at this redshift. There is a strong absorption feature at $-200\ \text{km s}^{-1}$ relative to z_{GRB} at the position of P $\text{V}\lambda$ 1117, but since we do not detect P $\text{V}\lambda$ 1128 at the same redshift this is likely an unrelated line. The strongest component of the high-ionization features is located at z_{GRB} , where C IV and Si IV show an additional component at $\approx -75\ \text{km s}^{-1}$ relative to z_{GRB} . The velocity components of N V are best fit following the low-ionization lines, represented by Si $\text{II}\lambda$ 1526 in the figure. The line profiles of O VI show two strong components, one at z_{GRB} , and the other at $\approx -200\ \text{km s}^{-1}$ relative to z_{GRB} . The X-ray derived metal column density used in Section 3.4 for this burst is from Zafar et al. (submitted).

A3 GRB 100425A at $z = 1.756\ 40$

The spectrum of GRB 100425A was secured 4.0 h after trigger with an acquisition magnitude of 20.6 mag. The H α column density and metallicity are adopted from Cucchiara et al. (2015). We detect high-ionization absorption features from C IV and Si IV (see Fig. B3) and measure an upper limit for N V of $\log N(\text{N}\text{V}) < 14.63$. We caution, however, that all features are located in regions with poor spectral S/N and O VI , S IV , and S VI are outside the spectral coverage of the UVB arm. Because of this we do not report column densities for these transitions. No information on the velocity components is available from C IV and Si IV , except that the absorption

³http://www.swift.ac.uk/xrt_spectra/00359530/




Figure B2. GRB090926A.




Figure B3. GRB100425A. The spectrum has been binned by a factor of 2.

line profiles cover $\approx -100 < z_{\text{GRB}} < +100 \text{ km s}^{-1}$. The X-ray derived metal column density used in Section 3.4 for this burst is from the *Swift*/XRT data base.⁴

⁴http://www.swift.ac.uk/xrt_spectra/00420398/




Figure B4. GRB111008A. The spectrum has been binned by a factor of 2.

A4 GRB 111008A at $z = 4.99146$

The spectrum of GRB 111008A was secured 8.5 h after trigger with an acquisition magnitude of 21.0 mag. The H I column density and metallicity are adopted from Sparre et al. (2014). We detect high-ionization absorption features from N v, C iv, and Si iv (see Fig. B4). The absorption lines from C iv and Si iv are saturated and partly blended, so we do not report column densities for these transitions. We report a non-detection of the remaining surveyed high-ionization species, but caution that they are all located in spectral regions with poor S/N. No information on the velocity components is available from C iv and Si iv, except that the absorption line profiles cover $\approx -200 < z_{\text{GRB}} < +100 \text{ km s}^{-1}$. N v is consistent with a single velocity component at $\approx z_{\text{GRB}}$, but we are only able to infer a lower limit N v due to line saturation. The X-ray derived metal column density used in Section 3.4 for this burst is from Zafar et al. (submitted).

A5 GRB 120119A at $z = 1.72883$

The spectrum of GRB 120119A was secured 1.4 h after trigger with an acquisition magnitude of 17.0 mag. The H I column density is adopted from Tanvir et al. (submitted) and was used for the determination of the metallicity. Thöne et al. (in preparation) measure $[\text{Si}/\text{H}] = -1.43 \pm 0.21$ from a fit to Si II λ 1808. We detect high-ionization absorption features from C iv and Si iv (see Fig. B5) and measure an upper limit for N v of $\log N(\text{N v}) < 15.15$. We caution,




Figure B5. GRB120119A. The spectrum has been binned by a factor of 2.

however, that N v is located in a region with a poor spectral S/N and O vi, S iv, and S vi are outside the spectral coverage of the UVB arm. The absorption lines from C iv and Si iv are heavily saturated and partly blended, so we do not report column densities for these transitions. We report a non-detection of the remaining surveyed high-ionization species, but caution that they are all located in spectral regions with poor S/N. No information on the velocity components is available from C iv and Si iv, except that the absorption line profiles cover $\approx -700 < z_{\text{GRB}} < 0 \text{ km s}^{-1}$. The X-ray derived metal column density used in Section 3.4 for this burst is from Zafar et al. (submitted).

A6 GRB 120327A at $z = 2.81482$

The spectrum of GRB 120317A was secured 2.1 h after trigger with an acquisition magnitude of 18.8 mag. The H i column density, metallicity, and high-ionization absorption lines are adopted from D’Elia et al. (2014). They detect all the surveyed high-ionization absorption features except for S iv and are consistent with being located at the central velocity component (out of three extending from $\approx \pm 100 \text{ km s}^{-1}$ relative to z_{GRB}) of the low-ionization species. They measure $\log N(\text{N v}/\text{cm}^{-2}) = 13.56 \pm 0.03$ which was used in our analysis. The X-ray derived metal column density used in Section 3.4 for this burst is from the *Swift*/XRT data base.⁵

A7 GRB 120815A at $z = 2.35820$

The spectrum of GRB 120815A was secured 1.69 h after trigger with an acquisition magnitude of 18.9 mag. The H i column density, metallicity, and X-ray derived metal column density used in Section 3.4 for this burst are adopted from Krühler et al. (2013). We detect high-ionization absorption features from N v, C iv, and Si iv (see Fig. B6). The absorption lines from C iv and Si iv are saturated and the derived column densities should only be considered as lower limits. We report a non-detection of the remaining surveyed high-ionization species, but caution that they are all located in spectral regions with poor S/N. The high-ionization line profiles are best fitted with two velocity components at z_{GRB} and $\approx -23 \text{ km s}^{-1}$




Figure B6. GRB120815A.

relative to z_{GRB} , similar to the low-ionization absorption lines, represented by Si ii λ 1808 in the figure.

A8 GRB 120909A at $z = 3.92882$

The spectrum of GRB 120909A was secured 1.7 h after trigger using the rapid-response mode with an acquisition magnitude of 21.0 mag. The H i column density is adopted from Tanvir et al. (submitted) and was used for the determination of the metallicity. Thöne et al. (in preparation) measure $[\text{S}/\text{H}] = -0.66 \pm 0.11$ from a combined fit to Si ii λ 1250, 1253. We detect high-ionization absorption features from N v, C iv, Si iv, S iv, and S vi (see Fig. B7). We only fit Voigt profiles to N v and Si iv since the other lines are either blended or saturated. P v is located in a spectral region with a poor S/N and O vi is heavily blended with the Ly α forest. The main velocity component of the high-ionization absorption lines is located at z_{GRB} , represented by Si ii λ 1250 in the figure. In addition, there is also a small component at $\approx -125 \text{ km s}^{-1}$ relative to z_{GRB} . The X-ray derived metal column density used in Section 3.4 for this burst is from the *Swift*/XRT data base.⁶

⁵http://www.swift.ac.uk/xrt_spectra/00518731/

⁶http://www.swift.ac.uk/xrt_spectra/00533060/




Figure B7. GRB120909A.

A9 GRB 121024A at $z = 2.30244$

The spectrum of GRB 121024A was secured 1.8 h after trigger with an acquisition magnitude of 20.0 mag. The H I column density and metallicity are adopted from Friis et al. (2015). We detect high-ionization absorption from C IV and Si IV (see Fig. B8) and measure an upper limit for N V of $\log N(\text{N V}) < 14.35$. Both of these two absorption lines are saturated and the derived column densities should only be considered as lower limits. We report a non-detection of the remaining surveyed high-ionization species, but caution that they are all located in spectral regions with poor S/N. The velocity components of C IV and Si IV show a weak, ionized cloud at z_{GRB} , and a highly complex distribution at (-600) – (-100) km s $^{-1}$ relative to z_{GRB} . For comparison, the low-ionization absorption line profiles, represented by Fe II λ 1608 in the figure, show two strong components, one at z_{GRB} and one at -400 km s $^{-1}$ relative to z_{GRB} . The X-ray derived metal column density used in Section 3.4 for this burst is from the *Swift*/XRT data base.⁷

A10 GRB 130408A at $z = 3.75792$

The spectrum of GRB 160408A was secured 1.9 h after trigger with an acquisition magnitude of 20.0 mag. The H I column density is




Figure B8. GRB121024A.

adopted from Tanvir et al. (submitted) and was used for the determination of the metallicity. Thöne et al. (in preparation) measure $[\text{Si}/\text{H}] = -1.38 \pm 0.12$ from a combined fit to Si II λ 1526, 1808. We detect high-ionization absorption features from N V, C IV, Si IV, and S VI. The three features O VI, P V, and S IV are all blended (see Fig. B9) and therefore we do not attempt to measure their column densities. The absorption line profile of N V is consistent with a single velocity component. The velocity components of C IV, Si IV, and S VI follow the same distribution as for the low-ionization line profiles, represented in the figure by Si II λ 1808. The X-ray derived metal column density used in Section 3.4 for this burst is from the *Swift*/XRT data base,⁸ but corrected for the measured redshift.

A11 GRB at $z = 5.91278$

The spectrum of GRB 130606A was secured 7.1 h after trigger with an acquisition magnitude of 19.0 mag. The H I column density, metallicity, and X-ray derived metal column density used in Section 3.4 for this burst are adopted from Hartoog et al. (2015). Since the intervening intergalactic medium has a high neutral fraction, the continuum on the blue side of the Ly α absorption feature is completely suppressed. Therefore, we only searched for high-ionization absorption lines redwards of Ly α . We detect N V, C IV,

⁷http://www.swift.ac.uk/xrt_spectra/00536580/

⁸http://www.swift.ac.uk/xrt_spectra/00553132/




Figure B9. GRB130408A.

and Si iv, all with multiple velocity components (see Fig. B10). C iv and Si iv are both saturated, so the column densities derived for these two species should only be considered as lower limits. While the velocity components of C iv and Si iv are consistent with the low-ionization absorption line profiles, represented by Si ii λ 1260 in the figure, N v has two main components at $\approx \pm 100$ km s⁻¹ compared to z_{GRB} .

A12 GRB 141028A at $z = 2.333\ 27$

The spectrum of GRB 141028A was secured 15.4 h after trigger with an acquisition magnitude of 20.0 mag. The H i column density is adopted from Tanvir et al. (submitted) and was used for the determination of the metallicity. Thöne et al. (in preparation) measure $[\text{Si}/\text{H}] = -0.75 \pm 0.15$ from a combined fit to Si ii λ 1260, 1526. We detect high-ionization absorption features from N v, C iv, Si iv, and P v (see Fig. B11). S vi λ 933, 944 are located bluewards of the spectral coverage of the UVB arm and the region around O vi and S iv has a poor S/N. The main velocity components of the high-ionization absorption line profiles are located at ≈ -100 km s⁻¹ from z_{GRB} . N v and P v are both well fitted with a single velocity component whereas Si iv and C iv show three and four velocity components, respectively. The X-ray derived metal column density




Figure B10. GRB130606A.




Figure B11. GRB141028A.

used in Section 3.4 for this burst is from the *Swift*/XRT data base, but corrected for the measured redshift.⁹

A13 GRB 141109A at $z = 2.994\ 38$

The spectrum of GRB 141109A was secured 1.9 h after trigger with an acquisition magnitude of 19.2 mag. The H i column density is adopted from Tanvir et al. (submitted) and was used for the determination of the metallicity. Thöne et al. (in preparation) measure $[\text{Zn}/\text{H}] = -1.45 \pm 0.21$ from a combined fit to Zn ii λ 2026, 2062. We detect high-ionization absorption features from N v, C iv, Si iv,

⁹http://www.swift.ac.uk/xrt_spectra/00020420/




Figure B12. GRB141109A.

S_{VI} , P_{V} , and S_{IV} (see Fig. B12). Strong absorption from Si_{IV} , C_{IV} , and P_{V} is observed and all features are mildly saturated. The velocity components and column densities of Si_{IV} and C_{IV} are hard to disentangle since they are both blended and are located in regions with poor S/N. The main component of N_{V} is located at $\approx 13 \text{ km s}^{-1}$ from z_{GRB} and while being best fitted by two components we only trust the one central fit. We are also only able to derive a lower limit to the column density for N_{V} due to line saturation. The detections of $S_{\text{VI}} \lambda \lambda 933, 944$, $P_{\text{V}} \lambda \lambda 1117, 1128$, and $\text{Si}_{\text{IV}} \lambda 1062$ are tentative since they all appear blended with the $\text{Ly} \alpha$ forest. If the detections of $P_{\text{V}} \lambda \lambda 1117, 1128$ are real, those are the only features with blueshifted velocity components compared to z_{GRB} , the others are at $(-400)-(0) \text{ km s}^{-1}$. The X-ray derived metal column density used in Section 3.4 for this burst is from the *Swift*/XRT data base.¹⁰

A14 GRB 150403A at $z = 2.05707$

The spectrum of GRB 150403A was secured 10.8 h after trigger with an acquisition magnitude of 19.1 mag. The H_{I} column density is adopted from Tanvir et al. (submitted) and was used for the determination of the metallicity. Thöne et al. (in preparation) measure $[\text{S}/\text{H}] = -0.80 \pm 0.35$ from a combined fit to $\text{Si}_{\text{II}} \lambda \lambda 1250, 1253$. We detect high-ionization absorption features from N_{V} , C_{IV} , and Si_{IV} (see Fig. B13). Strong absorption from Si_{IV} and C_{IV} is observed




Figure B13. GRB150403A.

and both features are mildly saturated. The four velocity components of both of these line profiles are similar to the low-ionization absorption features, represented in the figure by $\text{Si}_{\text{II}} \lambda 1526$, and the total line profiles extend from -200 to $+200 \text{ km s}^{-1}$. We find $\text{N}_{\text{V}} \lambda \lambda 1238, 1242$ to have a single velocity component centred at $\approx -32 \text{ km s}^{-1}$ relative to z_{GRB} . The spectral region around the lines $S_{\text{VI}} \lambda \lambda 933, 944$ is not covered by the UVB arm. $\text{O}_{\text{VI}} \lambda \lambda 1031, 1037$ are also located in a region with a poor to no spectral signal. The X-ray derived metal column density used in Section 3.4 for this burst is from the *Swift*/XRT data base.¹¹

A15 GRB 151021A at $z = 2.32975$

The spectrum of GRB 151021A was secured 0.75 h after trigger using the rapid-response mode with an acquisition magnitude of 18.2 mag. The H_{I} column density is adopted from Tanvir et al. (submitted) and was used for the determination of the metallicity. Thöne et al. (in preparation) measure $[\text{Si}/\text{H}] = -1.11 \pm 0.20$ from a combined fit to $\text{Si}_{\text{II}} \lambda \lambda 1526, 1808$. We detect high-ionization absorption features from N_{V} , C_{IV} , and Si_{IV} (see Fig. B14). Strong absorption from Si_{IV} and C_{IV} is observed and both features are mildly saturated. The five velocity components of both of these line profiles are similar to the low-ionization absorption features, represented in the figure by $\text{Si}_{\text{II}} \lambda 1526$, and the total line profiles extend from -200 to $+100 \text{ km s}^{-1}$. We report a weak detection of $\text{N}_{\text{V}} \lambda \lambda 1238, 1242$ with a single velocity component centred at $\approx 34 \text{ km s}^{-1}$ relative to z_{GRB} . For the remaining high-ionization absorption lines we surveyed, we report a non-detection but caution that the spectral regions around those lines have poor S/N. The X-ray derived metal column density used in Section 3.4 for this burst is from the *Swift*/XRT data base.¹²

¹⁰http://www.swift.ac.uk/xrt_spectra/00618024/

¹¹http://www.swift.ac.uk/xrt_spectra/00637044/

¹²http://www.swift.ac.uk/xrt_spectra/00660671/




Figure B14. GRB151021A.

A16 GRB 151027B at $z = 4.06463$

The spectrum of GRB 151027B was secured 5 h after trigger with an acquisition magnitude of 20.5 mag. The $H\text{I}$ column density is adopted from Tanvir et al. (submitted) and was used for the determination of the metallicity. Thöne et al. (in preparation) measure $[\text{Si}/\text{H}] = -1.62 \pm 0.24$ from a fit to $\text{SiII} \lambda 1526$. We detect high-ionization absorption features from CIV and SiIV (see Fig. B15) and measure an upper limit for NV of $\log N(\text{NV}) < 13.98$. We report a non-detection of NV and PV but caution that the spectral regions covering these two lines have poor S/N. S VI , O VI , and S IV , if present, are all blended. The velocity components of CIV and SiIV follow the same distribution as the low-ionization absorption line profiles, represented in the figure by $\text{SiII} \lambda 1526$. They show two components separated by only $\approx 10 \text{ km s}^{-1}$, but the total line profile covers $\pm 100 \text{ km s}^{-1}$ around z_{GRB} . The X-ray derived metal column density used in Section 3.4 for this burst is from the *Swift*/XRT data base.¹³

A17 GRB 160203A at $z = 3.51871$

The spectrum of GRB 161023A was secured 0.3 h after trigger using the rapid-response mode with an acquisition magnitude of 18.0 mag.




Figure B15. GRB151027B.

The $H\text{I}$ column density is adopted from Tanvir et al. (submitted) and was used for the determination of the metallicity. Thöne et al. (in preparation) measure $[\text{S}/\text{H}] = -1.26 \pm 0.11$ from a combined fit to $\text{SiII} \lambda 1250, 1253, \text{ and } 1259$. We detect high-ionization absorption features from CIV , SiIV , SIV , and S VI (see Fig. B16) and measure an upper limit for NV of $\log N(\text{NV}) < 13.58$. Strong absorption from SiIV and CIV is observed and both features are mildly saturated with a single (SiIV) or two (CIV) velocity components. We report a non-detection of NV in this burst, but caution that the spectral region around the absorption feature has a poor S/N. The most prominent high-ionization absorption features are centred at $\approx -70 \text{ km s}^{-1}$. There are tentative detections of O VI and PV but these features are heavily blended with unrelated lines from the $\text{Ly} \alpha$ forest. We were thus not able to securely fit an absorption profile to these lines. The X-ray derived metal column density used in Section 3.4 for this burst is from the *Swift*/XRT data base.¹⁴

A18 GRB 161023A at $z = 2.71067$

The spectrum of GRB 161023A was secured 3 h after trigger with an acquisition magnitude of 17.5 mag. The $H\text{I}$ column density is adopted from Tanvir et al. (submitted) and was used for the determination of the metallicity. Thöne et al. (in preparation) measure $[\text{Si}/\text{H}] = -1.24 \pm 0.09$ from a combined fit to $\text{SiII} \lambda 1260, 1526, \text{ and } 1808$. We detect high-ionization absorption features from NV , O VI , CIV , SiIV , SIV , S VI , and PV (see Fig. 2). Strong absorption from SiIV and CIV is observed and both features are mildly saturated with 2–3 velocity components. A single component at $\approx -120 \text{ km s}^{-1}$

¹³http://www.swift.ac.uk/xrt_spectra/00661869/

¹⁴http://www.swift.ac.uk/xrt_spectra/00672525/




Figure B16. GRB160203A.

is seen in N v, P v, S vi, O vi, and Si v. This is in contrast with the multiple velocity components seen in the low-ionization absorption features represented by Fe II λ 1608 in Fig. 2. We caution that the lines S vi λ 933, O vi λ 1031, 1037, Si v λ 1062, and P v λ 1128 are blended with unrelated absorption features from the Ly α forest. The X-ray derived metal column density used in Section 3.4 for this burst is from the *Swift*/XRT data base.¹⁵

APPENDIX B: VOIGT PROFILE FITS – TABLES AND FIGURES

Table B1. Voigt profile fits for GRB 090809 at $z = 2.737\,06$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	–	–	–	<14.43

Table B2. Voigt profile fits for GRB 090926A at $z = 2.106\,94$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	4 ± 2	15 ± 3	14.30 ± 0.19	14.30 ± 0.19
C iv	-6 ± 5	16 ± 3	15.94 ± 0.78	15.94 ± 0.78
Si iv	-76 ± 14	63 ± 13	13.62 ± 0.11	–
S iv	-6 ± 5	16 ± 3	15.19 ± 0.62	15.19 ± 0.62
S iv	-76 ± 14	63 ± 13	13.32 ± 0.11	–
S iv	0 ± 2	15 ± 3	14.79 ± 0.15	14.79 ± 0.15

Table B3. Voigt profile fits for GRB 100425A at $z = 1.756\,40$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	–	–	–	<14.63

Table B4. Voigt profile fits for GRB 111008A at $z = 4.991\,46$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v ^a	8 ± 10	50 ± 15	>14.00	>14.00

Table B5. Voigt profile fits for GRB 120119A at $z = 1.728\,83$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	–	–	–	<15.15

Table B6. Voigt profile fits for GRB 120815A at $z = 2.358\,20$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	-6 ± 7	16 ± 8	14.60 ± 0.18	14.60 ± 0.18
C iv	0 ± 2	18 ± 3	17.54 ± 0.18	17.55 ± 0.18
C iv	-23 ± 2	38 ± 5	15.46 ± 0.12	–
Si iv	0 ± 2	18 ± 3	17.40 ± 0.43	17.40 ± 0.43
Si iv	-23 ± 2	38 ± 5	14.87 ± 0.37	–

Table B7. Voigt profile fits for GRB 120909A at $z = 3.928\,82$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	-14 ± 4	41 ± 6	14.75 ± 0.11	14.75 ± 0.11

Table B8. Voigt profile fits for GRB 121024A at $z = 2.302\,44$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	–	–	–	<14.35

¹⁵http://www.swift.ac.uk/xrt_spectra/00020709/

Table B9. Voigt profile fits for GRB 130408A at $z = 3.757\ 92$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	-16 ± 2	31 ± 4	14.44 ± 0.07	14.44 ± 0.07
C iv	65 ± 3	16 ± 2	13.71 ± 0.04	15.12 ± 0.05
	0 ± 2	13 ± 3	10.83 ± 0.01	–
	-17 ± 2	28 ± 14	15.11 ± 0.05	–
Si iv	65 ± 3	16 ± 2	13.12 ± 0.02	14.42 ± 0.05
	0 ± 2	13 ± 3	13.60 ± 0.02	–
	-17 ± 2	28 ± 14	14.32 ± 0.04	–
S vi	65 ± 3	16 ± 2	13.50 ± 0.02	14.37 ± 0.05
	0 ± 2	13 ± 3	13.75 ± 0.02	–
	-17 ± 2	28 ± 14	14.17 ± 0.04	–

Table B10. Voigt profile fits for GRB 130606A at $z = 5.912\ 78$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	64 ± 1	13 ± 2	13.78 ± 0.03	14.50 ± 0.04
	-11 ± 4	57 ± 11	13.92 ± 0.06	–
	-83 ± 1	19 ± 1	14.16 ± 0.03	–
	-174 ± 4	28 ± 6	13.27 ± 0.07	–

Table B11. Voigt profile fits for GRB 141028A at $z = 2.333\ 27$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	-104 ± 20	10 ± 4	14.28 ± 0.10	14.28 ± 0.10
C iv	96 ± 7	35 ± 2	14.11 ± 0.02	14.96 ± 0.05
	-24 ± 3	66 ± 3	14.17 ± 0.02	–
	-88 ± 11	25 ± 14	14.71 ± 0.03	–
Si iv	107 ± 23	49 ± 3	13.47 ± 0.04	14.94 ± 0.07
	-39 ± 10	67 ± 7	13.69 ± 0.04	–
	-89 ± 11	12 ± 4	14.87 ± 0.06	–
P v	-67 ± 21	28 ± 12	14.86 ± 0.04	14.86 ± 0.04

Table B12. Voigt profile fits for GRB 141109A at $z = 2.994\ 38$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v ^a	13 ± 15	9 ± 3	$\gtrsim 14.85$	$\gtrsim 14.85$

Table B13. Voigt profile fits for GRB 150403A at $z = 2.057\ 07$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	-32 ± 3	48 ± 11	14.73 ± 0.14	14.73 ± 0.14
C iv	44 ± 2	99 ± 3	14.84 ± 0.07	15.75 ± 0.10
	22 ± 2	69 ± 3	15.16 ± 0.07	–
	-50 ± 4	5 ± 3	14.24 ± 0.02	–
	-196 ± 5	22 ± 5	15.52 ± 0.04	–
Si iv	120 ± 4	58 ± 7	13.93 ± 0.03	14.58 ± 0.08
	23 ± 2	55 ± 7	13.89 ± 0.05	–
	-10 ± 4	4 ± 2	12.64 ± 0.03	–
	-195 ± 5	42 ± 5	14.33 ± 0.04	–

Table B14. Voigt profile fits for GRB 151021A at $z = 2.329\ 75$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	34 ± 5	31 ± 19	14.80 ± 0.46	14.80 ± 0.46
C iv	47 ± 2	15 ± 3	12.21 ± 0.07	18.26 ± 0.17
	0 ± 2	19 ± 3	18.26 ± 0.10	–
	-52 ± 4	18 ± 3	11.25 ± 0.02	–
	-121 ± 5	35 ± 5	13.90 ± 0.04	–
	-160 ± 7	2 ± 3	14.70 ± 0.06	–
Si iv	47 ± 4	15 ± 7	13.88 ± 0.03	15.32 ± 0.07
	0 ± 2	19 ± 3	15.28 ± 0.05	–
	-52 ± 4	18 ± 3	13.55 ± 0.03	–
	-121 ± 5	35 ± 5	13.57 ± 0.04	–
	-160 ± 7	2 ± 3	12.27 ± 0.02	–

Table B15. Voigt profile fits for GRB 151027B at $z = 4.064\ 63$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	–	–	–	<13.98
C iv	0 ± 2	55 ± 3	13.53 ± 0.04	14.82 ± 0.09
	-9 ± 2	28 ± 3	14.80 ± 0.08	–
Si iv	0 ± 2	55 ± 7	13.64 ± 0.04	14.38 ± 0.10
	-9 ± 2	28 ± 3	14.29 ± 0.08	–

Table B16. Voigt profile fits for GRB 160203A at $z = 3.518\ 71$.

Ion	v_0 (km s ⁻¹)	b (km s ⁻¹)	$\log N$ (N in cm ⁻²)	$\log N(\text{total})$ (N in cm ⁻²)
N v	–	–	–	<13.58
C iv	-64 ± 2	17 ± 3	14.54 ± 0.07	14.56 ± 0.07
	-4 ± 2	15 ± 3	13.22 ± 0.04	–
Si iv	-117 ± 4	26 ± 7	14.47 ± 0.18	14.50 ± 0.17
S iv	-68 ± 4	39 ± 2	14.46 ± 0.07	15.79 ± 0.14
	-173 ± 34	28 ± 20	14.77 ± 0.08	–
	-230 ± 34	42 ± 20	15.72 ± 0.13	–
S vi	-89 ± 6	49 ± 8	14.22 ± 0.06	14.22 ± 0.06

This paper has been typeset from a \LaTeX file prepared by the author.