



HAL
open science

Simultaneous Visible Light Communication and Distance Measurement Based on the Automotive Lighting

Bastien Béchadergue, Luc Chassagne, Hongyu Guan

► **To cite this version:**

Bastien Béchadergue, Luc Chassagne, Hongyu Guan. Simultaneous Visible Light Communication and Distance Measurement Based on the Automotive Lighting. *IEEE Transactions on Intelligent Vehicles*, 2019, 4 (4), pp.532-547. 10.1109/TIV.2019.2938087 . hal-02398725

HAL Id: hal-02398725

<https://hal.science/hal-02398725>

Submitted on 7 Dec 2019

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

Simultaneous Visible Light Communication and Distance Measurement Based on the Automotive Lighting

Bastien Béchadergue, Luc Chassagne, *Member, IEEE*, and Hongyu Guan

Abstract—Visible light communication could be an interesting complement to the IEEE 802.11p-based vehicle-to-vehicle communication systems that are sensitive to interferences and delays in dense traffic scenarios such as platooning. Visible light could also provide a redundant distance measure that is crucial for path control in this application. In this paper, a system called visible light communication rangefinder and performing simultaneously vehicle-to-vehicle communication and range-finding using the headlamps and taillights is proposed for the first time. By exchanging a clock signal contained in Manchester-encoded signals, both the following and leading vehicles can share information and estimate their inter-distance through phase-shift measurement. The system is first presented theoretically and it is shown in particular that the Doppler effect has no significant impact on both functions. Then, it is modeled and validated using Simulink. Finally, both the range-finding and communication function are validated experimentally. The range-finding function is functional up to 25 m, and has a resolution of around 24 cm at 10 m, whereas the communication function provides a 500 kbps link with a BER below 10^{-6} up to 30 m.

Index Terms—Vehicle-to-vehicle communication, visible light communication, distance measurement, sensors, platooning

I. INTRODUCTION

ALTHOUGH fully autonomous cars are already on the roads for tests, the next generations of vehicles on the market will probably be automated for certain driving phases only. Platooning could be one of these phases. In platooning, a leading vehicle (LV) is followed by following vehicles (FV) that automatically adjust their position using, among others, vehicle-to-vehicle (V2V) communication and distance sensors. Started in the 1960s, the research on platooning has gained strong interest over the last decades to increase traffic flow and security [1]. This technique has thus been developed through several projects [2], [3], among which the European initiative SARTRE that achieved, in 2012, a fully autonomous, infrastructure independent, 5 to 10 m platoon led by a manually driven vehicle [4]. The European Truck Platooning Network is now targeting by 2020 a 0.3 s gap between two trucks in a platoon, which corresponds to 9 m at 110 km/h [5].

In most platooning projects, V2V communication is implemented with IEEE 802.11p-based systems, that support

high data rates over long ranges. IEEE 802.11p is at the heart of cooperative intelligent transportation systems (C-ITS), which ensure vehicular networking [6] through the exchange of similar types of messages [7]. In particular, cooperative awareness messages (CAM) are periodically sent to update the vehicle status information such as the speed or the position [8], which are critical to the trajectory control. However, the random access protocols defined by IEEE 802.11p may cause excessive delays imposing greater V2V distances to meet safety requirements [9]. Visible light communication (VLC), which allows data transmission using the vehicle lighting, has thus been proposed as a complementary technology [10]. In conjunction with IEEE 802.11p, it could indeed increase the reliability and scalability of the platoon [11], [12]. Although these works are theoretical analysis, prototyping efforts have also been made and outdoor communications over tens of meters using commercial off-the-shelf (COTS) LED headlamps or taillights have been reported [13], [14], [15], [16].

Similarly, several automotive range-finding technologies already exist [17], [18]. Frequency-modulated continuous-wave (FMCW) or ultra-wide band (UWB) time-of-flight (TOF) radars operating at 24 or 79 GHz are already widely used, especially for adaptive cruise control (ACC) [19]. Light-based sensors such as lidar are also progressively being deployed, despite their relatively high cost [20]. Although all these solutions provide long-range and high-resolution distance measurement, they may be rather sensitive to interferences [21], [22], an issue that will keep growing as the number of equipped vehicles will increase. Global positioning systems (GPS) can also be used for such purpose but this approach does not provide enough accuracy and does not work when the satellites are out of sight. Therefore, in [23], we proposed for the first time a complementary range-finding solution, the visible light rangefinder (VLR), using the headlamps and taillights of the vehicles for distance measurement. This concept was then validated experimentally in [24].

If both functions can be implemented separately using the automotive lighting, it could also be interesting to perform them using a single system. Simultaneous communication and range-finding with the same light source has not been extensively explored. In [25], Mizui *et al.* proposed a technique called boomerang transmission, where the FV first sends to the LV a pseudo-noise (PN) code signal using a laser source. Then the LV multiplies its own information with this PN code and sends the resulting signal to the FV. The FV is then able to retrieve the data using a PN matched filter. This filter is

Manuscript received...; revised... (*Corresponding author: Hongyu Guan.*)

The authors are with the Laboratoire d'Ingénierie des Systèmes de Versailles (LISV), UVSQ, Université Paris-Saclay, 10-12 avenue de l'Europe, 78140, Vélizy, France (email: luc.chassagne@uvsq.fr; hongyu.guan@uvsq.fr).

Bastien Béchadergue is also with the Vedecom Institute, 77 rue des Chantiers, 78000, Versailles, France (email: bastien.bechadergue@gmail.com).

also used to stop a TOF counter, started when the PN signal was first sent, so that an inter-vehicle distance estimation can be achieved. This system has been further developed over the years [26], [27], but needs additional light sources, generally lasers, instead of using the headlamps and taillights.

In this paper, our concept of VLR is extended into a visible light communication rangefinder (VLCR) able to support simultaneously data transmission and range-finding. In [23], the FV sends a simple clock to the LV that receives, processes and re-emits it. The FV then estimates the phase-shift introduced by the round-trip TOF to recover the distance. Here, the FV sends a clock through a Manchester-encoded CAM-like data signal. The LV is thus able to decode the data while recovering the underlying clock that it uses then to send its own information. The FV uses the same method and finally compares the retrieved clock with the original one to estimate their phase-shift and thus the V2V distance. The theoretical principles of the VLCR are further explained in Section II, and an analysis of the error sources impacting the distance measurement is carried out in Section III. The impact of the Doppler effect is in particular studied and found to be negligible. Then, in Section IV, Simulink simulations of the whole system show that our VLCR could be able to measure distances up to 30 m with a resolution of 66 cm, at a refresh rate of 267 Hz, while keeping the VLC bit-error rate (BER) below 10^{-6} over 45 m, at a data rate of 500 kbps. Finally, in Section V, both the range-finding and communication function are validated experimentally using prototypes based on COTS automotive lights. The range-finding function is functional up to 25 m, and has a resolution of around 24 cm at 10 m, whereas the communication function provides a 500 kbps link with a BER below 10^{-6} up to at least 30 m.

II. BASIC PRINCIPLES OF THE VISIBLE LIGHT COMMUNICATION RANGEFINDER

A. General Working Principles

Our VLCR is an extension of the VLR, previously proposed and studied through simulations in [23]. Therefore, the range-finding function of the VLCR is based on the very same principle as the VLR. Unlike usual range-finding technologies, the VLR cannot directly use the reflection by the target of a signal it is sending to estimate the distance. In radar or lidar, this echo is indeed strong enough to be detected and processed, mainly because its carrier wave is generated by a coherent radio or laser source. Here, the headlamps produce a polychromatic and non-coherent white light so that a major part of the optical power is diffused and lost after its reflection. To avoid this problem, the VLR is based on an active reflection principle: the target, here the LV, receives the light signal transmitted by the system, here the FV, and reconstructs it before re-emitting it. This way, the echo received by the FV can be properly detected and processed. Such a solution may be incompatible with the FMCW principles but is possible to combine with TOF measurement [23], [28].

In TOF measurement, a pulse is sent toward the target, which reflects it back so that the system receives the echo with a delay proportional to the system/target distance. A

variation of this method consists in sending a periodic signal at frequency f_e and observing its phase-shift φ with the echo [29]. The latter technique is particularly suited with active reflection by the target since it only has to re-emit the signal it is receiving while preserving its phase. In any case, with this method, the phase-shift φ is related to the light-velocity c and the V2V distance d by:

$$d = \frac{c}{2f_e} \cdot \frac{\varphi}{2\pi}, \quad (1)$$

In the VLR, the signal sent is thus a periodic signal, which does not allow the transmission of data. However, the measurement of a phase shift between two data signals is possible. The IEEE 802.15.7-2011 standard is the latest VLC standard that fully defines the different modulations that may be used [30]. For outdoor applications, it recommends the on-off keying non-return-to-zero (OOK-NRZ) modulation in conjunction with Manchester encoding. OOK-NRZ is the simplest form of light intensity modulations: a data bit 0 is transmitted by turning off the light source and a data bit 1 is sent by turning it on. Manchester encoding consists, for its part, to encode a data bit 0 into the symbol 01 and a 1 into 10. It is employed to limit the maximum number of consecutive 1 or 0 to two, thus preventing light flicker. It also removes the low frequency components of the data signal. More importantly, Manchester encoding is classically used in digital communications to ease clock recovery by ensuring frequent signal transitions [31]. Therefore, by sending Manchester-encoded data signals with OOK-NRZ, both ends of the VLR could also exchange a clock that is easy to recover. The combination of all these principles - active reflection and phase-shift measurement on the clock recovered from Manchester-encoded data signals - gives Fig. 1, the block diagram of our new VLCR.

The VLCR operates as follows: the FV first encodes the digital data d_{fv} using Manchester coding in order to build the CAM-like binary message m_e to transmit. m_e is then used to monitor the LED headlamps intensity through OOK-NRZ modulation, so that the data bits are sent to the LV at a fixed rate f_e . After free space propagation, the transmitted signal is received by the LV through a photodiode (PD). This received signal $m_{p'}$ is distorted and delayed compared to m_e by a time proportional to the V2V distance d . $m_{p'}$ is first processed in order to reconstruct the message. This processing step produces two output signals $d_{r'}$ and $m_{r'}$. On the one hand, $d_{r'}$ is sent to a first channel that decodes the received data. On the other hand, $m_{r'}$ is sent to a second channel, where a clock recovery phase locked-loop (PLL) is used to retrieve the clock $s_{r'}$ it contains.

This clock, of frequency f_e , is then used by the LV to transmit its own message signal $m_{e'}$ with the same generation, coding and emission process as previously described. $m_{e'}$ is received and processed after free space propagation by the FV, which simultaneously decodes the LV data d_{lv} and retrieves the clock signal s_r contained in the reconstructed data signal m_r . s_r and the initial clock s_e have a phase-shift φ proportional to the V2V distance d . Consequently, the FV can use these signals to determine an estimate φ_m of φ ,




Fig. 1. Block diagram of the VLCR system.

and thus a V2V distance estimate d_m using (1). If the main working principles of the VLCR are defined here, the decoding and phase-shift measurement techniques, as well as the signal reconstruction process used on both ends of the system, are still to be detailed. This is the object of the next two sections.

B. VLC Encoding and Decoding Technique

From the general description of the VLCR working principles just given, we understand that this system is first of all a traditional VLC system. Each vehicle sends a data signal using its headlamps or taillights to the other vehicle which receives it and decodes it. The range-finding function is performed as a parallel task that is not impacting the communication function.

The whole communication chain used by the VLCR from one vehicle to the other is represented on Fig. 2. The data source of the transmitting vehicle, for example its electronic control unit (ECU), generates a data stream that is first encoded using Manchester coding and then reshaped to form data packets of a specific form. In this work, we consider the data packets start with a fixed header followed by the Manchester encoded data payload. The resulting signal, denoted m_e when the FV acts as transmitter, is used to drive the transmit LED through an LED driver. After free space propagation, the data light signal is collected by the PD of the receiving vehicle and turned into a voltage signal by a transimpedance amplifier (TIA). This signal is then amplified and bandpass filtered in order to improve its overall SNR so that threshold detection can be used to reconstruct a square data signal d_r' .




Fig. 2. (a) VLC emission and (b) reception chains.

This reconstructed data signal finally has to be decoded. The method used here consists simply in considering that the

current bit state is the value of the data signal d_r (or d_r') after each rising edge of a decoding clock of frequency f_e . To maximize the efficiency of this method, the clock must be synchronized with the data signal, and is thus taken from the clock recovery PLL used for distance measurement. However, the signal processing chain previously described might, as we will see in Section IV-B, introduce distortions on the reconstructed data signal resulting in varying pulse widths. Since these pulse distortions mainly affect the edges of each bit, the recovered clock is here simply delayed by a certain amount of time so that each rising edge occurs approximately at the mid-period of the corresponding bit.

C. Phase-Shift Measurement Technique

In parallel with data decoding, the VLCR performs the range-finding function as a two step process. First, the clock is recovered from the signal sent by the FV and received by the LV in order for the LV to send back its own data. Then, the same clock recovery operation is performed by the FV and the resulting signal s_r is compared with the initial clock s_e sent by the FV in order to extract the phase-shift φ between both clocks. This clock recovery process is identical on both ends of the system. The data signal received m_p (or m_p') is first reconstructed using the processing chain represented on Fig. 2(b) and the resulting reconstructed signal m_r (or m_r') is then fed to the clock recovery PLL to get the clock signal s_r (or s_r').

Once both clock signals s_e and s_r are obtained, the phase-shift measurement process first starts with an heterodyning step: s_e and s_r are transposed to lower frequency signals s_{eh} and s_{rh} . This frequency transposition is performed with a D flip-flop gate cadenced by a clock s_h of frequency f_h linked with the frequency of operation f_e by a heterodyning factor r such that:

$$f_h = \frac{r}{r+1} f_e. \quad (2)$$

This factor r introduces a small time difference $1/(r f_e)$ between the periods of the input signal s_e or s_r and the heterodyning clock s_h . This way, the shape of the input signal is captured with a time resolution of $1/(r f_e)$ seconds even though the heterodyning block outputs a value every $1/f_h$

seconds in reality. Eventually, such a heterodyning technique is equivalent to a sampler of rate $1/(rf_e)$ taking $r + 1$ periods of input signal to output one full period of heterodyned signal. Therefore, the heterodyned signals s_{eh} and s_{rh} have an intermediate frequency f_i given by:

$$f_i = \frac{f_e}{r + 1}. \quad (3)$$

This behavior is illustrated by Fig. 3, when $r = 10$.




Fig. 3. Heterodyning of a signal s_e by undersampling with a synchronized clock s_h when $r = 10$.

After heterodyning of s_e and s_r , the resulting signals s_{eh} and s_{rh} are compared using a XOR gate to obtain a phase-shift signal s_φ composed of phase-shift pulses of rate $2f_e/(r + 1)$. The width of these pulses is then measured using the auto-digital phase-measurement technique [29] illustrated by Fig. 4. The phase-shift pulses s_φ , taken by groups of N , are combined with a clock signal s_{clock} of high-frequency f_{clock} through an AND gate. The resulting signal $s_{\varphi''}$ is composed of several sub-pulses fitting the original phase-shift pulses. The phase-shift φ can thus be estimated by simply counting the number of sub-pulses M corresponding to N phase-shift pulses. From this count value, the phase-shift estimate φ_m can be obtained using:

$$\varphi_m = \frac{2\pi M f_e}{(r + 1)N f_{clock}}, \quad (4)$$

which leads to a distance estimate d_m of d given by:

$$d_m = \frac{c}{2} \cdot \frac{M}{(r + 1)N f_{clock}} = \frac{c}{2} \cdot \frac{M f_i}{N f_e f_{clock}}. \quad (5)$$

Note that with this method, the phase-shift is necessarily given modulo- π , which may introduce an ambiguity in the distance measured. If the true phase-shift φ is larger than π , the system will output a distance corresponding to the difference between this phase-shift and π . Consequently, there is a non-ambiguity range d_{namb} which corresponds to the distances corresponding to phase shifts between 0 and π and which is given by:

$$d_{namb} = \frac{c}{4f_e}. \quad (6)$$

In any case, the refresh rate of the measurement f_{VLR} is given by:

$$f_{VLR} = \frac{2f_e}{(r + 1)N}. \quad (7)$$




Fig. 4. (a) Block diagram of the phase-shift measurement system and (b) illustration of its working principles.

III. THEORETICAL ANALYSIS OF THE SOURCES OF ERRORS

A. General Expression of the Distance Measurement Error

The distance measurement error δd_m can be obtained by differentiating the fundamental equation of the VLCR (5), which gives:

$$\delta d_m = d_m \left[\frac{\delta M}{M} + \frac{\delta f_i}{f_i} - \frac{\delta N}{N} - \frac{\delta f_e}{f_e} - \frac{\delta f_{clock}}{f_{clock}} \right]. \quad (8)$$

Each term has a specific meaning. δf_{clock} and δf_e represent the frequency drifts of the signals s_{clock} and s_e that may be caused by temperature variations or age. δN accounts for the potential non-synchronization between the gate signal s_{gate} and the phase-shift signal s_φ whereas δM stands for the ± 1 counting error that may be contained in M [29]. Logically, the latter source of error can be strongly mitigated by increasing the counter clock frequency [23].

Finally, δf_i gathers three distinct sources of errors. The intermediate frequency f_i is indeed the result of a heterodyning process involving the clock signals s_h and s_r . However, s_h is derived from the master clock s_{clock} via a PLL and may thus suffer from frequency drifts that will impact f_i . On the other hand, s_r might have in reality a frequency not equal to but slightly varying around f_e because of signal distortions experienced all along the transmission chain. For example, the LED drivers, the headlamps and taillights, the photo-receivers and the signal processing cards have in practice a limited bandwidth whereas the Manchester data signals to transmit m_e and $m_{e'}$ have by construction a very large spectrum.

Therefore, their edges will be softened, inducing pulse-width distortions preventing eventually from a perfect recovery of s_r . In addition, the different processing stages and the clock recovery PLL may add unwanted delays that will change the initial phase of the received clock. The impact of these various sources is surely massive but rather difficult to isolate in a formal way and will thus be studied through simulations in Section IV. However, δf_i also hides a third source of errors, this time purely intrinsic to the heterodyning step.

B. Heterodyning as a Source of Errors

In Fig. 3, the heterodyning process is illustrated in the case of an input signal s_e that is synchronized with the heterodyning clock s_h so that both signals have simultaneous rising edges every r periods. The resulting heterodyned signal s_{eh} is then the perfect transposition of s_e at frequency f_i . Unfortunately, the synchronization, in the sense just defined, of s_r with s_h is very unlikely since s_r contains an uncontrollable phase-shift induced by the return-trip TOF and the various processing delays. The reality will most probably look like the situation represented on Fig. 5.




Fig. 5. Illustration of the production of two phase-shift pulses with an heterodyning of factor $r = 10$.

In such a case, s_h might not detect the state transitions of s_r . For example, on Fig. 5, we can see that the first rising edge of s_h occurs while the input signal s_r is at low level, leading logically to a low level of s_{rh} . We have then to wait for the fifth rising edge of s_h to get the first rising edge of s_{rh} but this transition is clearly occurring shortly after the corresponding edge of s_r . Therefore, the pulse width of s_{rh} , which should follow the black dotted line, has instead a duration equal to an integer multiple of the heterodyning period, here $4/f_h$. In other words, this pulse width contains an error of at most $1/f_h$ seconds, which results eventually in a distance estimate error. In the worst case, there are indeed $\lfloor f_{clock}/f_h \rfloor$ additional clock counts in the phase measurement. If f_{clock} is large enough to limit the ± 1 count-induced measurement error to a few millimeters, the integer part notation can be dropped. By mixing the resulting value with (5), we can show that the maximum distance measurement error $\delta d_{m,het}$ induced by the undersampling process is:

$$\delta d_{m,het} = \frac{c}{2rf_e}. \quad (9)$$

C. Impact of the Doppler Effect

The various sources of errors detailed so far are derived considering the V2V distance is fixed. However, in real platooning configurations, this distance is always varying which may impact the distance measurement resolution through the well-known Doppler effect. In order to study analytically the potential impact of the Doppler effect, we consider that the FV is approaching the LV from an initial position x_0 at a constant speed v_0 , as represented on Fig. 6.




Fig. 6. Geometry of a platoon in a straight line configuration.

We also consider the VLCR is perfect, which means the clock signal retrieved s_r is exactly the clock sent s_e delayed by the return-trip TOF. In such a case, the only parts of the signals we are interested in are the edges, along with their moment of occurrence and the V2V distance at these moments. Specific notations are used to distinguish these different parameters. For example:

- the i -th rising edge of any signal s_x will be denoted s_{x_i} ,
- its moment of occurrence will be t_{x_i} ,
- the V2V absolute distance at that moment will be $d(t_{x_i})$.

Then, if the i -th rising edge of s_e is sent at time t_{e_i} , while the V2V distance is $d(t_{e_i})$, its echo will not be received $2d(t_{e_i})/c$ seconds later, as in the static case, but with a delay slightly smaller. If t_{r_i} is the time of reception and $\tau_i = t_{r_i} - t_{e_i}$ the delay of reception, then:

$$\tau_i = t_{r_i} - t_{e_i} = -\frac{x_0 + v_0 t_{e_i}}{c} - \frac{x_0 + v_0 \left(t_{e_i} - \frac{x_0 + v_0 t_{e_i}}{c} \right)}{c + v_0}. \quad (10)$$

Proof. We know that, in the general case, every rising edge s_{e_i} , sent by the FV at time t_{e_i} , will intersect the LV after a delay $\tau_{i,1} = d(t_{e_i})/c$. Given the uniform nature of the relative movement between the vehicles, and with respect to the coordinate system defined in Fig. 6, this delay will be:

$$\tau_{i,1} = -\frac{x_0 + v_0 t_{e_i}}{c}. \quad (11)$$

Assuming the reflection is instantaneous, the echo will then be received by the FV after a second delay $\tau_{i,2}$ that depends strongly on the speed v_0 . During the return-trip of the signal, if v_0 is positive, the FV moves indeed toward the LV, which reduces the V2V distance that the echo has to travel. $\tau_{i,2}$ can thus be simply determined as the intersection between two trajectories: the uniform movement of the echo, which starts from a null initial position with a constant speed c and goes toward the FV, and the uniform movement of the FV, which

keeps moving toward the LV at a constant speed v_0 , but now from the initial position $-d(t_{e_i} + \tau_{i,1})$:

$$-c\tau_{i,2} = -d(t_{e_i} + \tau_{i,1}) + v_0\tau_{i,2}. \quad (12)$$

By solving (12) and introducing (11), we can get:

$$\tau_{i,2} = -\frac{x_0 + v_0 \left(t_{e_i} - \frac{x_0 + v_0 t_{e_i}}{c} \right)}{c + v_0}, \quad (13)$$

which leads to a total delay $\tau_i = t_{r_i} - t_{e_i} = \tau_{i,1} + \tau_{i,2}$ of reception of the echo equal to (10). \square

During this delay, the FV travels a distance $v_0\tau_i$ which could interact with the distance measurement process, especially the heterodyning step, and thus generate a measurement error. As outlined in Section III-B, the VLCR outputs a measure as soon as an edge of s_r is detected by the heterodyning clock s_h . Let n be the index of the first edge of s_r indeed detected by s_h . According to (10), this edge, first sent at a certain time, will be received with a known delay τ_n , which leads to a distance measurement error of the perfect VLCR $\delta d_{m,perf}$ equal to:

$$\delta d_{m,perf} = \frac{v_0\tau_n}{2} + \frac{v_0\alpha_n}{rf_e} + \frac{c\alpha_n}{2rf_e}, \quad (14)$$

where $\alpha_n \in [0, 1[$ is a normalization parameter specific to the n -th transmitted pulse.

Proof. We consider here, without loss of generality, the k -th phase-shift pulse $s_{\varphi,k}$, delimited by s_{eh_k} and s_{rh_k} , the k -th rising edges of s_{eh} and s_{rh} , occurring at respective times t_{eh_k} and t_{rh_k} . If we are able to express its width Δt_k , then we can deduce the number of corresponding clock counts M_k and thus the distance measured d_{m_k} using (5). Then the measurement error δd_{m_k} will simply be the difference between the distance provided by the VLCR and the true V2V distance when this estimate is output:

$$\delta d_{m_k} = d_{m_k} - d(t_{rh_k}). \quad (15)$$

A first straightforward expression of Δt_k is given by:

$$\Delta t_k = t_{rh_k} - t_{eh_k}. \quad (16)$$

Considering that s_{e_1} and s_{h_1} , the very first rising edges of s_e and s_h , are occurring simultaneously at time $t = 0$, we can deduce, as shown in Fig. 5, that every rising edge of s_{eh} will occur at the same time as a rising edge of s_e and s_h . Therefore, t_{eh_k} is an integer multiple of the heterodyning period. In Fig. 5, we can observe that the end of the first phase-shift pulse occurs five rising edges of s_h , s_e and s_r after its beginning. Back to the general case, let n be this number of rising edges. We can deduce that:

$$t_{rh_k} = t_{eh_k} + \frac{n-1}{f_h} \implies \Delta t_k = \frac{n-1}{f_h}. \quad (17)$$

This phase-shift pulse width will correspond to a number of clock counts M_k equal to:

$$M_k = \left\lfloor \frac{(n-1)f_{clock}}{f_h} \right\rfloor, \quad (18)$$

where $\lfloor \cdot \rfloor$ denotes the integer part. This equation highlights the ± 1 count error pointed out in Section III-A, which does not

exceed 1 mm if the counter frequency is carefully chosen. Therefore, we can drop here the integer part notation and deduce, by mixing (18) with (5), that:

$$d_{m_k} \approx \frac{c(n-1)}{2rf_e}. \quad (19)$$

The problem is now to find a literal expression of n . With respect to Fig. 5, we understand that n is simply the index such that:

$$t_{r_{n-1}} > t_{h_{n-1}} \quad \text{and} \quad t_{r_n} < t_{h_n}. \quad (20)$$

On the one hand, we know that, in the general case, $t_{h_i} = (i-1)/f_h$. On the other hand, we can say that t_{r_i} is equal to the time $t_{e_i} = (i-1)/f_e$ of emission of the corresponding edge s_{e_i} plus the return-trip TOF τ_i given by (10). Considering these expressions of t_{h_i} and t_{r_i} , the two inequalities in (20) lead to:

$$n \leq rf_e\tau_n + 1. \quad (21)$$

Since n is an integer, then its true value will be $n = \lfloor rf_e\tau_n + 1 \rfloor + 1$ or equivalently:

$$n = rf_e\tau_n + 1 + \alpha_n, \quad (22)$$

where $\alpha_n \in [0, 1[$ is a real value such that $n \in \mathbb{N}$. By introducing this expression in (19), we can show that:

$$d_{m_k} = \frac{c\tau_n}{2} + \frac{c\alpha_n}{2rf_e}. \quad (23)$$

However, since τ_n is the return trip TOF between the moments t_{e_n} and t_{r_n} , we can deduce that:

$$\frac{c\tau_n}{2} = \frac{d(t_{e_n}) + d(t_{r_n})}{2}, \quad (24)$$

with:

$$d(t_{e_n}) = d(t_{eh_k}) - \frac{v_0(n-1)}{f_e}, \quad (25)$$

and

$$d(t_{r_n}) = d(t_{rh_k}) - v_0 \left(\frac{n-1}{f_e} + \tau_n \right). \quad (26)$$

In parallel, using the expression of t_{rh_k} given in (17) and mixing it with (22), it can be shown that the absolute V2V distance $d(t_{rh_k})$ when the VLR outputs the k -th distance estimate is:

$$d(t_{rh_k}) = -x_0 - v_0 t_{rh_k} = d(t_{eh_k}) - v_0(r+1)\tau_n - \frac{v_0\alpha_n}{f_h}. \quad (27)$$

By first mixing (25) and (26) with (24) and introducing the result in (23), an alternate expression of d_{m_k} can be found. This expression can then be used with (27) in (15) to get the final expression of the measurement error δd_{m_k} given in (14). \square

We can see that the first two terms of this equation are null if there is no relative movement between the vehicles ($v_0 = 0$), whereas the third term is independent of the speed. In addition, all three terms depend on the parameters τ_n or α_n which are related to the n -th and last transmitted pulse. Therefore, a measure between times t_e and t_r while traveling at a constant speed v_0 is the same as the measure started at time t_e , while the FV is static at a distance $d(t_{e_n})$, and stopped

at time t_r , after the speed has changed abruptly from 0 to v_0 at time t_{e_n} : only the movement between t_{e_n} and t_r will impact the measurement resolution.

The first term in (14) corresponds to half the distance traveled between the emission at time t_{e_n} of the n -th pulse and the reception of its echo. It highlights the fact that τ_n , which defines the end of the measure, is a delay between two very close but different distances. If for example, $|x_0| = 15$ m and $v_0 = 20$ km/h, this term is indeed under $1 \mu\text{m}$ and can thus be neglected. The second term is related to the limited time resolution of the undersampling process already pointed out in Section III-B. It stands for the contribution of the speed v_0 to this time resolution but only reaches a few tenth of nanometers and can also be neglected so we can conclude that relative V2V movements only induce negligible additional error.

The main source of errors induced by the undersampling step is actually the static error, represented by the third term in (14), and which limit case $\alpha_n = 1$ is exactly the error highlighted by (9). From (9), we understand that an increase of either the heterodyning factor r or the frequency of operation f_e limits this static error. For example, it reaches 9.37 cm when $f_e = 1$ MHz and $r = 1599$ but only 3.75 cm when $f_e = 1$ MHz and $r = 3999$ or 0.94 cm when $f_e = 4$ MHz and $r = 3999$. However, as shown by (7), an increase in the heterodyning factor mechanically reduces the intermediate frequency, and thus the refresh rate f_{VLR} , even though this reduction can be compensated by increasing f_e . In this work, a frequency of operation $f_e = 1$ MHz is considered. This value is indeed compatible with most COTS automotive lights which have a modulation bandwidth usually limited to a few megahertz. In this case, the non-ambiguity range d_{namb} given by (6) is 75 m, which is larger than the range we want the VLCR to cover.

IV. SIMULATION STUDY OF THE VISIBLE LIGHT COMMUNICATION RANGEFINDER

Now that all the different parts of our VLCR have been detailed, we can validate its functioning and evaluate its performances by Simulink simulations. In order to stick to the reality, we have used a standard VLC channel model that is detailed in Section IV-A, and carefully selected the different simulation parameters, as outlined in Section IV-B and IV-C. Therefore, we have been able to evaluate first the communication performances of the VLCR in Section IV-D. Finally, the range-finding capabilities of the system are tested in Section IV-E and compared with those of the VLR alone.

A. The VLCR Channel Model

The platoon configuration considered in the simulations is represented on Fig. 7. The FV uses one of its headlamps as transmitter and has a PD receiver just under whereas the LV uses a symmetrical equipment on its rear. There are no obstacles between both vehicles and the reflections on the road surface are ignored, which means a continuous direct line-of-sight (LOS) is considered between each transmitter/receiver pairs. In addition, crosstalk is ignored, as well as the Doppler effect.




Fig. 7. Platooning configuration considered in the simulations, with ϕ and ψ the irradiance and incidence angles and d the V2V distance.

The VLC LOS channel is modeled using the classical path-loss additive white Gaussian noise (AWGN) channel model [32]. In this model, the output current $Y(t)$ produced by the PD is linked with the optical power transmitted $X(t)$ by:

$$Y(t) = \gamma X(t) \otimes h(t) + n(t), \quad (28)$$

with γ the PD responsivity, $h(t)$ the channel impulse response and $n(t)$ the AWGN. The channel frequency response $H(f)$ is usually reduced to its DC gain $H(0)$ because it is considered flat in the frequency range of interest. In addition, the vehicle headlamps and taillights are modeled as Lambertian light sources, although they have in reality complex transmission beam patterns in order to meet international standards. The channel DC gain is then:

$$H(0) = \frac{(m+1)A_r}{2\pi d^2} \cos^m \phi \cos \psi, \quad 0 < \psi < \psi_c, \quad (29)$$

where ϕ and ψ are the irradiance and incidence angles, A_r is the radiant sensitive area of the PD, ψ_c is the PD field of view and m is the order of Lambertian emission, defined as $m = -\ln 2 / \ln(\cos \Phi_{1/2})$, with $\Phi_{1/2}$ the semi-angle at half power of the LED emitter. If the transmitted optical power is P_t , then the received light power P_r will be $P_r = H(0)P_t$ and the signal power S at the receiver side will be $S = \gamma^2 P_r^2$.

The main noise sources are shot noise and thermal noise. Shot-noise is induced by the incident luminous flux and is mainly due to daylight which is much stronger than any other light source. It is thus modeled as a signal independent white Gaussian noise of variance σ_{shot}^2 :

$$\sigma_{\text{shot}}^2 = 2q\gamma P_r B + 2qI_{bg}I_2 B, \quad (30)$$

with q the electronic charge, B the equivalent noise bandwidth, I_{bg} the background photocurrent, that can be estimated to $5100 \mu\text{A}$ in case of direct exposition or $740 \mu\text{A}$ in case of indirect exposition [33], and I_2 a noise bandwidth factor. Thermal noise occurs with charge carriers thermal agitation and is modeled as a signal independent Gaussian noise of variance $\sigma_{\text{thermal}}^2$:

$$\sigma_{\text{thermal}}^2 = \frac{8\pi k T_K}{G} \eta A_r I_2 B^2 + \frac{16\pi^2 k T_K \Gamma}{g_m} \eta^2 A_r^2 I_3 B^3, \quad (31)$$

with k Boltzmann's constant, T_K absolute temperature, G the open-loop voltage gain, η the fixed capacitance of photo-detector per unit area, Γ the field-effect transistor (FET) channel noise factor, g_m the FET transconductance and I_3 a noise-bandwidth factor. The total noise variance σ_{tot}^2 will

then be the sum of the shot noise and thermal noise $\sigma_{tot}^2 = \sigma_{shot}^2 + \sigma_{thermal}^2$, so that the SNR will be:

$$\text{SNR} = \frac{S}{\sigma_{tot}^2} = \frac{\gamma^2 H(0)^2 P_t^2}{\sigma_{shot}^2 + \sigma_{thermal}^2}. \quad (32)$$

B. Simulink Model of the VLCR

The software Simulink has been chosen to carry out the simulation study of the VLCR as it provides great flexibility with its block approach. The Simulink model developed is simply the transcription of the block diagram on Fig. 1 with, between the FV and LV main blocks, an additional block for the VLCR bidirectional channel just described.

1) *Message Format*: In this work, the transmission of CAM-inspired messages is considered. As defined in its standard [8], a CAM is composed of several frames, among which some are compulsory, like speed or heading, whereas others are optional. Therefore, a CAM is a complex message with variable length. However, one could estimate its length is usually between 400 and 600 bytes. Here, the CAM messages are thus modeled by frames of 4000 independent and identically distributed random bits following a uniform distribution, generated by the “Data” blocks of Fig. 1. Then, the “Message Encoding” blocks encode these bits using Manchester coding and incorporate then in frames started by 8 bits synchronization headers $H = 00001111$. When the messages are fully encoded, the “Emitter” blocks transmit them bit by bit using OOK-NRZ with a clock of frequency $f_e = 1$ MHz, which gives a data rate R_b of 500 kbps. Note that, as mentioned in Section II-A, Manchester coding limits the low frequency components of the data signal. It actually concentrates most of the signal energy around $f_e/2 = 500$ kHz and distributes the rest in decreasing side lobes. This information is crucial to set up an efficient signal processing strategy.

2) *Signal Reconstruction Stages*: An identical processing chain is implemented on both ends of the VLCR, in the “Receiver” blocks of Fig. 1. In the context of the VLR, this processing chain was composed of a bandpass filter of bandwidth 100 kHz centered on the frequency of operation $f_e = 1$ MHz and thus able to isolate the fundamental component of the square signal transmitted [24]. Such filtering strategy cannot be used by the VLCR as the signal transmitted is not a square signal anymore but a Manchester encoded data signal with the spectrum just described.

We know from [32] that from a communication perspective, the optimal filtering strategy to apply on Manchester encoded signals consists in a bandpass filter with a low-pass cut-off frequency equal to the data rate R_b and a high-pass cut-off frequency equal to $0.01R_b$, that is respectively 500 kHz and 5 kHz here. In practice, these filters are implemented using 2^{nd} order Butterworth analog filters in order to limit the simulation time. This filtering approach will be referred as “VLC filtering” in the rest of the paper. Fig. 8(a) to (d) illustrate the whole processing chain when using such filters. Fig. 8(c) shows the efficient noise removal properties of “VLC filtering” as well as the pulse distortion it introduces. The edges of the signal filtered are indeed strongly softened compared to the original square signal so that the pulse width

of the signal reconstructed by zero-crossing detection, shown on Fig. 8(d), may vary for a same logic state.

These pulse width distortions can be mitigated by using an alternative filtering approach which consists in letting some harmonics of the Manchester-encoded signal pass so that the sharpness of its edges is preserved, at the cost of a larger bandwidth and thus of less noise cut. In parallel, removing some of the slowest time-varying components of the signal, contained in the main lobe, will change every rising and falling edges into peaks so that they are easier to detect even though the signal will be weaker. This approach, that will be referred as “Distance Measurement (DM)” filtering in the rest of the paper, is illustrated by Fig. 8(e) to (h). Once again, two 2^{nd} order Butterworth analog filters are employed, but this time with low-pass and high-pass cut-off frequencies 2.5 MHz and 250 kHz. Fig. 8(g) shows the ability of these filters to highlight the pulse edges, even when the input is the low SNR signal represented on Fig. 8(f). Symmetrical thresholds can then be used to get the reconstructed message m_r , as shown in Fig. 8(h).




Fig. 8. (a) Data signal transmitted m_e' , (b) signal received m_p with AWGN of SNR = 2, before processing, and (c) after filtering with 2^{nd} order Butterworth filters of respective low-pass cut-off frequency 500 kHz and high-pass cut-off frequency 5 kHz (blue curve) and triggering threshold (red line), (d) signal d_r reconstructed by triggering. (e), (f), (g) and (h) represent the same processing chain with two 2^{nd} order Butterworth filters of respective low-pass cut-off frequency 2.5 MHz and high-pass cut-off frequency 250 kHz.

The reconstruction properties of these two filtering strategies can be compared by measuring, with a simple cross-correlation analysis, the similarity rate between the original data signal and its reconstructed version. Fig. 9 shows the similarity rates in both cases and compares them with the similarity rate obtained with the narrow bandpass filtering used in [24] for the VLR. It appears clearly that from an SNR of around -5 dB, the similarity rate ensured by “VLR filtering” is larger than with “VLC filtering” thanks to its more accurate edge detection properties. On the contrary, “VLC filtering” is much more reliable at very low SNR because it cuts more noise. This cross-correlation analysis can also be used to show that the

delay introduced by both approaches is stable and reaches 480 ns with “VLC filtering” and only 90 ns with “DM filtering”.




Fig. 9. Evolution of the similarity rate with the SNR according to the filtering strategy used. VLR filtering is given for comparison between the VLCR and the VLR.

3) *Clock Recovery PLL*: Once the reconstructed signal m_r (or $m_{r'}$) is obtained, a clock recovery PLL is used to get the clock signal s_r (or $s_{r'}$). At this stage, the critical parameter is the time needed by the PLL to converge toward the right phase. In the simulations, this function is modeled using the ‘Clock Recovery PLL’ block from the ‘Mixed-Signal Library’ for Simulink, specially designed for this purpose. Therefore, with the help of Manchester coding, it has been observed that when “DM filtering” is used on a message of SNR = 10 dB, the phase of s_r converges after less than 2 ms and remains stable with a rather constant delay of 1 ns with respect to m_r . By comparison, a car moving at 130 km/h only travels around 7 cm in 2 ms so the clock recovery is not a critical step in terms of processing time for dynamic range-finding applications. Note that this 1 ns delay is partly achieved thanks to the accurate edge detection provided by “DM filtering” since it reaches 250 ns when “VLC filtering” is used. However, note also that this value are given modulo- 2π , which means that it is hard to know exactly which filtering strategy experiences overall the smallest delay.

C. Summary of the Simulation Parameters

The values of the channel parameters and of the intrinsic parameters of the VLCR are listed in Table I. The receiver parameters are realistic values for a PD whereas the channel parameters are taken from [32] and correspond to typical values for a FET-based preamplifier. Since the emission and irradiance angles ϕ and ψ are null, the LV and FV both share the same longitudinal axis.

This assumption also allows to bypass the inability of the Lambertian model to capture the complexity of automotive beam patterns. The Lambertian model is indeed fully determined by the semi-angle at half power $\Phi_{1/2}$ and the total optical power transmitted P_t . Since lateral variations between the vehicles are not simulated, these parameters are simply set so that the luminous intensity produced by the light on the

lane of the vehicle, just under the horizontal plane of emission, reaches the value defined by automotive lighting regulations UNECE R112 for LED headlamps [34] and UNECE R7 for taillights [35]. This luminous intensity must indeed reach at least 1700 cd with both headlamps in the first case and at most 730 cd per taillight in the second case. In addition, note that the limited modulation bandwidth of the headlamps and taillights is modeled on both ends of the VLCR with simple low-pass filters.

Now that our simulation model is fully described, we can review the simulation results.

TABLE I
SIMULATION MODEL PARAMETERS

Parameter	Value	Parameter	Value
<i>General parameters</i>		<i>Emitter parameters</i>	
f_e	1 MHz	P_t	2 W (FV) / 1 W (LV)
R_b	500 kbps	$\Phi_{1/2}$	20°
Message length	4000 bits	<i>Receiver parameters</i>	
Header frame	00001111	γ	0.5 A/W
f_{clock}	100 MHz	A_r	50 mm ²
r	1500	ψ_c	55°
N	5	<i>Channel parameters</i>	
T_r	267 Hz	ϕ	0°
<i>VLC filtering</i>		ψ	0°
Type	Butterworth	I_{bg}	740 μ A
Order	2	I_2	0.562
$f_{-3dB(LP)}$	500 kHz	B	5 MHz
$f_{-3dB(HP)}$	5 kHz	T_K	298 K
<i>DM filtering</i>		η	112 pF/cm ²
Type	Butterworth	G	10
Order	2	Γ	1.5
$f_{-3dB(LP)}$	2.5 MHz	g_m	30 mS
$f_{-3dB(HP)}$	250 kHz	I_3	0.0868

D. VLC Performances

The communication function is first tested by evaluation of the BER and packet-error rate (PER) evolutions with the V2V distance d . The following results are obtained by transmitting 10^6 bits divided into 250 packets, separated by synchronization frames. The BER is measured as the ratio of wrong bits over the total number of bits transmitted and is obtained by comparing the Manchester-encoded bits transmitted and decoded. Similarly, the PER is the ratio of lost packets over the total number of packets, knowing that a packet is considered lost if at least one bit in the packet is wrong. Fig. 10 shows the BER and PER evolution with d when either “VLC filtering” or “DM filtering” is used.

Several conclusions can be drawn. First of all, it appears clearly that the curves with “VLC filtering” are shifted versions of those obtained with “DM filtering”. In other words, the behavior of both filtering approaches is similar once the first errors appear, but the range from which these errors start to appear is larger with “VLC filtering”. This result can be explained by the fact that “DM filtering” has poor header detection capabilities: by cutting too much into the lower part of the signal spectrum, “DM filtering” distorts the header waveform which is then not recognized.




Fig. 10. BER and PER evolution against the V2V distance by steps of 50 cm with both “VLC filtering” and “DM filtering”.

We can also note that the distribution of the errors is rather uniform, as the PER reaches quickly 100% which means each packet contains at least one error. More importantly, these results show the ‘error-free’ communication distance is in the best case around 45 m. Therefore, the communication function of the VLCR is, from the longitudinal range point of view, perfectly suited for platooning use case, where the V2V distances are usually around 10 m.

E. Distance Measurement Performances

The range-finding function is then evaluated. Fig. 11(a) shows the evolution of the distance measured with “DM filtering” and “VLC filtering” against the real V2V distance. These curves are obtained by varying the V2V distance from 1 m to 50 m and taking one measurement every 5 cm. We can see first that both approaches provide a linear distance estimation from 1 m to 45 m, even though local variations are clearly visible. After this distance, the measures obtained with “DM filtering” collapse whereas they keep increasing linearly with “VLC filtering”. However, there is in both cases a non-negligible offset. This offset is due to the phase response of the reconstruction filters and to the recovery PLL which introduce additional delays resulting in an increase in the distance estimated.

By looking closer at these offsets, we can actually note that they are rather constant between 1 m and 45 m. Therefore, in both cases, the distance provided can be corrected by removing their mean value. In practice, the mean offset can be estimated by addition of the delays introduced on both ends of the system. Each vehicle can periodically estimate its delay, for example by sending and processing an internal signal. The LV can then send the delay estimated through the VLC channel to the FV so that the latter can add it to its own delay and estimate the offset to remove.

After mean offset removal, we get a residual error which corresponds to the intrinsic error of the system. Fig. 11(b) shows the histogram of these errors in the case of “DM filtering”, after correction over the range going from 1 m

to 30 m. It has a Gaussian-like distribution with zero mean and standard deviation $\sigma = 0.33$ m which means the system resolution, defined as the $\pm\sigma$ confidence interval, is around 66 cm. Note that if correction is applied over different ranges, the distribution remains Gaussian-like. This behavior remains valid in the case of “VLC filtering” so the resulting standard deviations in both cases are given in Table II.

TABLE II
EVOLUTION, WITH THE DISTANCE, OF σ_{DM_f} AND σ_{VLC_f} , THE STANDARD DEVIATIONS OF THE DISTANCE ERROR IN THE CASE OF “DM FILTERING” AND “VLC FILTERING”.

Correction range	σ_{DM_f}	σ_{VLC_f}
1 to 5 m	24 cm	29 cm
1 to 10 m	26 cm	32 cm
1 to 20 m	33 cm	40 cm
1 to 30 m	33 cm	43 cm
1 to 40 m	40 cm	44 cm
1 to 45 m	44 cm	47 cm

It appears clearly that, whatever the range of correction, “DM filtering” provides a better measurement resolution than “VLC filtering”. This is due to the fact that “DM filtering” introduces less pulse distortions and thus enables a more accurate reconstruction of the signals received. This leads to a better stability of the PLL and, eventually, to a better resolution. However, the resolution in both cases gets worse with the range. This phenomenon can be explained by the fact that, as the V2V distance increases, the SNR of the signals received on both ends decrease. However, as illustrated by Fig. 9, the similarity rate between the signals reconstructed and the original signals drops quickly with low SNR. Consequently, even though filtering helps recover rather clear signals, the distortions contained in these signals are getting larger with the distance, which impacts eventually the measurement error.

In addition, we can observe that the measurement error is periodic with a 1.33 cycles/m, and thus reaches a peak every 75 cm, as shown by the fast Fourier transform (FFT) analysis on Fig. 11(c). This behavior is closely linked to the clock counting error δM coupled with the slight phase variations of the reconstructed clock s_r and the heterodyning process, as illustrated by Fig.5.

In any case, the overall measurement performances of the VLCR are worse than those of the VLR alone, which can provide distance resolutions under 30 cm over a range of 30 m [23]. This gap can be explained once again by Fig. 9: the reconstruction properties of the filters used by the VLR alone are way better than those of both the “DM filtering” and “VLC filtering” approaches. Consequently, even though the addition of the communication function is of great benefit, it comes necessarily with a degradation in the range-finding performances.

V. EXPERIMENTAL STUDY OF THE RANGE-FINDING AND COMMUNICATION FUNCTIONS

Now that the VLCR has been described theoretically and validated through simulations, we can implement prototypes of the communication and range-finding functions in order




Fig. 11. (a) Evolution, against the real distance (black dotted line), of the estimated distance using “DM filtering” (red dashes) and “VLC filtering” (blue curve), (b) histogram of the error after correction over the range 1 m to 30 m in the case of “DM filtering” with its Gaussian fit curve and (c) FFT of this error.

to confirm they are functional in reality. The implementation of the prototypes is first described in Section V-A. Then, the range-finding function is demonstrated in Section V-B. Finally, the tests of the communication function are detailed in Section V-D. Consequently, note that the VLCR is not properly implemented here, as both functions are built and tested separately. This choice was made to focus on the validation of the range-finding function, which is the major novelty of our system.

A. Prototypes Implementation

1) *Emitter Block*: The signal emission, corresponding to the blocks ‘LED’ and ‘Emitter’ on Fig. 1, is made in practice using an LED light source controlled by an LED driver. The light source used on the FV side is a COTS white headlamp based on a Nichia NC4W121A high-power phosphor LED. The overall module is controlled with a forward current limited to 600 mA, which gives a maximum luminous intensity of 16750 cd compliant with standard regulations for low beam headlamps [34]. On the LV side, another COTS white headlamp is used, but it is under-driven to meet taillights regulations [35].

Both light sources have a 3 dB bandwidth of 1.4 MHz, so the frequency of operation f_e is, as previously, set to 1 MHz. In order to drive these lamps, a specific LED driver is designed and built. This driver converts the 1 MHz small current complementary metal oxide semiconductor (CMOS) square signal of command s_e or $s_{e'}$, produced by a field programmable gate array (FPGA), into the 600 mA control signal. It is thus simply a metal oxide semiconductor FET (MOSFET), which gate is controlled by the signal of command, first amplified with an optocoupler so that the appropriate amount of current can flow through the LED.

2) *Signal Reception: PD and Processing Card*: After their emission, the light signals are collected and processed by dedicated electronic cards in order to be reconstructed: this is the signal reception chain, represented on Fig. 2(b) and corresponding to the blocks ‘PD’ and ‘Receiver’ in Fig. 1. First, the light signal is collected with a PD which produces a photocurrent turned into a voltage and amplified by a TIA. These two blocks are implemented with a COTS photo-receiver Thorlabs PDA8A of bandwidth 50 MHz and gain 50 kV/A.

When used in communication mode, this photo-receiver is directly connected to a Tektronix MDO3054 oscilloscope for offline decoding with MATLAB. This offline decoding is the same as the one implemented for the simulations and thus consists in “VLC filtering” and zero-crossing detection in order to retrieve the data stream transmitted and measure the error rate performances of the system.

On the other hand, when the system is used in range-finding mode, the Thorlabs PDA8A is connected to a custom-made reconstruction card embedding an 8-th order bandpass filter of center frequency 1 MHz and bandwidth 100 kHz, amplification stages providing a maximum gain of 200 V/A and a high-speed comparator. This card can turn noisy input signals of a few millivolts into a clean square CMOS signal of frequency f_e . This CMOS signal is then used to feed the LED driver in the case of the LV or an FPGA, for phase-shift measurement, in the case of the FV. As already detailed in [24], this card has very good reconstruction properties down to SNR as low as 5 dB. However, the whole processing chain introduces a delay between the input and output signals that is around 933 ns with the card used on the LV and 928 ns with the card used on the FV. These values are, in addition, varying with the atmospheric conditions and especially with the temperature which will necessarily have an impact on the distance estimated, as we will see in Section V-D.

3) *Phase-Shift Measurement Algorithm*: Once the signal received from the LV is reconstructed into a stable square

signal s_r , it is compared with the original square wave s_e for phase-shift measurement. This phase-shift measurement step is performed digitally by an FPGA which has actually three main roles: generate the data stream m_e and thus the clock signal s_e , heterodyne s_e and s_r and, finally, measure their phase-shift, which corresponds to the blocks ‘Data’, ‘Message Encoding’, ‘Clock Generator’ and ‘Phase Measurement’ in Fig. 1.

In practice, since the range-finding and communication functions are tested separately, the FPGA is only used as a Manchester data source operating at 500 kbps in communication mode (no need of phase-shift measurement) whereas it only generates a square signal of frequency $f_e = 1$ MHz in range-finding mode (no need of data and message encoding). In both case, the resulting signal is continuously fed to the LED driver. In addition, in range-finding mode, the PLL generates the counter clock s_{clock} of frequency $f_{clock} = 100$ MHz used for auto-digital phase measurement. Finally, a second PLL generates the heterodyning clock s_h of frequency f_h .

This heterodyning clock is obtained using an heterodyning factor $r = 3999$. As explained in Section III-C, such a value leads to an interesting compromise between measurement error and refresh rate. The resulting heterodyning frequency f_h is in this case 999750 kHz. Unfortunately, the resolution of the internal PLL of the FPGA is not sufficient to support this exact frequency, which is measured instead at 999746.9 kHz with a frequency counter Agilent 53132A. This frequency corresponds to a true heterodyning factor $r = 3950.007$. This clock is then used to cadence a D flip-flop gate coded in hardware description language (HDL), as the rest of the auto-digital phase measurement algorithm represented on Fig. 4. This algorithm outputs the number of clock ticks M that is stored and then converted into phase-shifts and distances with MATLAB. Note that since no averaging is used ($N=1$), the refresh rate of the measurement (7) is 506 Hz.

Tests of this algorithm show that the phase-shift measured is linear with slope +1 from 0 to 180°, and then linear again from 180° to 360° but with a slope -1. This confirms that our method has a non-ambiguity range of π in terms of phase-shift, which corresponds to (6) in terms of distance. In addition, it is found that the each measurement contains a small phase-shift error, and thus a distance error. As explained in Section III-B, these errors are due to the limited resolution of the heterodyning step. However, they remain under 3 cm which is in accordance with the maximum error (9) equal here to 3.79 cm when $r = 3950.007$. This behavior confirms eventually that our phase-shift measurement algorithm is fully functional.

B. Validation of the Range-Finding Function

1) *Experimental Set-Up and Protocol:* The set-up used to validate the range-finding function is represented on Fig. 12. The FV and LV are both modeled by moving tables on which all the equipment is installed, and placed in a controlled laboratory environment. The table modeling the FV is fixed whereas the table representing the LV is moved in order to vary the V2V distance from 5 m to 25 m by steps of 50 cm. Both tables are kept on the same longitudinal axis so

that both vehicles can be considered aligned in a straight line. At each step, the ‘true’ distance is first measured with a Laserliner LaserRange-Master 40 rangefinder which can measure distances up to 30 m with a typical resolution of ± 2 mm. Then, 4096 consecutive distance estimations are performed, in static conditions, with the system.




Fig. 12. (a) Structure of the set-up used during the range-finding experiments and (b) photo of this set-up with at the top the FV end and at the bottom the LV end.

2) *General Behavior and Measurement Correction:* Fig. 13 shows the evolution of the average distance measured against the real V2V distance. We can observe first that there is an inflection point around 10.5 m. This behavior is induced by the processing delays added by the reconstruction cards used on both ends of the system. These delays are such that the overall phase-shift between s_e and s_r at 5 m is larger than π . Consequently, as the V2V distance and thus the return trip TOF increases, the overall phase-shift gets larger, which leads to a decrease in the value output by the system, in accordance with the observations made in Section V-A3. Then, at 10.5 m, the sum of the various phase-shifts is such that s_e and s_r are in phase, which leads to a distance measured null. After this value, the phase-shift is again positive, but this time below π , hence the rising section on Fig. 13.

Fortunately, the processing delays remain, as in the simulations, rather constant. We can indeed observe from the linear fits on Fig. 13 that both the decreasing and rising sections are rather linear, with an absolute slope close to unity. Consequently, it should be possible to apply a correction rule on these first results to remove the electronic delays and thus the inflection point with the corresponding measurement




Fig. 13. Evolution of the average distance measured by the prototype against the real distance with the linear fits of its decreasing and increasing sections.

error. In practice, the measures are corrected by first, adding a controlled delay so that the final phase-shifts remain between 0 and π , whatever the true V2V distance. Then, a linear fit of the averaged distance measurement is performed in order to define the offset that is finally removed. Note that such a correction assumes the various delays remain constant with time, which is here relevant given the duration of the whole experiment. However, in real conditions, this correction step will have to be repeated periodically because, for example, of the temperature variations the vehicle can experience throughout a journey. In such a case, auto-calibration method for real conditions functioning can be implemented, as the one quickly proposed in Section IV-E.

C. Measurement Error and Resolution

The fixed correction rule previously exposed allows to remove the inflection point observed on Fig. 13 and thus a large part of the initial measurement error, defined as the difference between the distances output by the system and the true distances. However, there is still after correction a residual error. To characterize this error, we can study the distributions of the 4096 consecutive measures taken at each distance tested. It is found that this distribution is Gaussian-like with, each time, a specific standard deviation σ and mean value. First, it must be noted that the correction rule does not change this shape but simply shifts the mean value closer to zero. For example, the mean distance measured for a true distance of 18 m is 7.8 m. After correction, this value reaches 17.95 m, which gives a mean error after correction of 5 cm. More generally, these mean errors are varying between -35 cm and 35 cm, without specific distribution, but 75% of them are actually between -16 cm and 16 cm.

Then, the Gaussian like distribution of the consecutive measures made for a same true distance allow us to determine, for each distance tested, a distance measurement resolution. This resolution is, as in the simulations, defined as twice the standard deviation σ of the measurements distribution for each distance. Such a definition means that 70% of the values

output for a specific distance by the system will be contained in the interval centered on the mean value after correction at this distance plus or minus one standard deviation σ at this distance. Table III lists the resolution measured for the various true distances tests, as well as the corresponding percentage of error.

TABLE III
DISTANCE RESOLUTION AGAINST THE TRUE V2V DISTANCE.

True distance (m)	Resolution 2σ (cm)	% of error
4.988	14.18	2.8
7.483	16.44	2.2
10.001	23.60	2.4
12.49	24.52	2.0
15.001	30.94	2.1
17.498	31.68	1.8
20.027	52.16	2.6
22.499	60.90	2.7
24.985	77.04	3.1

These variations can be explained by the phase noise of the signal reconstructed s_r , and thus by the limits of the hardware implementation of our prototype. s_r is indeed supposed to be a square signal of fixed frequency f_e and duty cycle 50%. However, the reconstruction process, mixed with the limited bandwidth of the emitters on both sides, cannot guarantee such a stability in frequency and duty cycle. The resulting fluctuations will necessarily vary the phase-shift between s_r and the signal first sent s_e , and eventually the distance measured. Given the fact that this distribution is Gaussian-like, we can deduce this phase noise is Gaussian and that it gets stronger with the V2V distance, that is as the SNR of the signals received on both ends of the system decreases.

These various results finally allow us to plot, on Fig. 14, the evolution of the distance measured by our range-finding prototype, after correction, and with the corresponding error bars. We can conclude from these results that our system is functional, even though the performances reached so far are still lower than the measurement resolution of 30 cm at 30 m reported in [23]. This difference in performance can mainly be explained by the phase noise of s_r caused by the various distortions induced by the limited bandwidth of the transmit LED and of the PD, or by the filtering and comparison stages used to reconstruct s_r .

D. Validation of the Communication Function

Finally, the communication function of the VLCD is evaluated. The experimental set-up used for these experiments is represented on Fig. 15 and is very similar to the set-up of Fig. 12, used to validate the range-finding function. On one end of the system, the FPGA generates the Manchester data stream at a data rate $R_b = 500$ kbps. This data stream is fed to the LED driver, which controls the light intensity of the LED. On the other end of the system, the Thorlabs PDA8A photo-receiver collects the lights signal and turns it into a voltage signal that is directly sampled by a Tektronix MDO3054 oscilloscope. The resulting samples are then processed offline using MATLAB to evaluate the error rate performances of the link.




Fig. 14. Evolution of the distance measured after correction with the corresponding error bars (blue dots) and of the true V2V distance (red dashes).



Fig. 15. Experimental set-up used to test the communication function of the VLCR.

As in Fig. 12(b), both vehicles are modeled by tables that can be moved to simulate the V2V distance. These tables are placed in an indoor corridor of length 30 m, illuminated with standard neon tubes driven at 50 Hz providing a constant average illuminance of 150 lux. The V2V distance d is then varied from 5 m to 30 m by steps of 5 m and at each step, 10^6 data bits divided into packets of 4000 bits and separated by a header $H = 00001111$ are sent.

The MATLAB post-processing consists, as already mentioned, in a “VLC filtering” stage followed by zero-crossing detection so that the signal reconstructed can be compared to the data signal for BER and PER evaluation. After this offline processing stage, there were actually no errors found in the reconstructed data signal. Therefore, we can conclude, as summed-up in Table IV, that the BER remains below 10^{-6} up to at least 30 m. Note that such a result was obtained using the LED light in both the low-beam headlamp mode and the taillight mode. In addition, the same results were obtained at a data rate of 1 Mbps. In any case, we can conclude from these experiments that the communication function of the VLCR, which is nothing more than a simple VLC system, is suited for platooning applications, at least in terms of operation range.

TABLE IV
EVOLUTION OF THE BER WITH THE TRUE V2V DISTANCE AT 500 KBPS.

V2V distance (m)	BER
30	$< 10^{-6}$

VI. CONCLUSIONS AND FUTURE WORKS

A. Summary of the Findings

In this paper, a new concept of communication and range-finding system called VLCR and based on the automotive headlamps and taillights is proposed for the first time in the literature. The VLCR is a simple VLC system over which is added a distance measurement layer, performed through the measurement of the phase-shift between clock signals contained in the data signals. The theoretical basis of this system are detailed and an analytical study of the sources of errors is carried out. A simulation study then validates the operation principles of the VLCR. Finally, both its communication and range-finding functions are validated experimentally in order to bring a proof of concept.

Although not optimized from the hardware point of view, this prototype enables distance measurement up to 25 m and ensures a measurement resolution of around 24 cm at 10 m, with a refresh rate of 506 Hz. In parallel, it enables data transmission at 500 kbps of 4000 bits packets over at least 30 m with a BER below 10^{-6} . The various simulation and practical studies also show that the VLCR does not sacrifice any bandwidth to support the range-finding function since this function is performed in parallel. On the other hand, the range-finding performances are degraded by the communication function because of the inexact reconstruction of the data signal and the resulting phase variations of the clock reconstructed by the clock recovery PLL. Simulations show that the distance measurement resolution is twice larger with the VLCR than with the VLR only.

As a reminder, highway platooning requires a nominal V2V distance of 8 to 10 m, a refresh rate of the distance measurement of at least 50 Hz, a measurement error of a few centimeters, and a communication function ensuring a 20 ms latency when transmitting small packets of 400 bits. These results thus show that the automotive lighting can be used as a complement to lidar, radar and radio communication systems in a simple a low cost manner. Except for the expensive off-the-shelf photo-receivers and FPGA development board, the bill of material for the rest of the components is indeed around \$15. Therefore, we can easily imagine that an optimized version of the VLCR with dedicated components would be very cost-competitive.

B. Discussion and Future Works

Despite promising results, the distance measurement performances of our prototype must be optimized to reach standard platooning requirements. The main way to increase these performances is to enhance the hardware implementation of the prototype. For example, focusing lenses carefully designed could be used to optimize the amount of light detected by a front-end also improved in terms of gain and noise immunity. From the reconstruction step point of view, a better hardware design combined with a meticulous choice of the components would probably enhance the stability of the reconstructed signals. The resulting prototype would then be tested first under various lighting and interferences scenario and then in real traffic conditions to deepen the performance analysis.

Finally, the communication function would be added according to the principles proposed and validated through simulations in this paper, and then tested in real networked conditions.

In parallel, other solutions will be investigated. Our work has been focused so far on implementing our system according to the framework defined by the VLC standard IEEE 802.15.7-2011 [30], which recommends to use pulse modulations. However, joint communication and distance measurement has been a hot topic lately, especially with advanced modulation schemes like orthogonal frequency division multiplexing (OFDM). For example, in the IEEE 802.11-2016 standard, stations can measure their inter-distance using the fine time measurement (FTM) technique based on FTM frames containing timestamps sent back and forth to measure a timestamp difference corresponding to the TOF. Such a method could actually be used with the current version of the VLRC since only the data frames must be changed. It would then add a second distance measurement after the one given by phase-shift measurement, but at the cost of the bandwidth dedicated to V2V communication. This bandwidth could thus be increased using OFDM, but in this case, the clock recovery PLL, on which the distance measurement is based, would not work anymore. Consequently, moving toward OFDM to reach high data rates would require to change the range-finding method and use, for example, pilot symbols based techniques as proposed in [37].

REFERENCES


- [1] C. Bergenheim, S. Shladover, E. Coelingh, C. Englund, and S. Tsugawa, "Overview of platooning systems," presented at the 19th ITS World Congress, Vienna, Austria, 22–26 Oct. 2012.
- [2] S. Tsugawa, S. Jeschke, and S.E. Shladover, "A Review of Truck Platooning Projects for Energy Savings," *IEEE Trans. Intell. Veh.* **1**(1), 68–77 (2016).
- [3] A. Geiger, M. Lauer, F. Moosmann, B. Ranft, H. Rapp, C. Stiller, and J. Ziegler, "Team AnnieWAY's Entry to the 2011 Grand Cooperative Driving Challenge," *IEEE Trans. Intell. Transp. Syst.*, vol. 13, no. 3, pp. 1008-1017, Sep. 2012.
- [4] P. S. Jootel, "SAfe Road TRains for the Environment - Final Report," <http://www.sartre-project.eu/en/publications/Sidor/default.aspx>.
- [5] European Truck Platooning Network, "Vision truck platooning 2025", 2016. [Online] Available: <https://www.eutruckplatooning.com/Support/Videos/Vision+Truck+Platooning+2025+TNO/default.aspx>
- [6] S. Al-Sultan, M. Al-Doori, and H. Zedan, "A comprehensive survey on vehicular Ad Hoc network," *J. Netw. Comput. Appl.*, vol. 37, pp. 380-392, Jan. 2014.
- [7] A. Festag, "Cooperative intelligent transport systems standards in europe," *IEEE Commun. Mag.*, vol. 52, no. 12, pp. 166-172, Dec. 2014.
- [8] "Specification of Cooperative Awareness Basic Service," ETSI EN 302 687-2 (V1.3.1), Sep. 2014.
- [9] A. Böhm, M. Jonsson, and E. Uhlemann, "Performance comparison of a platooning application using the IEEE 802.11p MAC on the control channel and a centralized MAC on a service channel," in *Proc. 9th IEEE WiMob*, 2013, pp. 545-552.
- [10] M. Y. Abualhoul, M. Marouf, O. Shagdar, and F. Nashashibi, "Platooning control using visible light communications: A feasibility study," in *Proc. 16th IEEE ITSC*, 2013, pp. 1535-1540.
- [11] S. Ishihara, R. V. Rabsatt, and M. Gerla, "Improving reliability of platooning control messages using radar and visible light hybrid communication," in *Proc. IEEE VNC*, 2015, pp. 96-103.
- [12] M. Segata, R. L. Cigno, H.-M. Tsai, and F. Dressler, "On platooning control using IEEE 802.11p in conjunction with visible light communications," in *Proc. IEEE/IFIP WONS*, 2016, pp. 14.
- [13] M. Akanegawa, Y. Tanaka, and M. Nakagawa, "Basic study on traffic information system using LED traffic lights," *IEEE Trans. Intell. Transp. Syst.*, vol. 2, no. 4, pp. 197-203, Dec. 2001.
- [14] I. Takai, T. Harada, M. Andoh, K. Yasutomi, K. Kagawa, and S. Kawahito, "Optical Vehicle-to-Vehicle Communication System Using LED Transmitter and Camera Receiver," *IEEE Photonics J.*, vol. 6, no. 5, pp. 1-14, Oct. 2014.
- [15] S.-H. Yu, O. Shih, H.-M. Tsai, N. Wisitpongphan, and R. Roberts, "Smart automotive lighting for vehicle safety," *IEEE Commun. Mag.*, vol. 51, no. 12, pp. 50-59, Dec. 2013.
- [16] A.-M. Cailean, B. Cagneau, L. Chassagne, M. Dimian, and V. Popa, "Novel Receiver Sensor for Visible Light Communications in Automotive Applications," *IEEE Sens. J.*, vol. 15, no. 8, pp. 4632-4639, Aug. 2015.
- [17] J. Wenger, "Automotive radar - status and perspectives," in *Proc. IEEE CSIC'05*, 2005, pp. 21-24.
- [18] J. Hasch, "Driving towards 2020: Automotive Radar technology trends," in *Proc. IEEE ICMIM*, 2015, pp. 1-4.
- [19] J. Lee, Y.-A. Li, M.-H. Hung, and S.-J. Huang, "A Fully-Integrated 77-GHz FMCW Radar Transceiver in 65-nm CMOS Technology," *IEEE J. Solid-State Circuits*, vol. 45, no. 12, pp. 2746-2756, Dec. 2010.
- [20] C. Niclass, M. Soga, H. Matsubara, M. Ogawa, and M. Kagami, "A 0.18-um CMOS SoC for a 100-m-Range 10-Frame/s 200 96-Pixel Time-of-Flight Depth Sensor," *IEEE J. Solid-State Circuits*, vol. 49, no. 1, pp. 315-330, Jan. 2014.
- [21] M. Goppelt, H.-L. Blöcher, and W. Menzel, "Automotive radar - investigation of mutual interference mechanisms," *Adv. Radio Sci.*, vol. 8, pp. 55-60, Sep. 2010.
- [22] G. Kim, J. Eom, and Y. Park, "An Experiment of Mutual Interference between Automotive LIDAR Scanners," in *Proc. 12th ITNG*, 2015, pp. 680-685.
- [23] B. Béchadergue, L. Chassagne, and H. Guan, "Visible light phase-shift rangefinder for platooning applications," in *Proc. 19th IEEE ITSC*, 2016, pp. 2462-2468.
- [24] B. Béchadergue, L. Chassagne, et H. Guan, "Vehicle-to-Vehicle Visible Light Phase-Shift Rangefinder Based on the Automotive Lighting," *IEEE Sens. J.*, vol. 18, no. 13, pp. 5334-5342, July 2018.
- [25] K. Mizui, M. Uchida, and M. Nakagawa, "Vehicle-to-vehicle communication and ranging system using spread spectrum technique (Proposal of Boomerang Transmission System)," in *Proc. 43rd IEEE VTC*, 1993, pp. 335-338.
- [26] A. J. Suzuki and K. Mizui, "Laser radar and visible light in a bidirectional V2V communication and ranging system," in *Proc. IEEE ICVES'15*, 2015, pp. 19-24.
- [27] Z. Li, L. Liao, A. Wang, and G. Chen, "Vehicular optical ranging and communication system," *EURASIP J. Wirel. Commun. Netw.*, vol. 2015, no. 1, pp. 1-6, Jul. 2015.
- [28] C.-Y. Wen, R. D. Morris, and W. A. Sethares, "Distance Estimation Using Bidirectional Communications Without Synchronous Clocking," *IEEE Trans. Signal Process.*, vol. 55, no. 5, pp. 1927-1939, May 2007.
- [29] S. Liu, J. Tan, and B. Hou, "Multicycle synchronous digital phase measurement used to further improve phase-shift laser range finding," *Meas. Sci. Technol.*, vol. 18, no. 6, pp. 1756-1762, Jun. 2007.
- [30] S. Rajagopal, R. D. Roberts, and S.-K. Lim, "IEEE 802.15.7 visible light communication: modulation schemes and dimming support," *IEEE Commun. Mag.*, vol. 50, no. 3, pp. 72-82, Mar. 2012.
- [31] I. Glover and P. M. Grant, *Digital Communications*, 3rd ed. Pearson Education, 2010.
- [32] J. M. Kahn and J. R. Barry, "Wireless infrared communications," *Proc. IEEE*, vol. 85, no. 2, pp. 265-298, Feb. 1997.
- [33] A. J. C. Moreira, R. T. Valadas, and A. M. de O. Duarte, "Optical interference produced by artificial light," *Wirel. Netw.*, vol. 3, no. 2, pp. 131-140, May 1997.
- [34] "Headlamps emitting an asymmetrical passing-beam," ECE Regulation No. 112 - Rev.3, Jan. 2013.
- [35] "Position, stop and end-outline lamps," ECE Regulation No. 7 - Rev.6, Nov. 2012.
- [36] "IEEE Standard for Information technology–Telecommunications and information exchange between systems Local and metropolitan area networks–Specific requirements - Part 11: Wireless LAN Medium Access Control (MAC) and Physical Layer (PHY) Specifications," in *IEEE Std 802.11-2016 (Revision of IEEE Std 802.11-2012)*, vol., no., pp.1-3534, 14 Dec. 2016.
- [37] C. D. Ozkaptan, E. Ekici, O. Altintas, and Chang-Heng Wang, "OFDM Pilot-Based Radar for Joint Vehicular Communication and Radar Systems," in *2018 IEEE VNC*, Dec. 2018.



Bastien Béchadergue received the engineer degree from ISAE-Supaero, Toulouse, France and the M.S. in communication and signal processing from Imperial College London, London, UK in 2014. He received then his Ph.D. degree in signal and image processing in 2017 from the UVSQ, University Paris-Saclay, for his work on visible light communication and range-finding for automotive applications. His current research interests include optical wireless communications including LiFi but also optical camera communications.



Luc Chassagne received a B.S. in Electrical Engineering (1994) from Supelec (France) and received his Ph.D. (2000) in optoelectronics from the University of Paris XI, Orsay (France) for his work in the field of atomic frequency standard metrology. He is now Professor and Director of the LISV laboratory at the University of Versailles. The topics of interest in his research are nanometrology, sensors and Visible Light Communications.



Hongyu Guan received a B.S. in Electrical Engineering (2007) from ENSEIRB (France) and his Ph.D. (2012) in computer science from the University of Bordeaux I, Bordeaux (France) for his work on embedded systems for home automation. He is now Research associate and chief project at the LISV laboratory, University of Versailles. His current research interests are Visible Light Communications, ubiquitous, data fusion, sensors and nanometrology.