



**HAL**  
open science

## Evolution of CO<sub>2</sub>, CH<sub>4</sub>, and OCS abundances relative to H<sub>2</sub>O in the coma of comet 67P around perihelion from Rosetta /VIRTIS-H observations

Dominique Bockelée-Morvan, J. Crovisier, S. Erard, F. Capaccioni, C. Leyrat, G. Filacchione, P. Drossart, T. Encrenaz, N. Biver, M.-C. de Sanctis, et al.

### ► To cite this version:

Dominique Bockelée-Morvan, J. Crovisier, S. Erard, F. Capaccioni, C. Leyrat, et al.. Evolution of CO<sub>2</sub>, CH<sub>4</sub>, and OCS abundances relative to H<sub>2</sub>O in the coma of comet 67P around perihelion from Rosetta /VIRTIS-H observations. Monthly Notices of the Royal Astronomical Society, 2016, 462 (Suppl 1), pp.S170-S183. 10.1093/mnras/stw2428 . hal-02457942

**HAL Id: hal-02457942**

**<https://hal.science/hal-02457942>**

Submitted on 1 Aug 2022

**HAL** is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

# Evolution of CO<sub>2</sub>, CH<sub>4</sub>, and OCS abundances relative to H<sub>2</sub>O in the coma of comet 67P around perihelion from *Rosetta*/VIRTIS-H observations

Dominique Bockelée-Morvan,<sup>1</sup>★ J. Crovisier,<sup>1</sup> S. Erard,<sup>1</sup> F. Capaccioni,<sup>2</sup> C. Leyrat,<sup>1</sup> G. Filacchione,<sup>2</sup> P. Drossart,<sup>1</sup> T. Encrenaz,<sup>1</sup> N. Biver,<sup>1</sup> M.-C. de Sanctis,<sup>2</sup> B. Schmitt,<sup>3</sup> E. Kührt,<sup>4</sup> M.-T. Capria,<sup>2</sup> M. Combes,<sup>1</sup> M. Combi,<sup>5</sup> N. Fougere,<sup>5</sup> G. Arnold,<sup>4</sup> U. Fink,<sup>6</sup> W. Ip,<sup>7</sup> A. Migliorini,<sup>2</sup> G. Piccioni<sup>2</sup> and G. Tozzi<sup>8</sup>

<sup>1</sup>LESIA, Observatoire de Paris, PSL Research University, CNRS, Sorbonne Universités, UPMC Univ. Paris 06, Univ. Paris-Diderot, Sorbonne Paris Cité, 5 place Jules Janssen, F-92195 Meudon, France

<sup>2</sup>INAF-IAPS, Istituto di Astrofisica e Planetologia Spaziali, via del fosso del Cavaliere 100, I-00133 Rome, Italy

<sup>3</sup>Université Grenoble Alpes, CNRS, Institut de Planétologie et d'Astrophysique de Grenoble, F-38041 Grenoble, France

<sup>4</sup>Institute for Planetary Research, Deutsches Zentrum für Luft- und Raumfahrt (DLR), D-12489 Berlin, Germany

<sup>5</sup>Department of Climate and Space Sciences and Engineering, University of Michigan, Ann Arbor, MI 48109, USA

<sup>6</sup>Lunar Planetary Laboratory, University of Arizona, Tucson, AZ-85721, USA

<sup>7</sup>National Central University, 32054, Chung-Li, Taiwan

<sup>8</sup>INAF, Osservatorio Astrofisico di Arcetri, Largo E. Fermi 5, I-50125 Firenze, Italy

Accepted 2016 September 22. Received 2016 September 20; in original form 2016 July 1

## ABSTRACT

Infrared observations of the coma of 67P/Churyumov–Gerasimenko were carried out from 2015 July to September, i.e. around perihelion (2015 August 13), with the high-resolution channel of the Visible and Infrared Thermal Imaging Spectrometer instrument onboard *Rosetta*. We present the analysis of fluorescence emission lines of H<sub>2</sub>O, CO<sub>2</sub>, <sup>13</sup>CO<sub>2</sub>, OCS, and CH<sub>4</sub> detected in limb sounding with the field of view at 2.7–5 km from the comet centre. Measurements are sampling outgassing from the illuminated Southern hemisphere, as revealed by H<sub>2</sub>O and CO<sub>2</sub> raster maps, which show anisotropic distributions, aligned along the projected rotation axis. An abrupt increase of water production is observed 6 d after perihelion. In the meantime, CO<sub>2</sub>, CH<sub>4</sub>, and OCS abundances relative to water increased by a factor of 2 to reach mean values of 32, 0.47, and 0.18 per cent, respectively, averaging post-perihelion data. We interpret these changes as resulting from the erosion of volatile-poor surface layers. Sustained dust ablation due to the sublimation of water ice maintained volatile-rich layers near the surface until at least the end of the considered period, as expected for low thermal inertia surface layers. The large abundance measured for CO<sub>2</sub> should be representative of the 67P nucleus original composition, and indicates that 67P is a CO<sub>2</sub>-rich comet. Comparison with abundance ratios measured in the Northern hemisphere shows that seasons play an important role in comet outgassing. The low CO<sub>2</sub>/H<sub>2</sub>O values measured above the illuminated Northern hemisphere are not original, but the result of the devolatilization of the uppermost layers.

**Key words:** comets: general – comets: individual: 67P/Churyumov–Gerasimenko – infrared: planetary systems.

## 1 INTRODUCTION

Comets are among the most pristine objects of the Solar system. The chemical composition of nucleus ices should provide insights for the conditions of formation and evolution of the early Solar system. A large number of molecules have now been identified in cometary atmospheres, both from ground-based observations and

space, including in situ investigations of cometary atmospheres (Bockelée-Morvan et al. 2004; Biver et al. 2015a; Cochran et al. 2015; Le Roy et al. 2015; Biver & Bockelée-Morvan 2016). Molecular abundances relative to water present strong variations from comet to comet, and also vary along the comet orbit (e.g. Ootsubo et al. 2012; McKay et al. 2015, 2016; Biver & Bockelée-Morvan 2016). This chemical diversity is often interpreted as reflecting different formation conditions in the primitive solar nebula (e.g. A'Hearn et al. 2012). However, questions arise concerning the extent to which abundances measured in cometary atmospheres are

\* E-mail: dominique.bockelee@obspm.fr

representative of the pristine composition of nucleus ices. Models investigating the thermal evolution and outgassing of cometary nuclei show that the outgassing profiles of cometary molecules depend on numerous factors such as molecule volatility, thermal inertia of the nucleus material, nature of water ice structure, and dust mantling (De Sanctis, Capria & Coradini 2005; De Sanctis, Lasue & Capria 2010a; De Sanctis et al. 2010b; Marboeuf & Schmitt 2014).

The study of the development of cometary activity, with the goal to relate coma to nucleus chemical properties, is one of the main objectives of the *Rosetta* mission of the European Space Agency (Schulz 2012). *Rosetta* reached comet 67P/Churyumov–Gerasimenko (hereafter referred to as 67P) in 2014 August at  $r_h = 3.5$  au from the Sun, and accompanied it in its journey towards perihelion (2015 August 13,  $r_h = 1.24$  au), with the end of the mission in 2016 September. The scientific instruments on the orbiter and Philae lander provided complementary information on the physical and chemical properties of the nucleus surface and sub-surface, and of the inner coma. They revealed a dark, organic-rich and low-density bi-lobed nucleus with a morphologically complex surface showing different geological terrains, some of them with smooth dust-covered areas (Capaccioni et al. 2015; Sierks et al. 2015; Pätzold et al. 2016). Dust jets originating from active cliffs, fractures, and pits were observed (Vincent et al. 2016). Water vapour was first detected in 2014 June, at 3.93 au from the Sun (Gulkis 2014; Gulkis et al. 2015). In data obtained from pre-equinox (2015 May), the water outgassing was found to correlate well with solar illumination, though with a large excess from the brighter and bluer Hapi region situated in the Northern hemisphere (Biver et al. 2015b; Bockelée-Morvan et al. 2015; Feldman et al. 2015; Fink et al. 2016; Fougere et al. 2016a; Migliorini et al. 2016). In the Hapi active region, Visible and Infrared Thermal Imaging Spectrometer (VIRTIS) has observed that surficial water ice has diurnal variability showing sublimation and condensation cycle occurring with the change of illumination conditions (De Sanctis et al. 2015). In contrast, CO<sub>2</sub> originated mainly from the poorly illuminated Southern hemisphere (Hässig et al. 2015; Fink et al. 2016; Fougere et al. 2016a; Migliorini et al. 2016), where VIRTIS identified a CO<sub>2</sub> ice-rich area (specifically in the Anhur region; Filacchione et al. 2016b).

The large obliquity (52°) of the 67P rotation axis (Sierks et al. 2015) leads to strong seasonal effects on its nucleus, with the northern regions experiencing a long summer at large distances from the Sun whereas the southern polar regions are subjected to a short-lived, but extremely intense summer season around perihelion. In this paper, we present observations of H<sub>2</sub>O, CO<sub>2</sub>, <sup>13</sup>CO<sub>2</sub>, OCS, and CH<sub>4</sub> in the vapour phase undertaken with the high spectral resolution channel of the VIRTIS (Coradini et al. 2007) near perihelion (2015 early July to end of September). The paper is organized as follows: Section 2 presents the VIRTIS-H instrument, the data set, and raster maps of H<sub>2</sub>O and CO<sub>2</sub> which provide the context for the off-limb observations studied in the paper; in Section 3, we present the detected molecular emission lines and the fluorescence models used for their analysis; Section 4 presents the data analysis and the column densities measured for H<sub>2</sub>O, CO<sub>2</sub>, CH<sub>4</sub>, and OCS, and their relative abundances; an interpretation of the results and a discussion follow in Section 5.

## 2 OBSERVATIONS

### 2.1 VIRTIS-H instrument

The VIRTIS instrument is composed of two channels: VIRTIS-M, a spectroimager operating both in the visible (0.25–1 μm) and

infrared (1–5 μm) ranges at moderate spectral resolution ( $\lambda/\Delta\lambda = 70$ –380), and VIRTIS-H, a point spectrometer in the infrared (1.9–5.0 μm) with higher spectral resolution capabilities (Coradini et al. 2007). The infrared channel of VIRTIS-M stopped providing cometary data in 2015 May due to a cryocooler failure. Only VIRTIS-H data are used in this paper.

VIRTIS-H is a cross-dispersing spectrometer consisting of a telescope, an entrance slit, followed by a collimator, and a prism separating eight orders of a grating (Drossart et al. 2000; Coradini et al. 2007). The spectra investigated in this paper are in orders 0 (4.049–5.032 μm) and 2 (3.044–3.774 μm). Each order covers  $432 \times 5$  pixels on the detector. A ‘pixel map’ locates the illuminated pixels. The field of view (FOV) corresponds to a 5-pixel wide area on the focal plane array; in nominal mode (most data), the summation of the signals received on these pixels (actually only the three more intense) is performed onboard. The spectra are therefore sampled by 3456 spectral elements, 432 in each grating order. As for most *Rosetta* instruments, the line of sight (LOS) of VIRTIS is along the Z-axis of the spacecraft (S/C). The instantaneous FOV of the VIRTIS-H instrument is  $0.58 \times 1.74$  mrad<sup>2</sup> (the larger dimension being along the Y-axis).


The VIRTIS-H data are processed using the so-called CALIBROS pipeline. This pipeline subtracts dark current, corrects for the instrumental function (odd/even pixel effects, de-spiking), and calibrates the absolute flux of the spectra in radiance ( $\text{W m}^{-2} \text{sr}^{-1} \mu\text{m}^{-1}$ ). Stray light is present in some spectra on the short-wavelength side of each order, depending on the location of the nucleus with respect to the slit (Fig. 1).

The nominal numerical spectral resolving power  $\lambda/\Delta\lambda$  varies between 1300 and 3500 within each order, where  $\Delta\lambda$  is the grating resolution. The spectral sampling interval is 1.2–1.3 Δλ, and thus above the Nyquist sampling. In the current calibration, odd/even effects were overcome by performing spectral smoothing with a boxcar average over three spectral channels, thereby reducing the effective spectral resolution to a value  $\sim 2.7 \times \Delta\lambda$ , which was experimentally verified by fitting spectra of the H<sub>2</sub>O and CO<sub>2</sub> bands in orders 4 and 0, respectively (Debout 2015). The effective spectral resolution with the current calibration is  $\sim 800$  at 3.3 and 4.7 μm.

The geometric parameters of the observations have been computed using nucleus shape model SHAP5 v1.1, derived from Optical, Spectroscopic, and Infrared Remote Imaging System (OSIRIS) images (Jorda et al. 2016).

### 2.2 Data set

The data set was selected with the objective of studying spectral signatures of a number of species and derives their relative abundances. As presented in the following sections (see Fig. 1), five molecules (H<sub>2</sub>O, CO<sub>2</sub>, <sup>13</sup>CO<sub>2</sub>, OCS, and CH<sub>4</sub>) are detected unambiguously around perihelion (August 13.0908 UT), not considering organic molecules contributing to the 3.4 μm band. Whereas H<sub>2</sub>O and CO<sub>2</sub> present strong signatures at 2.7 and 4.3 μm, respectively, which were detected by VIRTIS-H starting from 2014 October (Bockelée-Morvan et al. 2015), these bands became optically thick around perihelion time. Hence, in this paper we consider the 2015 July–September period during which optically thin H<sub>2</sub>O and CO<sub>2</sub> hot bands, and <sup>13</sup>CO<sub>2</sub> are detected. An appropriate radiative transfer analysis (following, e.g. Debout, Bockelée-Morvan & Zakharov 2016) of the optically thick H<sub>2</sub>O and CO<sub>2</sub> bands will be presented in forthcoming papers. Specifically, we analysed the  $\nu_3 - \nu_2$  and  $\nu_1 - \nu_2$  H<sub>2</sub>O hot bands falling in the 4.4–4.5 μm range, and the CO<sub>2</sub>  $\nu_1 + \nu_3 - \nu_1$  bands at 4.3 μm.



**Figure 1.** Full VIRTIS-H spectrum obtained by averaging the three data cubes obtained on 2015 August 19. At this scale, the faint emissions from CH<sub>4</sub>, OCS, and H<sub>2</sub>O 4.5–5 μm bands are not easily distinguishable. The short-wavelength range of the spectral orders is contaminated by instrumental stray light (e.g. at 2.1 and 2.28 μm), resulting in a higher radiance.

Coma observations with VIRTIS-H were performed in various pointing modes, e.g. stared pointing at a fixed limb distance in inertial frame or raster maps. In this paper, we consider mostly those with the FOV staring at a distance of less than 5 km from the comet surface (distance from comet centre less than 7 km) along the projected comet–Sun line. These observations are those providing the largest signal-to-noise ratios (SNRs) in the spectra. In addition, we considered four data cubes with acquisitions scanning a line of 8-km long perpendicular to the Sun direction and above the illuminated nucleus (data of 2015 September 6–7, Table 1). The mean distances to the comet centre ( $\rho$ ) for the considered data cubes are between 2.7 and 6.9 km (Table 1).

Altogether 30 data cubes, lasting typically 3–4 h each, were selected. They are listed in Table 1, together with geometric parameters (phase angle, heliocentric distance  $r_h$ , and distance of the S/C to the comet, mean distance of the FOV with respect to the comet centre and position angle). For these observations, the acquisition time is 3 s, except for the July 12th and 27th observations for which it is 1 s, and the dark rate is 4 (one dark image in every four acquisitions). Frame summing has been performed onboard for data volume considerations, e.g. by summing pair of acquisitions. The total number of acquisitions in the data files is between 256 (case of first August 26th observation) and 7424 (observation of July 27th).

For most of the selected observations, the S/C was in the terminator plane (phase angle  $\sim 90^\circ$ ). Therefore, these observations were favourable for sampling molecules outgassed from the illuminated regions of the nucleus. However, the two last data cubes were acquired with a smaller phase angle  $\sim 50^\circ$ – $60^\circ$ , with the closest points to the LOS situated from less illuminated regions, so that less intense signals are expected (and indeed observed). During the period, the *Rosetta* S/C was at distances from the comet from 150 to 480 km (with the exception of the September 27 observation with the S/C at 1057 km, Table 1). The VIRTIS-H FOV then ranged from  $90 \times 260$  to  $280 \times 850$  m<sup>2</sup> in the orthogonal plane containing the

comet, which can be compared to the typical size of 67P nucleus of 2 km equivalent radius. This means that molecules detected in the FOV are potentially originating from a broad range of longitudes and latitudes.

### 2.3 Context VIRTIS-H raster maps

As a result of the  $52^\circ$  obliquity and the orientation of the 67P rotation axis (Sierks et al. 2015), the perihelion period corresponds to the time where only the southern regions are illuminated. During the July–September period, the subsolar latitude varied between  $-26^\circ$  and  $-52^\circ$ , with the lowest value reached on 2015 September 4.

In order to put the limb observations analysed in this paper into context, we show in Fig. 2 VIRTIS-H raster maps of the H<sub>2</sub>O 2.7 μm and CO<sub>2</sub> 4.3 μm bands obtained on 2015 July 30 and August 9, when *Rosetta* was at 181 and 303 km from the comet, respectively. These maps (not listed in Table 1) were obtained by slewing the S/C along the X S/C axis (with the Sun being in the  $-X$  direction), setting a line spacing in the Y direction. The observation duration is 3–4 h, i.e. 1/4 to 1/3 of the rotation period of  $\sim 12$  h (Sierks et al. 2015), so there is some smearing related to nucleus rotation. Spatial binning was applied, by averaging spectra into cells of sizes of 1 and 2 km. After baseline removal, the CO<sub>2</sub> band area was determined by Gaussian fitting, whereas that of the H<sub>2</sub>O band by summing the radiances measured in the wavelength interval 2.6–2.73 μm.

The distributions of the H<sub>2</sub>O and CO<sub>2</sub> band intensities display a fan-shaped morphology aligned along the south direction of the rotation axis (Fig. 2), indicating that these molecules were mainly released from the southern regions. Because the *Rosetta* S/C was moving around the comet, the position angle (PA) of the rotation axis in the (X, Y) S/C frame changed with time, spanning value between  $240^\circ$  and  $330^\circ$  in the July–November time frame (Table 1), with the Sun at  $+270^\circ$  in the adopted PA definition (PA =  $0^\circ$  for the  $+Y$  axis, PA =  $90^\circ$  for  $+X$  axis). VIRTIS-H maps acquired

**Table 1.** Logarithm of VIRTIS-H observations.

Obs Id	Start time (UT)	Duration (h)	Date wrt perihelion (d)	$r_h$ (au)	$\Delta(S/C)$ (km)	Phase ( $^\circ$ )	Pointing <sup>a</sup>		South Pole <sup>b</sup>	
							$\rho$ (km)	PA ( $^\circ$ )	PA ( $^\circ$ )	Aspect ( $^\circ$ )
00395011055	2015-07-08T21:11:00.3	3.51	-35.2	1.316	150	90	2.82	259	328	108
00395322550	2015-07-12T11:46:52.6	3.66	-31.6	1.302	153	89	2.70	274	327	101
00395742154	2015-07-17T08:15:55.9	2.56	-26.7	1.286	177	90	3.10	272	302	137
00396199623	2015-07-22T15:23:57.9	4.27	-21.4	1.271	169	89	2.69	266	319	110
00396220410	2015-07-22T21:10:24.7	3.60	-21.2	1.270	170	89	2.98	266	319	109
00396659230	2015-07-27T23:06:40.5	3.54	-16.1	1.259	177	90	4.01	247	311	60
00396826054	2015-07-29T21:20:59.8	3.24	-14.2	1.255	179	90	3.56	265	286	44
00396842044	2015-07-30T01:47:25.8	3.91	-14.0	1.255	177	90	3.59	265	281	43
00397038715	2015-08-01T08:25:16.8	0.67	-11.7	1.252	214	90	3.08	270	238	52
00397871165	2015-08-10T23:32:29.0	2.80	-2.1	1.244	323	89	6.23	286	242	123
00398347798	2015-08-16T11:56:25.1	3.31	3.4	1.244	327	89	3.58	267	288	127
00398603680	2015-08-19T11:08:06.5	3.24	6.4	1.246	329	90	2.96	263	302	115
00398619671	2015-08-19T15:34:33.4	3.91	6.6	1.246	327	90	2.97	262	303	114
00398640452	2015-08-19T21:20:58.5	3.24	6.8	1.246	326	90	3.47	262	304	112
00398729980	2015-08-20T22:13:06.6	3.91	7.8	1.247	325	90	4.58	258	307	105
00398970868	2015-08-23T17:07:54.5	3.10	10.6	1.250	340	87	3.78	256	309	80
00398986563	2015-08-23T21:29:29.5	3.78	10.8	1.251	343	87	3.82	255	308	78
00399198695	2015-08-26T08:17:52.6	1.02	13.3	1.254	414	83	4.25	264	302	59
00399208316	2015-08-26T10:58:13.4	3.56	13.4	1.254	410	83	3.95	263	301	57
00400195914	2015-09-06T21:25:16.9	3.91	24.8	1.280	339	108	4.92	266 <sup>c</sup>	231	124
00400216374	2015-09-07T03:06:16.9	3.24	25.0	1.281	332	110	4.87	268 <sup>c</sup>	231	127
00400232094	2015-09-07T07:28:16.8	3.91	25.2	1.282	327	111	4.83	268 <sup>c</sup>	232	131
00400252549	2015-09-07T13:09:16.0	3.24	25.5	1.282	322	112	4.83	270 <sup>c</sup>	232	134
00400407713	2015-09-09T08:15:16.0	1.08	27.3	1.288	331	119	3.14	263	255	156
00400433767	2015-09-09T15:29:34.0	4.05	27.6	1.289	324	120	3.72	262	263	157
00400470243	2015-09-10T01:37:26.0	4.18	28.0	1.290	318	120	5.78	263 <sup>d</sup>	274	158
00400748481	2015-09-13T06:54:44.2	3.51	31.2	1.301	313	110	3.58	265	307	132
00400765976	2015-09-13T11:46:19.3	3.64	31.4	1.302	312	108	3.61	265	307	129
00401717336	2015-09-24T11:55:21.0	4.07	42.4	1.347	488	63	5.02	275	317	60
00401994267	2015-09-27T16:57:54.5	3.51	45.6	1.362	1057	51	6.88	282	329	35

Notes. <sup>a</sup>Except when indicated, the FOV is staring at a fixed distance  $\rho$  from the comet centre at the given position angle PA which is close to the Sun direction (PA(Sun) = 270 $^\circ$ ).

<sup>b</sup>Orientation of South Pole direction defined by its PA in the plane of the sky and its aspect angle with respect to the LOS.

<sup>c</sup>The S/C was continuously slewing along the Y-axis, i.e. perpendicularly to the comet–Sun line providing data at  $y = -4$  to  $+4$  km with  $x$  being fixed; PA was ranging from 220 $^\circ$  to 310 $^\circ$ , only the mean PA is indicated.

<sup>d</sup>Two stared positions were commanded, whereas we used the closest to comet centre.

from 2015 August to November in different PA configurations all show a tight correlation between the orientation of the H<sub>2</sub>O and CO<sub>2</sub> fans and the north–south line (Bockelée-Morvan et al. 2016). This is consistent with in situ data obtained by the *Rosetta* Orbiter Spectrometer for Ion and Neutral Analysis (ROSINA; Fougere et al. 2016b).

As regards the stared off-limb observations considered in this paper, they probe coma regions at PA close to the projected comet–Sun line. The PA of the FOV is given for each data cube in Table 1. The angle between the PA of the FOV and the main fan direction is the range 0 $^\circ$ –70 $^\circ$  (with 70 per cent of the observations with an offset less than 45 $^\circ$ ). Since the angular width of the H<sub>2</sub>O and CO<sub>2</sub> fans was measured to be typically 110 $^\circ$  and 180 $^\circ$  for H<sub>2</sub>O and CO<sub>2</sub>, respectively (Bockelée-Morvan et al. 2016), coma regions within the molecular fan were observed most of the time.


### 3 OBSERVED FLUORESCENCE EMISSIONS AND MODELLING

#### 3.1 H<sub>2</sub>O

H<sub>2</sub>O is detected both in the 2.5–2.9  $\mu$ m (covered by orders 3–5 of the spectrograph) and in the 4.45–5.0  $\mu$ m range (order 0)


(Figs 1–3). The rovibrational lines detected in the 2.5–2.9  $\mu$ m region are from the  $\nu_3$  and  $\nu_1$  fundamental bands, and from several hot bands ( $\nu_1 + \nu_3 - \nu_1$ ,  $\nu_2 + \nu_3 - \nu_2$ , and the weaker  $\nu_1 + \nu_3 - \nu_3$  band; Bockelée-Morvan & Crovisier 1989; Villanueva et al. 2012). With the spectral resolution of the data, the rovibrational structure of these bands is partially resolved. The intensity of the  $\nu_3$  band is expected to be significantly affected by optical depth effects (Debout et al. 2016). Unfortunately, the low wavelength range of order 3 (where the optically thin hot bands are nicely detected) is somewhat affected by stray light within the instrument, requiring careful data analysis, which is outside the scope of the present work. Therefore, we focused on the analysis of the 4.45–5.0  $\mu$ m range where lines of the  $\nu_3 - \nu_2$  and  $\nu_1 - \nu_2$  H<sub>2</sub>O hot bands are present (Fig. 3).

Synthetic H<sub>2</sub>O spectra were computed using the model developed by Crovisier (2009). This model computes the full fluorescence cascade of the water molecule excited by the Sun radiation, describing the population of the rotational levels in the ground vibrational state by a Boltzmann distribution at  $T_{\text{rot}}$  (the rotation temperature  $T_{\text{rot}}$  is expected to be representative of the gas kinetic temperature in the inner coma of 67P). We verified that excitation by the Sun radiation scattered by the nucleus, and that by the nucleus thermal radiation



**Figure 2.** VIRTIS-H raster maps of the  $\text{H}_2\text{O}$  2.7  $\mu\text{m}$  and  $\text{CO}_2$  4.3  $\mu\text{m}$  bands. Top:  $\text{H}_2\text{O}$  on 2015 July 30, 19h:25 UT (ObsId: 00396898661). Middle and bottom:  $\text{H}_2\text{O}$  and  $\text{CO}_2$ , respectively, on 2015 August 9, 3h:10 UT (ObsId: 00397703949). The projection of the rotation axis (south direction) and the Sun direction are indicated. The observational parameters are: line spacings of 0.6 and 2 km, slew rates of 1.0 and 1.75  $\text{deg min}^{-1}$ , for July 30 and August 9, respectively. The maps were obtained after averaging spectra within cells of sizes of 1 (July 30) and 2 km (August 9).

can be neglected (this is the case for all the molecular bands studied in the paper). The model, which includes a number of fundamental bands and hot bands, uses the comprehensive  $\text{H}_2\text{O}$  ab initio data base of Schwenke & Partridge (2000), and describes the solar radiation as a blackbody. Synthetic spectra in the 4.4–4.5  $\mu\text{m}$  range



**Figure 3.** VIRTIS-H spectra in the range 4.45–5  $\mu\text{m}$  showing rovibrational lines of the  $\text{H}_2\text{O}$   $\nu_3 - \nu_2$  band, and the  $\text{OCS}$   $\nu_3$  band. The red line displays the fitted synthetic spectrum for a temperature of 120 K, including both  $\text{H}_2\text{O}$  and  $\text{OCS}$ . The green line shows the contribution due to  $\text{OCS}$  only. (A) July 17–22; (B) July 29–30; (C) August 19; (D) September 9, 13. The standard deviation for each spectral channel is shown in the bottom of the plots (for better reading, the error bars are offset with respect to the measured radiances); values in blue include time variations in the continuum. In the top plot, the standard deviation measured on a spectrum with no comet signal (and scaled to the observing time of the comet spectrum) is superimposed, in red.

closely resemble those obtained by the model of Villanueva et al. (2012), which uses the BT2 ab initio data base (Barber et al. 2006) and includes a more exact description of the solar radiation field including solar lines. However, in that spectral region, the excitation of the water bands is not affected by solar Fraunhofer lines (Villanueva, personal communication). Finally, to achieve the best accuracy for the band excitation and emission rates, the synthetic spectra were rescaled to match those obtained by Villanueva et al. (2012). The resulting total emission rate (g-factor) in the 4.2–5.2  $\mu\text{m}$  region is given in Table 2 for a gas temperature of 100 K (actually, as we fitted water lines in the 4.45–5.03  $\mu\text{m}$  range, we used the corresponding g-factor of  $1.19 \times 10^{-5} \text{ s}^{-1}$  at 1 au from the Sun). A synthetic spectrum at the spectral resolution of VIRTIS-H is shown in Fig. 4.

These models assume optically thin conditions, both in the excitation of the vibrational bands and in the received radiation. However, the observed  $\nu_3 - \nu_2$  rovibrational lines result from cascades from the  $\nu_3$  vibrational state, and one may wonder whether the solar


**Table 2.** Fluorescence g-factors.

Molecule	Band	Wavelength ( $\mu\text{m}$ )	g-factor <sup>a</sup> ( $\text{s}^{-1}$ )	Ref. <sup>b</sup>
H <sub>2</sub> O	$\nu_3 - \nu_2, \nu_1 - \nu_2$	4.2–5.2	$1.40 \times 10^{-5}$	(1)
CO <sub>2</sub>	$\nu_3$	4.26	$2.69 \times 10^{-3}$	(2)
CO <sub>2</sub>	$\nu_1 + \nu_3 - \nu_1$	4.30	$8.7 \times 10^{-5c}$	(3)
<sup>13</sup> CO <sub>2</sub>	$\nu_3$	4.38	$2.42 \times 10^{-3}$	(4)
CH <sub>4</sub>	$\nu_3$	3.31	$4.0 \times 10^{-4}$	(4)
OCS	$\nu_3$	4.85	$2.80 \times 10^{-3}$	(4)

Notes. <sup>a</sup>The total band g-factors are listed for  $r_h = 1$  au and scale as  $r_h^{-2}$ . They are computed for  $T_{\text{rot}} = 100$  K (but they only weakly depend upon  $T_{\text{rot}}$ ).

<sup>b</sup>References: (1) Villanueva et al. (2012); (2) Debout et al. (2016); (3) Crovisier (2009); (4) this work.

<sup>c</sup>Sum of the g-factors of the  $10^0 1_{11} - 10^0 0_{11}$  and  $10^0 1_1 - 10^0 0_1$  bands.




**Figure 4.** Simulated fluorescence spectra of H<sub>2</sub>O (black) and CO (red) for an effective spectral resolution of 800. The CO/H<sub>2</sub>O abundance ratio is 1 per cent and the rotational temperature is 100 K.

pump populating the  $\nu_3$  state is attenuated in the regions probed by the LOS. Using the radiative transfer code of Debout et al. (2016), we verified that the excitation of the  $\nu_3$  band is only weakly affected by optical depths (by 10 per cent at most). Because the hot bands are connecting weakly populated vibrational states, they are fully optically thin with respect to the received radiation, unlike the  $\nu_3$  band at 2.67  $\mu\text{m}$ .

### 3.2 The CO<sub>2</sub>, <sup>13</sup>CO<sub>2</sub> complex

The CO<sub>2</sub>  $\nu_3$  band shows strong fluorescence emission between 4.2 and 4.32  $\mu\text{m}$  (Fig. 5). A wing in the long-wavelength range extending up to about 4.35  $\mu\text{m}$  is present. It is attributed to fluorescence emission of two hot bands of CO<sub>2</sub>, namely the  $10^0 1_{11} - 10^0 0_{11}$  and  $10^0 1_1 - 10^0 0_1$  ( $\nu_1 + \nu_3 - \nu_1$  bands) centred at 2327.4 and 2326.6  $\text{cm}^{-1}$  (4.30  $\mu\text{m}$ ), respectively. A weak band extending from 4.35 to 4.42  $\mu\text{m}$  is present, identified as the <sup>13</sup>CO<sub>2</sub>  $\nu_3$  band. This is the first detection of <sup>13</sup>CO<sub>2</sub> and CO<sub>2</sub> hot bands in a comet. In optically thin conditions, these bands are much weaker than the CO<sub>2</sub> main band. A priori, their observation allows a determination of the CO<sub>2</sub> column density independently of transfer modelling. However, some modelling of the spectral shape of the CO<sub>2</sub> main band is required since: (i) the hot bands are blended with the *P* branch of the CO<sub>2</sub> main band in the observations considered here (whereas ob-




**Figure 5.** Example of model fit to a VIRTIS-H spectrum in the 4.2–4.6  $\mu\text{m}$  range. The considered spectrum is the mean of four data cubes obtained on 2015 September 6 and 7. Top panel: observed spectrum with standard deviations (black) and model fit (red). Bottom panel: observed spectrum and model fit for each individual band (grey, green, and blue lines for CO<sub>2</sub>, CO<sub>2</sub> hot bands, and <sup>13</sup>CO<sub>2</sub>, respectively); the continuum radiation due to dust thermal radiation has been removed; standard deviations are given in the bottom of the plot (see Fig. 3). Free model parameters are the baseline polynomial, and multiplying factors to CO<sub>2</sub>, <sup>13</sup>CO<sub>2</sub>, and H<sub>2</sub>O fluorescence spectra computed for a rotational temperature of 120 K. The ratio between the intensities of the CO<sub>2</sub> hot bands and the <sup>13</sup>CO<sub>2</sub> band is fixed to the expected value for <sup>12</sup>C/<sup>13</sup>C = 89.

servations obtained farther from the nucleus in the cold coma show distinctly the *R* branch of the hot bands); (ii) the CO<sub>2</sub> complex is close to the edge of order 0, with little margin for baseline removal.

As in the case of H<sub>2</sub>O, we modelled the fluorescence excitation of CO<sub>2</sub> and subsequent cascades in the optically thin approximation following Crovisier (2009), using line strengths and frequencies from the GEISA data base (Jacquinet-Husson et al. 2011). The g-factor for the sum of the two hot bands is 3.3 per cent of that of the main band (Table 2). For the  $\nu_3$  band of <sup>13</sup>CO<sub>2</sub>, synthetic spectra were computed assuming resonant fluorescence and using the HITRAN molecular data base (Rothman et al. 2013). The blend of the two hot bands is about three times more intense than the <sup>13</sup>CO<sub>2</sub>  $\nu_3$  band for a terrestrial <sup>12</sup>C/<sup>13</sup>C ratio of 89.

Fluorescence emission from the  $\nu_3$  band of C<sup>18</sup>O<sup>16</sup>O is not significant and will not be considered in the spectral analysis. This band is centred at 4.29  $\mu\text{m}$ , i.e. close to the wavelength of the hot bands. Assuming the terrestrial <sup>16</sup>O/<sup>18</sup>O ratio of 500, this band is estimated to be nine times less intense than the blend of the two hot bands.

Sample spectra of the CO<sub>2</sub>  $\nu_3$  band in optically thick conditions were calculated using a simple approach. For computing the excitation of the excited vibrational state, we used the escape probability formalism, following Bockelée-Morvan (1987). The intensity



**Figure 6.** VIRTIS-H spectrum in order 2 covering the CH<sub>4</sub>  $\nu_3$  band, obtained by averaging nine data cubes showing well-detected CH<sub>4</sub> emission (SNR > 20). The synthetic spectrum of CH<sub>4</sub> computed for a rotational temperature of 100 K is shown in red. The standard deviations are shown in the bottom of the plot (see Fig. 3). Species other than CH<sub>4</sub> (in particular C<sub>2</sub>H<sub>6</sub> and CH<sub>3</sub>OH) contribute to the signal longward 3.32  $\mu\text{m}$ .

of the individual lines ( $\text{W m}^{-2} \text{sr}^{-1}$ ) was then computed according to

$$I_{ul} = \frac{2hc\nu_{th}}{\lambda^4} \frac{p_u}{w_l p_l - p_u} (1 - e^{-\tau_{ul}}), \quad (1)$$

with the line opacity  $\tau_{ul}$  computed according to


$$\tau_{ul} = \frac{A_{ul} N w_u}{8\pi\lambda^3 \nu_{th}} \left( \frac{p_l}{w_l} - \frac{p_u}{w_u} \right), \quad (2)$$

where  $\lambda$  is the wavelength, the  $u$  and  $l$  indices refer to the upper and lower levels of the transition, respectively, with  $p_i$ ,  $w_i$ , and  $A_{ij}$  corresponding to level populations, statistical weights, and Einstein-A coefficient, respectively. This formula assumes thermal line widths described by the thermal velocity  $\nu_{th}$ .  $N$  is the column density along the LOS. The input parameters of this model are the column density and the rotational temperature. We adjusted these parameters to obtain a CO<sub>2</sub> band shape approximately matching the observed one. Both parameters affect the band shape, that is the width, the relative intensity of the  $P$ ,  $R$  branches, and the depth of the valley between the two branches. Because this model is very simplistic (see exact radiative transfer modelling of Debout et al. 2016), the input parameters that provide good fit to the data will not be discussed.

### 3.3 CH<sub>4</sub>

The  $\nu_3$  band of CH<sub>4</sub> at 3.31  $\mu\text{m}$  presents a  $P$ ,  $Q$ ,  $R$  structure. The strong  $Q$  branch, which is undetectable from ground-based observations due to telluric absorptions, is detected in 75 per cent of the considered VIRTIS-H cubes. The  $R$  lines, shortwards of 3.31  $\mu\text{m}$ , are also well detected when averaging several cubes, with relative intensities consistent with fluorescence modelling (Fig. 6). The discrepancy between the CH<sub>4</sub> fluorescence model and observations longward 3.32  $\mu\text{m}$  seen in Fig. 6 is caused by the blending of CH<sub>4</sub>  $P$  lines with molecular lines from other species. Indeed, ground-based spectral surveys of this spectral region in several comets show number of lines, especially from C<sub>2</sub>H<sub>6</sub> and CH<sub>3</sub>OH (Dello Russo et al. 2006, 2013). The analysis of the 3.32–3.5  $\mu\text{m}$  region, characteristic of C–H stretching modes of organic molecules, will be the object of a forthcoming paper.

Synthetic spectra of the  $\nu_3$  band of CH<sub>4</sub> simulated for various temperatures are shown in Fig. 7. They were computed for resonant fluorescence using the HITRAN data base (Rothman et al. 2013).



**Figure 7.** Fluorescence spectra of methane simulated for various rotational temperatures. The  $A$ ,  $E$ , and  $F$  spin species were assumed to be in equilibrium with the rotational temperature. The spectra are normalized to their maximum intensity; note that the spectral resolution is not adjusted to that of the VIRTIS-H instrument.

Although some observations point to low nuclear spin temperatures for methane (Kawakita et al. 2005), we assumed the distribution of the  $A$ ,  $E$ , and  $F$  spin species to be equilibrated with the rotational temperature. The low SNR does not allow us to study the spin distribution from the VIRTIS-H observations. The  $Q$  branch, which is an unresolved blend of  $\Delta J = 0$  lines of the three spin species, has a  $g$ -factor which is insensitive to the rotation (and spin) temperature for  $T \gtrsim 60$  K. It amounts to 30 per cent of the total band intensity. This branch alone will be used to estimate the CH<sub>4</sub> column density.

### 3.4 OCS and CO

The OCS  $\nu_3$  band at 4.85  $\mu\text{m}$  (C–O stretching mode) has a strength comparable to that of the CO<sub>2</sub>  $\nu_3$  band, allowing its detection even for small column densities in infrared cometary spectra (Dello Russo et al. 1998). In comet 67P, it is detected in most of the data cubes as a faint signal with a peak radiance similar to the strongest water lines nearby (Fig. 3). Our synthetic spectrum follows the model of Crovisier (1987), with a total  $g$ -factor of  $2.8 \times 10^{-3} \text{ s}^{-1}$  ( $r_h = 1$  au) updated from the HITRAN data base (Rothman et al. 2013).

In the same spectral region, with the actual VIRTIS-H spectral resolution, the rovibrational lines of the CO ( $\nu = 1 - 0$ ) band at 4.67  $\mu\text{m}$  are blended with the lines of water (Fig. 4). CO has been detected in comet 67P with the Alice and Microwave Instrument for the Rosetta Orbiter (MIRO) instruments (Feldman, personal

communication; Biver et al., in preparation) with an abundance relative to water of the order of 1 per cent. With a band g-factor of  $2.51 \times 10^{-4} \text{ s}^{-1}$  ( $r_h = 1 \text{ au}$ ), based on fluorescence calculations, CO emission is then expected to be faint in VIRTIS spectra. Therefore, the contribution of this band to the spectrum has been neglected in the investigation of the H<sub>2</sub>O lines. In Fig. 4, the CO spectrum expected for a CO/H<sub>2</sub>O abundance ratio of 1 per cent is superimposed on the H<sub>2</sub>O spectrum. A tentative estimation of the CO/H<sub>2</sub>O abundance based on VIRTIS-H spectra is provided in Section 4.

## 4 COLUMN DENSITY AND ABUNDANCE DETERMINATIONS


### 4.1 Fitting procedure

Observed spectra were analysed using the Levenberg–Marquardt  $\chi^2$  minimization algorithm, describing the spectra as a linear combination of a background continuum (polynomial) and fluorescence molecular emissions, modelled as presented in Section 3 and convolved to the spectral resolution of the analysed data (Section 2.1).

In the fitting procedure, the rotational temperature of the molecules was taken as a fixed parameter. In dense parts of the coma, the rotational states in the ground-vibrational state of the molecules are expected to be thermalized to the gas kinetic temperature, so that  $T_{\text{rot}} = T_{\text{kin}}$  locally. However, since the coma is not isothermal, VIRTIS spectra mix contributions of molecules at various  $T_{\text{rot}}$ , implying a rovibrational structure which depends in a complex way on the temperature and gas distributions, but which should reflect conditions in the denser parts of the coma probed by the VIRTIS LOS. We adopted a simplistic approach, and fixed  $T_{\text{rot}}$  according to available information for comet 67P. Indeed, molecular data obtained by the MIRO instrument onboard *Rosetta* show that the gas kinetic temperature follows in first order  $T_{\text{kin}}[\text{K}] = (4 \text{ [km]}/\rho[\text{km}]) \times 100 \text{ [K]}$  for  $\rho$  in the range 3–25 km, where  $\rho$  is the distance to comet centre (Biver, personal communication). The corresponding temperatures we used for the VIRTIS-H data showing detected CH<sub>4</sub> and OCS emissions are thus 80–130 K. We found that adopting specific temperatures for each data cube does not change significantly the results for CH<sub>4</sub> and OCS since the intensities of the CH<sub>4</sub> Q branch and of the OCS band are not sensitive to the temperature (above 60 K for CH<sub>4</sub>). We assumed  $T_{\text{rot}} = 100 \text{ K}$  for the fluorescence emissions of CH<sub>4</sub> and OCS. For H<sub>2</sub>O, CO<sub>2</sub> hot bands, and <sup>13</sup>CO<sub>2</sub>, the fit was performed for appropriate values of  $T_{\text{kin}}$ .

We used optically thick CO<sub>2</sub> spectra (Section 3.2) that provide reasonable fits to the CO<sub>2</sub>  $\nu_3$  band and to the overall CO<sub>2</sub> complex, with a multiplying coefficient to the synthetic spectrum as a free parameter. The <sup>12</sup>CO<sub>2</sub>/<sup>13</sup>CO<sub>2</sub> relative abundance was assumed to be terrestrial, that is the intensity of the CO<sub>2</sub> hot-bands relative to the <sup>13</sup>CO<sub>2</sub> band was fixed to be equal to 89 times the ratio of the g-factors.

The CO<sub>2</sub> complex was analysed by fitting the whole 4.05–4.8  $\mu\text{m}$  region, hence excluding the OCS band but including H<sub>2</sub>O emission lines. Conversely, the H<sub>2</sub>O and OCS emissions were studied considering the 4.45–5.01  $\mu\text{m}$  region, i.e. excluding the CO<sub>2</sub> complex. CO fluorescence emission was assumed to be negligible (Section 3.4). For the CH<sub>4</sub> band, the fit was performed in the 3.25–3.322  $\mu\text{m}$  region, ignoring the region where P lines are blended with other molecular lines. The fitting algorithm was successful in fitting the CH<sub>4</sub> Q branch. The degree of the polynomial used to fit the baseline was fixed to 2 for the CH<sub>4</sub> study, to 4 for H<sub>2</sub>O and OCS, and to 5 for the CO<sub>2</sub> complex. Smaller polynomial degrees often provided unsatisfactory results for the continuum background observed



**Figure 8.** VIRTIS-H spectra in the 4.2–4.5  $\mu\text{m}$  region (black), and model fits (red) to the CO<sub>2</sub> and <sup>13</sup>CO<sub>2</sub> bands. The continuum background is removed. A: July 29–30, August 1; B: August 10; C: August 16; D: August 19–23; E: August 26; F: September 6–7; G: September 9–13; H: September 24.

in order 0, which is due to dust thermal emission superimposed with some instrumental stray light at the shortest wavelengths (see Section 2.1).

An example of the result of the fitting procedure to the CO<sub>2</sub> complex is presented in Fig. 5, where the individual components are plotted. Other fits for different data sets are illustrated in Fig. 8. For most individual data cubes, the <sup>13</sup>CO<sub>2</sub> band is detected distinctly and the band intensity retrieved from the fit is well estimated. However, for the six first data cubes (July 8–27), the method led to an underestimation of the <sup>13</sup>CO<sub>2</sub> signal (as observed visually): the model fit fell below the observed <sup>13</sup>CO<sub>2</sub> emission. For these six observations, we also computed the intensity in the 4.34–4.42  $\mu\text{m}$  range lying above the background, and the intensities computed by the two methods were taken as providing the range of possible values for the <sup>13</sup>CO<sub>2</sub> band intensities. We note that often the model fails to fully reproduce the intensity of the P branch of <sup>13</sup>CO<sub>2</sub> (some residual is present at 4.4  $\mu\text{m}$ , Fig. 8). The origin of this residual is unclear.

**Table 3.** CO<sub>2</sub>, <sup>13</sup>CO<sub>2</sub> ν<sub>3</sub> band intensities, and <sup>13</sup>CO<sub>2</sub> column density.

Start time (UT)	$I(^{13}\text{CO}_2)$ (10 <sup>-5</sup> W m <sup>-2</sup> sr <sup>-1</sup> )	$I(\text{CO}_2)$ (10 <sup>-5</sup> W m <sup>-2</sup> sr <sup>-1</sup> )	CO <sub>2</sub> ν <sub>3</sub> atten. <sup>a</sup>	$N(^{13}\text{CO}_2)$ (10 <sup>18</sup> m <sup>-2</sup> )
2015-07-08 21:11:00.3	0.90 ± 0.40 <sup>b,c</sup>	16.20 ± 0.09 <sup>b</sup>	3–7	1.75 ± 0.77 <sup>b,c</sup>
2015-07-12 11:46:52.6	–	–	–	–
2015-07-17 08:15:55.9	0.90 ± 0.30 <sup>c</sup>	15.40 ± 0.02	3–7	1.70 ± 0.57 <sup>c</sup>
2015-07-22 15:23:57.9	1.20 ± 0.20 <sup>c</sup>	30.90 ± 0.04	3.4	2.20 ± 0.37 <sup>c</sup>
2015-07-22 21:10:24.7	0.43 ± 0.11 <sup>c</sup>	16.50 ± 0.03	2.3	0.80 ± 0.20 <sup>c</sup>
2015-07-27 23:06:40.5	0.53 ± 0.09 <sup>c</sup>	14.00 ± 0.01	2.8	0.97 ± 0.16 <sup>c</sup>
2015-07-29 21:20:59.8	0.53 ± 0.03	17.90 ± 0.04	2.6	0.95 ± 0.06
2015-07-30 01:47:25.8	0.43 ± 0.03	17.70 ± 0.04	2.2	0.78 ± 0.06
2015-08-01 08:25:16.8	0.87 ± 0.03	22.70 ± 0.04	3.4	1.57 ± 0.05
2015-08-10 23:32:29.0	0.35 ± 0.03	12.80 ± 0.04	2.4	0.62 ± 0.06
2015-08-16 11:56:25.1	1.27 ± 0.05	23.20 ± 0.09	4.9	2.25 ± 0.09
2015-08-19 11:08:06.5	2.34 ± 0.03	32.50 ± 0.05	6.4	4.18 ± 0.06
2015-08-19 15:34:33.4	2.03 ± 0.04	31.30 ± 0.07	5.8	3.62 ± 0.08
2015-08-19 21:20:58.5	2.07 ± 0.05	24.50 ± 0.07	7.5	3.69 ± 0.08
2015-08-20 22:13:06.6	1.51 ± 0.03	16.80 ± 0.04	8.0	2.69 ± 0.05
2015-08-23 17:07:54.5	1.63 ± 0.03	21.40 ± 0.05	6.8	2.92 ± 0.05
2015-08-23 21:29:29.5	1.73 ± 0.03	20.20 ± 0.04	7.6	3.10 ± 0.05
2015-08-26 08:17:52.6	1.59 ± 0.03	18.70 ± 0.04	7.6	2.86 ± 0.06
2015-08-26 10:58:13.4	1.90 ± 0.08	19.30 ± 0.11	8.8	3.44 ± 0.14
2015-09-06 21:25:16.9	0.91 ± 0.04	12.70 ± 0.07	6.4	1.71 ± 0.07
2015-09-07 03:06:16.9	0.96 ± 0.04	11.60 ± 0.07	7.4	1.81 ± 0.07
2015-09-07 07:28:16.8	0.90 ± 0.05	11.00 ± 0.07	7.3	1.70 ± 0.09
2015-09-07 13:09:16.0	0.94 ± 0.03	12.60 ± 0.05	6.7	1.78 ± 0.05
2015-09-09 08:15:16.0	2.03 ± 0.03	20.90 ± 0.04	8.7	3.87 ± 0.06
2015-09-09 15:29:34.0	1.22 ± 0.02	15.40 ± 0.03	7.0	2.32 ± 0.04
2015-09-10 01:37:26.0	0.90 ± 0.02	11.10 ± 0.02	7.2	1.71 ± 0.03
2015-09-13 06:54:44.2	1.44 ± 0.02	16.90 ± 0.02	7.6	2.81 ± 0.04
2015-09-13 11:46:19.3	1.77 ± 0.08	18.50 ± 0.13	8.5	3.45 ± 0.16
2015-09-24 11:55:21.0	0.64 ± 0.01	9.06 ± 0.02	6.3	1.34 ± 0.03
2015-09-27 16:57:54.5	0.32 ± 0.01	4.89 ± 0.01	5.8	0.68 ± 0.03

Notes. <sup>a</sup>Attenuation factor of the CO<sub>2</sub> ν<sub>3</sub> band, corresponding to the ratio between the ν<sub>3</sub> band intensity expected in optically thin conditions and the observed ν<sub>3</sub> band intensity (see text).

<sup>b</sup>Results obtained by averaging the data of July 8 and 12.

<sup>c</sup>Values and uncertainties cover results obtained using either multicomponent fit or the <sup>13</sup>CO<sub>2</sub> band area measured on the spectrum.

Examples of model fits to the H<sub>2</sub>O and OCS emissions are shown in Fig. 3. For this spectral region, we identified a shift by about 1 spectral channel (2.2 nm) between the expected and observed positions of the water lines. The shift is observed specifically for the lines in the 4.6–4.8 μm range, whereas the water lines shortward 4.6 μm suggest an error in the present spectral calibration by 1/2 channel. Therefore, the observed spectra were shifted by one channel when fitting the H<sub>2</sub>O and OCS emissions (also for Fig. 3). However, we did not apply any correction for fitting the CO<sub>2</sub> complex. Earth and Mars spectra taken with VIRTIS-H suggest an error of 1/2 pixel in the spectral registration. We expect further progress in the VIRTIS-H spectral calibration in the future. A close examination of the 67P spectra plotted in Fig. 3 shows some mismatch for the intensity of the H<sub>2</sub>O lines that may deserves further studies. In particular, the line at 4.81 μm is observed in all 67P spectra, and is most likely of cometary origin. Though water emission is expected at this wavelength, the intensity of this line is not consistent with water synthetic spectra (Figs 3 and 4).

A critical point in the analysis is the estimation of uncertainties. For the staring observations, the rms deviations can be estimated for each spectral channel by studying the variation with time of their intensity (computation of variance, then rms). However, for data cubes showing comet signal, the rms computed in this way is larger than statistical instrumental noise, since part of the variation is intrinsic to the comet and/or pointing mode. All uncertainties

provided in the tables and figures include the dispersion due to the varying intrinsic comet signal (including the continuum). In Fig. 3(A), we have superimposed the rms measured on a data cube presenting little comet signal, which is effectively much lower than the one computed with the adopted method. However, based on the fluctuations seen on the spectra, we believe that using instead these rms would underestimate uncertainties.

A number of spectral channels are much noisier than their neighbours (so-called ‘hot pixels’). ‘Hot pixels’ can be spotted in Figs 3, 5, and 6 from their higher errors. There are no hot pixels for the channels covering the CH<sub>4</sub> Q branch (Fig. 6). The fitting of H<sub>2</sub>O lines was performed by ignoring the very few ‘hot pixels’ near the water lines. The OCS band is also affected by hot pixels (see Fig. 3). These were not masked in the fitting analysis. The discrepancy observed at 4.87 μm between model fit and observed OCS band (see Fig. 3) is possibly of instrumental origin.

## 4.2 Results

Band intensities ( $I$ ) and column densities ( $N$ ) obtained from fitting are listed in Table 3 for CO<sub>2</sub>, and in Table 4 for H<sub>2</sub>O, OCS, and CH<sub>4</sub>. Regarding CO<sub>2</sub>, we also provide the attenuation factor  $f_{\text{atten}}$  of the main band which is determined from the CO<sub>2</sub> and <sup>13</sup>CO<sub>2</sub> ν<sub>3</sub> band intensities according to  $f_{\text{atten}} = 89 \times I(^{13}\text{CO}_2)/I(\text{CO}_2)$ . The attenuation factor corresponds to the ratio between the ν<sub>3</sub> band

**Table 4.** H<sub>2</sub>O, CH<sub>4</sub>, and OCS band intensities and column densities.

Start time (UT)		H <sub>2</sub> O		CH <sub>4</sub>		OCS	
		$I$ (10 <sup>-5</sup> W m <sup>-2</sup> sr <sup>-1</sup> )	$N^b$ (10 <sup>20</sup> m <sup>-2</sup> )	$I^a$ (10 <sup>-6</sup> W m <sup>-2</sup> sr <sup>-1</sup> )	$N^c$ (10 <sup>18</sup> m <sup>-2</sup> )	$I^a$ (10 <sup>-6</sup> W m <sup>-2</sup> sr <sup>-1</sup> )	$N^c$ (10 <sup>18</sup> m <sup>-2</sup> )
2015-07-08	21:11:00.3	1.82 ± 0.56	9.25 ± 2.88	–	–	6.87 ± 3.34	1.31 ± 0.63
2015-07-12	11:46:52.6	1.90 ± 0.14	10.10 ± 0.77	–	–	–	–
2015-07-17	08:15:55.9	1.22 ± 0.07	6.33 ± 0.36	–	–	8.82 ± 0.40	1.60 ± 0.07
2015-07-22	15:23:57.9	1.86 ± 0.08	10.00 ± 0.41	3.50 ± 0.13	2.97 ± 0.11	9.50 ± 0.48	1.68 ± 0.09
2015-07-22	21:10:24.7	1.90 ± 0.05	9.79 ± 0.28	–	–	3.49 ± 0.37	0.62 ± 0.06
2015-07-27	23:06:40.5	1.49 ± 0.04	6.48 ± 0.17	1.78 ± 0.10	1.48 ± 0.08	2.03 ± 0.28	0.35 ± 0.05
2015-07-29	21:20:59.8	1.49 ± 0.10	6.62 ± 0.44	–	–	5.00 ± 0.61	0.87 ± 0.11
2015-07-30	01:47:25.8	1.63 ± 0.11	7.27 ± 0.48	1.85 ± 0.17	1.53 ± 0.14	4.93 ± 0.64	0.85 ± 0.11
2015-08-01	08:25:16.8	1.63 ± 0.09	7.10 ± 0.39	2.99 ± 0.35	2.46 ± 0.29	5.93 ± 0.63	1.02 ± 0.11
2015-08-10	23:32:29.0	1.17 ± 0.11	4.19 ± 0.40	1.72 ± 0.29	1.40 ± 0.24	–	–
2015-08-16	11:56:25.1	2.01 ± 0.14	9.21 ± 0.63	2.58 ± 0.25	2.09 ± 0.20	6.43 ± 0.86	1.09 ± 0.15
2015-08-19	11:08:06.5	2.02 ± 0.10	10.20 ± 0.50	7.77 ± 0.16	6.33 ± 0.13	16.50 ± 0.65	2.82 ± 0.11
2015-08-19	15:34:33.4	2.42 ± 0.13	11.60 ± 0.64	5.40 ± 0.18	4.40 ± 0.15	16.90 ± 0.79	2.89 ± 0.13
2015-08-19	21:20:58.5	1.97 ± 0.13	8.90 ± 0.61	4.93 ± 0.22	4.02 ± 0.18	13.80 ± 0.79	2.36 ± 0.14
2015-08-20	22:13:06.6	2.03 ± 0.09	8.32 ± 0.38	6.83 ± 0.17	5.57 ± 0.14	9.54 ± 0.53	1.63 ± 0.09
2015-08-23	17:07:54.5	1.89 ± 0.08	8.27 ± 0.33	4.52 ± 0.18	3.71 ± 0.15	9.03 ± 0.48	1.55 ± 0.08
2015-08-23	21:29:29.5	1.65 ± 0.08	7.44 ± 0.36	5.53 ± 0.24	4.54 ± 0.20	8.07 ± 0.51	1.39 ± 0.09
2015-08-26	08:17:52.6	1.63 ± 0.08	6.87 ± 0.36	4.92 ± 0.41	4.06 ± 0.34	6.01 ± 0.70	1.04 ± 0.12
2015-08-26	10:58:13.4	2.14 ± 0.23	9.30 ± 0.99	7.38 ± 0.36	6.09 ± 0.30	7.73 ± 1.30	1.34 ± 0.23
2015-09-06	21:25:16.9	1.28 ± 0.12	5.25 ± 0.49	2.04 ± 0.22	1.76 ± 0.19	–	–
2015-09-07	03:06:16.9	1.37 ± 0.11	5.64 ± 0.43	–	–	3.91 ± 0.64	0.71 ± 0.12
2015-09-07	07:28:16.8	0.89 ± 0.15	3.64 ± 0.60	2.23 ± 0.25	1.93 ± 0.22	–	–
2015-09-07	13:09:16.0	1.30 ± 0.09	5.35 ± 0.35	3.71 ± 0.19	3.20 ± 0.16	–	–
2015-09-09	08:15:16.0	1.60 ± 0.09	8.22 ± 0.49	3.33 ± 0.24	2.90 ± 0.21	8.76 ± 0.59	1.59 ± 0.11
2015-09-09	15:29:34.0	1.56 ± 0.06	7.42 ± 0.30	4.12 ± 0.12	3.59 ± 0.11	6.13 ± 0.41	1.12 ± 0.08
2015-09-10	01:37:26.0	1.23 ± 0.04	4.93 ± 0.18	–	–	3.56 ± 0.34	0.65 ± 0.06
2015-09-13	06:54:44.2	1.47 ± 0.06	7.13 ± 0.29	3.71 ± 0.13	3.30 ± 0.12	7.40 ± 0.39	1.38 ± 0.07
2015-09-13	11:46:19.3	2.11 ± 0.21	10.00 ± 1.00	–	–	7.41 ± 1.13	1.38 ± 0.21
2015-09-24	11:55:21.0	0.81 ± 0.04	3.68 ± 0.19	4.07 ± 0.13	3.88 ± 0.12	–	–
2015-09-27	16:57:54.5	0.56 ± 0.04	2.41 ± 0.18	2.15 ± 0.13	2.10 ± 0.12	–	–

Notes. <sup>a</sup>Only values obtained from detection are given.

<sup>b</sup>Derived assuming a gas kinetic temperature varying with distance to comet centre ( $\rho$ ) following  $T_{\text{kin}} = (4/\rho[\text{km}]) \times 100$  K (with  $T_{\text{rot}} = T_{\text{kin}}$ ) and a g-factor of  $1.19 \times 10^{-5} \text{ s}^{-1}$  at 1 au from the Sun pertaining to the 4.45–5.03  $\mu\text{m}$  range.

<sup>c</sup>Derived assuming  $T_{\text{rot}} = 100$  K in the fluorescence model.

intensity expected in optically thin conditions and the observed  $\nu_3$  band intensity. This factor reaches values of 2–9. The varying correlation between CO<sub>2</sub> band intensity and attenuation factor is expected from radiative transfer calculations, because of azimuthal variations of local excitation related to the unidirectionality of the excitation source and to the 3D structure of the gas velocity field (Gersch & A’Hearn 2014; Debout et al. 2016).


Column densities provide partial information of the overall activity of the comet because (i) the FOV is sampling a small fraction of the coma at a location in the gaseous fan which is different each time (Section 2.3); (ii) 67P’s nucleus shape and outgassing behaviour is complex, and we indeed observe rotation-induced variations of column densities (see results for August 19). The evolution of the water column density in VIRTIS-H FOV is plotted in Fig. 9 for  $\rho = 4$  km. We corrected for the different distances from comet centre of the FOV assuming a  $1/\rho$  variation (but we did not correct for possible gas velocity variations). The low H<sub>2</sub>O column density observed for September 24 and 27 (the last two data points) is likely related to the small phase angle, as already discussed in Section 2.2. The measured column densities are consistent with those measured with the MIRO instrument (Biver et al., in preparation).

In order to constrain somewhat the CO abundance relative to water from VIRTIS-H spectra, spectral fitting of the 4.45–5.01  $\mu\text{m}$  region with a model including CO fluorescence emission, in

addition to H<sub>2</sub>O and OCS emissions, has been performed. Retrieved values are between 1 and 2 per cent, and consistent with Alice and MIRO results (Feldman, personal communication; Biver et al., in preparation). However, we estimate that further analyses on spectra obtained with an improved calibration are required to claim a CO detection in VIRTIS-H spectra.


An increase of water production a few days after perihelion is suggested from the column density, which is not related to the observing geometry (i.e. to an FOV positioned in a denser part of the gas fan at that time, Fig. 9A). This increase is consistent with the analysis of the VIRTIS-H H<sub>2</sub>O raster maps obtained regularly from July to November, which show that the water fan had its maximum brightness 6–7 d after perihelion (Bockelée-Morvan et al. 2016). Therefore, the measured relative abundances should be representative of the composition of the material released from the main outgassing areas in the July–September time frame. Concomitant with the 50 per cent increase of the water column density, a strong increase of the column densities (by factors of 2–3) of CO<sub>2</sub>, CH<sub>4</sub>, and OCS is also observed (Figs 9B–D).

Fig. 10 presents column density ratios, with water taken as the reference (hereafter referred to as relative abundances). A large increase of the CO<sub>2</sub> to H<sub>2</sub>O abundance ratio is measured, starting after perihelion, reaching values in the range 30–40 per cent from August 19 (i.e. 6 d after perihelion) and thereafter. This



**Figure 9.** Column densities of H<sub>2</sub>O, CO<sub>2</sub>, CH<sub>4</sub>, and OCS as a function of date with respect to perihelion (A)–(D), and position angles of the South Pole direction and FOV (E). (A)–(D) Measured column densities (dots with error bar) are rescaled to a distance of  $\rho = 4$  km assuming a  $1/\rho$  variation; the latitude of the subsolar point is plotted as a dashed line in plot (A). (E) The PA of the south direction is shown as a black line; the PA of the FOV are plotted with crosses; the projected comet–Sun direction at PA = 270° is indicated as a dashed line.

increase in the CO<sub>2</sub>/H<sub>2</sub>O abundance coincides with the increase in water production. The same trend is observed for CH<sub>4</sub>, whereas the evolution of the OCS abundance is somewhat chaotic, reaching however its peak value on August 19. Averaging data, there is typically a factor of 1.5 increase between OCS abundances measured pre-perihelion and post-perihelion (Table 5). Noteworthy, the investigated post-perihelion period corresponds to the illumination of



**Figure 10.** Column density ratios relative to water as a function of day with respect to perihelion.

**Table 5.** Abundances relative to water.

Molecule	Pre-perihelion	Post-perihelion
	2015 Jul. 8–Aug. 10 (%)	2015 Aug. 16–Sep. 27 (%)
CO <sub>2</sub>	14	32
CH <sub>4</sub>	0.23	0.47
OCS	0.12	0.18

the most southern latitudes (latitude of the subsolar point  $\sim -50^\circ$ , Fig. 9).

For the discussion in Section 5, we will assume that column density ratios are representative of production rate ratios. This is a good approximation if the spatial distributions of the molecules are similar. However, as judged from the brightness distribution of the CO<sub>2</sub> and H<sub>2</sub>O optically thick bands (Section 2.3), the angular

width of the CO<sub>2</sub> fan is smaller than that of the H<sub>2</sub>O fan. Therefore, the CO<sub>2</sub>/H<sub>2</sub>O production rate ratio from the most active regions is possibly underestimated.

## 5 DISCUSSION

The distributions of H<sub>2</sub>O and CO<sub>2</sub> in the inner coma of 67P have been measured by several *Rosetta* instruments since 2014, allowing the investigation of their local, diurnal, and seasonal variations. During pre-equinox, the water outgassing was found to follow solar illumination, with, however, an excess of production from the Hapi region in the neck/North Pole area, which photometric properties suggest enrichment in surface ice (De Sanctis et al. 2015; Fornasier et al. 2015a; Filacchione et al. 2016a). The CO<sub>2</sub>/H<sub>2</sub>O column density ratio above the illuminated Hapi region was measured to be small. Ratios in the range 1–3 per cent were determined from VIRTIS data for the 2014 November–2015 April period (Bockelée-Morvan et al. 2015; Migliorini et al. 2016). Similar values were measured above other regions of the Northern hemisphere (Bockelée-Morvan et al. 2015; Migliorini et al. 2016). These values are consistent with measurements at 3 au from the Sun made by ROSINA (Le Roy et al. 2015). On the other hand, a large CO<sub>2</sub> outgassing from the non-illuminated Southern hemisphere was observed, indicating a strong dichotomy between the two hemispheres with subsurface layers much richer in CO<sub>2</sub> in the southern regions (Luspay-Kuti et al. 2015; Fink et al. 2016; Migliorini et al. 2016). From annulus measurements surrounding the comet, Fink et al. (2016) inferred a CO<sub>2</sub>/H<sub>2</sub>O total production rate ratio of 3–5 per cent from data obtained in 2015 February and April. This ratio is not diagnostic of the relative amount of gases released from a specific region, because of the disparate origin of the two molecules. ROSINA measurements showed that the distribution of polar molecules is correlated with the H<sub>2</sub>O distribution (HCN, CH<sub>3</sub>OH), whereas that of apolar and more volatile species (CO, C<sub>2</sub>H<sub>6</sub>) is correlated with the CO<sub>2</sub> distribution (Luspay-Kuti et al. 2015). However, apolar CH<sub>4</sub> displayed an intriguing distinct behaviour from both CO<sub>2</sub> and water (Luspay-Kuti et al. 2015). The CH<sub>4</sub>/CO<sub>2</sub> ratio from the Northern and Southern hemispheres at 3 au from the Sun was estimated to be 5 and 0.7 per cent, respectively, from measurements with ROSINA (Le Roy et al. 2015). As for the CH<sub>4</sub>/H<sub>2</sub>O ratio it was estimated to 0.1 per cent above the Northern summer hemisphere (Le Roy et al. 2015). At 3 au from the Sun, 67P was releasing small amounts of OCS: OCS/H<sub>2</sub>O of 0.02 per cent above the Northern hemisphere and OCS/CO<sub>2</sub> of 0.1 per cent above the Southern hemisphere.

In this paper, we investigated outgassing from the southern regions when illuminated by the Sun. These regions were clearly much more productive than during the southern winter time. Using column densities at 4 km from the surface as a proxy of activity,  $N(\text{CO}_2)$  increased typically from  $\sim 10^{19} \text{ m}^{-2}$  at  $r_h = 1.9 \text{ au}$  (Migliorini et al. 2016) to a few  $10^{20} \text{ m}^{-2}$  at perihelion time (Table 3). The CH<sub>4</sub>/CO<sub>2</sub> ratio remained within a factor of 2; the value measured at 3 au, whereas the OCS/CO<sub>2</sub> ratio increased by factors of 6–9. Comparing now the relative amounts (with respect to water) of gases released from the two hemispheres when illuminated (keeping in mind the different heliocentric distances), the Southern hemisphere is up to a factor of 10 more productive in CO<sub>2</sub> and OCS relative to water, and by a factor of 2–5 more productive in CH<sub>4</sub>. Table 6 summarizes relative abundances measured above the two hemispheres at different seasons.

This seasonal variation in relative molecular abundances is related to the strong differences in illumination conditions experienced by the two hemispheres. The Northern hemisphere experiences a long

**Table 6.** Seasonal variations of abundance ratios (in per cent) measured in 67P.

Ratio (%)	North Summer <sup>a</sup>	Winter <sup>b</sup>	South Summer <sup>c</sup>	Other comets <sup>d</sup>
CO <sub>2</sub> /H <sub>2</sub> O	1–3	80	14–32	2.5–30
CH <sub>4</sub> /H <sub>2</sub> O	0.13	0.56	0.23–0.47	0.12–1.5
OCS/H <sub>2</sub> O	0.017	0.098	0.12–0.18	0.03–0.4
CH <sub>4</sub> /CO <sub>2</sub>	5	0.7	1.5–1.6	
OCS/CO <sub>2</sub>	0.7	0.1	0.6–0.9	

Notes. <sup>a</sup>Values at  $r_h = 3 \text{ au}$  from Le Roy et al. (2015), except for CO<sub>2</sub> measured at 1.8–2.9 au (Bockelée-Morvan et al. 2015; Migliorini et al. 2016).

<sup>b</sup>Values at  $r_h = 3 \text{ au}$  from Le Roy et al. (2015).

<sup>c</sup>Values from this work at  $r_h = 1.25\text{--}1.36 \text{ au}$ .

<sup>d</sup>Biver & Bockelée-Morvan (2016), Ootsubo et al. (2012), McKay et al. (2016), Mumma & Charnley (2011).

summer but at large heliocentric distances, implying low sublimation rates and very low surface ablation. Though 67P surface and subsurface layers present a low thermal inertia, a stratification in the ice composition is expected, with the more volatile species residing in deeper layers. The residence level of the volatile ices may be at a few tens centimetres from the surface, down to several metres, depending on the volatility of the ice (CO<sub>2</sub>, OCS, CH<sub>4</sub> in increasing order of volatility), the dust mantle thickness, thermal inertia, porosity, and illumination history (Marboeuf & Schmitt 2014). The detection of low levels of CO<sub>2</sub> production from the Northern hemisphere indicates that probably most of the CO<sub>2</sub> ice was below the level of the thermal wave, with only a small portion of CO<sub>2</sub> ice reached by the heat. Based on modelling, the CO<sub>2</sub>/H<sub>2</sub>O ratio measured in the Northern hemisphere during summer (1–3 per cent) should be lower than the nucleus undifferentiated value (Marboeuf & Schmitt 2014). In other words, values measured in the Northern hemisphere are not original, but the result of the devolatilization of the uppermost layers.

The increased gaseous activity of comet 67P as it approached the Sun led to the removal of devolatilized dust, thereby exposing less altered material to the Sun. Evidence for rejuvenation of the surface of 67P is given by a significant increase of the single scattering albedo and more bluish colours as 67P approached the Sun (Ciarnello 2016; Filacchione et al. 2016a). The absence of wide spread smooth or dust-covered terrains in the Southern hemisphere, together with the presence of large bright ice-rich areas (Fornasier et al. 2015b; El-Maarry et al. 2016) are lines of evidence that this hemisphere was subjected to strong ablation during the perihelion period. Models of the thermal evolution of 67P predict that the depth of ablation should have reached the underlayers where volatile ices are present (De Sanctis et al. 2010b; Marboeuf & Schmitt 2014). The observed enhancement of the CO<sub>2</sub>/H<sub>2</sub>O, CH<sub>4</sub>/H<sub>2</sub>O, and OCS/H<sub>2</sub>O abundance ratios could be the result of this ablation. Once the removal of devolatilized layers has proceeded, sustained dust removal due to the sublimation of water ice maintained volatile-rich layers near the surface, as suggested by the abundance ratios which remained high long after perihelion (Fig. 10). This requires the erosion velocity to be comparable or larger than the propagation velocity of the diurnal heat, a property expected near perihelion for low thermal inertia material (Gortsas et al. 2011). Should ablation have reached non-differentiated layers, abundances relative to water measured in the coma would then be representative of the nucleus initial ice composition. Simulations performed for comet 67P by Marboeuf & Schmitt (2014) (though not considering the large

obliquity of the spin axis) indeed predict a CO<sub>2</sub>/H<sub>2</sub>O production rate ratio near perihelion similar to the primitive composition of the nucleus for active regions not covered by a thick dust mantle. This model includes diurnal and seasonal recondensation of gases in the colder layers. A result of these simulations is that this process is ineffective in altering the CO<sub>2</sub>/H<sub>2</sub>O production rate ratio from the Southern hemisphere due to the strong erosion. Further modelling of 67P activity may provide alternative interpretations.

OCS is only slightly more volatile than CO<sub>2</sub> with a sublimation temperature of 57 K to be compared to 72 K for the latter species (Yamamoto 1985). Therefore, we should expect similar production curves, if these species are present in icy forms. The mean OCS/CO<sub>2</sub> ratios measured pre- and post-perihelion in the 2015 July 7 to September 27 period are effectively similar (0.6–0.9 per cent, Table 6) and comparable to the value measured above the Northern hemisphere at 3 au from the Sun by ROSINA (Le Roy et al. 2015). However, the OCS/CO<sub>2</sub> ratio measured above the Southern hemisphere at 3 au from the Sun is seven times lower (Le Roy et al. 2015). Possibly, this means that the thermal wave did not reach OCS-rich layers. Also, looking to the individual VIRTIS data obtained in the perihelion period, fluctuations in the OCS/CO<sub>2</sub> ratio are observed, possibly related to compositional or structural heterogeneities. A better understanding of the differences in OCS and CO<sub>2</sub> outgassing would need a larger data set (as that obtained by ROSINA).

As in the case of CO<sub>2</sub>, the observed large increase in CH<sub>4</sub> column density and CH<sub>4</sub>/H<sub>2</sub>O ratio at perihelion is consistent with a CH<sub>4</sub> outgassing front near the surface. The evolution of the sublimation interface of CH<sub>4</sub> pure ice, which is more volatile than CO<sub>2</sub> ice, has been examined by Marboeuf & Schmitt (2014). In this model, the ablation does not reach the CH<sub>4</sub> ice front, and no significant enhancement in CH<sub>4</sub> production is expected at perihelion. However, a large increase in CH<sub>4</sub> production would occur for CH<sub>4</sub> trapped in amorphous ice as the ablation reaches the crystallization front, or for CH<sub>4</sub> encaged in a clathrate hydrate structure. In the model of Marboeuf & Schmitt (2014), an obliquity of 0° is assumed, and results are provided for equatorial latitudes. Results obtained considering the 52° obliquity of 67P spin axis are given by De Sanctis et al. (2010b) for CO and CO<sub>2</sub> present in icy form. Contrary to Marboeuf & Schmitt (2014), this model predicts a strong outgassing of both CO<sub>2</sub> and CO in the Southern hemisphere at perihelion. This is because the important erosion that takes place in these regions during their short summer maintains the sublimation interface of volatile species as CO and CH<sub>4</sub> close to the surface.

The CH<sub>4</sub>/H<sub>2</sub>O ratio exhibits much less contrasting regional and seasonal variations than observed for CO<sub>2</sub> (Table 6). However, the same trend is observed. The maximum value is for south/winter, the minimum value is for north/summer, whereas the intermediate value is for south/summer. This might suggest that they are in a similar form and located in layers close to each other. Should CH<sub>4</sub> and CO<sub>2</sub> be both present in icy form, then less contrasted variations are expected for CH<sub>4</sub> because of its smaller sublimation temperature. Alternatively, CH<sub>4</sub> could be trapped in amorphous water ice inside 67P nucleus and released during ice crystallization, which occurs at a temperature a little below that of water ice sublimation. This could explain the small difference in CH<sub>4</sub>/H<sub>2</sub>O ratios measured above the two hemispheres during summer time. However, this scenario cannot explain the significant CH<sub>4</sub> outgassing from the non-illuminated hemisphere at 3 au from the Sun (Luspay-Kuti et al. 2015). Luspay-Kuti et al. (2016) propose the presence of CH<sub>4</sub> clathrate hydrates to explain the behaviour observed by ROSINA.

The column densities of H<sub>2</sub>O, CO<sub>2</sub>, CH<sub>4</sub>, and OCS show an abrupt increase at about 6 d after perihelion (Fig. 9). This is an

interesting coincidence with the results of the thermal model of Keller et al. (2015) applied to the real shape of 67P, which leads to a time lag of 6 d caused by the asymmetry of the subsolar latitude variation with respect to perihelion. However, this predicted maximum is quite flat and does not fit to the sudden increase we measured. An alternative explanation could be that the sublimation front is at some depth  $x$  below the surface and is reached by the maximum insolation energy of perihelion with some delay. The time-scale  $\tau$  of thermal conduction is defined as (Gortsas et al. 2011)

$$\tau = \rho c x^2 / k, \quad (3)$$

where  $\rho$  and  $c$  are the density and specific heat of the surface material, respectively, and  $k$  is its thermal conductivity. Using  $\tau = 6$  d ( $\sim 500\,000$  s) and standard thermophysical parameters for 67P (Shi et al. 2016) of  $\rho = 500$  kg m<sup>-3</sup>,  $c = 600$  J kg<sup>-1</sup> K<sup>-1</sup>, and  $k = 0.005$  W m<sup>-1</sup> K<sup>-1</sup> one gets a depth of about 7 cm. But also in this model one would expect a gradual increase of the production rates after perihelion. It is interesting to note that all measured species show nearly the same time lag although having different volatilities. According to Marboeuf & Schmitt (2014), fig. 4, none of the studied outgassing profiles (amorphous, clathrate, crystalline, and mixed) shows a similar behaviour as measured here. A plausible explanation could be that a volatile-poor insulating surface layer is quickly eroded near perihelion leading to a strong increase of activity of several volatiles in short time.

Production rate ratios relative to water of CO<sub>2</sub>, OCS, and CH<sub>4</sub> have been measured in numerous comets, and display variations by a factor of up to  $\sim 10$  (Table 6). The CO<sub>2</sub>/H<sub>2</sub>O ratio measured post-perihelion in 67P indicates that this comet is CO<sub>2</sub> rich. The OCS/H<sub>2</sub>O ratio is in the range of values measured in other comets, though the post-perihelion value is slightly above the mean value of  $\sim 0.1$  per cent (Biver & Bockelée-Morvan 2016). The CH<sub>4</sub>/H<sub>2</sub>O ratio in 67P is also within the range the values measured in other comets, but is by a factor of 2 lower than the ‘typical’ value of  $\sim 1$  per cent (Mumma & Charnley 2011).

The VIRTIS-H observations are consistent with a small CO/H<sub>2</sub>O production rate ratio (a few per cent at most) from the Southern hemisphere. This is in the range of values measured for Jupiter-family comets (JFC; see e.g. A’Hearn et al. 2012). The number of comets for which both CO and CO<sub>2</sub> abundances relative to water have been measured is very limited. Among the few JFC comets of the sample, only the small lobe of 103P/Hartley 2 investigated by the *EPOXI* mission have similarities with 67P Southern hemisphere, that is a high CO<sub>2</sub>/H<sub>2</sub>O ratio and a low CO/H<sub>2</sub>O ratio. The CO/CO<sub>2</sub> ratio is 0.01 (A’Hearn et al. 2012, and references therein), to be compared to the value of  $\sim 0.03$  measured above 67P Southern hemisphere, assuming CO/H<sub>2</sub>O = 1 per cent (Biver et al., personal communication).

## 6 CONCLUSION

This paper focused on the perihelion period during which the southern regions of comet 67P were heavily illuminated. The measured abundance ratios of CO<sub>2</sub>, CH<sub>4</sub>, and OCS and reported trends show that seasons play an important role in comet outgassing. The high CO<sub>2</sub>/H<sub>2</sub>O ratio measured in the coma is plausibly reflecting the pristine ratio of 67P nucleus, indicating a CO<sub>2</sub>-rich comet. On the other hand, the low CO<sub>2</sub>/H<sub>2</sub>O values measured above the illuminated Northern hemisphere are most likely not original, but the result of the devolatilization of the uppermost surface layers. The VIRTIS-H instrument acquired infrared spectra of H<sub>2</sub>O and CO<sub>2</sub>

during the whole *Rosetta* mission. Analysis of the whole data set will certainly provide further information on outgassing processes taking place on 67P's nucleus.

## ACKNOWLEDGEMENTS

The authors would like to thank the following institutions and agencies, which supported this work: Italian Space Agency (ASI – Italy), Centre National d'Études Spatiales (CNES – France), Deutsches Zentrum für Luft- und Raumfahrt (DLR – Germany), National Aeronautic and Space Administration (NASA – USA). VIRTIS was built by a consortium from Italy, France, and Germany, under the scientific responsibility of the Istituto di Astrofisica e Planetologia Spaziali of INAF, Rome (Italy), which leads also the scientific operations. The VIRTIS instrument development for ESA has been funded and managed by ASI, with contributions from Observatoire de Meudon financed by CNES and from DLR. The instrument industrial prime contractor was former Officine Galileo, now Selex ES (Finmeccanica Group) in Campi Bisenzio, Florence, Italy. The authors wish to thank the *Rosetta* Science Ground Segment and the *Rosetta* Mission Operations Centre for their fantastic support throughout the early phases of the mission. The VIRTIS calibrated data shall be available through the ESA's Planetary Science Archive (PSA) website. With fond memories of Angioletta Coradini, conceiver of the VIRTIS instrument, our leader and friend. DB-M thanks G. Villanueva for providing H<sub>2</sub>O fluorescence calculations.

## REFERENCES

- A'Hearn M. F. et al., 2012, *ApJ*, 758, 29  
 Barber R. J., Tennyson J., Harris G. J., Tolchenov R. N., 2006, *MNRAS*, 368, 1087  
 Biver N., Bockelée-Morvan D., 2016, *Astronomy in Focus XXIXA*, in press  
 Biver N. et al., 2015a, *Sci. Adv.*, 1, e1500863  
 Biver N. et al., 2015b, *A&A*, 583, A3  
 Bockelée-Morvan D., 1987, *A&A*, 181, 169  
 Bockelée-Morvan D., Crovisier J., 1989, *A&A*, 216, 278  
 Bockelée-Morvan D., Crovisier J., Mumma M. J., Weaver H. A., 2004, in Festou M. C., Keller H. U., Weaver H. A., eds, *Comets II*. Univ. Arizona Press, Tuscan, AZ, p. 391  
 Bockelée-Morvan D. et al., 2015, *A&A*, 583, A6  
 Bockelée-Morvan D. et al., 2016, 50th ESLAB Symposium From Giotto to Rosetta, Leiden  
 Capaccioni F. et al., 2015, *Science*, 347, aaa0628  
 Ciarnello M., 2016, *MNRAS*, in press  
 Cochran A. L. et al., 2015, *Space Sci. Rev.*, 197, 9  
 Coradini A. et al., 2007, *Space Sci. Rev.*, 128, 529  
 Crovisier J., 1987, *A&AS*, 68, 223  
 Crovisier J., 2009, in Sterken Käufel H. U., eds, *Deep Impact as a World Observatory Event: Synergies in Space, Time, and Wavelength*. Springer-Verlag, Berlin, p. 249  
 Debout V., 2015, PhD thesis, Université Paris-Diderot  
 Debout V., Bockelée-Morvan D., Zakharov V., 2016, *Icarus*, 265, 110  
 Dello Russo N., DiSanti M. A., Mumma M. J., Magee-Sauer K., Rettig T. W., 1998, *Icarus*, 135, 377  
 Dello Russo N., Mumma M. J., DiSanti M. A., Magee-Sauer K., Gibb E. L., Bonev B. P., McLean I. S., Xu L.-H., 2006, *Icarus*, 184, 255  
 Dello Russo N. et al., 2013, *Icarus*, 222, 707  
 De Sanctis M. C., Capria M. T., Coradini A., 2005, *A&A*, 444, 605  
 De Sanctis M. C., Lasue J., Capria M. T., 2010a, *AJ*, 140, 1  
 De Sanctis M. C., Lasue J., Capria M. T., Magni G., Turrini D., Coradini A., 2010b, *Icarus*, 207, 341  
 De Sanctis M. C. et al., 2015, *Nature*, 525, 500  
 Drossart P. et al., 2000, in Strojnik M., Andresen B. F., eds, *Proc. SPIE Vol. 4131, Infrared Spaceborne Remote Sensing VIII*. SPIE, Bellingham, p. 78  
 El-Maarry M. R., Thomas N., Pajola M., Massironi M., Marchi S., Keller H. U., Besse S., 2016, *Lunar Planet. Sci. Conf.*, 47, 2108  
 Feldman P. D. et al., 2015, *A&A*, 583, A8  
 Filacchione G. et al., 2016a, *Icarus*, 274, 334  
 Filacchione G. et al., 2016b, *Science*, in press  
 Fink U. et al., 2016, *Icarus*, 277, 78  
 Fornasier S. et al., 2015a, *A&A*, 583, A30  
 Fornasier S. et al., 2015b, *Am. Astron. Soc.*, DPS Meeting, 47, 500.06  
 Fougere N. et al., 2016a, *A&A*, 588, A134  
 Fougere N. et al., 2016b, *MNRAS*, in press  
 Gersch A. M., A'Hearn M. F., 2014, *ApJ*, 787, 36  
 Gortsas N., Kühr E., Motschmann U., Keller H. U., 2011, *Icarus*, 212, 858  
 Gulkis S., 2014, *Cent. Bureau Electron. Telegrams*, 3912, 1  
 Gulkis S. et al., 2015, *Science*, 347, aaa0709  
 Hässig M. et al., 2015, *Science*, 347, aaa0276  
 Jacquinet-Husson N. et al., 2011, *J. Quant. Spectrosc. Radiat. Transf.*, 112, 2395  
 Jorda L. et al., 2016, *Icarus*, 277, 257  
 Kawakita H., Watanabe J.-I., Furusho R., Fuse T., Boice D., 2005, *ApJ*, 623, L49  
 Keller H. U. et al., 2015, *A&A*, 583, A34  
 Le Roy L. et al., 2015, *A&A*, 583, A1  
 Luspay-Kuti A. et al., 2015, *A&A*, 583, A4  
 Luspay-Kuti A. et al., 2016, *Sci. Adv.*, 2, e150178  
 McKay A. J. et al., 2015, *Icarus*, 250, 504  
 McKay A. J., Kelley M. S. P., Cochran A. L., Bodewits D., DiSanti M. A., Russo N. D., Lisse C. M., 2016, *Icarus*, 266, 249  
 Marboeuf U., Schmitt B., 2014, *Icarus*, 242, 225  
 Migliorini A. et al., 2016, *A&A*, 589, A45  
 Mumma M. J., Charnley S. B., 2011, *ARA&A*, 49, 471  
 Ootsubo T. et al., 2012, *ApJ*, 752, 15  
 Pätzold M. et al., 2016, *Nature*, 530, 63  
 Rothman L. S. et al., 2013, *J. Quant. Spectrosc. Radiat. Transf.*, 130, 4  
 Schulz R., 2012, *Planet. Space Sci.*, 66, 1  
 Schwenke D. W., Partridge H., 2000, *J. Chem. Phys.*, 113, 6592  
 Shi X. et al., 2016, *A&A*, 586, A7  
 Sierks H. et al., 2015, *Science*, 347, aaa1044  
 Villanueva G. L., Mumma M. J., Bonev B. P., Novak R. E., Barber R. J., DiSanti M. A., 2012, *J. Quant. Spectrosc. Radiat. Transf.*, 113, 202  
 Vincent J.-B. et al., 2016, *A&A*, 587, A14  
 Yamamoto T., 1985, *A&A*, 142, 31

This paper has been typeset from a  $\text{\TeX}/\text{\LaTeX}$  file prepared by the author.