



HAL
open science

Effect of hot isostatic pressing on the critical defect size distribution in AlSi7Mg0.6 alloy obtained by selective laser melting

Matthieu Bonneric, Charles Brugger, Nicolas Saintier

► To cite this version:

Matthieu Bonneric, Charles Brugger, Nicolas Saintier. Effect of hot isostatic pressing on the critical defect size distribution in AlSi7Mg0.6 alloy obtained by selective laser melting. *International Journal of Fatigue*, 2020, 140, pp.105797. 10.1016/j.ijfatigue.2020.105797 . hal-02924060

HAL Id: hal-02924060

<https://hal.science/hal-02924060>

Submitted on 27 Aug 2020

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

Effect of hot isostatic pressing on the critical defect size distribution in AlSi7Mg0.6 alloy obtained by selective laser melting

Matthieu Bonneric^{a,b,*}, Charles Brugger^a, Nicolas Saintier^a

^a Arts et Metiers Institute of Technology, University of Bordeaux, CNRS, Bordeaux INP, INRAE, HESAM Université, I2M Bordeaux, F-33400 Talence, France

^b IRT Saint Exupéry, B612 - 3 rue Tarfaya- CS 34436, 31405 Toulouse cedex, France

Keywords:

Additive manufacturing
Al-Si alloys
Defects
Fatigue

This study focuses on the influence of defect density on the sizes of the critical defects responsible for fatigue failure in AlSi7Mg0.6 alloy produced by Selective Laser Melting. Samples having similar microstructures and different defect densities were obtained combining Hot Isostatic Pressing and T6 treatments. Defect populations were analyzed using X-ray tomography, and fatigue tests were performed to determine the critical defect distributions. A method allowing for the prediction of these distributions from the CT scan data was then proposed, and discussed with regard to the actual distributions obtained from the fatigue tests.

1. Introduction

Over the past ten years, there was an ongoing effort to improve the quality of the parts produced by Selective Laser Melting (SLM), in particular for the Al-Si alloys [1–3]. However, in these materials the fatigue damage remains driven by defects [4–6], whose generation during the manufacturing process cannot be fully avoided despite the serious improvements in the laser powder-bed fusion technologies. In Al-Si alloys, these process induced defects usually correspond to lack-of-fusion defects, which have tortuous shapes and result from un-melted areas, and to gas pores resulting from the entrapment of gas bubbles [7,8].

The influence of defects on the fatigue behavior is a well-known issue on which there is a substantial literature. In particular, it is well established that the defect size is one of the key parameters governing the fatigue strength of metals [9,10]. Several studies demonstrated that the fatigue strength of defective materials can be properly depicted using the Kitagawa–Takahashi diagram [11–13], which describes the evolution of the fatigue strength as a function of the sizes of the defects that were responsible for fatigue failure. These approaches are based on fracture mechanics, and consider the defects as cracks that are likely to propagate under a cyclic loading [14,15].

As the prediction of the fatigue strength requires the value of the critical defect size, several methods were proposed to assess the probability related to the size of the largest defect contained in the volume V of any loaded part. These methods are usually based on the statistical

analyses of the defect size distributions obtained from metallography or X-ray tomography analyses. A common procedure consists in the observation of N distinct metallographic cross-sections having the same area S_0 , and the measurement of the size of the largest defect found in each section. The different measurements are then used to build and identify a Large Extreme Value Distribution (LEVD) associated to the defect size [16,17]. This statistical law, which is associated to the inspected section S_0 , can then be manipulated to predict the LEVD associated to the volume V of the loaded part by accounting for volume effects [18]. More recently, a similar concept of extreme value statistics was applied on CT scan observations to assess the probability related to the size of the largest defect contained in the volume V of AlSi10Mg parts produced by SLM [19].

However, the size is not the only parameter to consider in the identification of the critical defects. The position of the defect with respect to the surface of the loaded part is also an important issue [10], and the critical fatigue cracks usually initiate at surface or subsurface defects in the High Cycle Fatigue (HCF) regime, even in the presence of larger internal defects [20–22]. This predominance of failures originating from surface or subsurface defects was also observed for the Al-Si alloys produced by SLM [23,4]. This latter phenomenon can be accounted for in the prediction of the size distribution of the critical defects by restricting the aforementioned volume V to a sub-volume corresponding to the subsurface portion of the loaded part. The application of such a procedure, which assumes that the critical defect is the largest defect found in the subsurface portion of the part, has provided

* Corresponding author at: Arts et Metiers Institute of Technology, University of Bordeaux, CNRS, Bordeaux INP, INRAE, HESAM Université, I2M Bordeaux, F-33400 Talence, France.

E-mail address: matthieu.bonneric@ensam.eu (M. Bonneric).

satisfying results for the AlSi10Mg alloy produced by SLM [24].

Although the detrimental impact of the defects is frequently reported in the literature on the Al-Si alloys produced by SLM, the potential benefits of a Hot Isostatic Pressing (HIP) treatment was rarely studied. Some studies showed that the application of HIP without any subsequent heat-treatment lead to a significant decrease of the strength and fatigue resistance, even if the porosity is reduced [25,26]. In addition, several studies showed that the fatigue performance and ductility can be improved by the application of a T6 treatment, although these improved properties come at the expense of some tensile strength [27–29]. Recently, the combination of HIP with a subsequent T6 treatment was investigated for the AlSi10Mg alloy [30]. The authors found that this treatment produced a microstructure similar to the only T6 material, but was ineffective in eliminating all the defects.

This study aims to investigate the influence of the reduced defect density induced by HIP prior to a T6 treatment on the critical defect distribution for the case of the AlSi7Mg0.6 alloy, in order to better understand the fatigue properties resulting from this treatment with respect to an only T6 treatment. The defect populations were analyzed using X-ray tomography for both HIP + T6 and T6 materials. Uniaxial fatigue tests were conducted, and the SEM observations of the fracture surfaces allowed for the characterization of the critical defect distributions. An approach was then proposed to predict these distributions from the CT scan data, and discussed with regard to the actual distributions obtained from fracture surfaces.

2. Material and methods

Cylindrical samples were produced on a SLM 280HL powder bed machine on the additive manufacturing platform (FUTURPROD) of I2M institute, using the AlSi7Mg0.6 aluminium alloy. The process parameters recommended by the manufacturer for Al-Si alloys were used (see Table 1), and the powders were dried under inert environment at 150°C for 12 h prior to the manufacturing. All samples were built in the vertical direction. A first batch of samples was then subjected to a T6 heat-treatment, consisting in a solution treatment at 535°C for 2 h, followed by a water quenching and an artificial aging at 170 °C for 4 h. These samples will be referred as T6 samples in what follows. A second batch of samples was subjected to a HIP treatment consisting in 2 h at 500 °C under 100 MPa, and then to the T6 treatment described above. These samples will be referred as HIP + T6 samples in what follows. Fatigue specimens, whose dimensions are provided in Fig. 1, were machined from these two batches after heat-treatments. The machined surface finish was meant to prevent from the influence of the surface roughness on the fatigue behavior, as this work focuses on the influence of defects.

Fig. 2 provides observations of the microstructures related to the two heat-treatments considered in this study. These observations showed no significant difference between the two microstructures at a microscopic scale. Both T6 and HIP + T6 lead to the complete elimination of the initial dendritic structure, with the development of Si precipitates at grain boundaries. In addition, the average grain sizes were measured from the transverse sections see (Fig. 2a and c) and were found to be 10 µm for both T6 and HIP + T6.

The defect populations in T6 and HIP + T6 specimens were characterized using X-ray tomography. For each batch, the gauge lengths of 6 fatigue specimens were fully imaged with a voxel size of 4.7 µm, corresponding to an inspected volume of 1710 mm³. The obtained data were analyzed using the AVIZO and ImageJ software. A median filter




Fig. 1. Geometry of the machined specimens used for HCF fatigue tests.

was systematically applied in a first place to reduce the noise and obtain an almost uniform gray level in the melted regions. The use of a threshold on the gray levels then allows for the separation of the different defects from the bulk material. It should be specified that only thresholded objects with at least 8 voxels were considered to be defects. Different features were evaluated for each defect (position, volume, sphericity, etc...). In particular, the distribution of the Murakami \sqrt{area} parameter [31], which is commonly used to depict defect criticality with respect to fatigue, was assessed using a script with the ImageJ software. As the fatigue behavior is mostly driven by the large defect population, only the defects of size $\sqrt{area} > 30 \mu\text{m}$ were selected to build defect size distributions. The choice of this threshold value will be justified in Section 4.

Micro-hardness measurements (Vickers) were performed on mirror polished samples, applying a 100 g load with a 10 s indentation time. For each sample, 25 indentations were conducted on both transverse and longitudinal sections. In addition to T6 and HIP + T6 samples, an as-built (AB) sample was also tested to have reference values corresponding to the initial metallurgical state.

Tension/tension fatigue tests were conducted on a Zwick resonant machine at room temperature in air and at a frequency of 80 Hz. All specimens were tested applying a $R = 0.1$ load ratio. The stop criterion was a frequency drop of 0.5 Hz corresponding to a crack of approximately 1.5 mm in depth, or a maximum number of cycles of 2×10^6 cycles. The staircase method was used to assess the fatigue resistance at 2×10^6 cycles. Following this procedure, each specimen was tested at one stress level only. The step between two levels was 20 MPa for the T6 material and 10 MPa for the HIP + T6 material. Please note that the non-broken specimens were also subjected to a Locati procedure by steps of 10 MPa until failure was detected, in order to observe the critical defect through SEM observations. However the results from these Locati procedures were not reported in the S-N curve presented in Section 3.3.

3. Results


3.1. Defect characterization

The total number of defects found in the whole volume inspected with X-ray tomography was 244000 for T6 specimens, and 41000 for HIP + T6 specimens. Thus, the HIP treatment has a non negligible impact on the defect density, although it does not allow for the complete elimination of the defects, most likely due to the presence of gas trapped in the defects. Fig. 3 shows the evolution of the size $V^{1/3}$ evaluated with respect to the sphericity S for the defect populations related to the T6 and HIP + T6 specimens. When considering the large


Table 1

Process parameters recommended for Al-Si alloys.


Layer thickness	Laser power	Scan velocity	Hatches pacing	Scanning strategy	Base plate heating	Atmosphere
30 µm	350 W	1650 mm/s	130 µm	Stripes	150 °C	Argon




(a) T6 sample - Transverse section



(b) T6 sample - Longitudinal section



(c) HIP+T6 sample - Transverse section



(d) HIP+T6 sample - Longitudinal section

Fig. 2. Observations of the microstructures after a chemical etching using Keller's reagent.




Fig. 3. Analysis of the defects observed with X-ray tomography: defect size $V^{1/3}$ as a function of sphericity S .

defects in T6 specimens, meaning those with $V^{1/3} > 60 \mu\text{m}$, the sphericity ranges within 0.2 and 1.0 with a mean value of 0.68, which reflects the significant variability in the morphology of the defects generated by the SLM process. When considering the defects of size $V^{1/3} > 60 \mu\text{m}$ in HIP + T6 specimens, the sphericity values fall within a narrower range with a mean value of 0.55. This general decrease in the sphericity was attributed to a flattening of the defects induced by the HIP treatment, which was observed on three-dimensional views of the defects analyzed

with X-ray tomography (Fig. 4). Indeed, the visualization of some particular defects in T6 specimens (Fig. 4a and b) and HIP + T6 specimens (Fig. 4c and d) suggests that the defects tend to be flattened with respect to the building direction when a HIP treatment is applied prior to T6. This assumption was later confirmed by the observations of the fracture surfaces, where the critical defects in the HIP + T6 specimens were found less deep than the critical defects related to T6 specimens.


Fig. 5b shows the cumulative distributions of the defect size $\sqrt{\text{area}}$ in T6 and HIP + T6 specimens. Only the defects of size $\sqrt{\text{area}} > 30 \mu\text{m}$ were selected to build these distributions, which corresponded to 42000 defects in T6 specimens and 12000 defects in HIP + T6 specimens. Although the HIP treatment prior to T6 was responsible for a significant reduction of the number of defects, as illustrated by the defect count histogram shown in Fig. 5a, the two distributions were found almost identical. This unique distribution can be fitted with a generalized Pareto distribution, for which the expression of the cumulative distribution function is:

$$F(x) = 1 - \left(1 + \gamma \frac{x - u}{\sigma}\right)^{-\frac{1}{\gamma}} \quad (1)$$


where $\gamma = 0.105$, $u = 29.97 \mu\text{m}$, $\sigma = 9.22 \mu\text{m}$.

3.2. Hardness measurements


Fig. 6 provides the results of the micro-hardness measurements. The hardness was approximately 120 HV in both transverse and longitudinal directions for the as-built condition. After T6, the hardness is slightly decreased to 110 HV in the transverse direction and to 100 HV




(a) Defect in T6 sample of size $\sqrt{area} = 116 \mu\text{m}$



(b) Defect in T6 sample of size $\sqrt{area} = 93 \mu\text{m}$



(c) Defect in HIP+T6 sample of size $\sqrt{area} = 135 \mu\text{m}$




(d) Defect in HIP+T6 sample of size $\sqrt{area} = 147 \mu\text{m}$

Fig. 4. Three dimensional views of particular defects observed with X-ray tomography. The building direction is indicated (BD).

in the longitudinal direction. The inability of the T6 treatment to enhance the hardness of Al-Si alloys produced by SLM was already reported in the literature [32,30], and one might assume that the development of precipitates during the treatment does not overcome the loss of the fine Si network, which is most likely the main contributor to the strengthening of the as-built material. When HIP is applied prior to T6, the hardness is 120 HV in both transverse and longitudinal directions, as for the as-built condition. Thus, the application of the HIP prior to T6 results in a hardness that is slightly higher compared to the T6 condition. Since the HIP treatment consists in both heating 2 h at 500 °C and applying 100 MPa, the increase in the Vickers hardness could possibly be attributed either to a better dissolution of the alloying elements leading to a better precipitation hardening, or to a density increase. A work is in progress to evaluate the effect of the sole thermal part of the treatment, but it is not possible yet to differentiate thermal and mechanical effects.

3.3. Fatigue tests

Fig. 7 shows the S-N curves obtained with a $R = 0.1$ load ratio for T6 and HIP + T6 specimens. The fatigue resistances at 2×10^6 cycles $\sigma_{max,d}$ evaluated with the staircase method was $152 \text{ MPa} \pm 8 \text{ MPa}$ for T6 specimens, and $177 \text{ MPa} \pm 10 \text{ MPa}$ for HIP + T6 specimens. Thus, the



(a) Defect count histogram (logarithmic scale)





Fig. 6. Comparison of the micro-hardness measurements between as-built samples (AB), T6 samples and HIP + T6 samples.

application of the HIP treatment prior to T6 allowed for a slight increase (16%) in the fatigue resistance, although no significant difference was observed between the two batches in terms of fatigue lives shown in Fig. 7.

For T6 specimens, SEM observations of the fracture surfaces indicated that the fatigue cracks systematically initiated at defects. These critical defects mostly corresponded to lack-of-fusion defects (Fig. 8a) and gas pores (Fig. 8b), which are usually observed in the Al-Si alloys produced by SLM. In some rare cases (3 cases among the 22 specimens



(b) Cumulative distribution

Fig. 5. Defect size distributions corresponding to the observations of T6 samples and HIP + T6 samples with X-ray tomography.





Fig. 7. S-N curves for a R = 0.1 load ratio for T6 specimens and HIP + T6 specimens.


observed), clusters of small gas pores were also found responsible for fatigue failure (Fig. 8c). This particular kind of defect could also be observed in the T6 specimens characterized with X-ray tomography, and the observations indicated that the clusters were contained within a few layer thicknesses, as illustrated in Fig. 9. One might assume that

these defects resulted from a local poor powder spreading, although their precise origin is difficult to determine. Besides, it is interesting to note that such clusters were never observed in the HIP + T6 specimens. However, as they were rare, and due to the inability of properly measuring their sizes from the observations of the fracture surfaces, the clusters were not accounted for in any of the analyzes presented in this study. The sizes \sqrt{area} of the other critical defects were evaluated using the measurements of the defect areas on the fracture surfaces, as illustrated in Figs. 8a and b. Please note that, for the sake of consistency with X-ray tomography data, the effective defect size – as defined in [33] for instance – was not considered in the present study. The sizes of the critical defects ranged from 20 μm to 117 μm for the T6 specimens, and no distinction could be made between the lack-of-fusion defects and the gas pores regarding their sizes. In addition, it appeared that all these defects were close to the surface of the specimens, and the distance d between the surface and the center of the defect did not exceed 85 μm . However, no correlation was found between the sizes of the defects and the thicknesses of the bridge of material between the defect and the specimen surface. It should be noted that all defect measurements are provided in Tables 2 and 3 at the end of the document.


SEM observations of the fracture surfaces indicated that the fatigue cracks also initiated at surface or subsurface defects for the HIP + T6 specimens, as illustrated in Fig. 10. The sizes of the critical defects ranged from 37 μm to 125 μm , and the distance between the surface



(a) Lack-of-fusion defect




(b) Single Gas pores




(c) Cluster of small gas pores

Fig. 8. Examples of typical critical defects observed on the fracture surfaces of T6 specimens after fatigue testing.



(a) Top view



(b) Side view

Fig. 9. Three dimensional views of a cluster of small gas pores in a T6 specimen observed with X-ray tomography.

and the center of the defect did not exceed 90 μm. One can note that these values are very similar to those related to the T6 specimens. In addition, Fig. 11 shows the cumulative size distributions of the critical defects observed in the T6 and HIP + T6 specimens, where one can see that the two distributions are nearly identical. Thus, even if the application of the HIP treatment prior to T6 allowed for a significant decrease of the defect density compared to the T6 material, it did not affect the distribution of the critical defects responsible for fatigue failure. One can also note that the defects in Fig. 11 might appear in small bundles of the same size, as for the defects of sizes 60 μm, 80 μm and 100 μm in the T6 material. Since none of the steps involved in the measurement of these values may introduce such a threshold effect, the latter one is probably related to the manufacturing process. However, this relation was not investigated in the present study.

4. Discussion

The previous results show that the application of a HIP treatment prior to T6 has a very limited impact on the fatigue behavior. Indeed, it was shown in Fig. 7 that the S-N curves of the T6 and HIP + T6 materials overlap, and the examination of the fracture surfaces indicated that the fatigue cracks in the HIP + T6 material initiated on defects of sizes and positions similar to the T6 material. Yet, a slight increase in the fatigue strength assessed with the staircase method was observed. However, as opposed to other additively manufactured alloys for which the improvement of the fatigue properties mostly results from the elimination of the defects, it is believed that this slight increase is only the result of the slight increase in the material strength highlighted by






Fig. 11. Cumulative size distributions of the critical defects constructed using the measurements from the fracture surfaces.

the micro-hardness measurements (Fig. 6). Indeed, according to the Murakami theory [10], the increase in the Vickers hardness between T6 and HIP + T6 materials produces a 9% increase in the fatigue strength, which is less but close to the 16% increase that was experimentally observed.

The fact that the cumulative size distributions of the critical defects observed in the T6 and HIP + T6 batches (Fig. 11) are nearly identical



(a)



(b)

Fig. 10. Examples of typical critical defects observed on the fracture surfaces of HIP + T6 specimens after fatigue testing.




Fig. 12. Description of the approach employed to predict the distribution of the maximum defect size in the subsurface area of a fatigue specimen.




Fig. 13. Prediction of the distribution of the maximum defect size in the subsurface area of a fatigue specimen for T6 specimens and HIP + T6 specimens.

was somewhat unexpected, considering that the T6 and HIP + T6 materials display almost identical defect size distributions (Fig. 5) but quite different defect densities. Indeed, 12000 defects of size $\sqrt{areaa} > 30 \mu\text{m}$ were found in the whole volume inspected with X-ray tomography for the HIP + T6 specimens, which was 1710 mm^3 . This corresponded to a defect density of 7.02 mm^{-3} . For the T6 specimens, 42000 defects of size $\sqrt{areaa} > 30 \mu\text{m}$ were found, corresponding to a defect density of 24.55 mm^{-3} . One could expect this lower defect density for the HIP + T6 specimens to result in statistically smaller critical defects when a relatively small volume is considered, namely the subsurface area of a fatigue specimen which is approximately 20 mm^3 . In order to better understand these experimental results, this section focuses on the effect of defect density on the size distribution of the

critical defects, assuming that the critical defect in a fatigue specimen is the largest defect in the subsurface area. Fig. 12 describes the approach used to predict the distribution of the maximum defect size in the subsurface area of a fatigue specimen using the X-ray tomography observations presented in Section 3.1.

First, as described in Section 2, the gauge lengths of fatigue specimens, each of them having a volume V_{CT} , were fully imaged using X-ray tomography. For each batch, 6 specimens were observed, leading to a total inspected volume $V_{tot} = 6 V_{CT}$. This data allowed to plot the cumulative defect size distributions (Fig. 5), and to identify the coefficients of Eq. (1), both associated with the volume V_{tot} . Second, a script was implemented to generate uniformly distributed defects in a similar V_{tot} volume, with no intersection with the volume surface. The size distribution followed Eq. (1). The number of defects in the volume is the number of defects experimentally observed in Fig. 5 (12000 for the HIP + T6 specimens, 42000 for the T6 specimens). A sub-volume V_{sub} corresponding to the subsurface area of a fatigue specimen is then defined. This sub-volume corresponds to the area where fatigue cracks may initiate. Its depth has therefore been set to $85 \mu\text{m}$, which is the maximal distance between the specimen surface and the center of the critical defect observed on the fracture surface. The largest defect size in this sub-volume is finally selected and retained. This defect generation and sub-volume selection procedure is repeated 5000 times to generate a maximum defect size distribution associated with V_{sub} .

Fig. 13 shows (dotted lines) the distributions obtained following this approach. As expected, the lower defect density for the HIP + T6 material compared to the only T6 actually results in a shift of the maximum defect size distribution. One should note that, among the 5000 defects selected through the procedure, none had a size $\sqrt{areaa} < 40 \mu\text{m}$. This means that the predicted distributions do not depend on the choice made for the threshold value in Section 2, where only defects with a size $\sqrt{areaa} > 30 \mu\text{m}$ were retained to build defect size distributions from CT scan data. In other words, as the size of the largest defect in V_{sub} systematically exceeds $40 \mu\text{m}$, there is no need to




Fig. 14. Influence of the the depth of the sub-volume V_{sub} , designated as e , on the predicted distribution.

consider the defects smaller than the $30 \mu\text{m}$ threshold value to predict the size distribution of the largest defect in V_{sub} in the present study. Another way to demonstrate that this threshold value has no influence is to count the number of defects in V_{sub} . About 160 defects were present in each sub-volume for the HIP + T6 material, and 540 for the T6 material. This means that the threshold value is certainly low enough to ensure there is at least one defect in V_{sub} for each draw. As explained earlier, the depth of the sub-volume V_{sub} has been initially set to $85 \mu\text{m}$, which is the maximal observed depth of a critical defect. In order to evaluate the sensitivity to this depth, the procedure was also applied for $50 \mu\text{m}$ and $120 \mu\text{m}$ values. The obtained distributions are depicted in Fig. 14. The medians of the distributions predicted for $50 \mu\text{m}$, $85 \mu\text{m}$ and $120 \mu\text{m}$ depth values were equal to $67 \mu\text{m}$, $86 \mu\text{m}$ and $97 \mu\text{m}$ for the HIP + T6 material, and $75 \mu\text{m}$, $100 \mu\text{m}$ and $113 \mu\text{m}$ for the T6 material, respectively. For both materials, as expected, increasing the sub-volume V_{sub} induces a larger amount of defects in the sub-volume, and then larger maximum defect sizes. Moreover, whatever the depth value, the lower defect density associated with the HIP treatment always results in a shift of the maximum defect size distribution. Regarding the median of the distribution, this shift is not much sensitive to the depth value and is about 15%. In what follows, the depth value was kept to $85 \mu\text{m}$.

Fig. 15 compares the experimental distributions from the fracture surfaces, for which no significant difference was observed between the HIP + T6 and T6 (Fig. 11), and the predicted distributions, for which a lower defect density reduces the sizes of the larger defects found in V_{sub} at each draw (Fig. 13). Since not many experimental data were

available, a Gumbel distribution describing the cumulative size distribution of the critical defects was estimated for each material, and the associated 95% confidence intervals were calculated by bootstrapping and depicted on Figs. 15 and 16. Predictions are overall similar to the SEM observations. However, one can note that they are more accurate for the HIP + T6 material (Fig. 15b) than for the T6 material (Fig. 15a). Indeed, for the T6 specimens, the difference between experimental and predicted data is noticeable: critical defects on which fatigue cracks actually initiated are smaller than larger defects found in V_{sub} . One explanation could be that the number of critical defects experimentally measured was not sufficient to build a representative size distribution. Another explanation could be that the larger defect found in V_{sub} is not always the critical one, as fatigue damage may initiate on a smaller defect, either due to its position, morphology, or to the surrounding microstructure.

In order to assess the first assumption, 20 distributions were predicted for each batch using a reduced number of defects corresponding to the number of critical defects observed on fracture surfaces (19 and 9 for the T6 and HIP + T6 batches, respectively). The objective here was to numerically assess how the size distribution may vary when only a few defects are used instead of 5000. The obtained results are provided in Fig. 16. When considering the distributions associated to the T6 material, it comes clear that the variability associated with a limited number of defects does not explain the difference between experimental and predicted results.

Thus, it is likely that this discrepancy results from the second






Fig. 15. Comparison of the predicted distributions of the maximum defect size in the subsurface area of a fatigue specimen with the distributions constructed using the measurements of the actual critical defect sizes from the fracture surfaces.



(a) T6 specimens - 19 defects per distribution



(b) HIP+T6 specimens - 9 defects per distribution

Fig. 16. Predicted distributions of the maximum defect size in the subsurface area of a fatigue specimen constructed with a reduced number of defects. Comparison with the distributions constructed using the measurements of the actual critical defect sizes from the fracture surfaces.

assumption, meaning that the larger defect found in V_{sub} is not always the critical one. This is consistent with the result on Fig. 15b where the difference between the experimental and predicted distributions is much less pronounced for the HIP + T6 material, for which V_{sub} contains less defects. Indeed, the probability to find a small defect in V_{sub} whose criticality is greater than that of the largest defect, due to its local morphology or microstructure for instance, is lower when the defect density is reduced.

5. Conclusion

The results of this work can be summarized as follows:

1. A HIP process prior to a T6 treatment has no significant impact on the fatigue behavior compared to a T6 treatment, as the fatigue cracks in the HIP + T6 material still initiate on defects whose sizes and positions are similar to the T6 material. Only a slight increase in the fatigue strength was observed (+16%), which was attributed to the slight increase in the material hardness.
2. The HIP process does not change the defect size distribution, but allows for a significant decrease in the defect density.

3. Simulations of the critical defect size distribution showed that an increase in the defect density induces larger critical defects. However, these calculations rely on the assumption by which the critical defect is the largest one within the subsurface area of the loaded part, and the comparison with the experimental results suggests that this assumption becomes inaccurate for high defect densities, as for the T6 material.

Declaration of Competing Interest

None.

Acknowledgments

This work falls within the framework of the Andduru project hosted by the French Institute of Technology IRT Saint Exupery, supported by Occitanie Region and industrial partners. In addition, the specimens were produced on the FUTURPROD additive manufacturing platform of I2M institute.

Table 2

Measurements of critical defect features from the fracture surface - T6 material.

Size \sqrt{areaa} (μm)	Distance from the center to the surface (μm)	Smallest distance to the surface (μm)
62	48	0
99	55	8
21	21	10
33	27	0
63	49	18
78	37	0
61	50	0
33	26	6
115	84	16
78	71	0
77	68	20
98	79	18
77	56	29
58	32	8
77	53	0
46	21	0
117	79	13
62	42	14
20	21	9

Table 3

Measurements of critical defect features from the fracture surface - HIP + T6 material.

Size \sqrt{area} (μm)	Distance from the center to the surface (μm)	Smallest distance to the surface (μm)
102	92	0
67	44	0
58	26	0
55	26	0
61	44	12
38	29	14
84	68	16
125	76	0
37	38	14

Appendix A

References

- Olakanmi E, Cochrane R, Dalgarno K. A review on selective laser sintering/melting (SLS/SLM) of aluminium alloy powders: processing, microstructure, and properties. *Prog Mater Sci* 2015;74:401–77. <https://doi.org/10.1016/j.pmatsci.2015.03.002>.
- Rao H, Giet S, Yang K, Wu X, Davies C. The influence of processing parameters on aluminium alloy A357 manufactured by Selective Laser Melting. *Mater Des* 2016;109:334–46. <https://doi.org/10.1016/j.matdes.2016.07.009>.
- Aboulkhair N, Maskery I, Tuck C, Ashcroft I, Everitt N. Improving the fatigue behaviour of a selectively laser melted aluminium alloy: Influence of heat treatment and surface quality. *Mater Des* 2016;104:174–82. <https://doi.org/10.1016/j.matdes.2016.05.041>.
- Romano S, Brückner-Foit A, Brandão A, Gumpinger J, Ghidini T, Beretta S. Fatigue properties of AlSi10Mg obtained by additive manufacturing: Defect-based modelling and prediction of fatigue strength. *Eng Fract Mech* 2018;187:165–89. <https://doi.org/10.1016/j.engfracmech.2017.11.002>.
- Siddique S, Imran M, Walther F. Very high cycle fatigue and fatigue crack propagation behavior of selective laser melted AlSi12 alloy. *Int J Fatigue* 2017;94:246–54. <https://doi.org/10.1016/j.ijfatigue.2016.06.003>.
- Yang K, Rometsch P, Jarvis T, Rao J, Cao S, Davies C, et al. Porosity formation mechanisms and fatigue response in Al-Si-Mg alloys made by selective laser melting. *Mater Sci Eng: A* 2018;712:166–74. <https://doi.org/10.1016/j.msea.2017.11.078>.
- Siddique S, Imran M, Wycisk E, Emmelmann C, Walther F. Influence of process-induced microstructure and imperfections on mechanical properties of AlSi12 processed by selective laser melting. *J Mater Process Technol* 2015;221:205–13. <https://doi.org/10.1016/j.jmatprotec.2015.02.023>.
- Galy C, Le Guen E, Lacoste E, Arvieu C. Main defects observed in aluminum alloy parts produced by SLM: From causes to consequences. *Addit Manuf* 2018;22:165–75. <https://doi.org/10.1016/j.addma.2018.05.005>.
- Murakami Y, Endo T. Effects of small defects on fatigue strength of metals. *Int J Fatigue* 1980;2(1):23–30. [https://doi.org/10.1016/0142-1123\(80\)90024-9](https://doi.org/10.1016/0142-1123(80)90024-9).
- Murakami Y. *Metal fatigue: effects of small defects and nonmetallic inclusions*. Elsevier Edition; 2002.
- Vincent M, Nadot Y, Nadot-Martin C, Dragon A. Interaction between a surface defect and grain size under high cycle fatigue loading: Experimental approach for Armc0 iron. *Int J Fatigue* 2016;87:81–90. <https://doi.org/10.1016/j.ijfatigue.2016.01.013>.
- Le V, Morel F, Bellett D, Saintier N, Osmond P. Simulation of the Kitagawa-Takahashi diagram using a probabilistic approach for cast Al-Si alloys under different multiaxial loads. *Int J Fatigue* 2016;93:109–21. <https://doi.org/10.1016/j.ijfatigue.2016.08.014>.
- Beretta S, Romano S. A comparison of fatigue strength sensitivity to defects for materials manufactured by AM or traditional processes. *Int J Fatigue* 2017;94:178–91. <https://doi.org/10.1016/j.ijfatigue.2016.06.020>.
- Kitagawa T. Applicability of fracture mechanics to very small cracks, ASM. *Proceedings of 2nd international conference on mechanical Metalspark*. 1976. p. 627–31.
- El Haddad M, Topper T, Smith K. Prediction of non propagating cracks. *Eng Fract Mech* 1979;11(3):573–84. [https://doi.org/10.1016/0013-7944\(79\)90081-X](https://doi.org/10.1016/0013-7944(79)90081-X).
- Murakami Y. Inclusion rating by statistics of extreme values and its application to fatigue strength prediction and quality control of materials. *J Res Nat Inst Stand Technol* 1994;99(4):345–51. <https://doi.org/10.6028/jres.099.032>.
- Le V, Morel F, Bellett D, Saintier N, Osmond P. Multiaxial high cycle fatigue damage mechanisms associated with the different microstructural heterogeneities of cast aluminium alloys. *Mater Sci Eng: A* 2016;649:426–40. <https://doi.org/10.1016/j.msea.2015.10.026>.
- Makkonen L, Rabb R, Tikanmäki M. Size effect in fatigue based on the extreme value distribution of defects. *Mater Sci Eng: A* 2014;594:68–71. <https://doi.org/10.1016/j.msea.2013.11.045>.
- Romano S, Brandão A, Gumpinger J, Gschweidt M, Beretta S. Qualification of AM parts: Extreme value statistics applied to tomographic measurements. *Mater Des* 2017;131:32–48. <https://doi.org/10.1016/j.matdes.2017.05.091>.
- Andreu O, Pessard E, Koutiri I, Penot J, Dupuy C, Saintier N, et al. A competition between the contour and hatching zones on the high cycle fatigue behaviour of a 316L stainless steel: Analyzed using X-ray computed tomography. *Mater Sci Eng: A* 2019;757:146–59. <https://doi.org/10.1016/j.msea.2019.04.101>.
- El Khoukhi D, Morel F, Saintier N, Bellett D, Osmond P, Le V, et al. Experimental investigation of the size effect in high cycle fatigue: Role of the defect population in cast aluminium alloys. *Int J Fatigue* 2019;129. <https://doi.org/10.1016/j.ijfatigue.2019.105222>.
- Wilson P, Saintier N, Palin-Luc T, Bergamo S. Isothermal fatigue damage mechanisms at ambient and elevated temperature of a cast Al-Si-Cu aluminium alloy. *Int J Fatigue* 2019;121:112–23. <https://doi.org/10.1016/j.ijfatigue.2018.11.016>.
- Yadollahi A, Shamsaei N. Additive manufacturing of fatigue resistant materials: Challenges and opportunities. *Int J Fatigue* 2017;98:14–31. <https://doi.org/10.1016/j.ijfatigue.2017.01.001>.
- Romano S, Abel A, Gumpinger J, Brandão A, Beretta S. Quality control of AlSi10Mg produced by SLM: Metallography versus CT scans for critical defect size assessment. *Addit Manuf* 2019;28:394–405. <https://doi.org/10.1016/j.addma.2019.05.017>.
- Uzan N, Shneck R, Yeheskel O, Frage N. Fatigue of AlSi10Mg specimens fabricated by additive manufacturing selective laser melting (AM-SLM). *Mater Sci Eng: A* 2017;704:229–37. <https://doi.org/10.1016/j.msea.2017.08.027>.
- Tradowsky U, White J, Ward R, Read N, Reimers W, Attallah M. Selective laser melting of AlSi10Mg: Influence of post-processing on the microstructural and tensile properties development. *Mater Des* 2016;105:212–22. <https://doi.org/10.1016/j.matdes.2016.05.066>.
- Bagherifard S, Beretta N, Monti S, Riccio M, Bandini M, Guagliano M. On the fatigue strength enhancement of additive manufactured AlSi10Mg parts by mechanical and thermal post-processing. *Mater Des* 2018;145:28–41. <https://doi.org/10.1016/j.matdes.2018.02.055>.
- Domfong Ngnekou J, Nadot Y, Henaff G, Nicolai J, Ridosz L. Influence of defect size on the fatigue resistance of AlSi10Mg alloy elaborated by selective laser melting (SLM). *Proc Struct Integr* 2017;7:75–83. <https://doi.org/10.1016/j.prostr.2017.11.063>.
- Maskery I, Aboulkhair N, Tuck C, Wildman R, Ashcroft I, Everitt N, et al. Fatigue performance enhancement of selectively laser melted aluminium alloy by heat treatment. *Solid Freeform Fabric Symp* 2015:1017–25.
- Kan W, Nadot Y, Foley M, Ridosz L, Proust G, Cairney J. Factors that affect the properties of additively-manufactured AlSi10Mg: Porosity versus microstructure. *Addit Manuf* 2019;29. 100805.
- Murakami Y, Endo M. Quantitative evaluation of fatigue strength of metals containing various small defects or cracks. *Eng Fract Mech* 1983;17(1):1–15. [https://doi.org/10.1016/0013-7944\(83\)90018-8](https://doi.org/10.1016/0013-7944(83)90018-8).
- Aboulkhair N, Tuck C, Ashcroft I, Maskery I, Everitt N. On the Precipitation Hardening of Selective Laser Melted AlSi10Mg. *Metall Mater Trans A* 2015;46(8):3337–41.
- Masuo H, Tanaka Y, Morokoshi S, Yagura H, Uchida T, Yamamoto Y, et al. Effects of defects, surface roughness and hip on fatigue strength of Ti-6Al-4V manufactured by additive manufacturing. *Proc Struct Integr* 2017;7:19–26. <https://doi.org/10.1016/j.prostr.2017.11.055>.