



HAL
open science

Numerical Simulation of Wave Impacts with Interfacial Phase Change: An Isothermal Averaged Model

Matthieu Ancellin, Laurent Brosset, Jean-Michel Ghidaglia

► **To cite this version:**

Matthieu Ancellin, Laurent Brosset, Jean-Michel Ghidaglia. Numerical Simulation of Wave Impacts with Interfacial Phase Change: An Isothermal Averaged Model. *European Journal of Mechanics - B/Fluids*, 2018, 72, pp.631-644. 10.1016/j.euromechflu.2018.08.001 . hal-02935980

HAL Id: hal-02935980

<https://hal.science/hal-02935980v1>

Submitted on 10 Sep 2020

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

Numerical Simulation of Wave Impacts with Interfacial Phase Change: An Isothermal Averaged Model

Matthieu Ancellin^{a,b,1,*}, Laurent Brosset^a, Jean-Michel Ghidaglia^b

^a*GTT (Gaztransport & Technigaz), Saint-Rémy-lès-Chevreuse, France*

^b*CMLA, ENS Paris-Saclay, CNRS, Université Paris-Saclay, Cachan, France*

Abstract

Most current numerical simulations on sloshing impact loads do not take into account the possibility of evaporation and condensation of the fluid. Thus, in order to evaluate the influence of phase change the goal of this work is to develop a numerical model able to simulate a wave impact with phase change. Such a model should describe compressible multiphase flows with separate phases, including non-equilibrium interfacial phase change. A first prototype is presented in this paper based on an isothermal Volume-Of-Fluid-type model for the representation of the liquid-vapor interface and a non-conservative advection term for the modelling of phase change. Discretization of the model is made in the Finite Volume framework using a Roe-type scheme. Some original numerical test cases for the validation of the code are discussed and preliminary results for a simplified impact test case are presented.

1. Introduction

In the transportation of Liquefied Natural Gas (LNG) in tanks on floating structures, such as LNG carriers, one of the principal current technologies is to store the LNG at ambient pressure and cryogenic temperature using a membrane
5 containment system that completely covers the inner sides of the tank walls.

*Corresponding author

Email addresses: matthieu.ancellin@ucd.ie (Matthieu Ancellin), lbrosset@gtt.fr (Laurent Brosset), jmg@cmla.ens-cachan.fr (Jean-Michel Ghidaglia)

¹Present address: School of Mathematics and Statistics, University College Dublin, Ireland

When the sea is rough, the motion of the ship induces significant movement of the liquid in the tank, which can induce violent impacts on the containment system. When designing such containment systems, Gaztransport & Technigaz (GTT) has to ensure that these impacts do not cause any damage during the
10 working life of the floating structure. Typically, sloshing assessment is based on tests using a model tank, normally at scale 1:40. The tank is filled with water and a heavy gas, and is placed on a hexapod platform which allows it to be moved with six degrees of freedom. The heavy ullage gas is chosen such that the gas-to-liquid density ratio is the same as at full scale. Measurements
15 are made using several pressure sensors that are placed in the impact areas. A complex methodology based on a long-term approach [1] is followed, which enables the probability of failure for any limit state of the containment system to be derived.

However, the complete physics of a real wave impact are not modeled in such
20 an experiment. In particular, phase change (evaporation and condensation) is expected to occur in the full-scale LNG tank since the fluid is close to thermodynamic equilibrium. Unfortunately, its influence on impact loads has not been studied in detail, until now. The final goal of this work is to add a phase change model to a numerical simulation of wave impact and better understand
25 the influence of phase change.

Sloshing tests with boiling water and vapor in conditions close to the phase boundary have been performed [2]. Statistically, the pressure at the impact wall was found to be smaller with water and vapor than with water and non-condensable gases. Hence, the authors attributed the pressure reduction to phase
30 change.

Simulating a wave impact with phase change adds a new layer of difficulty to an already complex problem. Indeed, the numerical model with phase change should already include complex properties of the two fluids like their compressibility [3]. Furthermore, it is impossible to directly validate such simulations
35 because experimental results of wave impact tests (or sloshing tests with a sin-

gle impact) show a high variability of the local pressure measurements. This variability is due to the development of free surface instabilities triggered by the escaping gas flow, even when the global wave shape is accurately reproduced (see also for example [4]). More details on wave impact physics can be found in
40 [5].

The only attempts (to our knowledge) to create such a simulation with phase change have been made by [6] for the scenario of a liquid block free falling onto a solid surface and by [7] for two single impact waves obtained by sloshing model tests (without experiment as a reference). Their results seem to be in line with
45 those observed by [2] during sloshing tests with water and vapor.

The problem of phase change influence on sloshing wave impacts is related to the problem of sloshing influence on boil-off evaporation in cryogenic tanks. In the latter boil-off problem, a slow steady heat flow from the exterior of the cryogenic tank can warm up the content of a tank. As a consequence, the
50 liquid evaporates and the pressure rises inside the tank. Sloshing influences this phenomenon, as studied by [6] and [8], among others. However, these problems differ because the spatial scale of the boil-off problem is the size of the tank and the time scale is hours or days, whereas the spatial scale of our problem is the region of impact and the time scale is the duration of the impact. Different
55 modelling approaches should thus be used to describe these two problems.

A great variety of phase change models exists for two-fluid CFD codes, depending on the kind of flow that is being modeled. These models can be sorted using the characteristic size and characteristic duration of the problems they are designed for. The spatial characteristic size of the problem changes the rep-
60 resentation of the interface: from a microscopic interface of finite thickness (e.g. [9]) to an industrial averaged macroscopic model (e.g. [10, 11]). The description of interfacial phase change needs to be adapted to the description of the interface. Independently, the characteristic time scale of the problem determines how the relaxation towards liquid-vapor equilibrium is modeled: from instantaneous

65 liquid-vapor equilibrium (e.g. [12]) to total non-equilibrium. (Other references used in this work on the modelling of phase change includes [13] and [14].)

The specific space and time scales of the wave impact problem described earlier set the frame of reference of our model. Although a wave impact may involve a complex flow made of droplets and bubbles caused by free surface 70 instabilities, all the numerical studies of wave impacts described previously considered only a relatively smooth zero-thickness interface between pure phases. Existing phase change models at this macroscopic scale include [15] and [16]. However, a wave impact is a very brief and violent phenomenon. Thus, unlike in [15] and [16], both fluids are modeled as compressible and no equilibrium 75 hypothesis is made between phases at the interface.

For slow evaporation and condensation the evolution of the interface can be modelled using a Stefan model [17]. In such a model the mass flow rate can be seen as a Lagrange multiplier ensuring the instantaneous equilibrium condition $p = p^{\text{sat}}(T)$ at the interface. Since an equilibrium hypothesis at the interface 80 might not be applicable to the wave impact problem, a non-equilibrium model of the Hertz-Knudsen model type [18, 19] will be considered instead. The mass flow rate in this model is proportional to the distance to equilibrium and the interface is brought back to equilibrium in finite time.

In the present paper, the compressible flow with two separate phases is 85 modelled using a Volume-Of-Fluid-type model that is similar to those of [20], [21] or [22]. The liquid gas interface is implicitly captured as liquid-gas mixtures cells, forming a numerically “diffuse” interface, without any special numerical treatment. Although this kind of model can be less accurate than alternatives, such as interface tracking schemes, they are easier to develop and implement, 90 especially in two or three-dimensions. In this paper, our goal is to add non-equilibrium interfacial phase change into such a model. Since diffusion at the interface is a numerical bias, one of the objectives of this work is to ensure that the phase change rate is as independent as possible of the interface profile.

Phase change is a complex process involving pressure variations, large local

95 temperature variations, as well as a velocity discontinuity at the interface. The
temperature variations are due to the large latent heat released or captured
by the mass that changes phase, whereas the pressure variations and velocity
jump are due to the density ratio between phases. Correctly including all of this
phenomena in a diffuse interface model is a difficult task. During the derivation
100 of our model in the next section, the hypothesis of an isothermal flow will be
made to simplify the task. This hypothesis is very strong, as the wave impact
cannot be expected to be an isothermal process. However, this work should be
seen as only a first step towards more realistic models of wave impacts with
phase change. The same kind of approximation for the study of wave impacts
105 is used in other state-of-the-art work, such as [23].

The simplifying assumption of a pure chemical species (either pure water or
pure methane) will also be made. Actual LNG is a mixture of several compo-
nents, where the exact composition has an effect on the phase change behavior
of the fluid. However, for the sake of simplicity, multispecies mixtures will not
110 be discussed here.

Only phase change at the interface between liquid and gas are discussed in
this paper. Nucleation, that is the appearance of new droplets in the gas or new
bubbles in the liquid, is not expected to be necessary for the understanding of
the influence of phase change on wave impacts [24, 25].

115 Among the existing compressible-flow models with phase change, the closest
to the model presented in this paper are the exact Riemann solver of [26] and
[27] and the stiff source term models of [28] and [29]. The former describes the
liquid-vapor with phase change by adding one more discontinuity to the solution
of the Riemann problem between two phases. This discontinuity follows the
120 Rankine-Hugoniot conditions for a non-zero mass flow rate which is the phase
change rate. The model presented in this paper gives a similar solution to the
Riemann problem (see [24]). However, at the core of our model we place the
hyperbolic set of equations instead of the Riemann problem solution. The work
of [28] and [29] describe numerically the interface as a liquid-vapor mixture zone
125 in which phase change is modelled as a source term. Our model also involves a

numerical mixture zone at the interface. Instead of a stiff source term of order zero, we describe phase change using a first order term, as will be seen in the following sections. The behavior of the first order term is expected to be less dependent on numerical diffusion at the interface. The relation between these
130 models and our approach has also been discussed in [30].

In the first few paragraphs of the next section, a model describing the evolution of a flow with two separated phases is presented. Simulation of the model is made using the Finite Volume method, where the model is averaged using a new description of the averaged phase change term. After some simplifications
135 (including the hypothesis of an isothermal flow), a non-conservative hyperbolic system describing the averaged two-phase flow is derived. The numerical scheme used for the simulation of this system is described in Section 3. In particular, the discretization of the non-conservative phase change terms is discussed. The resulting Roe-type scheme is a variant of the scheme proposed in [31].

This scheme is applied in the next section to several simple validation test cases, which illustrate some of the benefits and limitations of the model and its discretization. In particular, it shows that the thickness of the numerical mixture layer at the interface has almost no consequence for the phase change simulation. Finally, in the last section of this paper, the model is applied to
145 idealized wave impact test cases. Preliminary conclusions on the influence of phase change on wave impact loads can then be derived.

The present work is part of a series of contributions to modelling of wave impacts with phase change. The present model has been introduced in [24] along with another interface reconstruction scheme (which will be published in
150 a subsequent article) and a surrogate model updating the model presented in [32]. These different works explore various approaches and shed light on different aspects of phase change modelling. A summary of the models and some partial physical conclusions are presented in [33].

2. Physical model

155 In this section, the mathematical description of two-fluid flow with interfacial phase change will be discussed.

2.1. A sharp interface model

The two phases are flagged using the order parameter $\chi(x, t)$ that describes the local phase: $\chi = 1$ for the gas and $\chi = 0$ for the liquid.

160 At an interface, the evolution of χ can be written as follows [24]:

$$\partial_t \chi + (u - J/\rho) \cdot \nabla \chi = 0, \quad (1)$$

where the vector J denotes the interfacial surfacic mass flux aligned with the normal vector at the interface. Note that even when both fluids are at rest ($u = 0$), the interface between the two phases can evolve due to phase change.

Using the standard conservative equations for the fluid (mass, momentum and total energy - see (2a) to (2c) below), the balance equations for two fluid phases separated by a free surface can thus be written as:

$$\partial_t \rho + \nabla \cdot (\rho u) = 0, \quad (2a)$$

$$\partial_t (\rho u) + \nabla \cdot (\rho u \otimes u + p \mathbb{I}) = 0, \quad (2b)$$

$$\partial_t (\rho E) + \nabla \cdot ((\rho E + p) u + q) = 0, \quad (2c)$$

$$\partial_t (\chi \rho) + \nabla \cdot (\chi \rho u) - J \cdot \nabla \chi = 0, \quad (2d)$$

165 where ρ , u , p , and $E = e + |u|^2/2$ denote respectively density, velocity, pressure and specific total energy of the fluid. Equation (2d) has been obtained by combining (1) with (2a).

In general, the diffusive heat flux q is given by Fourier's law. More terms can be added on the right-hand side of (2) to describe, for instance, gravity, inertial accelerations or viscosity. In this paper, we focus only on the transport 170 terms of the equations (including the phase change term $J \cdot \nabla \chi$).

As discussed in [24, 30], this model is hyperbolic without the heat diffusion term. The solution of the Riemann problem for this system contains four waves:

two sonic waves with velocity $u \pm c$, one contact discontinuity with velocity u and one liquid-vapor interface with velocity $u - J/\rho$. The Rankine-Hugoniot
175 conditions around the latter are the usual boundary conditions around an inter-
face with phase change (see e.g. [34]). If the flow is assumed to be isothermal,
this solution is similar to the one described in [26].

We can write

$$J = J_{l \rightarrow g} \nu_{l \rightarrow g} = J_{l \rightarrow g} \nabla \chi / |\nabla \chi|, \quad (3)$$

where $J_{l \rightarrow g}$ is the evaporation mass flux and $\nu_{l \rightarrow g}$ is the unit normal vector at
180 the interface oriented from the liquid to the gas phase. (Note that the above
notation of $|\nabla \chi| \nu_{l \rightarrow g} = \nabla \chi$ as $\nu_{l \rightarrow g} = \nabla \chi / |\nabla \chi|$ should be approached with care
since $\nabla \chi$ is a Dirac distribution.) Equation (2d) can then be reformulated as

$$\partial_t(\chi \rho) + \nabla \cdot (\chi \rho u) = J_{l \rightarrow g} |\nabla \chi|. \quad (4)$$

In this form, the phase change term can be understood as a source term for this
gas mass balance equation. The term $|\nabla \chi|$ can be seen as an interfacial area
185 term localizing the interface. In this article, the notation of (2d) is preferred
because it is closer to the form of a usual system of conservation equations.

The extra variable J has been introduced to the equations and thus one more
closure relation is needed. This can take the form of an expression relating the
interfacial mass flux J to the local thermodynamical state:

$$J = \mathcal{J}_{l \rightarrow g}(p_g, T_g, p_l, T_l) \nu_{l \rightarrow g}, \quad (5)$$

190 where $\mathcal{J}_{l \rightarrow g}$ is an expression for the evaporation mass flux as a function of the
local pressures and temperatures p_g , T_g , p_l and T_l , respectively in the gas and
the liquid.

The expression for $\mathcal{J}_{l \rightarrow g}$ must be compliant with the second law of ther-
modynamics to ensure the physical relevance of the model (and thus the good
195 behavior of the numerical code). This point will not be discussed in more depth
in this paper. Later in this paper, we will focus on an isothermal evolution at
temperature T_0 and the mass flux across the interface will thus be of the form

$$J \propto (p^{\text{sat}}(T_0) - p_g) \nu_{l \rightarrow g},$$

where p^{sat} denotes the saturation pressure of the considered chemical species.

The influence of the liquid-vapor interface on the domain boundary conditions will not be tackled here. In 1D, it is simply assumed that the interface does cross not the boundary of the domain. Thus, only the usual boundary conditions for the Euler equations apply (see e.g. [35]). In 2D, the description of the boundary conditions may require the study of the physics of the liquid-vapor-wall contact point, which is out of the scope of this paper. Symmetry boundary conditions are assumed at the domain edges for the 2D test case in Section 4.2.

From system (2) it is possible to deduce the conservation equations:

$$\partial_t(\chi\rho) + \nabla \cdot (\chi\rho u) - J \cdot \nabla\chi = 0, \quad (6a)$$

$$\partial_t(\chi\rho u) + \nabla \cdot \chi(\rho u \otimes u + p\mathbb{I}) - (u \otimes J + p\mathbb{I})\nabla\chi = 0, \quad (6b)$$

$$\partial_t(\chi\rho E) + \nabla \cdot \chi((\rho E + p)u + q) - (JE + pu + q) \cdot \nabla\chi = 0. \quad (6c)$$

They are the balance laws for gas mass, gas momentum and gas total energy [24]. The corresponding equations for the liquid can be derived by subtracting (6) from (2).

2.2. Averaging

Equations (6) will now be averaged for numerical resolution in an Eulerian finite volume framework. The reader can refer to [11] for a complete study on the derivation of such an averaged model. In this paper, we will focus on the phase change terms of the form $J \cdot \nabla\chi$, for which a different approach to [11] will be proposed.

2.2.1. Averaged phase change term

This approach is motivated by the consistency of the averaged model, in the sense that the averaged model should converge to the exact model when the size of the averaging volume goes to zero. A lack of consistency in an averaged model is not necessarily a problem. For a complex flow (as for instance in [10], [11] or [36]), the resolution of the computation will never be increased to

capture scales at which the phases are separated. It is thus more important to ensure that the chosen approximations are experimentally valid at large scale rather than asymptotically consistent. However, this is not the case when the
 225 averaged model is aimed at the description of a cell (or a few cells) of a liquid-vapor interface between two separated fluids, such as in [21], [22] or [28]. In these references, as well as in our work, the mixture is a numerical bias at the interface. Several numerical techniques can be used to limit the size of the mixture layer, but this size is never perfectly controlled. Our objective is
 230 that phase change should be as independent as possible of the thickness of the numerical mixture layer at the interface, and that consistency with the exact model (6) is maintained when the thickness goes to zero.

The averaging operator will be denoted by $\overline{}$ in the following paragraphs. In the usual approach, as seen in e.g. [11], the phase change term is averaged as

$$\overline{J \cdot \nabla \chi} \simeq \overline{J_{l \rightarrow g}} \mathcal{A}_i,$$

235 where $\overline{J_{l \rightarrow g}}$ is a local average interfacial evaporation mass flux and \mathcal{A}_i is a local interfacial area density, which is typically a function of the gas volume fraction $\alpha_g = \overline{\chi}$.

The resulting phase change term is of order 0 (*i.e.* it does not contain derivatives of the state variables). The interface evolves in a similar way to a
 240 reaction-diffusion equation. It is possible to check if the total exchanged mass is strongly influenced by the thickness of the mixture layer. Moreover, it is not an easy task to write a reaction-diffusion equation which converges asymptotically towards a discontinuous wave front (see e.g. [37, 38]).

Besides, let us note that the “standard” averaged model without phase change
 245 (see e.g. [31]) is consistent. The term $p \nabla \chi$ in (6b), that can be seen as an interfacial condition between the two fluids (pressure force of one upon the other), is usually averaged as $p \nabla \alpha_g$ (plus other source terms), which naturally degenerates into $p \nabla \chi$.

The interfacial phase change is also described in (2) and (6) as a first order

250 term. To take an average in a consistent way, it seems reasonable to use a first order term. We will follow the example of $p\nabla\chi$ and average the term $J \cdot \nabla\chi$ under the following form

$$\overline{J \cdot \nabla\chi} \simeq \overline{J} \cdot \nabla\alpha_g.$$

As for the pressure term, additional source terms could have been added to the approximation, but since it is assumed that these terms become negligible
 255 when the averaging volume goes to 0 (that is $\alpha_g \rightarrow 0$ or 1), they will not be considered here. In the remainder of this paper, the notation is simplified by using J instead of \overline{J} .

2.2.2. Average balance equations

In this paragraph, the usual notation is used for two phase flows ($\alpha := \alpha_g$
 260 is the void fraction, ρ_g and ρ_l are the densities of the gas and liquid phases, u_g and u_l their velocities, E_g and E_l their total specific energies) and the following standard approximations are made

$$\overline{\chi(\rho u \otimes u + p)} \simeq \alpha_g (\rho_g u_g \otimes u_g + p_g),$$

$$\overline{\chi((\rho E + p)u + q)} \simeq \alpha_g ((\rho_g E_g + p_g) u_g + q_g),$$

where p_g is the gas pressure, given by the equation of state $p_g = p(\rho_g, e_g)$, and
 265 similarly for the liquid phase.

After averaging of equations (6) and their counterparts for the liquid phase, and neglecting the diffusive and source terms, the following six equations system is found:

$$\partial_t(\alpha_k \rho_k) + \nabla \cdot (\alpha_k \rho_k u_k) + J \cdot \nabla \alpha_k = 0, \quad (7a)$$

$$\partial_t(\alpha_k \rho_k u_k) + \nabla \cdot (\alpha_k (\rho_k u_k \otimes u_k + p_k \mathbb{I})) - P \nabla \alpha_k = 0, \quad (7b)$$

$$\partial_t(\alpha_k \rho_k E_k) + \nabla \cdot (\alpha_k ((\rho_k E_k + p_k) u_k + q_k)) - Q \cdot \nabla \alpha_k = 0, \quad (7c)$$

for $k = l$ or g . The momentum flux (or stress tensor) P across the interface between two phases is $P \nabla \alpha_g = \overline{(u \otimes J + p \mathbb{I}) \nabla \chi}$, and the energy flux Q is defined as $Q \cdot \nabla \alpha_g = \overline{(J E + p u + q) \cdot \nabla \chi}$.

2.2.3. Closure

270 In n spatial dimensions, this problem depends on $9 + 6n$ variables ($\alpha_g, \rho_g, u_g, E_g, p_g, q_g, \alpha_l, \rho_l, u_l, E_l, p_l, q_l, J_{l \rightarrow g}, P \nabla \alpha, Q \cdot \nabla \alpha$).

The system (7) to which $\alpha_g + \alpha_l = 1$, two equations of state and the Fourier laws in both phases are added, contains in total $7 + 4n$ equations. Hence $2 + 2n$ closure relations are missing.

275 The mass and energy fluxes can be related to the local thermodynamic states at the interface (see [24]) in the form:

$$J = \mathcal{J}_{l \rightarrow g}(p_g, T_g, p_l, T_l) \nu_{l \rightarrow g}, \quad Q = \mathcal{Q}_{l \rightarrow g}(p_g, T_g, p_l, T_l) \nu_{l \rightarrow g}.$$

The following closure relation for P can be added:

$$P \nabla \alpha = (u_g \otimes J + p_g \mathbb{I}) \nabla \alpha = (u_l \otimes J + p_l \mathbb{I}) \nabla \alpha, \quad (8)$$

which is a generalization of the single-pressure closure $p_g = p_l$. This expression for $P \nabla \alpha$ ensures the consistency of the averaged model.

280 2.3. Single-velocity hypothesis

The averaged model described in the previous paragraphs will not be studied in more depth in this paper. Instead, a simplified model derived from it will be discussed.

2.3.1. Derivation

285 The single-pressure and single-velocity hypotheses ($p_g = p_l$ and $u_g = u_l$) are often used for modelling flows with two separated phases when the numerical method involves mixture cells for the description of the interface (as for instance in [21] or [22]). These hypotheses are consistent with the boundary conditions around an interface without phase change. However, at an interface with phase
290 change this is no longer true.

Indeed, at a liquid-vapor interface with phase change, the flow respects the following jump conditions (see e.g. [34]):

$$p_g - p_l = J \cdot (u_l - u_g), \quad (9)$$

$$(u_g - u_l) \cdot \nu_{l \rightarrow g} = J \left(\frac{1}{\rho_g} - \frac{1}{\rho_l} \right). \quad (10)$$

The velocity jump in (10) is due to the difference in densities: a change in
 295 velocity compensates for the change in density to keep a continuous mass flow
 across the interface. The pressure jump in (9) can be seen as the corresponding
 Venturi effect.

The usual single-velocity and single-pressure hypotheses are replaced with
 relations (9) and (10). This is completed with the following standard condition
 300 for the tangential velocities:

$$u_g \cdot \nu^\perp = u_l \cdot \nu^\perp, \quad (11)$$

for any tangential vector ν^\perp at the interface.

These simplifying hypotheses will be applied to the following isothermal
 system directly derived from (7) and (8):

$$\partial_t(\alpha_k \rho_k) + \nabla \cdot (\alpha_k \rho_k u_k) - J \cdot \nabla \alpha_k = 0, \quad (12a)$$

$$\partial_t(\alpha_k \rho_k u_k) + \nabla \cdot (\alpha_k (\rho_k u_k \otimes u_k + p_k \mathbb{I})) - (u_k \otimes J + p_k \mathbb{I}) \nabla \alpha_k = 0, \quad (12b)$$

for $k = l, g$.

The averaged quantities ρ_m and u_m are defined such that:

$$\rho_m = \sum \alpha_k \rho_k, \quad \rho_m u_m = \sum \alpha_k \rho_k u_k.$$

Using this notation, the single-velocity hypothesis (10) can be rewritten as

$$u_m - \frac{J}{\rho_m} = u_k - \frac{J}{\rho_k}. \quad (13)$$

305 Mass fraction ξ is defined as $\xi_k \rho_m = \alpha_k \rho_k$. for $k = l, g$ and from definition
 of ρ_m , $\xi_g + \xi_l = 1$.

Finally, the two mean pressures \bar{p} and \underline{p} are introduced as

$$\underline{p} = \sum \alpha_k p_k, \quad \bar{p} = \sum \xi_k p_k.$$

For simplicity, the following notation is used for the rest of the article:

$$\xi := \xi_g, \quad \alpha := \alpha_g.$$

Using this notation and hypotheses (9), (10) and (11), system (12) can be rewritten as [24]

$$\partial_t \rho_m + \nabla \cdot (\rho_m u_m) = 0, \quad (14a)$$

$$\partial_t \rho_m u_m + \nabla \cdot (\rho_m u_m \otimes u_m + \underline{p} \mathbb{I} + (\bar{p} - \underline{p}) \nu_{l \rightarrow g} \otimes \nu_{l \rightarrow g}) = 0, \quad (14b)$$

$$\partial_t \xi \rho_m + \nabla \cdot (\xi \rho_m u_m + J(\alpha - \xi)) - J \cdot \nabla \alpha = 0. \quad (14c)$$

In 1D, this system becomes

$$\partial_t \rho_m + \partial_x (\rho_m u_m) = 0, \quad (15a)$$

$$\partial_t \rho_m u_m + \partial_x (\rho_m u_m^2 + \bar{p}) = 0, \quad (15b)$$

$$\partial_t \xi \rho_m + \partial_x (\xi \rho_m u_m + J(\alpha - \xi)) - J \cdot \partial_x \alpha = 0. \quad (15c)$$

2.3.2. Simplification and summary

310 The system presented in the previous paragraphs is complicated and in this form its resolution (in particular in 2D or 3D) would be difficult. Therefore, some simplifications will be made.

The hypotheses (9) and (10) can be written as

$$u_g - u_l = O(J), \quad p_g - p_l = O(J^2).$$

For small mass flux J the pressure difference at the interface is neglected. Moreover the following assumption is made:

$$\nabla (J(\alpha - \xi)) - J \cdot \nabla \alpha \simeq -J \cdot \nabla \xi.$$

Hence, the simplified system becomes:

$$\partial_t \rho_m + \nabla \cdot (\rho_m u_m) = 0, \quad (16a)$$

$$\partial_t (\rho_m u_m) + \nabla \cdot (\rho_m u_m \otimes u_m + p \mathbb{I}) = 0, \quad (16b)$$

$$\partial_t (\xi \rho_m) + \nabla \cdot (\xi \rho_m u_m) - J \cdot \nabla \xi = 0. \quad (16c)$$

315 Only system (16) will be used to compute the test cases that follow. This averaged system is conveniently similar to the isothermal version of the original

system (2), and so the discussion on the hyperbolicity of the isothermal system and its solution to the Riemann problem are still valid.

System (16) is completed by the following closure relations:

$$\rho_g = \mathcal{R}_g(p), \quad \rho_l = \mathcal{R}_l(p), \quad \alpha = \frac{\xi \rho_m}{\rho_g}, \quad \rho_m = \alpha \rho_g + (1 - \alpha) \rho_l, \quad (17)$$

320 where functions \mathcal{R}_g and \mathcal{R}_l are isothermal equations of state for the two phases. When the phase change kinetics in (5) are included, the system contains $6 + 2n$ equations for $6 + 2n$ variables $(\rho_m, u_m, p, \xi, \rho_g, \rho_l, \alpha, J)$.

The variables ρ_m, u_m and ξ are the averaged equivalents of the exact variables ρ, u and χ . The averaged versions are expected to converge to their exact 325 counterparts when the size of the averaging volume goes to zero. In the rest of this paper, only the averaged quantities will be considered and the m index will be dropped for the sake of readability.

Note that two averaged versions of the order parameter χ have actually been introduced: the mass fraction ξ and the volume fraction α . Due to the density 330 ratio, both values can be fairly different (as seen for example in Figure 4 below). Some of the difficulties of this model come from this difference as we will see in Section 4

3. Discretization

In this section the discretization of the system (16) will be discussed.

3.1. Discretization of the non-conservative terms

The model (16) involves a non-conservative term of the form $J \cdot \nabla \xi$. The discretization strategy is to approximate the term locally using a conservative term. This approach is inspired by (but different from) the strategy of [31]. This approximation is presented in the general case of a system with non-conservative 340 terms of the form

$$\partial_t v + \nabla \cdot F(v) + C(v) : \nabla v = 0, \quad (18)$$




Figure 1: Example decomposition of the cells (solid red lines) into sub-cells (dashed blue lines) for the integration of 2D non-conservative terms.

where $C(v)$ is a tensor and $:$ denotes the tensor-matrix product such that the result is a vector. However in this paper only our simple phase change term will be tested.

Each cell will be decomposed into sub-cells for the linearization of the non-
 345 conservative terms. The final scheme does not depend on the chosen decomposition, as it is only a technical tool for the derivation of the discretized equation.

Let K be a cell with its neighbors denoted by $\mathcal{N}(K)$. Cell K is divided into $\#\mathcal{N}(K)$ sub-cells $\{K_L\}_{L \in \mathcal{N}(K)}$, such that K_L is only in contact with the neighboring cell L (see Figure 1 for an example). If K is a convex polygon (or
 350 polyhedron), such a partition of K is easily achieved by joining the center of mass of the cell to each of its corners.

The existence of a flux function G is assumed on the two neighboring sub-cells, which approximates the non-conservative term around each face, in the following way:

$$\forall x \in K_L \cup L_K, \quad C(v) : \nabla v \simeq \nabla \cdot G_{K,L}(v). \quad (19)$$

355 In the spirit of [31] we could have taken

$$G_{K,L}(v) = C(\mu_{K,L}) A^{-1}(\mu_{K,L}) F(v)$$

where $\mu_{K,L}$ is an average state between v_K and v_L and

$$A(v) = \frac{\partial F}{\partial v}.$$

For our phase change model (16), we will instead choose the simpler

$$\forall x \in K_L \cup L_K, \quad J \cdot \nabla \xi \simeq \nabla \cdot (\mathcal{J}_{l \rightarrow g}(v_K, v_L) (\nu_{l \rightarrow g})_{K,L} \xi), \quad (20)$$

where $\mathcal{J}_{l \rightarrow g}$ is the physical evaporation mass flux as defined in (5) and $(\nu_{l \rightarrow g})_{K,L}$ is the normal vector to the liquid-vapor interface as approximated at the mesh
360 face.

Using the approximation (19), the spatial derivative of the partial differential equation system can be integrated as follows [24]:

$$\int_K (\nabla \cdot F + C : \nabla v) dx \simeq \sum_{L \in \mathcal{N}(K)} |\partial K \cap \partial L| [\Phi_{K,L} - G_{K,L}(v_K)] \cdot \nu_{K,L}, \quad (21)$$

where $\Phi_{K,L}$ denotes the numerical flux approximating $F + G_{K,L}$ at the interface between K and L , $|\partial K \cap \partial L|$ is the area of the interface and $\nu_{K,L}$ is its normal
365 unit vector.

3.2. Numerical flux

Let us now discuss the approximation of the flux at the interface. The discretization proposed below is based on the Roe-type scheme of [31].

In the previous section it has been seen how an equation is locally approx-
370 imated with non-conservative terms as a conservation equation. Let us thus consider a conservation equation of the form

$$\partial_t v + \partial_x F(v) = 0. \quad (22)$$

Multiplying this equation by $A(v) = \frac{\partial F}{\partial v}$, we get

$$\partial_t F(v) + A(v) \partial_x F(v) = 0. \quad (23)$$

At an interface between cells K and L this equation is approximated in the form

$$\partial_t F(v) + \tilde{A}(v_K, v_L) \partial_x F(v) = 0, \quad (24)$$

375 where the matrix \tilde{A} is such that

$$\tilde{A}(v, v) = A(v).$$

Equation (24) is linear, so it is easily solved exactly to find the flux between the cells.

This approach is similar to the Roe scheme, although we aim to avoid the need for a Roe matrix condition $\tilde{A}(v_K, v_L) \cdot (v_K - v_L) = (F_K - F_L)$ by linearizing
 380 (23) instead of (22) (see also [31]).

In [31] an average state $\mu_{K,L}$ at the interface is used to define \tilde{A} . At a liquid-vapor interface the definition of an intermediate state between liquid and gas might be problematic (for instance, it is not clear how to define the equation of state of this average state). Thus below, a matrix \tilde{A} is defined, which
 385 depends minimally on any intermediate state. This choice will be validated by demonstrating good properties of the resulting scheme (see Section 3.3).

We denote λ_k as the k -th eigenvalue of A , l_k as an associated left eigenvector and $L = (l_k)_{1 \leq k \leq n}$ as a matrix of left eigenvectors, such that $A = L^{-1} \text{diag}(\lambda_k) L$.

390 We call “upwind- l ” Finite Volume with Characteristic Flux (FVCF) scheme the finite volume scheme which uses the following numerical flux on the face between cells K and L in the direction of the unit normal vector $\nu_{K,L}$:

$$\phi_{K,L} = \frac{F(v_K) + F(v_L)}{2} \cdot \nu_{K,L} + \text{sgn} \tilde{A}(v_K, v_L) \left(\frac{F(v_K) - F(v_L)}{2} \cdot \nu_{K,L} \right), \quad (25a)$$

where

$$\text{sgn} \tilde{A}(v_K, v_L) = \tilde{L}(v_K, v_L)^{-1} \text{diag}(\text{sgn}(\lambda_k(\mu_{K,L}))) \tilde{L}(v_K, v_L). \quad (25b)$$

For all k , the k -th line of the eigenvector matrix \tilde{L} is defined by

$$\left(\tilde{L}(v_K, v_L) \right)_k = \begin{cases} l_k(v_K) & \text{if } \lambda_k(\mu_{K,L}) > 0, \\ l_k(v_L) & \text{if } \lambda_k(\mu_{K,L}) < 0, \\ l_k(\mu_{K,L}) & \text{else,} \end{cases} \quad (25c)$$

395 and $\mu_{K,L}$ is an average state between v_K and v_L .

This numerical flux corresponds to the following upwind resolution of (24):

$$\begin{cases} l_k(v_K)\phi_{K,L} = l_k(v_K)(F(v_K) \cdot \nu_{K,L}) & \text{if } \lambda_k(\mu_{K,L}) > 0, \\ l_k(v_L)\phi_{K,L} = l_k(v_L)(F(v_L) \cdot \nu_{K,L}) & \text{if } \lambda_k(\mu_{K,L}) < 0. \end{cases} \quad (26)$$

The case when $\lambda_k(\mu_{K,L}) = 0$ has not really been studied in this work, but it is expected to be unimportant in most simulations.

The reader is referred to [35] for a discussion on the discretization of the
400 boundary conditions with this kind of scheme.

The application of numerical flux (25) to the linearized non-conservative system described in Section 3.1 gives

$$\begin{aligned} \Phi_{K,L} = & \frac{(F + G_{K,L})(v_K) + (F + G_{K,L})(v_L)}{2} \cdot \nu_{K,L} \\ & + \operatorname{sgn} \left[\widetilde{\mathbf{A}}_{K,L}(v_K, v_L) \right] \frac{(F + G_{K,L})(v_K) - (F + G_{K,L})(v_L)}{2} \cdot \nu_{K,L}, \end{aligned} \quad (27)$$

where

$$\mathbf{A}_{K,L}(v) = \frac{\partial(F + G_{K,L})}{\partial v}.$$

3.3. Maximum principle

405 As mentioned previously, this scheme has good properties with respect to the maximum principle of the variable ξ as studied for instance in [39]. For the sake of clarity, only the 1D case will be presented here.

Assuming

$$\max \left(\Phi_{j+1/2}^\rho - J_{j+1/2}, 0 \right) - \min \left(\Phi_{j-1/2}^\rho - J_{j-1/2}, 0 \right) - J_{j-1/2} + J_{j+1/2} \leq \rho_j \frac{\Delta x}{\Delta t}, \quad (28a)$$

and

$$\forall j, \quad \operatorname{sgn} \left[\left(u - \frac{J}{\rho} \right) (\mu_{j+1/2}) \right] = \operatorname{sgn} \left[\Phi_{j+1/2}^\rho - J_{j+1/2} \right], \quad (28b)$$

410 this scheme respects the local discrete maximum principle of ξ , that is

$$\forall j, \quad \forall n, \quad \min(\xi_{j-1}^n, \xi_j^n, \xi_{j+1}^n) \leq \xi_j^{n+1} \leq \max(\xi_{j-1}^n, \xi_j^n, \xi_{j+1}^n). \quad (29)$$

The first condition (28a) is a CFL-like condition on $u - J/\rho$. In most practical cases, this should be less restrictive than the CFL condition for $u \pm c$, where c is the speed of sound.

The second condition (28b) is an implicit condition on $\text{sgn}(\lambda_2(\mu_{j+1/2}))$.
 415 For the “upwind- l ” FVCF scheme, this is the only role played by the averaged state $\mu_{j+1/2}$. Using the velocity of the acoustic solver

$$u_{j+1/2} = \frac{\rho_j c_j u_j + \rho_{j+1} c_{j+1} u_{j+1}}{\rho_j c_j + \rho_{j+1} c_{j+1}} + \frac{p_j - p_{j+1}}{\rho_j c_j + \rho_{j+1} c_{j+1}},$$

as the velocity of the intermediate state $\mu_{j+1/2}$ is sufficient in most practical cases.

Equation (29) is important because it ensures that non-physical mass frac-
 420 tions, $\xi < 0$ or $\xi > 1$, do not appear. For instance, the numerical scheme of [20] does not respect this property and non-physical mass fractions can appear, even for simple 1D advection problems without phase change. These non-physical values often cause the simulation to fail. The development of the new variant of the FVCF scheme presented in the previous paragraphs was motivated by this
 425 property.

4. Validation test cases

Some simple test cases are presented in this section that aim to validate the model and its implementation. In particular, one of our objectives is to create a model for which phase change is as independent as possible of the thickness
 430 of the numerical mixture layer at the interface. However, no reference test case for this kind of model was found in the literature, thus original test cases will be proposed.

4.1. 1D forced oscillating phase change

The purpose of this first test case is to validate the ability of the code to
 435 describe the interface and deal with non-trivial density ratios. In order to focus on these points, the mass flux will be independent of the system evolution. Using

this hypothesis, an analytical solution will be provided for comparison with the numerical results.




Figure 2: Initial conditions for the test cases given in Sections 4.1 and 4.3.

Considering a tube of section S and length H that is closed at both ends.
 440 The tube is initially filled with a volume $S \times h_{g,0}$ of gas and $S \times (H - h_{g,0})$ of liquid (see Figure 2). These phases respectively follow the isothermal ideal gas and isothermal stiffened gas equations of state, that is:

$$\rho_g(p) = \frac{p}{c_{g,0}^2}, \quad \rho_l(p) = \rho_{l,0} + \frac{p - p_0}{c_{l,0}^2},$$

where $c_{g,0}$ and $c_{l,0}$ are the respective sound speeds in the gas and liquid. We denote by $\rho_{g,0}$ and $\rho_{l,0}$ the densities at the reference pressure p_0 (that is $p_0 =$
 445 $\rho_{g,0} c_{g,0}^2$).

4.1.1. Choice of $J_{l \rightarrow g}$

An evaporation mass flux $J_{l \rightarrow g}(t)$ is set at the interface to be $J_{l \rightarrow g}(t) = A \sin(\omega t)$ with constant coefficients A and ω . The choice of A and ω is governed by the following constraints:

- 450 • The pressure must remain positive (and thus the densities also remain positive). For this, it is sufficient to set

$$A > 0. \tag{30a}$$

- The fluid velocity must be subsonic $\forall t$, $u(t) < c$, with the following upper bound for the escaping gas velocity

$$\max(u_g) \leq \frac{\max(|J_{l \rightarrow g}|)}{\min(\rho_g)} = \frac{A}{\rho_{g,0}} < c_{g,0}. \tag{30b}$$

Note that this upper bound is actually never reached during the simulation
 455 because maximum $|J_{l \rightarrow g}|$ does not occur at the same time as minimum
 ρ_g .

- In order to compare with the analytical solution, the variations in mass flux must be slow enough for the homogeneous pressure hypotheses to be valid:

$$\omega \ll \frac{c_{g,0}}{H}. \quad (30c)$$

460 4.1.2. Dimensionless form

The previous equations can be rewritten in dimensionless form. Dimensionless variables are denoted with a tilde and they are defined as

$$h_g = h_{g,0} \tilde{h}_g, \quad \rho_g = \rho_{g,0} \tilde{\rho}_g, \quad \rho_l = \rho_{g,0} \tilde{\rho}_l, \quad t = \frac{h_{g,0}}{c_{g,0}} \tilde{t},$$

$$p = p_0 \tilde{p}, \quad J_{l \rightarrow g} = \rho_{g,0} c_{g,0} \tilde{J}_{l \rightarrow g}.$$

The equations of state then read:

$$\tilde{\rho}_g = \tilde{p}, \quad \tilde{\rho}_l = \frac{1 + \text{CR}(\tilde{p} - 1)}{\text{DR}}.$$

465 where DR and CR are respectively the density ratio and compressibility ratio, defined as follows:

$$\text{DR} = \frac{\rho_{g,0}}{\rho_{l,0}}, \quad \text{CR} = \frac{\rho_{g,0} c_{g,0}^2}{p_0} \times \frac{p_0}{\rho_{l,0} c_{l,0}^2} = \frac{\rho_{g,0} c_{g,0}^2}{\rho_{l,0} c_{l,0}^2}.$$

The total length of the domain is written in dimensionless form as the aspect ratio \tilde{H}

$$\tilde{H} = \frac{H}{h_{g,0}}.$$

The mass flux can be written as

$$\tilde{J}_{l \rightarrow g} = \text{Ma} \sin(\tilde{\omega} \tilde{t}),$$

470 where

$$\tilde{\omega} = \frac{\omega h_{g,0}}{c_{g,0}}, \quad \text{Ma} = \frac{A}{\rho_{g,0} c_{g,0}}.$$

The dimensionless number Ma can be understood as the Mach number associated with the maximal escaping gas velocity in equation (30b).

The initial conditions can be written in dimensionless form as

$$\tilde{p}(0, \tilde{x}) = 1, \quad \begin{cases} \xi(0, \tilde{x}) = 1 & \text{if } 0 < \tilde{x} < 1, \\ \xi(0, \tilde{x}) = 0 & \text{if } 1 < \tilde{x} < \tilde{H}. \end{cases}$$

where the dimensionless abscissa \tilde{x} is defined as $h_{g,0} \tilde{x} = x$.

475 Finally, conditions (30) become

$$0 < \text{Ma} < 1, \quad \tilde{\omega} \tilde{H} \ll 1.$$

The problem depends on five parameters, which are DR, CR, \tilde{H} , Ma and $\tilde{\omega}$. Table 1 proposes some values for these parameters, where the values of DR and CR are inspired by the properties of water and steam.

DR	10^{-3}
CR	$4 \cdot 10^{-5}$
\tilde{H}	2
Ma	0.1
$\tilde{\omega}$	0.05

Table 1: Dimensionless parameters used for the numerical resolution.

4.1.3. Analytical solution

480 Assuming a homogeneous pressure in the tube, the dimensionless pressure is the solution of: [24]

$$(1 + \text{CR}(\tilde{p} - 1)) \left(\tilde{H} - \frac{1 + \hat{m}(t)}{\tilde{p}} \right) - \tilde{H} + 1 + \text{DR} \hat{m}(t) = 0 \quad (31)$$

where $\hat{m}(t)$ is the dimensionless exchanged mass:

$$\hat{m}(t) = \int_0^{\tilde{t}} \tilde{J}_{l \rightarrow g}(s) \, ds.$$

In practice, the role of liquid compressibility is negligible for the studied fluids. Thus, it can be neglected and the dimensionless pressure $\tilde{p}(t)$ can be

485 written as

$$\tilde{p} = \frac{1 + \hat{m}(t)}{1 + \text{DR} \hat{m}(t)} + O(\text{CR}). \quad (32)$$

4.1.4. Results and comments




Figure 3: Evolution of dimensionless total mass of gas (top) and dimensionless pressure in the middle of the domain (bottom) as functions of dimensionless time for the numerical simulations and the reference solution. Parameters are given in Table 1. The period is $2\pi/\tilde{\omega} \simeq 125$.

In Figure 3 the time variation of total mass of gas and pressure in the domain is shown. Due to the liquid being very dense and almost incompressible, the volume of gas is nearly constant and the pressure is thus proportional to the total mass of gas (equal in dimensionless magnitude). The numerical results are in good agreement with the exact solution, except for the coarser meshes with 30 and 60 cells.

The inaccuracy of the coarser meshes can be explained by studying the




Figure 4: Profiles of mass fraction ξ and of volume fraction α after one period (at $\tilde{t} \simeq 125$), for the same numerical computations as in Figure 3.

mass fraction profile, shown in Figure 4. Numerical diffusion in the coarser
 495 simulations has enlarged the interface, so that it reaches the boundary of the
 domain. In this situation the total exchanged gas mass is no longer the same
 ($\int |\nabla \xi| dx \neq 1$). The numerical diffusion is reduced for finer meshes and the bias
 that occurs due to the interface interacting with the boundary appears later in
 the computation.

500 Within a single period, the numerical diffusion rate changes with the phase
 change rate. However, on average over several periods, the thickness of the
 diffused interface will grow according to $\sqrt{t \Delta x}$. Indeed, for a first order upwind
 scheme such as ours, the numerical diffusion coefficient is proportional to the
 cell size Δx (see [40] for a derivation of the equivalent equation). Thus, the
 505 time taken for the interface to reach the domain boundary will be proportional
 to the number of cells in the mesh, as seen in Figure 3 between the 30 and 60
 cell cases.

Except for this limiting case in which the mixture layer covers the whole gas
 domain, the numerical solution stays consistent with the analytical solution,
 510 despite the change in the thickness of the mixture layer.

The diffusion of the volume fraction α is almost symmetrical around the
 expected position of the interface. Due to the low density ratio, the profiles of
 ξ and α appear to be significantly different.

In Figure 5, the velocity profile is shown at a time of maximal evaporation
 515 rate. Gas is escaping the interface to the right, which is demonstrated by a
 positive velocity. The velocity of the liquid is almost zero (the liquid is in
 fact slightly compressed by the pressure rise). A jump in velocity appears at
 the interface, as presented in (10). The jump is diffused along the profile in a
 similar way to ξ . A zero velocity is imposed by the boundary condition at the
 520 walls, causing a linear velocity gradient in the gas phase.

Finally, the gas velocity profile is shown in Figure 6. The gas velocity \widetilde{u}_g
 is computed from the mixture velocity $\widetilde{u} \equiv \widetilde{u}_m$ with the help of (13). In the diffuse
 interface (approximately between $\widetilde{x} = 1.0$ and $\widetilde{x} = 1.3$), the gas velocity is not
 affected by the mixture and is the exact gas velocity at the interface in these




Figure 5: Profiles of dimensionless mixture velocity at $\tilde{t} \simeq 155$ (approximately 5/4 of a period, at a time when the evaporation mass flux is maximal) for the same numerical computations as in Figure 3.




Figure 6: Profiles of dimensionless gas velocity and mixture velocity at $\tilde{t} \simeq 155$ (at $5/4$ of a period when the evaporation mass flux is maximal) for the numerical computation with 120 cells. The gas velocity is computed from the mixture velocity using (13). On the left hand side, the mixture is pure liquid and the velocity of the gas is irrelevant.

525 conditions. The gas velocity profile converges towards the mixture velocity, as
 530 seen in Figure 5, when the diffusion of the interface tends to zero.

4.2. 2D forced oscillating phase change

This test case is an extension of the 1D test case in the previous section in
 two dimensions. Its purpose is to prove the multi-dimensional validity of the
 530 model.

4.2.1. Setup




Figure 7: Schematic of the 2D forced phase change test case. By symmetry, only the top right corner will be solved numerically.

Consider a gas bubble of initial radius r_0 surrounded by liquid (see Figure 7)
 enclosed in a square domain. As for the previous test case, the fluids are de-
 scribed by the isothermal ideal gas and isothermal stiffened gas equations of
 535 state.

Assuming that the pressure is homogeneous in the whole domain and that
 the liquid is heavy and incompressible (that is $DR \ll 1$ and $CR \ll 1$), then the
 pressure satisfies:

$$p(t) = p_0 \left(1 + \frac{2}{\rho_{g,0} r_0} \int_0^t J_{l \rightarrow g}(s) ds \right). \quad (33)$$

4.2.2. Interface normal vector evaluation

540 The surfacic mass flux at the interface is given by the same arbitrary expression $J_{l \rightarrow g}(t) = A \sin(\omega t)$ as used in the 1D case. However, in 2D the linearization of the phase change term $J \cdot \nabla \xi$ also requires the computation of the unit normal at the liquid vapor interface $\nu_{l \rightarrow g}$, as seen in (20).

The simplest method is a first order approximation of the following form:

$$(\nu_{l \rightarrow g})_{K,L} = \begin{cases} +\nu_{K,L} & \text{if } \xi_K > \xi_L, \\ -\nu_{K,L} & \text{else.} \end{cases} \quad (34)$$

545 This choice of discretization of $\nu_{l \rightarrow g}$ may reduce the quality of the solution by affecting the total exchanged mass. Namely, the approximation of the interface orientation influences the total length (in 3D the total surface) of the interface. This phenomenon is illustrated in Figure 8. In this case, the total length of the interface is $4/\pi$ times longer than the actual length. The total exchanged mass
 550 will thus be larger for a given surfacic mass flux. To illustrate this phenomenon, the following numerical results are compared to the following variant of (33), which takes this bias into account:

$$p = p_0 \left(1 + \frac{2}{\rho_{g,0} r_0} \frac{4}{\pi} \int_0^t J_{l \rightarrow g}(s) ds \right). \quad (35)$$




Figure 8: Approximation of an arc circle on a Cartesian mesh. If the radius of the circle is 1, the length of the discrete interface (in red) is always 2, for any grid resolution. The discrete interface length does not converge towards the actual length of the interface, which is $\pi/2$.

The unit normal at the interface may be expressed as $\nu_{l \rightarrow g} \simeq \frac{\nabla \xi}{|\nabla \xi|}$. For a higher order numerical resolution, this can be evaluated with the following formula:

$$\frac{\partial \xi}{\partial x} \simeq \frac{(\xi_{NE} - \xi_{NW}) + (\xi_{SE} - \xi_{SW})}{4 \Delta x} \quad (36a)$$

$$\frac{\partial \xi}{\partial y} \simeq \frac{(\xi_{NW} - \xi_{SW}) + 2(\xi_N - \xi_S) + (\xi_{NE} - \xi_{SE})}{4 \Delta x} \quad (36b)$$

where the notation is given in Figure 9. The complete study of this kind of discretization (including, for instance, the behavior at the boundary of the domain) is beyond the scope of this paper.




Figure 9: Notation used for the numerical evaluation of the unit normal vector at the liquid-vapor interface on a Cartesian mesh as given in (36). The cells are squares of size $\Delta x \times \Delta x$. Here, we wish to linearize the phase change term at the interface between cells N and S.

Finally, for this particular test case, let us notice that the exact shape of the interface is always known. Due to the problem having spherical symmetry, the normal vector is always given by:

$$\nu_{l \rightarrow g} = \frac{1}{\sqrt{(x - x_0)^2 + (y - y_0)^2}} \begin{pmatrix} x - x_0 \\ y - y_0 \end{pmatrix}, \quad (37)$$

where (x_0, y_0) is the center of symmetry of the problem.

These three methods for the computation of $\nu_{l \rightarrow g}$ will be used in the following numerical simulations and their results will be compared.

4.2.3. Results and comments

Several computations have been carried out with the same parameters as the 1D case (see Table 1). Figure 10 displays the evolution of the pressure as a function of time for various discretizations of the unit normal at the interface. All computations have been made with $\text{CFL} = 0.25$.




Figure 10: Evolution of the dimensionless pressure (at the center of the domain) as a function of dimensionless time for various mesh sizes and different approximations of the unit normal at the liquid-vapor interface. The plain and dashed red lines are the reference analytical solutions.

As expected, the first order reconstruction of the interface normal (34) is close to the biased analytical solution (35), while the second order reconstruction (36) gives a result that is closer to the exact solution. However, only the exact value of the normal, as given by (37), gives the same pressure as the analytical pressure (33).

In the 1D case, the effective interfacial area $\int |\nabla \xi| dx$ remains the same when the interface is diffused (providing the boundaries of the domain are not crossed). So the total mass exchanged between the phases is not affected by numerical diffusion.

The situation is more complex for the 2D problem because smearing of the liquid-vapor mass fraction distribution actually affects the effective interfacial area. Figure 11 shows the spatial distribution of ξ and α after one oscillation. Due to the density ratio, the gradients of mass fraction ξ and volume fraction




Figure 11: Level set for the mass fraction ξ (in blue) and the volume fraction α (in red) after one period ($\tilde{t} = 125$) for an 80×80 cell mesh using the discretization given by (34). To be compared with Figure 4.

580 α are not superimposed (as in Figure 4). Although the effective interfacial area $\int |\nabla \alpha| dx$ remains fairly constant, the effective interfacial area $\int |\nabla \xi| dx$ changes. Since the $\nabla \xi$ term is playing the role of locating the interface in (16), the total quantity of exchanged mass is thus reduced and any pressure oscillations are damped after the first peak.

585 Some good properties of the code have been demonstrated using the 1D test case, particularly regarding the independence of the numerical solution with regard to the thickness of the mixture layer. However, the 2D case is more difficult and some work should still be done to better capture the solution.

Although $\nabla \xi$ naturally appeared in the derivations of Section 2, checks could
 590 be made to show whether its replacement with $\nabla \alpha$ would improve the quality of the model. This replacement is actually a major change in the implementation: the approximation (20) has to be modified and the diagonalization of the advection matrix in the scheme (25) might be significantly affected. In preliminary

tests, this replacement led to a less smooth and less stable velocity profile at
 595 the interface in comparison with Figure 5. The term $\nabla\xi$ appeared in Section 2
 as a consequence of the single velocity hypothesis (2.3) and it is thought to be
 the reason of the good behavior of our code with respect to the velocity jump
 in 1D.

4.3. 1D return to equilibrium

600 Finally, a simple test case is given that challenges the ability of the code to
 deal with less trivial expressions for the mass flux.

4.3.1. Setup

As mentioned in Section 2.1, the relaxation mass flux will take the following
 form:

$$J_{l\rightarrow g} = \rho_{g,0} c_{g,0} \Omega \frac{p_0 - p_g}{p_0}. \quad (38)$$

605 A constant dimensionless relaxation rate $\Omega > 0$ is chosen according to sim-
 ilar constraints as (30b). Here, we set $\Omega = 0.1$ and $p(t = 0) - p_0 \sim 0.1 p_0$, and
 thus $\max(|J|) \sim 0.01 \rho_{g,0} c_{g,0}$. This is the highest relaxation rate that could be
 simulated for a 120 cell mesh with a CFL number of 0.8, which corresponds to
 $\Delta\tilde{t} \simeq 2 \cdot 10^{-3}$. A higher relaxation rate can be achieved by reducing the time
 610 step. However, in our tests, this time step is still several orders of magnitude
 below the characteristic relaxation time $1/\Omega$. The validity range of the hypothe-
 ses given in Sections 2.3.2 and 3.3 should be investigated further, as well as the
 stability of the explicit Euler time discretization.

Two variants of the initial condition are used with different interface dif-
 615 fusions to check the robustness of the numerical scheme and the influence of
 the interface thickness. These initial conditions are shown in Figure 12. The
 equations of state and initial condition are similar to the test case in Section 4.1
 and Table 1. The magnitudes ξ and α cannot both have symmetrical profiles:
 it has been chosen to have symmetrical α magnitude to ensure that the total
 620 mass of gas and liquid are the same with or without the diffused interface.




Figure 12: Initial profiles of mass fraction ξ (solid blue lines) and volume fraction α (dashed red lines), for the sharp initial condition (left) and the diffuse initial condition (right). On the left, the mass fraction and the volume fraction curves are superimposed.

Four different initial pressures will be tested for both evaporation ($p < p_0$) and condensation ($p > p_0$).

Assuming the pressure to be homogeneous in the gas phase and the volume available for the gas phase to be constant (due to the low density ratio), the dimensionless pressure can be shown to respect:

$$\frac{d\tilde{p}}{dt} = \Omega(1 - \tilde{p}). \quad (39)$$

This analytical solution will be compared to the numerical results.

4.3.2. Results and Discussion

Figure 13 presents the evolution of the mass and pressure. In all cases, the system relaxes to the $p = p_0$ equilibrium state. Both mesh refinement and initial diffusion of the interface do not lead to any difference in the evolution of the total gas mass. However, the pressure at the center of the domain is slightly affected, although the mean pressure over the whole domain is the same at all resolutions.

The staircase like behavior of the pressure evolution for the cases with a sharp initial interface is caused by pressure waves emitted by the phase change at the interface. These waves take a finite amount of time to travel through the gas phase to the boundary of the domain and return to the interface.




Figure 13: Evolution of dimensionless total gas mass (top) and dimensionless pressure at the center of the domain (bottom) as a function of dimensionless time for four different initial pressures, two initial interface diffusions and two different mesh refinements (16 cases in total). The pressures are compared to the analytical solution in (39). The mass evolution curves are superimposed for a given initial pressure.

For a diffuse initial interface the compression wave emitted by the interface is smoother than the sharp shock emitted by the sharp interface. Moreover, the interaction of a pressure wave with a diffuse interface can lead to pressure oscillations inside the diffuse interface, probably due to spatial gradients in the speed of sound. This effect does not seem to influence the phase change relaxation.

The staircase effect would probably not appear experimentally since real liquid-vapor phase change is not isothermal: it is directed by the thermal diffusion of the latent heat as well as the pressure evolution.

5. Application to a simplified 2D impact case




Figure 14: Scheme of the simplified impact test case from [41].

In order to evaluate the effect of phase change on a 2D liquid impact, the numerical test case of [41] is now studied. It is a simple impact scenario consisting of a free falling rectangular liquid block within a much larger rectangular tank of gas (see Figure 14). This test was first proposed by [41] and was used as a benchmark study organized within the ISOPE conferences in 2010 and 2013. Despite its simplicity, this test case shows the different steps of a liquid impact on a solid surface, including the incompressible and then compressible escape of the gas from the space between liquid and wall. Previously, this test case has been studied with phase change by [6].

The fluids are modeled by the same isothermal equations of state (isothermal ideal gas and isothermal stiffened gas) as in the previous test cases. The acceleration due to gravity ($g = 10 \text{ m s}^{-1}$) is modeled classically as a momentum source term on the right hand side of (16) and discretized using the Euler forward method.

For a more efficient numerical resolution of the problem, an adaptive mesh refinement method, based on a quad-tree approach has been used. An example result at the time of maximum pressure is shown in Figure 15 along with the mesh. The mesh is refined when either the norm of the gradient of mass fraction,

the norm of the gradient of volume fraction or the norm of the gradient of pressure are above an arbitrary threshold. Though the finest mesh cells are $2^{-4} \text{ m} = 62.5 \text{ mm}$ in size, the result is still far from mesh convergence. Due to the coarseness of the mesh in comparison with the highest resolution results of [4], for example, and due to the formation of a numerical mixture layer at the interface, a strong mitigation of the impact pressure is observed. Anyway, since here the gas is modeled as isothermal, the impact time and pressure would be different to the reference adiabatic simulations. Nonetheless, we can compare our own simulations with and without phase change.

In Figure 16, the evolution of the pressure at the center of the impact wall is shown for three different values of the phase change coefficient Ω as defined in (38). Despite the promising properties of the numerical scheme, direct simulation of the higher relaxation rate is not possible, as already mentioned for the previous test case. The dashed lines in Figure 16 are the cases where it was necessary to add the following fix to get an answer:

$$\xi^{n+1*} = \min(1, \max(0, \xi^{n+1})).$$

Although a supplementary numerical bias might have been introduced in our solutions, this gives a clear idea of the expected qualitative behavior for higher phase change rates. Further work, such as an implicit resolution of the stiff phase change term, may be required here.

A magnification of the pressure peak due to phase change is observed. These results are comparable to the tendencies observed by [6] for the same test case. A more violent impact is observed due to gas vanishing by condensation, which is in addition to gas escaping between the free surface and the wall. Put simply, there is a lower resistance to the falling liquid when more gas escapes, which causes the impact velocity to be higher.

The maximal pressure observed is actually not the pressure of the direct impact of the liquid, but is instead the pressure in a thin gas pocket which is holding the liquid away from the surface, as is visible in Figure 15. The formation of this gas pocket is affected by the entrapment of gas in the diffuse




Figure 15: Mesh (left) and density (right) (in kg m^{-3}) initially (above) and at the time of maximum pressure (below).

695 interface, but it is not only a numerical artifact as it has been observed in other
work, such as [41]. A shortening of the oscillation period of the gas pocket
pressure is observed due to phase change. This can be explained by condensation
causing a reduction in the volume of trapped gas during the impact. Indeed, for
the problem of a piston oscillating on a gas pocket [42], the period of oscillation
700 is shown to change with the size of the gas pocket. The effect of phase change
on the piston problem has also been discussed in [24] and [32].




Figure 16: Pressure at the center of the impact wall as a function of time. Without phase change ($\Omega = 0$) and for several relaxation rates Ω with phase change.

6. Conclusion

A physical model that describes a flow with two separate phases including
phase change has been presented and an averaged version of the model has then
705 been derived. Unlike other averaged models that are commonly used, phase
change is described by a non-conservative advection term. At the interface, this
approach limits the influence of the numerical mixture layer thickness on phase

change.

A Roe-type scheme for the discretization of this model is also presented,
710 which is a new variant of the FVCF scheme from [31]. By using an alterna-
tive upwinding matrix, the scheme has improved behavior with respect to the
maximum principle of the mass fraction. The alternative matrix allows us to
solve stiffer problems than in previous computations of a similar type, such as
[20]. Indeed, such models that do not respect the maximum principle discussed
715 in Section 3.3, often see the appearance of non-physical negative mass frac-
tions which cause the simulation to end prematurely, even for constant-velocity
advection problems without phase change.

This result has several shortcomings and can only be considered as prelim-
inary. Improvements are still necessary, especially for the stiffest phase change
720 problems, and implicit resolution of the stiff phase change term could be the
next step. Also, higher order discretization in space and further study of the
automatic mesh refinement criteria could help to improve the quality of the
solution with and without phase change.

Thus far, only an isothermal version of the model has been derived and
725 implemented. Such a strong hypothesis is not physically justified for liquid-
vapor phase change, and particularly not for the problem of liquid impacts on
solid walls. This model is nonetheless useful to help understand the behavior
of a numerical code when dealing with strong changes in fluid density. The
model and discretization presented in this paper are able to simulate relatively
730 high evaporation rates at the interface between separated fluids with realistic
densities.

In the final section of this paper, the effect of phase change on a simple wave
impact test case has been computed. Phase change causes gas to disappear
which results in a higher impact velocity of the liquid on the wall. However, the
735 isothermal hypotheses may cause an overestimation of the magnitude of this
effect. According to surrogate models [24], the latent heat may indeed be a
limiting factor. The simulations shown in the final section have several other
shortcomings (such as relatively high diffusion of the liquid-vapor interface) and

should therefore be considered as a prototype.

740 Instead of the isothermal hypothesis, a model with a similar level of complexity could have been built by considering an adiabatic evolution in which the latent heat is artificially set to zero. Such a model would have brought results closer to the usual wave impact models in the case without phase change. However, such a model would be as approximate as the current model when
745 it comes to evaluating the influence of phase change. Besides, the isothermal phase change hypothesis is more common in the literature and it has allowed us to compare our model to [26] in [24].

A further challenge for phase change simulations is dealing with a high latent heat. The mixture model defined in this paper makes the evaluation of the
750 entropy creation at the interface difficult. Thus, it is not easy to distribute the latent heat in the diffused interface in a way that is compatible with the second law of thermodynamics. In [25], a naive extension of (16) that includes the energy equation has nonetheless been used. However, this system has not been rigorously derived and the treatment of the latent heat across a diffuse interface
755 might present some difficulties.

The results presented in this work are in contradiction to the experimental results of [2] discussed earlier, in which a pressure reduction was noticed. In this paper, only a single aspect of the influence of phase change on wave impacts has been discussed: that is the effect on the compressed escaping gas in front of the
760 liquid before the impact. Other works using different approaches [24, 32, 33] have shown a pressure reduction in the entrapped gas pockets after the impact. Further work is necessary to have a complete description of the total effect of phase change during a complete impact.

Let us finally note that a realistic wave impact involves free surface instabilities, which have not been taken into account in this work. Phase change in
765 aerated liquids leads to a reduction in the acoustic pressure for a given impact velocity. If the developed instabilities are roughly modeled as a layer of aerated liquid, it may then be possible to observe both an increase in the impact velocity, as in Section 5, and a decrease in the maximal pressure. Improved understand-

770 ing of the physics of wave impacts in the presence of free surface instabilities is
thus needed to make conclusions on the effect of phase change.

7. Acknowledgment

This work was carried out during the Ph.D. degree studies of the first author,
with the support of GTT and the Association Nationale de la Recherche et de la
775 Technologie (ANRT) through *CIFRE* contract 2013/1301. The authors thank
John Redford (CMLA) for proof-reading the article.

8. References

- [1] E. Gervaise, P.-E. de Sèze, S. Maillard, Reliability-based methodology for
sloshing assessment of membrane LNG vessels, in: Proc. of the 19th Int.
780 Offshore and Polar Eng. Conf., Vol. 3, ISOPE, 2009, pp. 183–191.
- [2] S. Maillard, L. Brosset, Influence of density ratio between liquid and gas
on sloshing model test results, Int. J. of Offshore and Polar Eng. 19 (4)
(2009) 271–279.
- [3] W. Lafeber, L. Brosset, H. Bogaert, Elementary loading processes (ELP)
785 involved in breaking wave impacts: findings from the sloshel project, in:
Proc. of the 22nd Int. Offshore and Polar Eng. Conf., Vol. 3, ISOPE, 2012,
pp. 265–276.
- [4] P.-M. Guilcher, Y. Jus, N. Couty, L. Brosset, Y.-M. Scolan, D. Le Touzé, 2d
790 simulations of breaking wave impacts on a flat rigid wall – part 1: influence
of the wave shape, in: Proc. of the 24th Int. Offshore and Polar Eng. Conf.,
Vol. 3, ISOPE, 2014, pp. 232–245.
- [5] F. Dias, J.-M. Ghidaglia, Slamming: Recent progress in the evaluation of
impact pressures, Annual Review of Fluid Mechanics 50 (2018) 243–273.

- [6] P. Behruzi, M. Konopka, F. de Rose, G. Schwartz, Cryogenic slosh modeling
795 in LNG ship tanks and spacecrafts, in: Proc. of the 24th Int. Offshore and
Polar Eng. Conf., Vol. 3, ISOPE, 2014, pp. 209–217.
- [7] P. Behruzi, D. Gaulke, D. Haake, L. Brosset, Modeling of impact waves in
LNG ship tanks, *Int. J. Offshore and Polar Eng.* 27 (1) (2017) 18–26.
- [8] T. Arndt, M. Dreyer, P. Behruzi, M. Winter, A. vanForeest, Cryo-
800 genic sloshing tests in a pressurized cylindrical reservoir, in: 45th
AIAA/ASME/SAE/ASEE Joint Propulsion Conference & Exhibit, 2009,
p. 4860.
- [9] D. Jamet, O. Lebaigue, N. Coutris, J. M. Delhayé, The second gradient
method for the direct numerical simulation of liquid–vapor flows with phase
805 change, *J. Comput. Phys.* 169 (2) (2001) 624–651.
- [10] D. Bestion, The physical closure laws in the CATHARE code, *Nucl. Eng.
and Des.* 124 (3) (1990) 229–245.
- [11] M. Ishii, T. Hibiki, *Thermo-fluid dynamics of two-phase flow*, Springer New
York, 2011.
- 810 [12] I. Toumi, A weak formulation of Roe’s approximate riemann solver, *J.
Comput. Phys.* 102 (2) (1992) 360–373.
- [13] J. G. Collier, J. R. Thome, *Convective boiling and condensation*, Clarendon
Press, 1994.
- [14] A. Faghri, Y. Zhang, *Transport phenomena in multiphase systems*, Elsevier,
815 2006.
- [15] D. Juric, G. Tryggvason, Computations of boiling flows, *Int. J. Multiph.
Flow* 24 (3) (1998) 387–410.
- [16] C. Kunkelmann, Numerical modeling and investigation of boiling phenom-
ena, Ph.D. thesis, TU Darmstadt (2011).

- 820 [17] J. Stefan, Über die Theorie der Eisbildung, Monatshefte für Mathematik und Physik 1 (1) (1890) 1–6.
- [18] R. Marek, J. Straub, Analysis of the evaporation coefficient and the condensation coefficient of water, International Journal of Heat and Mass Transfer 44 (1) (2001) 39–53.
- 825 [19] V. K. Badam, V. Kumar, F. Durst, K. Danov, Experimental and theoretical investigations on interfacial temperature jumps during evaporation, Experimental Thermal and Fluid Science 32 (1) (2007) 276–292.
- [20] F. Dias, D. Dutykh, J.-M. Ghidaglia, A two-fluid model for violent aerated flows, Computers & Fluids 39 (2) (2010) 283–293.
- 830 [21] J. J. Kreeft, B. Koren, A new formulation of Kapila’s five-equation model for compressible two-fluid flow, and its numerical treatment, J. Comput. Phys. 229 (18) (2010) 6220–6242.
- [22] A. Bernard-Champmartin, F. De Vuyst, A low diffusive Lagrange-remap scheme for the simulation of violent air-water free-surface flows., J. Comput. 835 Phys. 274 (2014) 19–49.
- [23] P. D. Hicks, LNG-solid impacts with gas cushioning and phase change, Journal of Fluids and Structures 80 (2018) 22 – 36.
- [24] M. Ancellin, Sur la modélisation physique et numérique du changement de phase interfacial lors d’impacts de vagues, Ph.D. thesis, École normale 840 supérieure Paris-Saclay (2017).
- [25] M. Ancellin, L. Brosset, J.-M. Ghidaglia, Preliminary numerical results on the influence of phase change on wave impacts loads, in: Proc. of the 26th Int. Offshore and Polar Eng. Conf., Vol. 3, ISOPE, 2016, pp. 886–893.
- 845 [26] M. Hantke, W. Dreyer, G. Warnecke, Exact solutions to the Riemann problem for compressible isothermal Euler equations for two-phase flows with and without phase transition, Q. of Appl. Math. 71 (3) (2013) 509–540.

- [27] C. Rohde, C. Zeiler, A relaxation Riemann solver for compressible two-phase flow with phase transition and surface tension, *Appl. Numer. Math.* 95 (2014) 267–279.
- 850 [28] R. Saurel, F. Petitpas, R. Abgrall, Modelling phase transition in metastable liquids: application to cavitating and flashing flows, *J. Fluid Mech.* 607 (2008) 313–350.
- [29] S. Le Martelot, R. Saurel, B. Nkonga, Towards the direct numerical simulation of nucleate boiling flows, *Int. J. Multiph. Flow* 66 (2014) 62–78.
- 855 [30] M. Ancellin, L. Brosset, J.-M. Ghidaglia, A hyperbolic model of nonequilibrium phase change at a sharp liquid–vapor interface, in: C. Klingenberg, M. Westdickenberg (Eds.), *Theory, Numerics and Applications of Hyperbolic Problems I (Hyp2016)*, Springer International Publishing, Cham, 2018, pp. 59–69.
- 860 [31] J.-M. Ghidaglia, A. Kumbaro, G. Le Coq, On the numerical solution to two fluid models via a cell centered finite volume method, *Eur. J. Mech. B/Fluids* 20 (6) (2001) 841–867.
- [32] M. Ancellin, L. Brosset, J.-M. Ghidaglia, Influence of phase transition on sloshing impact pressures described by a generalized Bagnold’s model, in: Proc. of the 22nd Int. Offshore and Polar Eng. Conf., Vol. 3, ISOPE, 2012, pp. 300–310.
- 865 [33] M. Ancellin, L. Brosset, J.-M. Ghidaglia, Numerical study of phase change influence on wave impact loads in LNG tanks on floating structures, in: Proc. of the 37th Int. Conf. on Ocean, Offshore and Arctic Eng. (OMAE2018), 2018.
- 870 [34] J. M. Delhaye, Jump conditions and entropy sources in two-phase systems. local instant formulation, *Int. J. Multiph. Flow* 1 (3) (1974) 395–409.

- [35] J.-M. Ghidaglia, F. Pascal, On boundary conditions for multidimensional hyperbolic systems of conservation laws in the finite volume framework, Tech. rep., École normale supérieure de Cachan (2002).
875
- [36] S. Faure, J.-M. Ghidaglia, Violent flows in aqueous foams i: Physical and numerical models, *Eur. J. Mech. B/Fluids* 30 (4) (2011) 341–359.
- [37] G. Witterstein, Sharp interface limit of phase change flows, *Adv. in Math. Sci. and Appl.* 20 (2) (2010) 585–629.
- 880 [38] H. W. Alt, G. Witterstein, Distributional equation in the limit of phase transition for fluids, *Interfaces and Free Boundaries* 13 (4) (2011) 531–554.
- [39] B. Larrouturou, How to preserve the mass fractions positivity when computing compressible multi-component flows, *J. Comput. Phys.* 95 (1) (1991) 59–84.
- 885 [40] L. Zhang, Modélisation, analyse et simulations d’écoulements en thermohydraulique par modèles à six équations, Ph.D. thesis, École normale supérieure Paris-Saclay (2017).
- [41] J.-P. Braeunig, L. Brosset, F. Dias, J.-M. Ghidaglia, Phenomenological study of liquid impacts through 2d compressible two-fluid numerical simulations, in: *Proc. of the 19th Int. Offshore and Polar Eng. Conf.*, Vol. 3, ISOPE, 2009, pp. 21–29.
890
- [42] L. Brosset, J.-M. Ghidaglia, P.-M. Guilcher, L. Le Tarnec, Generalized Bagnold model, in: *Proc. of the 23rd Int. Offshore and Polar Eng. Conf.*, Vol. 3, ISOPE, 2013, pp. 209–223.