Confidence as a Priority Signal

David Aguilar-Lleyda, Maxime Lemarchand, Vincent de Gardelle

1   **Title:** Confidence as a priority signal

2   **Authors:** David Aguilar-Lleyda[1]*, Maxime Lemarchand[1], Vincent de Gardelle[2]

3   **Affiliations:**

4   [1]Centre d'Économie de la Sorbonne (CNRS & Université Paris 1 Panthéon-
5   Sorbonne), 112 Boulevard de l'Hôpital, 75013 Paris, France
6   [2]Paris School of Economics & CNRS
7   *corresponding author:
8   email: aguilarlleyda@gmail.com
9   address: Maison des Sciences Économiques, 112 Boulevard de l'Hôpital,
10   75013 Paris, France
11
12

1 Abstract: When dealing with multiple tasks, we often find ourselves in the problem of
2 establishing the order in which to tackle them. Here we asked whether confidence, the
3 subjective feeling in the accuracy of our decisions, plays an active role in this ordering
4 problem. In a series of experiments, we show that confidence acts as a priority signal when
5 ordering responses about tasks already completed, or ordering tasks that are to be made. In
6 experiments 1-3, participants were engaged in a dual task and categorized perceptual
7 stimuli along two dimensions. We found that they tended to give first the decision in which
8 they were more confident. We also prove that confidence drives prioritization above and
9 beyond task difficulty or response accuracy, and we discard alternative interpretations in
10 terms of response availability or task demands. In experiments 4-6, we show that when
11 participants have to select which of two sets of trials they want to perform first, they engage
12 first in the set associated with higher confidence, and we extend this finding to situations
13 involving non-perceptual (mental calculation) decisions. Our results thus support the role of
14 confidence as a priority signal, thereby demonstrating a new way in which it regulates
15 human behavior.
16
17
18 Keywords: decision-making, confidence, planning, prioritization, metacognition
19
20 Highlights
21   • We show that when having to decide the order in which to approach two tasks,
22   humans prefer to start with the one they feel more confident in.
23   • This holds both when deciding in which order to report two already completed tasks,
24   and when deciding the order in which to tackle two tasks yet to complete. Our results
25   are replicated in perceptual and non-perceptual situations.
26   • The role of confidence on prioritization cannot be reduced to that of task difficulty or
27   response accuracy.
28   • Our findings demonstrate a new way in which confidence regulates human behavior.
29
30
31

1   It is frequent to start a day at work by compiling in a to-do list all the tasks to complete that
2   day. But once the list is written, where do we start? Which task shall we tackle first, and
3   which tasks can be postponed? Of course, this problem is sometimes solved by taking into
4   account external constraints, such as scheduled meetings, imminent deadlines, or the
5   limited availability of specific tools or collaborators. In other circumstances, however, we are
6   free to decide in which order to complete our tasks. In such unconstrained situations,
7   humans may not perform their tasks in a random order, and they might instead exhibit some
8   systematic preference for doing one task before another. Here, we suggest that confidence
9   may play a role in this prioritization problem. In a situation where two tasks have to be done,
10   individuals may address first the one about which they feel more confident. In a situation
11   where two completed tasks have to be reported, individuals may start by the one in which
12   they were more confident. In both situations, confidence would be a priority signal.
13
14   Different considerations make this hypothesis plausible. Firstly, even in the absence of
15   external rewards, the feeling that we have completed a task successfully, and that we can
16   cross an item off our to-do list, may be intrinsically rewarding. Confidence corresponds to
17   this feeling of success in the task. This feeling is generally valid in perceptual[1,2] and memory
18   tasks[3], where confidence typically correlates with performance (although some dissociations
19   have been documented[4–6]). Therefore, in order to secure rewards as soon as possible,
20   people could seek to complete first the task in which they are more confident[7]. Another
21   reason to expect that humans would use confidence as a priority signal is to reduce their
22   mental workload[8] before facing the most demanding tasks. Indeed, having multiple pending
23   tasks can diminish our cognitive resources, so to avoid facing the most demanding tasks
24   with a reduced mental workload, agents could complete first the less demanding tasks, in
25   which they are more confident. To do so, they could compare their confidence across the
26   different tasks at hand[9,10], and prioritize them accordingly.
27
28   We evaluated whether confidence serves as a priority signal in a series of experiments
29   involving elementary decisions. Our first experiment aimed at evaluating whether confidence
30   would relate to the prioritization of responses between two perceptual decisions already
31   made. On each trial (see Figure 1A), participants (n=28) were presented an array of colored
32   letters and they had to report both the dominant color (orange or blue) and the dominant
33   letter (X or O) in the stimulus. Immediately after they had to give a confidence rating for each
34   choice, on a subjective probability scale of success ranging from 50% (i.e. pure guess) to
35   100% (i.e. completely certain of being correct). By calibrating the stimulus before the main
36   experiment (see methods), we obtained for each task an easy and a hard condition, which
37   corresponded to an expected 90% and 60% of correct responses, respectively. As Figure 1B
38   shows, observed performance in the experiment closely matched expected performance.
39
40

Figure 1 | Experiment 1: design and results. A. Overview of a trial. An array of 80 elements appeared for 1s. Each element could be an O or an X, colored blue or orange. After the stimuli disappeared, a response screen appeared. Four boxes were presented, each containing one of the four elements related to the choice. Participants gave their response to the color task by clicking on the box containing either the blue or the orange square, and to the letter task by clicking on the box containing either the O or the X. Next two scales, one for the color task and another for the letter task, appeared on the screen disposed as a cross. Participants could then rate their confidence on each task's decision, from 50 (total uncertainty) to 100 (total certainty). **B.** Observed performance as a function of expected performance, both in percentage, split by task type. Bars represent averages across participants, with error bars denoting 95% confidence intervals. Dots represent individual participants. Top and bottom dashed lines help indicate where 90% and 60% observed performance would lay, respectively. **C.** Average confidence rating given for the second choice within a trial, as a function of that for the first choice. Dots represent individual participants, and the black, solid line represents a linear fit of the data. Participants below the dashed, identity line expressed more confidence in their first choices, and vice versa. **D.** Density of the proportion of trials where the first choice had a higher confidence rating than the second choice. The black density corresponds to the whole dataset, the green density corresponds only to those EE and HH trials where both choices were correct, and the red density corresponds only to those EE and HH trials where both choices were errors. Densities are drawn by using each participant's data, with each participant's average shown as an individual dot at the bottom. Across-participant averages are displayed as big dots with error bars showing 95% confidence intervals. The dashed line corresponds to equal confidence ratings for first and second choices.

Critically, although participants were not asked to report their judgments in a specific order, we expected that they would report first the judgment associated with a higher confidence. This was indeed the case on average across trials: confidence in the first choice was higher than confidence in the second choice (Figure 1C, t(27) = 6.425, *p* < 0.001, 95% CI [4.166, 8.075], *d* = 1.214). It was also the case within each trial: as seen in Figure 1D, the proportion of trials in which the confidence associated to the first choice was greater than that associated to the second was systematically greater than 0.5 (t(27) = 4.339, *p* < 0.001, 95% CI [0.546, 0.628], *d* = 0.820). Furthermore, this pattern held even when the two perceptual dimensions had the same difficulty level and responses were both correct (green line in Figure 1D, t(27) = 2.400, *p* = 0.024, 95% CI [0.508, 0.600], *d* = 0.454) or both incorrect (red line in Figure 1D, t(27) = 2.150, *p* = 0.041, 95% CI [0.503, 0.643], *d* = 0.406). Note that, by

4

1 construction, this later analysis confirms that participants' priority was driven by confidence
2 per se, and not simply by task difficulty or response accuracy.
3
4 To strengthen this point, we conducted four more analyses on this data, which showed that
5 confidence affects priority above and beyond task difficulty (expected accuracy) and actual
6 accuracy. First, in a logistic regression model, we found that responding to the color task first
7 was significantly predicted from the difference in reported confidence between the two tasks
8 (β = 0.045, S.E. = 0.002, p < 0.001), even when the difference in actual accuracy (β = 0.002,
9 S.E. < 0.001, p < 0.001) and in expected performance (β = 0.003, S.E. = 0.001, p = 0.004)
10 between the two tasks were included as predictors in the same regression. Second, we
11 compared this regression model with a simpler one that only included the difference in
12 expected performance and actual accuracy between tasks, and we found that including
13 confidence significantly improved the model (log-likelihood: full model = -6083.624, no
14 confidence model = -6644.367; $\chi^2(1)$ = 1121.486, p < 0.001). Third, in a different but similar
15 approach, we could predict priority from confidence (p < 0.001) in a regression in which we
16 included as an offset the prediction of priority by expected performance and actual accuracy.
17 These analyses were conducted on the full data and are presented in more details in
18 supplementary information 4. In our last analysis our goal was to pit confidence against
19 accuracy by evaluating whether participants would prioritize an error made with greater
20 confidence over a less confident but correct response. To do so, we focused on a narrow
21 subset of trials where participants made an error for one dimension and a correct response
22 for the other, but expressed a greater confidence in their error than in their correct response.
23 Pooling all participants together (due to the limited number of trials per participant), we
24 performed a binomial exact test and found indeed that the proportion of trials where the error
25 was prioritized was greater than 0.5 (actual proportion = 0.570, n = 1384 trials, p < 0.001).
26 Results were similar if only taking trials where the two dimensions had the same difficulty
27 level (proportion = 0.591, n = 658 trials, p < 0.001). Thus, when confidence and accuracy
28 were dissociated, the former still drove prioritization of responses. This not only reinforces
29 the idea that the role of confidence cannot be reduced to that of accuracy, but also suggests
30 that the role of confidence is preponderant.
31
32 In the experiment described above, participants may have associated their confidence
33 ratings with task priority simply because they had to explicitly report their confidence. Our
34 result (i.e. 'most confident response first') would be strengthened if replicated with a
35 paradigm that eliminated this possibility of an implicit demand effect. In our second
36 experiment, thus, we tested our hypothesis without asking for confidence ratings, and we
37 relied instead on task difficulty as a proxy for confidence. Indeed, in our first experiment we
38 observed that reported confidence was greater for easy tasks than for hard tasks, and also
39 greater for correct responses than for errors (for details see supplementary information 3.2.),
40 as typically found in the confidence literature[1,3,11].
41
42 In Experiment 2, we therefore asked a new set of participants (n=20) to perform the same
43 dual task without confidence ratings. Figure 2A depicts the proportion of times the first
44 response was related to the color task, in each of the four possible kind of trials: easy color -
45 easy letter (EE), easy color - hard letter (EH), hard color - easy letter (HE), and hard color -
46 hard letter (HH). If confidence truly guided the priority of the responses, participants should
47 exhibit a bias towards responding to the easy task before the difficult task. We found that,
48 indeed, the color judgment was reported first more in EH trials than in HE trials (42% vs.

1 37% of trials). This difference in proportion was highly consistent across participants (t(19) =
2 3.059, *p* = 0.006, 95% CI [0.018, 0.097], *d* = 0.684), as illustrated by Figure 2B. In other
3 words, participants' task prioritization was affected by task difficulty, as a proxy for
4 confidence, such that participants exhibited an easy-first bias. For completeness, we also
5 confirmed that the same results were obtained in Experiment 1 (see supplementary
6 information 3.3.).
7

8
9 **Figure 2 | Experiment 2 & Experiment 3: results. A.** For Experiment 2, proportion of trials where the color task
10 was first responded to, as a function of the type of trial (EE = easy color, easy letter; EH = easy color, hard letter;
11 HE = hard color, easy letter; HH = hard color, hard letter). Each set of four dots connected by lines represents
12 one participant. Bigger dots represent average proportions across participants, and error bars denote 95%
13 confidence intervals. The dashed line corresponds to no preference towards responding first to the color or the
14 letter task. **B.** For Experiment 2, density of the difference between proportion color task chosen first for EH trials
15 and proportion color task chosen first for HE trials. The density is drawn by using the difference of proportions for
16 each participant. The across-participant average is displayed as a big dot with error bars showing 95%
17 confidence intervals. The dashed line corresponds to no difference between EH and HE trials. **C.** For Experiment
18 3, density of the difference between proportion color task chosen first for EH trials and proportion color task
19 chosen first for HE trials. The three densities, one for each delay, are drawn by using the difference of
20 proportions for each participant. Across-participant averages are displayed as big dots with error bars showing
21 95% confidence intervals. The dashed line corresponds to no difference between EH and HE trials.
22
23 In our third experiment, we wanted to discard one possible interpretation of our results in
24 terms of response availability. Because in our previous experiments the response screen
25 was presented immediately after the stimuli disappeared, one could argue that only the
26 decision for the easy task had been reached by then. If that was true, then the easy-first
27 priority effect could be due to response availability rather than confidence. To tackle this
28 concern, we modified our previous experiment by introducing a delay (0s, 2s, or 4s,
29 randomized across trials) between the stimulus offset and the onset of the response screen.
30 We reasoned that, if the easy-first effect was only driven by response availability at the
31 response screen onset, then it should disappear for long delays. We ran this experiment with
32 new participants (n=30) and then calculated again the proportion of trials in which color was
33 first responded to in EH trials and in HE trials, now for each delay condition. We found that
34 the main effect of trial type was significant overall ($F(1,29)$ = 6.098, *p* = 0.020, η_p^2 = 0.174),
35 with an easy-first bias replicating our previous studies. Although the main effect of delay was
36 also significant ($F(2,29)$ = 12.760, *p* = 0.020, η_p^2 = 0.306), it did not interact with trial type (*p* =
37 0.679, see also Figure 2C). This data thus ruled out the concern that participants responded
38 to the easy task first because it was the only task for which a decision was available by the
39 time the response screen was presented.
40

1   The experiments described so far showed that confidence acts as a priority signal at the
2   level of response execution: when engaged in a dual task, participants tend to communicate
3   first the response associated with greater confidence. In what follows, we investigated the
4   prioritization between two tasks, instead of between responses. In other words, in a situation
5   where two tasks have to be completed separately (much like our introductory "to-do list"
6   example), we asked whether participants would engage first in the task that they feel more
7   confident about. In such situations, participants may rely on prospective confidence, that is
8   their anticipation about the probability of success in a task before they actually do it, which
9   can be based for instance on prior experience with the same task[12,13]. We implemented this
10   idea in our next experiments. First we familiarized participants with two conditions, one
11   eliciting higher confidence than the other. Then in a subsequent test phase, they would face
12   again the same two conditions, in the order they preferred, and we evaluated whether they
13   would prioritize the condition associated with higher confidence.
14
15   Our fourth experiment was conducted on a new sample of participants (n=31), which
16   completed 32 experimental blocks, each constituted of a familiarization and a test phase
17   (Figure 3A). In the familiarization phase, participants completed two sets of trials. Each set
18   contained 6 trials, and was associated with a name and a task (either color or letter).
19   Importantly, one set contained only hard trials, while the other set contained only easy trials.
20   Difficulty was calibrated before the experiment (Figure 3B), and the order of the easy and
21   hard set in the familiarization phase was random. After completing the familiarization phase,
22   the test phase started: participants were presented with the names of both sets, and they
23   could choose the order in which they wanted to complete 4 trials of each set. They knew that
24   performance in these test trials would determine their final payoff. Critically, participants
25   chose more often to face the easy set first (Figure 3C, t(30) = 2.284, p = 0.030, 95% CI
26   [0.503, 0.557], d = 0.410). These results thus demonstrate that prospective confidence too
27   can establish the priority of one task over another. Interestingly, whether the two sets
28   involved different tasks or the same task did not affect this priority effect (p = 0.256). This
29   suggests that the comparison of the two sets involved relatively abstract representations, as
30   was found for confidence comparison[9,14].
31

Figure 3 | Experiment 4: design and results. A. Overview of one block. The familiarization phase made participants practice with 6 trials of two different sets, with each set introduced by a screen stating its name and

the type of task participants would have to respond to. During the test phase participants had to complete 4 trials of each set. At the beginning of the phase, a screen with the names of both sets was presented, and participants clicked on the name of the set they wanted to start with. **B.** For the familiarization phase, observed performance as a function of expected performance, both in percentage, split by task type. Bars represent averages across participants, with error bars denoting 95% confidence intervals. Dots represent individual participants. Top and bottom dashed lines help indicate where 90% and 60% observed performance would lay, respectively. **C.** Density of the proportion of blocks where participants chose to complete first the 4 trials from the set with an easy task. One of the displayed densities corresponds to blocks where both tasks were the same, the other to those where they were different. Both densities are drawn by using each participant's data. Across-participant averages are displayed as big dots with error bars showing 95% confidence intervals. The dashed line corresponds to easy and hard tasks being chosen first equally often.

In Experiment 5 (n=29), our goal was to further demonstrate that task prioritization between two sets of trials depends on confidence above and beyond performance. To do so, we reproduced the structure of Experiment 4 while dissociating confidence from performance, by capitalizing on previous work showing that confidence can be biased by the variability of the evidence available for the perceptual decision[15–18]. On each trial, participants were presented with 8 circles colored between red and blue, and they had to judge whether the average color was closer to red or to blue. We compared two conditions (Figure 4A). Within a block, one set of trials had circles with high mean evidence (the average color was far away from the midpoint between red and blue) and with high evidence variability, while the other set featured trials with low mean evidence (the average color was close to the midpoint) and low variability (more homogeneous hue across circles). These two conditions were matched in terms of decision accuracy ($t(28) = -0.993$, $p = 0.329$, 95% CI [-0.080, 0.028], $d = -0.184$, see Figure 4B), but confidence ratings collected after the main experiment confirmed that participants were slightly more confident in the *low* condition ($t(28) = -3.151$, $p = 0.004$, 95% CI [-5.855, -1.242], $d = -0.585$, see Figure 4C), as found in previous studies with these stimuli[16,17]. We thus expected to find that participants would prioritize the low condition over the high condition. Overall, this effect was not clear at the group level: the proportion of blocks where the low condition set was chosen first was not different from 0.5 (t-test: $t(28) = 0.851$, $p = 0.402$, 95% CI [-0.026, 0.062], $d = 0.158$, Figure 4D). Crucially, however, when looking at the inter-individual heterogeneity, we found that the expected priority effect towards the low condition was more pronounced for participants expressing greater confidence in the low condition when compared to the high condition (Figure 4E). Given the presence of a clear outlier (who always prioritized the first presented set, irrespectively of the condition), the relation between these two effects was confirmed with a robust correlation analysis ($r = 0.427$, $p = 0.021$). Of note, prioritization of the low condition was not correlated with a performance advantage towards the low condition ($r = -0.099$, $p = 0.611$). After excluding the outlier, we could also predict the priority effect from the confidence effect in a regression across participants ($\beta = 0.015$, $t = 3.399$, $p = 0.002$), even after adding the performance difference between the two conditions as a covariate in the regression ($p = 0.253$). In sum, Experiment 5 shows that participants who experienced more confidence in the low condition also tended to prioritize this condition in their task planning, even when task accuracy was equal.

Figure 4 | Experiment 5: design and results. A. Example stimulus for each of the conditions. The mean evidence generating each sample from the high condition is of high evidence, but across-sample variability is also high. For the low condition, the generative mean is of lower evidence, but variability is also lower. **B.** For all trials of the experimental part, average observed performance as a function of expected performance, both in percentage, split by condition. Bars represent averages across participants, with error bars denoting 95% confidence intervals. Dots represent individual participants. The horizontal dashed line indicates where 75% observed performance would lay. **C.** Average confidence ratings across participants, split by condition. Error bars denote 95% confidence intervals. Dots depict individual participants. **D.** Density of the proportion of blocks where participants chose to complete first the the set whose trials belonged to the low condition. The density is drawn by using each participant's data. The across-participant average is displayed as a big dot, with error bars showing 95% confidence intervals. The dashed line corresponds to low and high condition sets being chosen first equally often. **E.** Proportion of blocks where participants chose to complete first the the set whose trials belonged to the low condition, as a function of the difference between the average confidence for low condition trials minus the average confidence for high condition trials. Each dot depicts an individual participant. The line depicts a linear fit of the data excluding the outlier (rightmost dot).

Finally, we aimed at evaluating the generalizability of our findings beyond perceptual decisions. For this, we conducted another experiment to test whether priority towards easier problems would also manifest itself when considering simple mental calculation. On each trial, two schematics of mental calculation problems were presented (Figure 5A). One was a priori more difficult than the other, in the sense that it included a multiplication or a division (e.g. "x+y/z"), instead of only additions or subtractions (e.g. "x+y-z"). The problems were

1 otherwise matched in the number of elements and operations they involved. Participants had
2 to click on one of the schematics to reveal the actual problem, which they then had to solve.
3 Immediately after, participants had to solve the non-chosen problem. Although there was no
4 difference in response accuracy between easy and hard problems ($p = 0.883$), the response
5 times for the hard problems were significantly longer (Figure 5B, $t(100) = 10.001$, $p < 0.001$,
6 95% CI [3.010, 4.499], $d = 0.995$), proving that they were more demanding. Most
7 participants predominantly chose to solve the easy problem first (Figure 5C, $t(100) = 6.146$,
8 $p < 0.001$, 95% CI [0.590, 0.676], $d = 0.612$). This experiment thus replicated and extended
9 beyond perceptual tasks our previous findings of an easy-first bias in task prioritization.
10

11
12 **Figure 5 | Experiment 6: design and results. A.** Overview of one trial. Two schematics of simple mental
13 calculation problems were presented, one easier to solve than the other. Participants clicked on the one they
14 wanted to solve first. The actual problem was then revealed, and participants had to type their response. Then
15 they had to do the same with the other problem. **B.** Average response time, in seconds, as a function of the
16 difficulty of the problem. Bars show the average across participants, while dots connected by lines represent
17 each individual participant. **C.** Density of the proportion of blocks where participants chose to respond first to the
18 easy problem. The density is drawn by using the proportion for each participant. The across-participant average
19 is displayed as a big dot with error bars showing 95% confidence intervals. The dashed line corresponds to easy
20 and hard problems being chosen equally often.
21
22 To summarize, we found that, when having to prioritize responses or tasks, participants
23 exhibited a systematic bias towards engaging first in the response or the task in which they
24 had greater confidence. We replicated this finding in 6 experiments. Converging evidence
25 came from different measures, using task difficulty and observed accuracy as proxies for
26 confidence, but also using actual confidence ratings, and even exploring situations where
27 performance and confidence were dissociated. In terms of generalizability, we demonstrated
28 that this effect was present in both situations involving retrospective confidence (experiments
29 1-3) and prospective confidence (experiments 4-6), and both situations involving perceptual
30 and non-perceptual tasks, such as mental calculation.
31
32 Situations in which we face multiple tasks present a huge diversity, and task prioritization is
33 likely determined by a varied set of factors, most of which were not manipulated in our
34 design. For instance, prioritization can be driven by personal interest and the familiarity with
35 the task[19]. We did also not manipulate the duration of each task, although there is evidence
36 from real-life situations where people tended to approach first the shortest tasks[20]. Although
37 in our experiments the two tasks were presented simultaneously, previous research has
38 shown that task prioritization also depends on the time at which task-relevant information is
39 presented[21]. We therefore only claim that confidence is one among many forces driving task
40 prioritization. In our data, we find a large inter-individual variability in the general tendency to
41 prioritize the color or the letter task (Figure 2A, see also supplementary information 6.1.),

1   and we found that the locations of the different choice options on the screen could also bias
2   task priority (see supplementary information 6.2.). Whether this variability is due to strategies
3   or heuristics explicitly chosen by participants, or to differences in their perceptual or decision
4   processes, remains to be investigated. Another factor that deserves more scrutiny is the
5   reward associated with each task, which should affect task priority. In our experiments, we
6   purposefully avoided any difference in reward between both tasks within a trial. We also did
7   not instruct or incentivize participants to prioritize the more confident or the more accurate of
8   the two decisions. In sum, nothing in the instructions or the reward structure pushed
9   participants to prioritize one task over the other. Some of the aforementioned features could
10 be manipulated in future studies, and whether humans change their priorities under such
11 manipulations is an open empirical question.
12
13 Another important issue for future research is whether this strategy of approaching the easy
14 task first is adaptive. A priori, reducing the mental workload before tackling more difficult
15 tasks could be beneficial. In our data, however, we found no clear evidence that addressing
16 the easy task first led to better performance. Overall, participants were neither better nor
17 worse when responding first to the easy task than when responding first to the hard task
18 (see supplementary information 7.1.). To further investigate this issue, we conducted an
19 additional experiment comparing a free response order condition (which replicated
20 Experiment 2) to an imposed order condition in which the choice for the hard task was
21 required either first or second (see supplementary information 7.2.). We found that
22 participants' performances were similar between these two conditions, suggesting that, in
23 our paradigm, the confidence-driven prioritization does not lead to an advantage in task
24 performance. In other words, while we cannot claim that there is no advantage behind
25 confidence-driven prioritization, our manipulation could not find it.
26
27 Our study highlights a new way in which confidence actively shapes our behavior. It
28 therefore contributes to a growing literature showing how confidence is not a mere
29 commentary on performance but actually affects individual or collective decisions. Previous
30 research showed how, when agents interact, the confidence with which an advice is
31 expressed affects the use of this information by others[22–24] and how well the group will
32 perform[25]. At the individual level, confidence may serve as a teaching signal when feedback
33 is unavailable[26–29]. It also influences the amount of resources we engage in a task[17,30]. Here
34 we show that confidence does not only determine how we do a task, but also when we plan
35 to do it.
36
37 Understanding how people decide to perform one task before another may have practical
38 consequences for the management of individuals and organizations. This motivated some
39 studies that focused on different applied scenarios. Some of this previous work already
40 found that individuals address easier tasks first when they can decide their task schedule.
41 For instance, students appear to prioritize easier course assignments over difficult ones[31],
42 and the expected easiness of finding the relevant information affects their prioritization of a
43 web-search task over another[19]. Physicians at an emergency department do prioritize easy
44 patient cases, especially under high workload contexts[7]. The present study makes several
45 unique contributions to this research topic: we extend this result to situations involving
46 immediate decisions, we link the easy-first bias to confidence, and we offer a strict control
47 over performance in the task via our psychophysical procedures. Finally, although we did not
48 find a clear consequence from the easy-first bias on performance, previous research has

1   shown that in another context this strategy was associated with both short-term benefits and
2   long-term costs. Indeed, prioritizing easy cases allowed physicians to treat more patients per
3   unit of time, but across individuals it was associated with a lower productivity and less
4   revenue for the hospital[7]. Understanding whether and how similar short-term benefits and
5   long-term costs may arise in other contexts, and in particular in situations where individuals
6   have to perform multiple perceptuo-motor tasks at the same time, constitutes an exciting
7   topic for future research.
8

Methods

Participants

11   Participants (Exp1=28, Exp2=20; Exp3=30; Exp4=31; Exp5=29; Exp6=101) were healthy
12   adults recruited from the Laboratoire d'Économie Experimentale de Paris. They reported
13   normal or corrected-to-normal vision, and provided informed consent. Participation was
14   compensated based on performance and duration, at an average rate of 12€ per hour. The
15   Paris School of Economics ethics committee approved the experimental procedures after
16   determining that they complied with all the ethical regulations. Participants were tested in
17   sessions of up to 20 individuals. The number of participants in each experiment depended
18   on the number of people showing up for that particular experiment. We aimed at a minimum
19   of 20 participants in each experiment.

Apparatus

21   Experiments were run using MATLAB Psychtoolbox[32] on a computer screen (17', 1024x768
22   pixel resolution, 60 Hz refresh rate) viewed from approximately 60 cm. Stimuli appeared on a
23   grey background.

Perceptual task (experiments 1-4)

25   For experiments 1-4, the task consisted in reporting the dominant letter and the dominant
26   color of an array of 80 letters (Xs or Os), colored blue or orange (see Figure 1A). Each trial
27   started with a 500 ms fixation cross, followed by a 300 ms blank period, and then by the
28   stimulus, which was presented for 1 s. Each letter, in Arial font, occupied approximately 0.5º
29   (degrees of visual angle). Elements were presented within a 10º wide imaginary square.
30   These stimuli were based on the code available at
31   https://github.com/DobyRahnev/Confidence-leak and used in a previous publication[33].
32
33   For Experiments 1-3, after the stimuli disappeared, the response screen was presented,
34   which consisted in 4 square boxes that contained a blue square, an orange square, a white
35   O and a white X (see Figure 1A). The 4 boxes were randomly arranged in a 2x2 grid on each
36   trial. Participants gave their response by clicking on a color box and a letter box, in their
37   preferred order. A first response on one dimension (e.g. clicking on the X box) made the
38   corresponding boxes disappear, leaving only the boxes for the other dimension (e.g. the
39   orange box and the blue box), which required a second response. Participants completed 4
40   parts of 4 blocks each, with 25 trials per block. Between block and block, participants could
41   rest for 15 seconds, and at the end of each part they could take self-timed breaks.

1

Manipulation of task difficulty (experiments 1-4)

For each perceptual task, difficulty was manipulated by changing the proportion of the dominant over the non-dominant feature. After a short training, we used psychophysical staircases to estimate, separately for each task, the proportion of items that should be used for responses to be 90% correct (*easy* condition) or 60% correct (*hard* condition). Details of the training and staircase procedure are presented in supplementary information 1.1. We then used these parameters in the main experimental part to manipulate difficulty on the letter (easy vs. hard) and color (easy vs. hard) tasks, orthogonally within each participant, in a 2x2 factorial design. For experiments 1-3, we collected 100 trials for each of the 4 conditions, with trials of all conditions intermixed within blocks.

Experiment 1: confidence ratings

In Experiment 1, after participants made their two choices, they had to rate their confidence on each of them. Two confidence scales were simultaneously presented, one horizontal for the color task and one vertical for the letter task (see Figure 1A). Each scale featured the two response categories at its ends (which corresponded to 100% confidence) and an empty region at its center (near which confidence was at 50%). The two choices participants had made on that trial were surrounded by a yellow circle. Participants gave their confidence levels on both tasks by clicking on the corresponding scales, and then validated the ratings by clicking at the center of the screen. Participants were told that maximum uncertainty (no preference between their response and the other option within the same task) corresponded to a 50% confidence, and absolute certainty on the choice to a 100% confidence.

Experiment 2: choice-only

Trials in Experiment 2 closely resembled those in Experiment 1, except for the fact that no confidence had to be rated. Thus, the trial finished after participants made a choice for each task on the response screen.

Experiment 3: varying delays

In Experiment 3, we manipulated the time between stimulus offset and the presentation of the response screen, which was set to 0, 2 or 4 seconds (counterbalanced across trials).Considering the response times for our previous experiments (see supplementary information 3.4.), 4s ensured that participants had reached both decisions by the time the response screen was presented.

Experiment 4: anticipated difficulty in prospective confidence

In Experiment 4, participants only responded to one task on each trial. Therefore, the response screen uniquely contained the two relevant boxes. The main part was organized in 32 blocks. All blocks included a familiarization and a test phase (Figure 3A). During the familiarization phase, participants completed two sets of 6 trials. Each set was associated to a single task (color or letter), a difficulty level (easy or hard), and an animal name (randomly chosen without replacement from a predefined list of common names). Based on staircases ran before the main phase, the proportion for the task-relevant dimension was

1   experimentally controlled, such that for each block, one set contained difficult trials and the
2   other easy trials (for the non-relevant dimension, the proportion was always set at 50%).
3   This manipulation was not revealed to participants but they could learn the difficulty of each
4   set by performing the task during the familiarization phase. After the familiarization, the test
5   phase started. Participants saw a screen with two horizontally aligned boxes presenting (in a
6   random position) the animal names of the two sets just completed. 4 trials of each set had to
7   be completed, with reward in that block depending on performance in that part. Participants
8   decided the order in which to complete the test trials of each set by clicking on the name of
9   the set they desired to complete first. We used animal names to avoid any obvious order
10 bias (set A vs B, or 1 vs 2) for this decision (for the complete list of set names, see
11 supplementary information 9.1.). Across blocks, we manipulated factorially the task
12 (color/letter) used for the first set in the block, the task (color/letter) used for the second set,
13 and the order of the difficulty levels used for the two sets (easy first vs. hard first). This
14 design resulted in 8 conditions, presented in a randomized order as a sequence 4 times per
15 participant.

Experiment 5: dissociation between performance and confidence

16

17 For Experiment 5, participants had to categorize the average color of a set of 8 circles as
18 more red or blue. Each trial started with a black fixation cross presented for 400 ms, followed
19 by 8 circles presented simultaneously for 200 ms. Each circle was uniformly colored in RGB
20 space as [255*t, 0, 255*(1-t)] with a color parameter t taking values between 0 (full blue) and
21 1 (full red). The circles, each with an area of 2500 pixels, were regularly spaced on an
22 imaginary circle 120 pixels from fixation. After the stimulus disappeared, the fixation cross
23 turned white and participants had to make a response. For all parts of the experiment, within
24 each block of trials, red was the dominant component (and thus the correct response) for
25 50% of the trials, and blue for the other 50%. Participants had to use the E and R keys of the
26 keyboard to indicate whether the average color was closer to red or to blue. The mapping
27 between each of the two keys and each of the two color responses was randomized across
28 participants.
29
30 On each trial, the color parameter t for each circle was sampled from a standard normal
31 distribution, then multiplied with the standard deviation of the corresponding condition (high:
32 SD= 0.20, low: SD=0.05) and then added to the mean of the corresponding condition, which
33 was determined with a staircase procedure at the beginning of the experiment (see
34 Supplementary Material 1 for details).
35
36 The main part of this experiment greatly resembled that of Experiment 4. On each of its 32
37 blocks, participants were introduced to two sets of trials, each with an animal name: for one
38 set, the generative mean was high, but so was the SD (high condition), whereas for the other
39 both mean and SD were low (low condition). After a familiarization phase where 6 trials of
40 each set were completed, participants had to complete 4 more trials of each set, with these
41 test trials determining payoff at the end of the experiment. However, they could choose the
42 order in which to complete them by clicking on the name of the set they wanted to start with.
43 Apart from the nature of the stimulus, the main difference with respect to Experiment 4 was
44 that the expected difficulty of both sets was always 75%, with the difference between sets
45 laying on the mean and variability of the circles that were generated on each trial. For each
46 participant, we achieved the values leading to a 75% expected performance through an

1   initial staircase procedure for each condition. For more details, see supplementary
2   information 8.
3
4   After the main part of this experiment, participants completed a part where 8 blocks of 24
5   trials were presented. Each trial could have the mean and SD values previously used for the
6   high condition, or those used for the low condition. These two types of trials were interleaved
7   within each block, with each type appearing the same number of times. The crucial feature
8   of this final part was that, after their response, confidence had to be reported. Confidence
9   was given by clicking on a vertical scale that, as in Experiment 1, ranged from 50 to 100.
10   Confidence was only required in this part, and not before, to avoid biasing the participants'
11   priority choices in the previous part.
12

Experiment 6: anticipated difficulty in a mental calculation task

14   The stimuli used in Experiment 6 were different from those used in the previous
15   experiments. On each trial, two horizontally aligned boxes appeared (see Figure 5A), each
16   containing a simple formula (e.g. "a+2b") . Our formulas involved letters connected by basic
17   operators (+, -, *, /) and were sometimes nested by brackets. Both problems were similar
18   except for the operators connecting their respective letters. One of the problems (easy)
19   contained additions and subtractions, while the other (hard) contained multiplications and
20   divisions. The easy and hard box were randomly positioned on the left or the right of the
21   screen on every trial. Participants had to solve both problems in their prefered order. By
22   clicking on one box, the letters of the formula in that box were replaced by one-digit integers.
23   Participants then typed their response, which appeared inside a box below the problem.
24   They could change it as they wanted before pressing the ENTER key to validate it. Then, the
25   non-clicked on problem appeared for participants to give their response through the same
26   method. Each participant completed the same 20 pairs of questions (listed in supplementary
27   information 9.2.), but in a random order. The initial presentations of formulae ensured
28   participants could not try to solve the problems before making a choice.

Payoff

30   Performance on the main part of the experiments determined the final amount of money
31   participants won. In experiments 2 and 3, for each of the 16 blocks, a random trial was
32   chosen. Within that trial, the choice for either color or letter was also randomly picked. If that
33   choice had been correct, the participant received 1 €, and 0 € otherwise. This payoff method
34   ensured participants kept a stable performance and did not relax their attention or
35   automatized their responses during some trials.
36
37   In Experiment 1, the payoff system was slightly different. Once a trial and a choice had been
38   selected within a block, a number was selected from a uniform distribution between 0 and
39   100. If the number was lower than the confidence given for that choice, the payoff depended
40   on performance. If the number was higher, another random number was sampled from a
41   uniform distribution between 0 and 100. If this number was smaller than the random number
42   previously drawn, 1€ was given, and 0€ otherwise. This system has previously[34] been
43   adopted to ensure that participants try to accurately rate their confidence, since their payoff

depends on it. On top of this, participants were awarded a fixed 3€ just for the added length reporting confidence gave to the experiment.

In Experiment 4, payoff was similar to Experiment 2, but given the more numerous and shorter blocks, each of them could be rewarded with only 0.5€. The rest between blocks was also shorter, with a duration of 10 s.

Experiment 5 had a payoff like Experiment 4, but we also added an extra compensation for the final trials where confidence had to be reported. For each of the 8 blocks in which trials were divided, participants could receive 0.5€ in a procedure like that used in Experiment 1, where reward could depend on performance or on confidence.

Experiment 6 had a payoff system which mimicked that of the previous experiments. At the end of the experiment, two trials were chosen randomly. For each of these selected trials, the answer to one of the problems was picked. If the answer was correct, participants received 1€, and nothing otherwise.

Before starting each experiment, participants were carefully informed about the procedure. The payoff structure and its objective were made clear, and the fact that reward did not depend on their response times was also pointed out.

Statistics

All reported t-tests and binomial exact tests are two-tailed. All ANOVA are repeated measures. For t-tests, effect size is reported by using Cohen's d_z, written here as d, which was calculated using Rosenthal's formula[35]: the t statistic was simply divided by the square root of the sample size. For ANOVA, effect size is reported by using partial eta squared (η_p^2). For each factor, this was calculated by taking the sums of squares of the condition, and dividing it by the sums of squares of the condition plus the sums of squares of the error[36]. Logistic regressions were performed with R's function glmer, by using maximum likelihood and a logit link function.

Code availability

The code used to produce the analyses and the figures that appear on this study are available from the corresponding author upon reasonable request.

References

1. Peirce, C. S. & Jastrow, J. *On Small Differences of Sensation*. (1885).

2. Fleming, S. M., Dolan, R. J. & Frith, C. D. Metacognition: computation, biology and function. *Philos. Trans. R. Soc. Lond. B Biol. Sci.* **367**, 1280–1286 (2012).

3. Dallenbach, K. M. The relation of memory error to time interval. *Psychol. Rev.* **20**, 323–337 (1913).

4. Wilimzig, C., Tsuchiya, N., Fahle, M., Einhäuser, W. & Koch, C. Spatial attention

increases performance but not subjective confidence in a discrimination task. *J. Vis.* **8**, 7 (2008).

5. Zylberberg, A., Barttfeld, P. & Sigman, M. The construction of confidence in a perceptual decision. *Front. Integr. Neurosci.* **6**, (2012).

6. Rahnev, D. A., Maniscalco, B., Luber, B., Lau, H. & Lisanby, S. H. Direct injection of noise to the visual cortex decreases accuracy but increases decision confidence. *J. Neurophysiol.* **107**, 1556–1563 (2012).

7. Kc, D. S., Staats, B. R., Kouchaki, M. & Gino, F. Task Selection and Workload: A Focus on Completing Easy Tasks Hurts Long-Term Performance. *SSRN Electronic Journal* (2017). doi:10.2139/ssrn.2992588

8. Moray, N. *Mental Workload: Its Theory and Measurement*. (Springer Science & Business Media, 2013).

9. de Gardelle, V. & Mamassian, P. Does confidence use a common currency across two visual tasks? *Psychol. Sci.* **25**, 1286–1288 (2014).

10. de Gardelle, V. & Mamassian, P. Is confidence amodal? Confidence comparison across dimensions of a visual stimulus. *J. Vis.* **13**, 57–57 (2013).

11. Kepecs, A., Uchida, N., Zariwala, H. A. & Mainen, Z. F. Neural correlates, computation and behavioural impact of decision confidence. *Nature* **455**, 227–231 (2008).

12. Wright, G. Changes in the realism and distribution of probability assessments as a function of question type. *Acta Psychol.* **52**, 165–174 (1982).

13. Fleming, S. M., Massoni, S., Gajdos, T. & Vergnaud, J.-C. Metacognition about the past and future: quantifying common and distinct influences on prospective and retrospective judgments of self-performance. *Neurosci Conscious* **2016**, niw018 (2016).

14. de Gardelle, V., Le Corre, F. & Mamassian, P. Confidence as a Common Currency between Vision and Audition. *PLoS One* **11**, e0147901 (2016).

15. de Gardelle, V. & Mamassian, P. Weighting mean and variability during confidence judgments. *PLoS One* **10**, e0120870 (2015).

16. Boldt, A., de Gardelle, V. & Yeung, N. The impact of evidence reliability on sensitivity and bias in decision confidence. *J. Exp. Psychol. Hum. Percept. Perform.* **43**, 1520–1531 (2017).

17. Desender, K., Boldt, A. & Yeung, N. Subjective Confidence Predicts Information Seeking in Decision Making. *Psychol. Sci.* **29**, 761–778 (2018).

18. Herce Castañón, S. *et al.* Human noise blindness drives suboptimal cognitive inference. *Nat. Commun.* **10**, 1719 (2019).

19. Spink, A., Park, M. & Koshman, S. Factors affecting assigned information problem ordering during Web search: An exploratory study. *Inf. Process. Manag.* **42**, 1366–1378 (2006).

20. Ibanez, M., Clark, J. R., Huckman, R. S. & Staats, B. R. Discretionary Task Ordering: Queue Management in Radiological Services. *Management Science* (2017).

doi:10.2139/ssrn.2677200

21.   Sigman, M. & Dehaene, S. Dynamics of the central bottleneck: dual-task and task uncertainty. *PLoS Biol.* **4**, e220 (2006).

22.   Zalesny, M. D. Rater confidence and social influence in performance appraisals. *J. Appl. Psychol.* **75**, 274–289 (1990).

23.   Paese, P. W. & Kinnaly, M. Peer Input and Revised Judgment: Exploring the Effects of (Un) Biased Confidence. *J. Appl. Soc. Psychol.* **23**, 1989–2011 (1993).

24.   Zarnoth, P. & Sniezek, J. A. The Social Influence of Confidence in Group Decision Making. *J. Exp. Soc. Psychol.* **33**, 345–366 (1997).

25.   Massoni, S. & Roux, N. Optimal group decision: A matter of confidence calibration. *J. Math. Psychol.* **79**, 121–130 (2017).

26.   Hainguerlot, M., Vergnaud, J.-C. & de Gardelle, V. Metacognitive ability predicts learning cue-stimulus associations in the absence of external feedback. *Sci. Rep.* **8**, 5602 (2018).

27.   Zylberberg, A., Wolpert, D. M. & Shadlen, M. N. Counterfactual Reasoning Underlies the Learning of Priors in Decision Making. *Neuron* **99**, 1083–1097.e6 (2018).

28.   Guggenmos, M., Wilbertz, G., Hebart, M. N. & Sterzer, P. Mesolimbic confidence signals guide perceptual learning in the absence of external feedback. *Elife* **5**, (2016).

29.   Daniel, R. & Pollmann, S. Striatal activations signal prediction errors on confidence in the absence of external feedback. *Neuroimage* **59**, 3457–3467 (2012).

30.   van den Berg, R., Zylberberg, A., Kiani, R., Shadlen, M. N. & Wolpert, D. M. Confidence Is the Bridge between Multi-stage Decisions. *Curr. Biol.* **26**, 3157–3168 (2016).

31.   Puffer, S. M. Task-Completion Schedules: Determinants and Consequences for Performance. *Hum. Relat.* **42**, 937–955 (1989).

32.   Brainard, D. H. The Psychophysics Toolbox. *Spat. Vis.* **10**, 433–436 (1997).

33.   Rahnev, D., Koizumi, A., McCurdy, L. Y., D'Esposito, M. & Lau, H. Confidence Leak in Perceptual Decision Making. *Psychol. Sci.* **26**, 1664–1680 (2015).

34.   Massoni, S., Gajdos, T. & Vergnaud, J.-C. Confidence measurement in the light of signal detection theory. *Front. Psychol.* **5**, 1455 (2014).

35.   Rosenthal, R. Meta-Analytic Procedures for Social Research. (1991). doi:10.4135/9781412984997

36.   Lakens, D. Calculating and reporting effect sizes to facilitate cumulative science: a practical primer for t-tests and ANOVAs. *Front. Psychol.* **4**, 863 (2013).

1   Acknowledgements

7

Supplementary information

1. Training and calibration for experiments 1 to 4

1.1. Procedures

Participants started the experiment with 10 training trials for each task in isolation. During the color training, all the 80 letter elements were either O or X. The color task also started at its easiest, with all the 80 elements being of one color, but it became more difficult at the rate of one element per trial. The predominant color and letter were determined randomly on every trial. After the stimuli, only the two boxes for the color task appeared, and the participant gave a response only for that task. A similar procedure was followed for the letter training block, but with all the elements being one color, and the letter task getting more difficult. The order in which these two training blocks were presented was counterbalanced across participants.

After the training, participants were told that the real experiment was about to start, composed by 5 parts of 4 blocks each. In the first part, the proportion of elements was manipulated with a staircase procedure that would allow the presentation of performance-adjusted easy and hard trials in the subsequent parts. This procedure was not disclosed to participants, to avoid any temptation to manipulate it. The staircase followed a one-up/one-down procedure with unequal up and down steps (see e.g. García-Pérez, 1998). Specifically, the initial number of elements in the dominant category was set to 64 out of 80 elements (80%-20%) for both tasks, and, it was decreased by one element after a correct response, and increased by four elements after an error. We then used the 100 trials of that first part to estimate for each task a psychometric function, so as to generate parameters for the following parts. For the color task, this function represented the probability of choosing blue as a function of the number of blue elements, and was fit with a cumulative Gaussian; the same for the probability of choosing O for the letter task. To calculate the number of elements corresponding to a 90% performance (our easy condition) in the color task, we used 40 plus or minus the semi-difference between the number of blue elements for which the psychometric curve predicted a 90% and 10% of blue choices, rounded to its nearest integer. Note that by doing so, we assumed that in the main part participants would not be biased towards one response category. Similar procedures were carried out to obtain parameters for the 60% performance (hard condition), and for both difficulties of the letter task. As can be seen in the results section of the main text and in Figure S1, observed performance in the main experiment closely matched the targeted performance.

In Experiment 4, since each trial only required responding to one task, previous to the main part two staircases were run sequentially, one for the color task and one for the letter task, with a randomized order across participants. Each of them had 100 trials, and the elements of the non-relevant task were kept stable at a proportion of 40/40. These trials were presented to participants as a training part, before the main experiment.

1 ## 1.2. Mean and SD of stimulus elements

2 The following table indicates the number of elements in the dominant category, in the easy
3 condition and in the hard condition, for the color task and the letter task. Means and
4 standard deviations across participants are reported. These parameters were estimated
5 using a staircase procedure for each task (see previous section) and used in the main part of
6 experiments 1 to 4. However, the color and letter staircase procedures were run in parallel
7 for experiments 1 to 3, and one after the other for Experiment 4. The total number of
8 elements in the display was always 80, and the number of elements in the non-dominant
9 category was adjusted accordingly.

10

	Color task				Letter task			
	easy		hard		easy		hard	
Exp #	M	SD	M	SD	M	SD	M	SD
1	48.3	2.62	41.8	0.585	62.1	7.58	44.3	1.47
2	47.7	3.06	41.5	0.761	56.7	6.21	43.3	1.26
3	47.9	2.37	41.5	0.509	56.4	4.84	43.2	0.971
4	45.8	1.54	41.1	0.301	55.4	3.91	43.2	0.860

11

1 ## 1.3. Expected and observed performance

2

3

4

5
6 **Figure S1. Expected and observed performance for experiments 2 to 4. A.** For Experiment 2, observed
7 performance as a function of expected performance, both in percentage, split by task type. Bars represent
8 averages across participants, with error bars denoting 95% confidence intervals. Dots represent individual
9 participants. Top and bottom dashed lines help indicate where 90% and 60% observed performance would lay,
10 respectively. **B.** Same as A, but separately for each time delay of Experiment 3. **C.** Same as A, but separately for
11 the familiarization and test phase of Experiment 4.

1 ## 2. Training and calibration for Experiment 5

2

3 Before the main part and the confidence trials, two other parts were run.

4

5 The experiment started with 20 easy training trials that familiarized participants with the
6 structure of each trial. After each response, feedback on their performance was given by
7 displaying the message 'CORRECT' or 'ERROR'.

8

9 After the training trials, participants were told that they were going to do a second, longer
10 training session. In fact, in this session the generative mean of the stimulus parameter t was
11 updated according to a staircase procedure, to obtain 75% accuracy in both the high
12 condition and the low condition. We used a one-up/one-down procedure with unequal up
13 and down steps. The starting value for the mean was 0.75, and it was reduced by 0.0078
14 after a correct response and increased by 0.032 after an error. This mean parameter
15 determined the signal strength towards red, and on a random half of the trials we used 1-t to
16 obtain blue trials. This staircase procedure was conducted separately for the high condition
17 (SD=0.2) and low condition (SD=0.05) in two interleaved staircases of 100 trials each. When
18 the staircase phase was finished, we estimated for each condition the value leading to an
19 expected performance of 75%. We did so as in previous experiments. Importantly, during
20 this part feedback on performance was still given after each trial in order for participants to
21 learn where the midpoint between red and blue laid. Feedback was removed for the main
22 part and for the final trials where confidence reports were required.

23

1 # 3. Supplementary analyses for Experiment 1

2

3 ## 3.1. Confidence in the first choice vs. in the second choice

4 In the main text, Figure 1D shows the distribution of confidence pooled across all trial types,
5 but also pooled across same-difficulty trial types (EE and HH combined). In order to provide
6 more detailed information, Figure S2 shows the information for each trial type, with Figure
7 S2A showing the data for the whole dataset, Figure S2B showing the data only those trials
8 where both choices were correct, and Figure S2C showing the data only for those trials
9 where both choices were errors.

10

11
12 **Figure S2. Confidence in the first vs. in the second choice. A.** For Experiment 1, density of the proportion of
13 trials where the first choice had a higher confidence rating than the second choice, split by trial type. Densities
14 are drawn by using each participant's data. Across-participant averages are displayed as big dots with error bars
15 showing 95% confidence intervals. The dashed line corresponds to equal confidence ratings for first and second
16 choices. **B.** Same as A, but taking only trials in which both choices were correct. **C.** Same as A, but taking only
17 trials in which both choices were errors.

18

19 ## 3.2. Confidence as a function of difficulty and accuracy

20 Except for Experiment 1, we did not ask participants for confidence ratings. Thus, we had to
21 rely instead on different proxies for confidence to find support for our priority effect. We used
22 expected difficulty and response accuracy as proxies for confidence. These measures have
23 repeatedly been found to correlate with confidence (Kepecs, Uchida, Zariwala, & Mainen,
24 2008; Peirce & Jastrow, 1885; Sanders, Hangya, & Kepecs, 2016). We first checked that
25 such links were also present in Experiment 1. To do so, we fitted a linear mixed model
26 (LMM) with average confidence as dependent variable, and task type (color vs. letter),
27 accuracy (correct vs. error) and expected difficulty (easy vs. hard) as fixed effects.
28 Participants were treated as random effects. We chose an LMM over an ANOVA due to the
29 big difference between the number of correct and error trials. Two participants were
30 excluded due to the absence of any error trial when the tasks were easy. The fixed effects of
31 expected difficulty ($t(20767.359) = 5.697$, $p < 0.001$) and accuracy ($t(20767.635) = 20.401$, p
32 < 0.001) were significant, but also their interaction ($t(20767.331) = -13.193$, $p < 0.001$). As
33 Figure S3A illustrates, the average confidence ratings were higher for easy than for hard
34 stimuli when the choice made by participants had been correct, and lower for easy than for
35 hard stimuli when errors are considered. The fixed effect of task type was not significant ($p =$
36 0.121), and it produced no significant interaction with expected difficulty ($p = 0.379$), but it
37 did with accuracy ($t(20767.444) = 3.427$, $p < 0.001$), and there was a triple interaction among

1 all the fixed effects ($t(20767.305)$ = -2.352, p = 0.019). This pattern of results replicates
2 classic findings and reaffirms the validity of the measures we used for the analyses in
3 Experiment 2.
4

5 3.3. Priority effects from task difficulty in Experiment 1

6 After establishing that task difficulty was associated with confidence in our setup, we could
7 evaluate their relationship to priority, as we did in our analyses of experiments 2 and 3
8 (Figure 2). We report here the same analyses applied to Experiment 1. We can mimic Figure
9 2A and plot the proportion of choosing color first across the different trial types (Figure S3B).
10 Individual task biases toward the color or the letter task can be seen, as well as the
11 difference between EH and HE trials. This difference can be better appreciated in Figure
12 S3C (that resembles Figure 2B). The color task was first responded to on 66% of EH trials
13 and on 50% of HE trials. The difference was significant across participants ($t(27)$ = 6.231, p
14 < 0.001, 95% CI [0.107, 0.212], d = 1.178).
15

16
17
18 **Figure S3 | Experiment 1: supplementary data. A.** Average confidence ratings across participants, as a
19 function of task difficulty, and split between correct and error trials (color-coded) and by task type (different
20 panels). Error bars denote 95% confidence intervals. **B.** Proportion of trials where the color task was first
21 responded to, as a function of the type of trial (EE = easy color, easy letter; EH = easy color, hard letter; HE =
22 hard color, easy letter; HH = hard color, hard letter). Each set of four dots connected by lines represents one
23 participant. Bigger dots represent average proportions across participants, and error bars denote 95% confidence
24 intervals. The dashed line corresponds to no preference towards responding first to the color or the letter task. **C.**
25 Density of the difference between proportion color task chosen first for EH trials and proportion color task chosen
26 first for HE trials. The density is drawn by using the difference of proportions for each participant. The across-
27 participant average is displayed as a big dot with error bars showing 95% confidence intervals. The dashed line
28 corresponds to no difference between EH and HE trials.
29

30 3.4. Response times

31 Experiment 3 implemented a variable delay between the removal of the perceptual stimuli
32 and the presentation of the response screen. The values the delay could acquire were
33 decided based on the typical response times in our previous experiments. Figure S4 shows
34 the distribution of response times for the first and second choices in Experiment 1.
35 Response times correspond to the time between the presentation of the response screen
36 until a click was made on a response square (first choice), or to the time between this first
37 click and a second click corresponding to the other task (second choice). Longer response
38 times for the first choice are most likely due to the initial decision of which task to respond to
39 first, plus the initial identification of how each element was mapped on the screen. For the

1   two non-zero delay values in Experiment 3, we selected 2s, and 4s. The first value was
2   longer than the response time for most choices, and the second was big enough to assume
3   that the decision for the hard task should already have been reached.
4

5
6   **Figure S4.** Response times density of the first and second choice in Experiment 1. Densities are drawn by using
7   the whole distribution of trials for all participants. Participant averages are depicted as single dots.

1 # 4. Logistic regression tables for Experiment 1

2

3 The next tables contain the fixed effects of the logistic regressions that were ran for
4 Experiment 1, as well as the comparison between models.

5

6 In all models, the dependent variable was always the probability of responding to the color
7 task first, and participant id was included as a random effect.

8

9 In what follows, we use the following abbreviations for the predictors:
10 - DiffExpPerf: difference in expected performance (color minus letter).
11 - DiffActAcc: difference in accuracy (color minus letter).
12 - DiffConf: difference in reported confidence (color minus letter).

13

14 Analysis 1: Logistic regression using the full model
15 All data, full model, logistic regression

	β estimate	Standard error	z value	p
Intercept	0.616	0.241	2.554	0.011
DiffExpPerf	0.003	0.001	2.910	0.004
DiffActAcc	0.002	0.000	4.936	<0.001
DiffConf	0.045	0.002	29.474	< 0.001

16

17 Analysis 2: Comparison with a 'partial model' without the confidence predictor
18 All data, partial model, logistic regression

	β estimate	Standard error	z value	p
Intercept	0.574	0.244	2.353	0.019
DiffExpPerf	0.009	0.001	8.886	< 0.001
DiffActAcc	0.004	0.000	9.742	< 0.001

19

20 All data, model comparison between partial and full model

Model	Deg.freedom	AIC	BIC	logLik	deviance
partial	4	13296.734	13326.029	-6644.367	13288.734
full	5	12177.248	12213.866	-6083.624	12167.248

21 $\chi^2(1) = 1121.4864$, $p < 0.001$

22

23 Analysis 3: Two-step regression approach
24 Here, we used the predicted values of the 'partial model' as an offset in another regression,
25 in which priority was predicted by the 'residual confidence' (ResidConf), that is the
26 confidence (DiffConf) left unexplained by accuracy (DiffActAcc) and expected performance
27 (DiffExpPerf).

	β estimate	Standard error	z value	p
Intercept	0.026	0.022	1.191	0.234
ResidConf	0.043	0.001	26.700	< 0.001

28

29

30 We replicated these analyses and obtained similar results if we only included trials with
31 different difficulty levels for the two tasks (EH and HE trials), to ensure that our results hold
32 when difficulty varies across the two tasks.

33

1 Analysis 1bis: Logistic regression using the full model

2 Different-difficulty data, full model, logistic regression

	β estimate	Standard error	z value	p
Intercept	0.579	0.231	2.506	0.012
DiffExpPerf	0.002	0.001	2.072	0.038
DiffActAcc	0.003	0.001	4.766	< 0.001
DiffConf	0.046	0.002	21.637	< 0.001

3

4 Analysis 2bis: Comparison with a "partial model" without the confidence predictor

5 Different-difficulty data, partial model, logistic regression

	β estimate	Standard error	z value	p
Intercept	0.520	0.234	2.222	0.026
DiffExpPerf	0.009	0.001	7.940	< 0.001
DiffActAcc	0.004	0.000	8.248	< 0.001

6

7 Different-difficulty data, model comparison between partial and full model

Model	Deg.freedom	AIC	BIC	logLik	deviance
partial	4	6703.503	6703.056	-3347.751	6695.503
full	5	6097.282	6130.473	-3043.641	6087.282

8 $\chi^2(1) = 608.221$, $p < 0.001$

9

10 Analysis 3bis: Two-step regression approach

11 This analysis mimics, with the different-difficulty data, what is performed in analysis 3.

	β estimate	Standard error	z value	p
Intercept	0.023	0.031	0.750	0.453
ResidConf	0.045	0.002	21.836	< 0.001

12

1 # 5. Difference in observed accuracy between first and second choice, for
2 experiments 1 to 3

3

4 Apart from confidence ratings and expected accuracy, another validation of the link between
5 priority and confidence could come from data on observed response accuracy. Indeed, since
6 accuracy correlates with confidence in our experimental conditions (as found in our first
7 study), the confidence-priority link could translate into an accuracy-priority link.

8

9 For our first three experiments, we looked at whether, within a trial, first choices were on
10 average more accurate than second choices. We found evidence for that in all three
11 experiments (Experiment 1: $t(27) = 5.319$, $p < 0.001$, 95% CI [0.041, 0.092], $d = 1.005$;
12 Experiment 2: $t(19) = 2.969$, $p = 0.008$, 95% CI [0.011, 0.066], $d = 0.664$; Experiment 3: $t(29)$
13 $= 2.880$, $p = 0.007$, 95% CI [0.007, 0.041], $d = 0.526$).

14

15 We also checked if these results held when only including trials with equal difficulty levels
16 (EE and HH) in the analysis. We used this subset of our data to guarantee that this measure
17 was independent from our previous analysis that linked priority to task difficulty by comparing
18 EH and HE trial types. In the same-difficulty case, the comparison of accuracy between the
19 first and second choice was significant for Experiment 1 ($t(27) = 2.698$, $p = 0.012$, 95% CI
20 [0.007, 0.054], $d = 0.510$) and Experiment 2 ($t(19) = 2.097$, $p = 0.049$, 95% CI [0.000, 0.060],
21 $d = 0.469$), while it was only a non-significant trend for Experiment 3 ($t(29) = 1.856$, $p =$
22 0.074, 95% CI [-0.002, 0.035], $d = 0.339$). The densities of the accuracy differences can be
23 seen in Figure S5.

24

25
26 **Figure S5 | A.** For Experiment 1, proportion of accuracy on the first choice minus proportion of accuracy on the
27 second choice, displayed as a density across participants. The black density corresponds to the whole dataset,
28 the grey one only to EE and HH trial types. Across-participant averages are displayed as big dots with error bars
29 showing 95% confidence intervals. The dashed line corresponds to no difference in accuracy between first and
30 second choices. **B.** Same as A, but for Experiment 2. **C.** Same as A, but for Experiment 3.

31

32 Although we would like to link these results to our analysis relating confidence to priority,
33 there could be however other possible explanations for the fact that accuracy in the first
34 choice is higher than accuracy in the second choice. For instance, memory limitations could
35 impair the second choice, or participants may set a different speed-accuracy trade-off
36 between the first and second choices.

37

6. Task and position biases

6.1. Task-related bias

Apart from confidence, other factors could have influenced choice order in our experiments. For instance, biases related to the nature of the task. As Figure 2A and Figure S3B show, some participants were overall more biased towards responding first to the color task, while some others were biased towards the letter task. For the three first experiments, a monotonic measure of bias magnitude could be obtained by averaging the proportion of trials where color was chosen first across trial types, and taking the absolute value of this average. This bias magnitude could be related to one of the measures of the priority effect. For Figure S6 we chose to relate it to the difference of proportions of trials where the color task was chosen first between EH and HE trials (the same measure shown for experiments 1, 2 and 3 in figures S3C, 2B and 2D, respectively). A Pearson correlation between the color/letter bias magnitude and the priority effect yielded a significant negative relationship (r = -0.370, p = 0.001), which suggests that a bigger task bias decreases the priority effect based on confidence.

Figure S6. For experiments 1, 2 and 3, difference between proportion color task chosen first for EH trials and proportion color task chosen first for HE trials, as a function of the magnitude of the color/letter bias. Each dot represents a participant. The inset text shows the r and p of a Pearson correlation between the variables on each axis, and the solid, black line on the plot represents the respective linear fit of the data.

6.2. Position-related bias

In our experiments, another possible bias has to do with the position of response boxes. Some participants may have favored certain positions on the screen when making their choices by clicking on the response box occupying that position. Figure S7 plots, for all 5 experiments, the proportion of trials for which the response occupying each of the possible screen positions was chosen first. For the first three experiments, a two-way repeated measures ANOVA was run, with the proportion of trials chosen as a dependent variable, and with vertical (top-bottom) and horizontal (left-right) position of the response boxes as factors. For Experiment 1 the main effect of vertical position was significant ($F(1,27)$ = 24.387, $p <$ 0.001, η_p^2 = 0.475), with horizontal position (p = 0.371) and interaction between both (p = 0.239) being non-significant. For Experiment 2 vertical position reached significance ($F(1,19)$

31

1   = 11.460, p = 0.03, η_p^2 = 0.376), with horizontal position (p = 0.309) and interaction (p =

2   0.105) being non-significant. For Experiment 3, both the main effects of vertical (F(1,29) =

3   30.020, p < 0.001, η_p^2 = 0.186) and horizontal (F(1,29) = 6.630, p = 0.015, η_p^2 = 0.509)

4   position were significant, but not their interaction (p = 0.997). Overall, there was a tendency

5   to favor top response boxes when making the first choice. In the case of Experiment 4, we

6   could explore a possible position bias when choosing which set of trials to face first. That

7   bias would either favor the left or the right choice boxes. The proportion of blocks for which

8   the left box was chosen was significantly bigger than 0.5 (t(30) = 2.352, p = 0.025, 95% CI

9   [0.512, 0.668], d = 0.422), thus revealing a tendency to choose the left box. The same

10   analysis was repeated for Experiment 5, revealing a non-significant trend in the same

11   direction (t(28) = 1.908, p = 0.067, 95% CI [0.495, 0.636], d = 0.354). A similar analysis

12   could be done for Experiment 6, now with the proportion of problems for which the left box

13   was chosen. This was significantly bigger than 0.5 (t(100) = 7.840, p < 0.001, 95% CI [0.635,

14   0.727], d = 0.855), again showing a bias towards choosing the left box.

1

2

3
4 **Figure S7. A.** For experiments 1, 2 and 3, for each of the four possible positions response boxes could have,
5 proportion of trials where the first choice was made on the choice box occupying that position. Bars represent
6 across-participant averages, with error bars showing 95% confidence intervals. Each participant's average is
7 displayed with a single dot. The horizontal, dashed line marks a proportion of 0.25, corresponding to a non-
8 biased ideal. **B.** For Experiment 4, proportion of blocks where the chosen set occupied the left choice box. The
9 bar represents across-participant averages, with the error bar showing 95% confidence interval. Each
10 participant's average is displayed with a single dot. The horizontal, dashed line marks a proportion of 0.5,
11 corresponding to a non-biased ideal. **C.** Same as B, but for Experiment 5. **D.** For Experiment 6, proportion of
12 problems where the chosen problem occupied the left choice box. The bar represents across-participant
13 averages, with the error bar showing 95% confidence interval. Each participant's average is displayed with a
14 single dot. The horizontal, dashed line marks a proportion of 0.5, corresponding to a non-biased ideal.
15

7. Effect of an easy-first approach on performance

7.1. Experiments 1 to 5

After finding an easy-first effect in our data, a logical follow-up question is whether dealing first with easy tasks improves performance as compared to dealing first with difficult tasks. We first tackled this question by analyzing previous data. We took the dataset from experiments 1 to 3 and selected only those trial types where the two tasks had different difficulty (EH and HE). We then split that subset of data between those trials where the easy task had been chosen first and those where the hard task had been chosen first. Then we calculated the average observed performance per participant, but we did so split by the expected difficulty of each task within a trial, in order to appreciate possible differences between easy and hard tasks. This is illustrated in Figure S8A. We ran a two-way repeated measures ANOVA, where the dependent variable was observed performance and the factors were the expected difficulty of the task chosen first, and expected difficulty of the task at hand. As expected, the main effect of task difficulty was significant for all experiments (Experiment 1: $F(1,27) = 1097.485$, $p < 0.001$, $\eta_p^2 = 0.976$; Experiment 2: $F(1,19) = 481.122$, $p < 0.001$, $\eta_p^2 = 0.962$; Experiment 3: $F(1,29) = 912.556$, $p < 0.001$, $\eta_p^2 = 0.969$). On the other hand, the main effect of difficulty of the task chosen first was not significant for the first two experiments (Experiment 1: $p = 0.911$; Experiment 2: $p = 0.150$), reaching marginal significance for Experiment 3 ($F(1,29) = 3.579$, $p = 0.069$, $\eta_p^2 = 0.110$). Interestingly, the interaction between the main two factors was significant for Experiment 1 ($F(1,27) = 17.278$, $p < 0.001$, $\eta_p^2 = 0.390$) and Experiment 2 ($F(1,19) = 7.394$, $p = 0.014$, $\eta_p^2 = 0.280$), and marginally significant for Experiment 3 ($F(1,29) = 3.527$, $p = 0.071$, $\eta_p^2 = 0.108$). As Figure S8A helps to illustrate, the direction of this interaction seemed to imply that, when the task was hard, responding to it first improved performance, as compared to when it was responded to first. The same happened when the task was easy: performance on it was better when responded to first. Thus, independently of the difficulty, responding to a task first seemed to bring an advantage in performance on that particular task, but there was no overall advantage behind responding always easy-first or hard-first.

We conducted a similar analysis for Experiment 4. However, each trial had only one task, so the variables we worked with were different. We took all the trials from the test phase and, for each participant, we calculated average performance, grouping trials by their set's expected difficulty (easy vs. hard) and by the expected difficulty of the set that the participant chose to do first on that block (easy vs. hard). This can be seen in Figure S8B We then used both variables as factors and performance as dependent variable for a two-way repeated measures ANOVA. The only significant main effect was expected difficulty ($F(1,30) = 924.600$, $p < 0.001$, $\eta_p^2 = 0.969$), with the difficulty of the chosen set ($p = 0.981$) and the interaction between both main effects ($p = 0.857$) not reaching significance. Thus, we found no evidence of any impact on performance of choosing certain difficulty first.

In Experiment 5 both conditions had the same expected difficulty. Thus, we could not look into a possible advantage of tackling first the easy task. However, we could still investigate whether prioritizing the low condition led to a better performance. We ran a two-way repeated measures ANOVA with average observed performance for the test phase as

1 dependent variable. As factors, we used that trial's condition, and the condition that block's
2 prioritized set belonged to. No main effects reached significance (trial's condition: p = 0.578;
3 block's prioritized condition: p = 0.912), and the interaction between both was not significant
4 either (p = 0.494). Figure S8C helps see the absence of a relationship between any
5 prioritization and performance.
6
7 We finally focused on Experiment 6. Given the ceiling effect on performance for this
8 experiment, though, we used response time as the dependent variable. For each participant,
9 we calculated median response times (in order to downweight outliers corresponding to trials
10 where the participant took a considerable time to respond) per problem, grouping problems
11 within a trial according to their expected difficulty, and to the expected difficulty of the
12 problem the participant chose to do first on that block (see Figure S8D). However, in order to
13 have data from every participant on each category, we had to remove 4 participants who
14 always chose the easy problem first. After running an ANOVA, the main effect of the
15 problem's difficulty reached significance ($F(1,79)$ = 24.570, p < 0.001, η_p^2 = 0.237), but not
16 the main effect of the difficulty of the chosen problem (p = 0.189), or their interaction (p =
17 0.516). Response times, then, were not affected by an easy-first approach.
18

19

20
21
22 **Figure S8. A.** For experiments 1 to 3 (different panels), observed performance (as a percentage) as a function of
23 the expected difficulty of the task (x-axis) and the task first responded to (color-coded). Bars represent averages
24 across participants, with error bars denoting 95% confidence intervals. Dots represent individual participants.
25 Only data from the EH and HE trial types was used. Top and bottom dashed lines help indicate where 90% and
26 60% observed performance would lay, respectively. **B.** Same as A, but for Experiment 4. Only trials from the test
27 phase are used. However, the task first responded to refers to the whole block. **C.** For Experiment 5, observed
28 performance (as a percentage) as a function of the condition for that trial (x-axis) and the condition whose set
29 was prioritized in that block (color-coded). Bars represent averages across participants, with error bars denoting

35

1 95% confidence intervals. Dots represent individual participants. The dashed line indicates where 75% observed
2 performance would lay.Only trials from the test phase are used. **D.** For Experiment 6, response time as a function
3 of expected difficulty of the problem (x-axis) and the problem first responded to (color-coded to match the rest of
4 the figure). Dots represent the median response times of individual participants, and bars represent the average
5 of those medians.
6

7 ## 7.2. Supplementary experiment controlling response order

8 We decided to run an experiment with a new sample (n=16), where the central manipulation
9 consisted in controlling response order. In half the trials response order was free, exactly as
10 in experiments 1 to 3. In half the other trials, though, response order was imposed. After the
11 stimulus, only two choice boxes appeared on the screen: either those related to the color
12 task, or those related to the letter task. After a choice was made, the two boxes were
13 replaced by those two corresponding to the other task, and participants had to make the
14 second choice. Half the trials with imposed order required responding to color and then to
15 letter, and vice versa in the other half. Within a trial, the difficulty of the two tasks was always
16 different: thus, trials were only either EH or HE, with half the trials within a block being of
17 each trial type. Participants completed 4 parts of 4 blocks each, with each block having 24
18 trials. That number was chosen so, within a block, the same trial type (EH or HE) and
19 response order (imposed easy first, imposed hard first, or free, with this one being presented
20 as many times as both imposed orders together) were presented at the same ratio, although
21 in a random order. As for the payoff system, it was exactly as in Experiment 2.
22

23 Performance in this experiment is illustrated in Figure S9A. We ran a three-way ANOVA with
24 observed performance as dependent variable, and where the three factors were response
25 order condition (free vs. imposed), task difficulty (easy vs. hard) and task responded to first
26 (easy vs. hard). As expected, the main factor of task difficulty was highly significant (F(1,15)
27 = 616.9, p < 0.001, η_p^2 = 0.976), but none of the other factors nor interactions reached
28 statistical significance (condition: p = 0.929; task responded to first: p = 0.923; condition x
29 task difficulty: p = 0.788; condition x task responded to first: p = 0.669; task difficulty x task
30 responded to first: p = 0.414; triple interaction: p = 0.188).
31

32 In order to further strengthen the main claim of our study, we also used the data from the
33 present experiment to find support for priority based on confidence. As already done with
34 previous experiments, we chose to use expected difficulty as a proxy for confidence. When
35 comparing the two trial types of this experiment, we found that the color task was responded
36 to first on 54% of EH trials and on 49% of HE trials. The difference of proportions, plotted in
37 Figure S9B, was significant across participants (t(15) = 2.467, p = 0.026, 95% CI [0.007,
38 0.100], d = 0.617), thus providing further support for our central message.
39

Figure S9 | Supplementary experiment controlling response order: results. A. For both response order types (different panels), observed performance (as a percentage) as a function of expected difficulty of the task (x-axis) and the task first responded to (color-coded). Bars represent averages across participants, with error bars denoting 95% confidence intervals. Dots represent individual participants. Top and bottom dashed lines help indicate where 90% and 60% observed performance would lay, respectively. **B.** Density of the difference between proportion color task chosen first for EH trials and proportion color task chosen first for HE trials. The density is drawn by using the difference of proportions for each participant. The across-participant average is displayed as a big dot with error bars showing 95% confidence intervals. The dashed line corresponds to no difference between EH and HE trials. The sample size for this experiment was 16 participants, each participant completing 384 trials.

1   ## 8. Supplementary performance analyses for Experiment 5

2

3   The present section offers a more in-depth analysis of performance in Experiment 5. We
4   compare performance among different parts or phases of our experiment and offer figures to
5   illustrate some of the information given in the main body of the manuscript.

6

7   In the main text we showed that performance was not different between the low and the high
8   conditions (see also Figure 4B). This analysis was conducted over all trials across different
9   parts of the experiment: the familiarization and test phases of the main part, and the final
10 trials where confidence had to be reported. We confirmed that performance was also similar
11 between the low and high conditions when analyzing separately the familiarization phase
12 ($t(28) = -1.027$, $p = 0.313$, 95% CI [-0.087, 0.029], $d = -0.191$), the test phase ($t(28) = -0.468$,
13 $p = 0.643$, 95% CI [-0.070, 0.044], $d = -0.087$), and the confidence trials ($t(28) = -1.281$, $p =$
14 0.211, 95% CI [-0.100, 0.023], $d = -0.238$). This is illustrated in Figure S10A.

15

16 Also in the main text we showed the relationship between the greater confidence in the low
17 condition and the greater tendency to prioritize low condition sets. This relationship could not
18 be explained by a performance advantage in low condition trials, as previously reported, as
19 no significant correlation was found between the difference of performance between low and
20 high trials and the proportion of blocks where the low condition set was chosen first ($r = -$
21 0.099, $p = 0.611$). This is illustrated in Figure S10B.

22

23 Finally, we made sure that performances among the different parts of the experiment were
24 similar within participants. This is important, since in our study we link performance in the
25 main part of the experiment with confidence in the final trials where it had to be reported. We
26 found that across participants, performance in the familiarization trials was correlated with
27 performance in the test trials, both for the high condition ($r = 0.820$, $p < 0.001$) and for the
28 low condition ($r = 0.928$, $p < 0.001$). Figure S10C illustrates this. We then pooled all the trials
29 of the main part together and ran a correlation with performance on the final trials where
30 confidence had to be rated (see Figure S10D). The correlation was significantly positive for
31 both conditions (high: $r = 0.720$, $p < 0.001$; low: $r = 0.831$, $p < 0.001$).

32

Figure S10. Supplementary performance analyses for Experiment 5. A. For the familiarization and test phases of the main part, and for the final trials where confidence reports were required, observed performance as a function of expected performance, both in percentage, split by condition. Bars represent averages across participants, with error bars denoting 95% confidence intervals. Dots represent individual participants. The horizontal dashed line indicates where 75% observed performance would lay. **B.** Proportion of blocks where participants chose to complete first the the set whose trials belonged to the low condition, as a function of the difference, for the familiarization phase, between the average performance for low condition trials minus the average performance for high condition trials. The line depicts a linear fit of the data. **C.** Average performance for the familiarization trials against average performance for the test trials. Each participant is depicted with two dots, one corresponding to each condition (color-coded). Lines represent linear fits for each condition's data. **D.** Average performance for the main part of the experiment (with the familiarization and test trials being pooled together) against average performance for those trials where confidence had to be rated. Each participant is depicted with two dots, one corresponding to each condition (color-coded). Lines represent linear fits for each condition's data.

1   # 9. Stimulus materials

2

3   ## 9.1. Complete list of animal names used for experiments 4 and 5

4   The following list contains all the animal names used to label sets in experiments 4 and 5
5   . The original French name is written first in capital letters, as displayed in the experiment,
6   followed by the English translation (between brackets).
7

ABEILLE (bee)	AGNEAU (lamb)	AIGLE (eagle)
ANTILOPE (antelope)	AUTRUCHE (ostrich)	BABOUIN (baboon)
BALEINE (whale)	BISON (bison)	BUFFLE (buffalo)
CANARD (duck)	CASTOR (beaver)	CHAMEAU (camel)
CHENILLE (caterpillar)	CHEVAL (horse)	CHÈVRE (goat)
CHIEN (dog)	CHOUETTE (barn owl)	CIGOGNE (stork)
COCHON (pig)	COYOTE (coyote)	CRIQUET (cricket)
DAUPHIN (dolphin)	ÉCUREUIL (squirrel)	ÉLÉPHANT (elephant)
ESCARGOT (snail)	FOURMI (ant)	FURET (ferret)
GAZELLE (gazelle)	GIRAFE (giraffe)	GORILLE (gorilla)
GUÉPARD (cheetah)	HAMSTER (hamster)	HERISSON (hedgehog)
HIBOU (owl)	HYENE (hyena)	JAGUAR (jaguar)
LAPIN (rabbit)	LIMACE (slug)	LOUTRE (otter)
LUCIOLE (firefly)	MARMOTTE (groundhog)	MOINEAU (sparrow)
MOUTON (ram)	OTARIE (seal)	PANDA (panda)
PAPILLON (butterfly)	PIGEON (pigeon)	POISSON (fish)
PONEY (pony)	POULE (chicken)	RENARD (fox)
RENNE (reindeer)	REQUIN (shark)	SANGLIER (boar)
SCARABÉE (beetle)	SERPENT (snake)	SINGE (ape)
SOURIS (mouse)	TAUREAU (bull)	TIGRE (tiger)
TORTUE (turtle)	VACHE (cow)	VAUTOUR (vulture)
ZEBRE (zebra)		

1 ## 9.2. Complete list of arithmetic problems used for Experiment 6

2 The following list shows the schematics, actual problem and answer for each pair of easy
3 and hard arithmetic problems used in Experiment 6. The two problems within a pair (each
4 row) were always presented together.
5

Easy question			Hard question		
Schematics	Problem	Answer	Schematics	Problem	Answer
a+b	2+3	5	a*b	2*3	6
(a+b)+c	(2+4)+5	11	(a+b)*c	(2+4)*5	30
a-b	8-4	4	a/b	8/4	2
(a-b)-c	(9-5)-2	2	(a+b)/c	(9+5)/2	7
(a+b)-c	(4+2)-2	4	(a-b)/c	(4-2)/2	1
(a-b)+c	(8-2)+3	9	(a-b)*c	(8-2)*3	18
2a+b	2*5+4	14	a/2b	5/2*4	10
a+2b	3+2*6	15	2a*b	2*3*6	36
2a+(b-c)	2*4+(5-2)	11	a*(b+2*c)	4*(5+2*2)	36
a-2b+c	5-2*2+5	6	2a*b/c	2*5*2/5	4
a+(2b-c)	3+(2*6-4)	11	a*(2b-c)	3*(2*6-4)	24
a-b+2c	9-3+2*2	10	2a/b+c	2*9/3+2	8
(a+b+c)-d	(1+9+6)-3	13	(a+b-c)*d	(1+9-6)*3	12
(a-b-c)-d	(9-1-2)-6	0	(a-b-c)/d	(9-1-2)/6	1
(a+b-c)-d	(7+2-4)-3	2	(a-b-c)*d	(7-2-4)*3	3
(a-b-c)-d	(9-1-4)-2	2	(a+b-c)/d	(9+1-4)/2	3
(a+b)+(2c-d)	(3+6)+(2*5-1)	18	(a+b)*(c+2d)	(3+6)*(5+2*1)	63
(a+2b)+(c+d)	(5+2*4)+(9+3)	25	(a-b)*(2c-d)	(5-4)*(2*9-3)	15
(a+b)+(c-2d)	(8+6)+(2-2*5)	6	2(a+b)/(c+d)	2*(8+6)/(2+5)	4
(a+b)+(c+2d)	(9+1)+(6+2*2)	20	2(a-b)/(2c-d)	2*(9-1)/(6-2)	4

6

10. References

García-Pérez, M. A. (1998). Forced-choice staircases with fixed step sizes: asymptotic and small-sample properties. *Vision Research*, *38*(12), 1861–1881.

Kepecs, A., Uchida, N., Zariwala, H. A., & Mainen, Z. F. (2008). Neural correlates, computation and behavioural impact of decision confidence. *Nature*, *455*(7210), 227–231.

Peirce, C. S., & Jastrow, J. (1885). *On Small Differences of Sensation*.

Sanders, J. I., Hangya, B., & Kepecs, A. (2016). Signatures of a Statistical Computation in the Human Sense of Confidence. *Neuron*, *90*(3), 499–506.