

Global climate modeling of Saturn's atmosphere. Part IV: Stratospheric equatorial oscillation

Déborah Bardet, Aymeric Spiga, Sandrine Guerlet, Simon Cabanes, Ehouarn Millour, Alexandre Boissinot

▶ To cite this version:

Déborah Bardet, Aymeric Spiga, Sandrine Guerlet, Simon Cabanes, Ehouarn Millour, et al.. Global climate modeling of Saturn's atmosphere. Part IV: Stratospheric equatorial oscillation. Icarus, 2021, 354, pp.114042. 10.1016/j.icarus.2020.114042. hal-03082393

HAL Id: hal-03082393 https://hal.science/hal-03082393v1

Submitted on 22 Aug 2022

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.



- Global climate modeling of Saturn's atmosphere.

 Part IV: stratospheric equatorial oscillation.
- Deborah Bardet^{a,*}, Aymeric Spiga^{a,b}, Sandrine Guerlet^a, Simon Cabanes^c,
 Ehouarn Millour^a, Alexandre Boissinot^a
- ^aLaboratoire de Météorologie Dynamique / Institut Pierre-Simon Laplace (LMD/IPSL),
- Sorbonne Université, Centre National de la Recherche Scientifique (CNRS), École
 Polytechnique, École Normale Supérieure (ENS), address: Campus Pierre et Marie Curie
- Polytechnique, Ecole Normale Superieure (ENS), address: Campus Pierre et Marie Curi 8 BC99, 4 place Jussieu, 75005 Paris, France
- ^bInstitut Universitaire de France (IUF), address: 1 rue Descartes, 75005 Paris, France
 ^cDICEA. Sapienza Universià di Roma, address: Via Eudossiana 18, 00184 Rome, Italy

11 Abstract

The Composite InfraRed Spectrometer (CIRS) on board Cassini revealed an equatorial oscillation of stratospheric temperature, reminiscent of the Earth's Quasi-Biennial Oscillation (QBO), as well as anomalously high temperatures under Saturn's rings. To better understand these predominant features of Saturn's atmospheric circulation in the stratosphere, we have extended to the upper stratosphere the DYNAMICO-Saturn global climate model (GCM), already used in a previous publication to study the tropospheric dynamics, jets formation and planetary-scale waves activity. Firstly, we study the higher model top impact on the tropospheric zonal jets and kinetic energy distribution. Raising the model top prevents energy and enstrophy accumulation at tropopause levels. The reference GCM simulation with 1/2° latitude/longitude resolution and a raised model top exhibits a QBO-like oscillation produced by resolved planetary-scale waves. However, the period is more irregular and the downward propagation faster than observations. Furthermore, compared to the CIRS temperature retrievals, the modeled QBO-like oscillation underestimates by half both the amplitude of temperature anomalies at the equator and the vertical characteristic length of this equatorial oscillation. This QBO-like oscillation is mainly driven by westward-propagating waves; a significant lack of eastward wave-forcing explains a fluctuating eastward phase of the QBO-like oscillation.

August 3, 2020

^{*}Corresponding author: deborah.bardet@lmd.jussieu.fr $Preprint\ submitted\ to\ Icarus$

We also show that the seasonal cycle of Saturn is a key parameter of the establishment and the regularity of the equatorial oscillation. At 20°N and 20°S latitudes, the DYNAMICO-Saturn GCM exhibits several strong seasonal eastward jets, alternatively in the northern and southern hemisphere. These jets are correlated with the rings' shadowing. Using a GCM simulation without rings' shadowing, we show its impact on Saturn's stratospheric dynamics. Both residual-mean circulation and eddy forcing are impacted by rings' shadowing. In particular, the QBO-like oscillation is weakened by an increased drag caused by those two changes associated with rings' shadowing.

Keywords: Saturn, Atmosphere, dynamics, stratosphere

1. Introduction

18

The longevity of the Cassini mission permitted an unprecedented spatial and seasonal coverage of Saturn's stratosphere. In particular, the Composite InfraRed Spectrometer (CIRS) instrument on board Cassini revealed stratospheric phenomena analogous to ones occuring in Earth's and Jupiter's stratospheres (Dowling, 2008).

Firstly, seasonal monitoring of hydrocarbons in Saturn's stratosphere suggests a conceivable inter-hemispheric transport of stratospheric hydrocarbons (Guerlet et al., 2009, 2010; Sinclair et al., 2013; Fletcher et al., 2015; Sylvestre et al., 2015), similar to the Earth's Brewer-Dobson circulation which affects the stratospheric ozone distribution (Murgatroyd and Singleton, 1961; Dunkertton, 1979; Solomon et al., 1986; Butchart, 2014). The Cassini mission further revealed a lack of temperature minimum under the rings' shadow (that was expected by the radiative balance Fletcher et al. (2010); Friedson and Moses (2012); Guerlet et al. (2009, 2010, 2014)), which is an additional hint of subsidence motion in the winter hemisphere.

Secondly, a crucial discovery is that temperatures retrieved from thermal infrared spectra in Saturn's stratosphere exhibit an equatorial oscillation with semi-annual periodicity (Orton et al., 2008; Fouchet et al., 2008). During the

13-Earth-years cruise of Cassini around Saturn, CIRS and radio occultations measurements permitted to characterize this equatorial oscillation of temperature and its downward propagation over seasonal timescales (Guerlet et al., 2011; Li et al., 2011; Schinder et al., 2011; Guerlet et al., 2018). Alternatively eastward and westward stacked jets are associated with the temperature signatures detected by Cassini, according to the thermal wind equation. This oscillation 37 is called Saturn "Quasi-Periodic Oscillation" or "Semi-Annual Oscillation", due to its half-Saturn-year periodicity. Equatorial oscillations appear to be common phenomena in planetary stratospheres. Observations of Jupiter's stratosphere revealed an equatorial oscillation of temperature (Leovy et al., 1991; Orton et al., 1991) associated with a wind propagation reversal (Friedson, 1999; Simon-Miller et al., 2007). This oscillation exhibits a period of 4.4 Earth years and has been designated as the jovian Quasi-Quadrennial Oscillation. Equatorial oscillations are also suspected on Mars (Kuroda et al., 2008; Ruan et al., 2019). Those equatorial oscillations in planetary atmospheres are reminiscent of the Earth's stratospheric Quasi-Biennial Oscillation (QBO) and Semi-Annual Oscillation 47 (SAO) (Lindzen and Holton, 1968; Andrews et al., 1983; Baldwin et al., 2001). 48 Earth's Quasi-Biennial Oscillation (QBO) results from wave-mean flow interactions (Reed et al., 1961; Andrews et al., 1983; Baldwin et al., 2001). The QBO is driven by the vertical propagation of tropospheric waves – both planetary-51 scale and mesoscale waves – to stratospheric altitudes where they break either by becoming convectively unstable or by encountering critical level (depending on vertical and horizontal wavelengths, wave phase speeds and vertical shear (Lindzen and Holton, 1968; Dunkerton, 1997)). Critical levels play a central role in driving the alternate eastward/weastward QBO phases by zonal momentum transfer. Radiative and mechanical damping of the waves also induce 57 wave absorption by the mean flow, as suggested by Holton and Lindzen (1972). Equatorially trapped waves carry eastward and westward momentum. During wave breaking, momentum is transferred to the mean flow, changing the largescale zonal wind field and driving an axisymmetric meridional circulation. The observed Earth's QBO displays a vertical stack of warm and cold anomalies

due to this meridional circulation: adiabatic warming in the subsidence region produces warm anomalies and adiabatic cooling in the upwelling region produces cold anomalies (Plumb and Bell, 1982). The induced large-scale thermal perturbations, and zonal wind reversal, oscillate with an average period of 28 months and a mean downward propagation rate of 1 km per month on Earth (Reed et al., 1961; Mayr and Lee, 2016). The eastward and westward phases of the Earth's equatorial oscillation are of similar amplitude and are created by a diversity of eastward- and westward-propagating wave sources (Dunkerton, 1997; Hamilton et al., 2001; Giorgetta et al., 2002; Ern and Preusse, 2009). The terrestrial QBO's eastward phase is produced by the wave breaking of eastward-propagating gravity waves (from tropospheric moist convection) and Kelvin waves. Kelvin waves contribute to about 30% of the eastward forcing (Ern and Preusse, 2009), whereas mesoscale gravity waves contribute to 70% of the eastward forcing (Dunkerton, 1997). The westward phase of the Earth's QBO is induced by Rossby and mixed Rossby-gravity waves' breaking, as they carry westward momentum. Furthermore, inertia-gravity waves transport eastward and westward zonal momentum, thus are involved in both the eastward 79 and westward phases of the QBO (Baldwin et al., 2001).

Despite differences in their periods, Jupiter's and Saturn's equatorial oscillations share similarities with the Earth's (Dowling, 2008), which raises questions about the driving mechanisms of the gas giants' equatorial oscillations. Building on tools developed throughout the long history of Earth's atmospheric modeling, numerical models of global circulation on Jupiter and Saturn have been developed for almost 20 years. Stratospheric oscillations on gas giants have been previously addressed by a handful of those models. Three studies employed a quasi-two-dimensional modeling framework that only resolves meridional and vertical structure and parameterizes longitudinal forcing. On the one hand, Li and Read (2000) demonstrated that the major contribution to a QBO-like oscillation in Jupiter's atmosphere was planetary-scale waves (Rossby, mixed Rossby-gravity and Kelvin waves). On the other hand, Friedson (1999) and Cosentino et al. (2017) showed that a parameterization of mesoscale gravity

waves enabled to reproduce the observed jovian equatorial oscillation – with no need to invoke planetary-wave forcing.

100

101

102

103

104

105

106

109

110

111

113

114

115

117

118

119

120

123

Regardless of the nature of waves invoked in these studies, QBO-like oscillations are phenomena resulting from wave propagation in longitude, latitude and on the vertical that cannot be fully resolved by 2D models: the 3D propagation of waves, and their impact on global circulation, must be parameterized in 2D models. Thus, to better understand the wave-mean flow interactions leading to the observed gas giants' equatorial oscillations, atmospheric models must solve the three-dimensional dynamics. A fully three-dimensional model to study in detail the global troposphere-to-stratosphere circulation in gas giants has only been recently developed, because of the huge computational resources required to resolve eddies arising from hydrodynamical instabilities that putatively force equatorial oscillations. Showman et al. (2019) were the first to show the development of a QBO-like oscillation in an idealized 3D global primitive-equation model for gas giants and brown dwarfs. Their model uses a random wave forcing parameterization at the radiative-convective boundary to drive equatorial oscillations, and a Newtonian scheme to represent radiative heating/cooling in the thermodynamics energy equation. A stack of eastward and westward jets that migrate downward over time is created in the stratosphere of Showman et al. (2019)'s model, analogous to Earth's QBO, with a range of periods similar to Jupiter's and Saturn's equatorial oscillations. Nevertheless, the QBO-like oscillations depicted in their model occur at higher pressure (between 10^5 and 10^3 Pa) than the observations (Saturn's equatorial oscillation extends from 10^3 to 1 Pa).

To gain further insights on Saturn's equatorial oscillation, this work aims at adopting the three-dimensional approach of Showman et al. (2019) with a more realistic representation of radiative transfer and wave dynamics in Saturn's stratosphere. The present paper is part IV of a series of papers about global climate modeling of Saturn. In part I, Guerlet et al. (2014) built a complete seasonal radiative model for Saturn. In part II, Spiga et al. (2020) coupled this radiative model to a new hydrodynamical core (Dubos et al., 2015) to obtain

the DYNAMICO-Saturn Global Climate Model (GCM). Using this GCM tailored for Saturn, Spiga et al. (2020) simulated Saturn's atmosphere from the troposphere to the lower stratosphere for 15 Saturn years at fine horizontal resolution, without any prescribed sub-grid-scale wave parameterization. The DYNAMICO-Saturn GCM simulation described in Spiga et al. (2020) produced consistent thermal structure and seasonal variability compared to Cassini CIRS measurements, mid-latitude eddy-driven tropospheric eastward and westward jets commensurate to those observed (and following the zonostrophic regime – see section 3 for details – as is argued in the part III paper by Cabanes et al. (2020)), and planetary-scale waves such as Rossby-gravity (Yanai), Rossby and Kelvin waves in the tropical waveguide. While the simulations in Spiga et al. (2020) exhibited stacked eastward and westward jets in the equatorial stratosphere, those jets were not propagating downwards, contrary to the observed equatorial oscillation. The likely reason for this is that the model top was too low and the vertical resolution too coarse to address the question of a QBO-like oscillation in the stratosphere.

126

127

128

130

131

132

133

135

136

137

140

141

142

144

145

146

149

150

151

154

In this paper, we use the DYNAMICO-Saturn model as in Spiga et al. (2020) with a top of the model extended to the higher stratosphere. As in the part II paper, the simulations presented here include neither a gravity-wave drag nor the bottom thermal forcing invoked in Showman et al. (2019). Planetary-scale waves involved in the equatorial dynamics are triggered by both baroclinic and barotropic instabilities associated to tropospheric jets in our DYNAMICO-Saturn GCM (Spiga et al., 2020). We describe here the benefits on the strato-spheric dynamics of using a wider vertical extent in our GCM. In section 2, we describe briefly our DYNAMICO-Saturn GCM. Section 3 presents, through comparison between Spiga et al. (2020) and our results, the impact on dynamical spectral regime of raising the model top. Section 4 focuses on the stratospheric dynamics and wave-mean flow interactions producing a QBO-like oscillation in our Saturn GCM. We also tested the Saturn annual cycle influences in its equatorial oscillation periodicity in section 5. In addition, a strong seasonal wind reversal is obtained at 20°N and 20°S. We study this phenomenon and discuss

the impact of the rings' shadowing on the stratospheric tropical dynamics in section 6. Summary, conclusions and perspectives for future improvements are explained in section 7.

2. DYNAMICO-Saturn

A complete description of the DYNAMICO-Saturn is available in Spiga et al. (2020). A Global Climate Model (GCM) is composed of two parts: a dynamical core to resolve the Navier-Stokes equations on planetary scales and a physical package which is an ensemble of parameterizations to describe sub-grid-scale processes. The Saturn GCM developed at Laboratoire de Météorologie Dynamique employs DYNAMICO, a dynamical core using an icosahedral grid that ensures conservation and scalability properties in massively parallel resources (Dubos et al., 2015). It solves the primitive hydrostatic equations assuming a shallow atmosphere. Our DYNAMICO-Saturn features an optional absorbing ("sponge") layer with a Rayleigh drag acting on the topmost model layers. As in Spiga et al. (2020), we did not use it in simulations presented in this paper since previous studies (Shaw and Shepherd, 2007; Schneider and Liu, 2009; Liu and Schneider, 2010) show that using such an absorbing layer poses problems of angular momentum conservation.

The physical package used in our DYNAMICO-Saturn is tailored for Saturn, particularly regarding radiative transfer (this is fully detailed in the part I paper by Guerlet et al. (2014)). Radiative transfer computations use correlated-k tables, tabulated offline from detailed line-by-line computations. Methane, ethane and acetylene are included in radiative contributions, as well as H₂-H₂ and H₂-He collision-induced absorption and aerosol layers in the troposphere and the stratosphere. Rings' shadowing is taken into account in radiative computations. The internal heat flux prescribed at the bottom of the model is used as a boundary condition for radiative transfer calculations. Possible unstable temperature lapse rates, induced after radiative transfer calculations, are modified by a convective adjustment scheme: the vertical profile of temperature is instantaneously brought back to the dry adiabat.

Most simulation settings in this part IV paper are analogous to those adopted in the part II paper by Spiga et al. (2020). For our reference simulation, we employ DYNAMICO-Saturn with an approximate horizontal resolution of 1/2°

in longitude/latitude. The time step of calculations is 118.9125 seconds, with physical packages called every half a Saturn day and radiative computations done every 20 Saturn days, because of the long radiative timescales in tropo-sphere and stratosphere of gas giants. The values of all parameters detailed in Table 1 of Spiga et al. (2020) are set similarly in the simulations of this paper. The major difference between Spiga et al. (2020) (Part II) and the present Part IV reference simulation is the inclusion of 61 levels in the vertical dimension, extending from the troposphere $p_{bottom} = 3.10^5$ Pa (or 3 bars) to the upper stratosphere $p_{top} = 10^{-1} \text{ Pa } (1 \text{ } \mu \text{bar}).$

In this study, we opt for a reasonable yet not particularly high vertical discretization. Unlike Showman et al. (2019), we do not attempt to test the sensitivity of the modeled equatorial oscillation to vertical resolution. We choose, instead, to make a simulation long enough to reach a steady state in the troposphere (at least 8 simulated Saturn years, see Spiga et al. (2020)) and to simulate several cycles of the equatorial oscillation in the stratosphere. This is crucial to obtain interactions between the troposphere and the stratosphere, and create a conceivable and stable equatorial oscillation. This choice of modeling strategy does not allow us to attest that the results presented here are vertically convergent, which is deferred to another study. It is possible that a simulation with twice as many levels over the same pressure range would give quantitatively different results.

Simulations using our DYNAMICO-Saturn are initialized at every horizontal grid point with a vertical profile of temperature computed by a 1D radiative-convective equilibrium model of Saturn's atmosphere (Guerlet et al., 2014), using the same physical parameterizations than our DYNAMICO-Saturn GCM. The single-column simulation starts with an isothermal profile and runs for twenty Saturn years to reach the annual-mean steady-state radiative-convective equilibrium. The initial zonal and meridional winds are set to zero in our simulations. DYNAMICO-Saturn simulations requires radiative and dynamical spin-up of about five simulated Saturn years for the tropopause levels to ensure a dynamical steady-state (Spiga et al., 2020). In what follows, we present 13-

221

222

224

225

228

229

230

231

232

233

234

235

237

238

239

240

242

243

247

3. Impact of the extended model top on Saturn's atmospheric dynamics

Saturn's atmosphere is dominated by zonal jets, invariant in the longitudinal direction (i.e. flow axisymmetry) and alternatively prograde (eastward) and retrograde (westward) in latitude. The spherical curvature of the planetary fluid layer acts to channel kinetic energy into the zonal direction via the so-called β -effect, where the parameter $\beta = 2\Omega\cos\varphi/a$ is the variation of the Coriolis force with Saturn's radius a, rotation rate Ω and latitude φ . This dynamical regime is referred to as zonostrophic macroturbulence (Sukoriansky et al., 2002; Galperin et al., 2014). Further discussions on this topic can be found in the Part III paper Cabanes et al. (2020).

Here, we present a comparison of tropospheric and stratospheric jets as simulated by Spiga et al. (2020) versus the present work, to check that the dynamical regime is conserved with the new vertical grid. Figure 1 displays altitude/latitude sections of zonal-mean zonal wind after 11 years of simulation for each vertical grid. Both simulations present similar results in the troposphere, although with some notable differences. The 32-vertical-level simulation (Spiga et al. (2020), Figure 1(a)) exhibits about 10 jets, over latitude, each one extending from 3×10^5 Pa (or 3 bars) to the model top (10² Pa or 1 mbar) except the equatorial one. At the equator, there is a stacking of eastward and westward jets between 2×10^4 Pa and the model top. With an extended vertical range (Figure 1(b), model top at 10^{-1} Pa), we now distinguish 14 jets into the troposphere and 9 jets in the stratosphere. The equatorial stacking of wind seen in 32-level simulation is now clearly localized between 2×10^4 Pa (tropopause) and the model top. Contrary to previous GCM works (Lian and Showman, 2008, 2010; Schneider and Liu, 2009), we remark that some of eastward jets of the 61-level simulation, particularly ones closer to the equator, decay with altitude, which is not the case in the 32-level one (except for the equatorial jet). In

both simulations, the jets beyond 60° latitudes do not exhibit this decay with altitude. Thus the behavior of our 61-level troposphere-to-stratosphere simulation is more consistent with observations for the lower latitudes (Fletcher et al., 2019). We also note that the equatorial tropospheric eastward jet is less intense 252 in our reference (61-level) simulation than in the 32-level simulation of Spiga et al. (2020).

250

25

254

255

256

257

259

260

261

264

265

268

269

270

273


274

275

278

We now extend our comparison by computing the spherical harmonic decomposition of horizontal velocity maps from our 61-level simulation, using the same tools as in the Part III paper (Cabanes et al., 2020) for the 32-level simulation. When spherical harmonic functions are invoked, energy spectra depend on non-dimensional total and zonal indices n and m respectively (Boer, 1983). The axisymmetric flow component defines the jets and corresponds to the zonal index m=0. The non-axisymmetric flow component, or residual, defines waves and eddies and corresponds to all other indices $m \neq 0$. We report on Figure 2 the time evolution of the total energy integrated over all indices, for the upper troposphere and the lower stratosphere. The general tendency shows that the total energy in the troposphere is similar in our 61-level simulation and in the 32-level simulation of Spiga et al. (2020). However, the stratosphere is more energetic than the troposphere and the energetic intensity reduces by a factor of two when we extend the model top in the 61-level simulation.

We show the temporal average of the spectral quantities at steady state in the upper troposphere in Figure 3 and the lower stratosphere in Figure 4. A common feature of the 32-level and 61-level simulations is that the energetic magnitude of the zonal jets (i.e. axisymmetric spectra in red) is bounded by the $0.5\beta^2 n^{-5}$ spectral law of the zonostrophic theory coined by Sukoriansky et al. (2002). The energetic maximum is well estimated by the Rhines typical index $n_R = a(\beta/2U)^{1/2}$ (Rhines, 1977), which sets typical jets' size to $\sim 38,000$ km in the troposphere and $\sim 44,000$ km in the stratosphere (see details in Figure 3). At Rhines scale, the energy of the jets is two orders of magnitude higher than the residual energy spectra, namely the energy contained in waves and eddies. To disclose the dynamical transfers underlying this jet-dominated






Figure 1: Altitude/latitude cross sections of the zonal-mean zonal wind, at the northern spring equinox, comparing Spiga et al. (2020) results (32 vertical levels, 1(a)) and our results using 61 vertical levels (1(b)).




Figure 2: Time evolution of the total energy (m² s⁻²) in the two last simulated Saturn years for each simulations. Red and green curves correspond to the 32-level simulation at $p \sim 1.9 \times 10^4$ Pa and $p \sim 4.9 \times 10^2$ Pa respectively. Blue and black curves correspond to the reference simulation at $p \sim 1.9 \times 10^4$ Pa and $p \sim 4.9 \times 10^2$ Pa respectively.

flow, we also report in Figures 3 and 4 the spectral fluxes of energy and enstrophy. In all simulations, spectral fluxes clearly show the predominance of an inverse cascade of energy at large scale and a direct cascade of enstrophy at small scale. This energy-enstrophy double cascade scenario is a well-known feature of quasi-two-dimensional (2D) turbulence, when a turbulent flow is made quasi-2D by confinement to a shallow atmosphere and under rapid planetary rotation (Pouquet and Marino, 2013; Cabanes et al., 2020). For the 32-level simulation, Cabanes et al. (2020) showed that the inverse cascade of energy results from the barotropization of baroclinic eddies at small scales and drives the large scale atmospheric flow.

What Figures 3 and 4 also show is that the eddy spectra is different in our 61-level simulation compared to the 32-level simulation analyzed in Spiga et al. (2020) and Cabanes et al. (2020). In the 32-level simulation, the tropospheric residual spectrum barely fits the well-known Kolmogorov-Kraichnan (KK) law $\epsilon^{2/3}n^{-5/3}$ (Kraichnan, 1967a) evocative of the inverse turbulent cascade with the energy transfer rate $\epsilon = 2 \times 10^{-6}$ W Kg⁻¹. Conversely, in the 61-level reference




Figure 3: Comparative spectral analysis of the 32-level simulation (left) and the reference simulation (right) in the upper tropospheric level $p \sim 1.9 \times 10^4$ Pa. Spectral quantities are averaged in time, over the tenth to twelfth simulated Saturn years, and in altitude, over pressure levels (1.7 Pa. Top panels show kinetic energy spectra: the zonal spectrain red (i.e. axisymmetric m = 0 mode), the residual spectra in black (i.e. sum over all nonaxisymmetric $m \neq 0$ modes shown separately), the modal spectra are shown for zonal modes m=1 to 5 in green. Middle and bottom panels represent the spectral energy and enstrophy fluxes respectively. Positive fluxes corresponds to downscale energy/enstrophy transfers (a "direct" cascade) and negative fluxes are upscale energy/enstrophy transfers (an "inverse" cascade). All spectral quantities are function of the total indices n. At any typical length scale in latitude L, one can attribute a typical index by the relation $n = 2\pi a/L$. Dashed lines are (black) the theoretical Kolmogorov-Kraichnan law $6\epsilon^{2/3}n^{-5/3}$ with the energy transfer rate $\epsilon=2\times 10^{-6}~{
m W~kg^{-1}}$ (Kraichnan, 1967b) and (red) the theoretical zonostrophic law $0.5\beta^2n^{-5}$. The vertical dotted lines are the Rhines indices $n_R = a(\beta/2U)^{1/2}$, with U the square root of the total energy presented in Figure 2. It corresponds to the typical length scale $\sim 32,000$ km for both simulations. All our calculation 1consider a parameter $\beta=4\times 10^{-12}~\rm m^{-1}~s^{-1}$ estimated at mid-latitude $\varphi = 45^{\circ}$.

simulation, the -5/3 KK slope does not apply to the residual spectrum that shows an energetic bump at intermediate indices (i.e. 10 < n < 100). The 32level simulation also features very energetic non-axisymmetric modes m = 1, 2, 3(see modal spectra in green) that dominate in the residual spectrum beyond the Rhines index $(n < n_R)$ and extend the -5/3 slope to small indices (i.e. down to $n \sim 2$). Such modes or waves are absent in the 61-level simulation and energy of the residual spectrum decreases at indices smaller than the Rhines index. It is likely that the energetic m = 1, 2, 3 modes enforced in the 32-level simulation are artifacts of the shallow geometry. By extending the model top, we also release part of the flow confinement in the vertical that promotes a quasi-2D flow. This release might explain the reduction of the energy and enstrophy fluxes in the 61-level simulation compared to the 32-level simulation. The raise of model top towards stratospheric levels appears to significantly impact the statistical properties of the tropospheric flow. Saturn's direct observations, akin to those used for Jupiter in Young and Read (2017), are required to further validate our model.

29

200

301

302

303

304

307

308

310

311

312

313

314

315

316

317

320

321

322

325

Statistical properties are mostly similar in the upper troposphere and in the lower stratosphere (Figure 4). The 32-level simulation preserves a -5/3 residual spectrum that prevails at all indices in the lower stratosphere. In the 61-level simulation, the residual spectrum is substantially steepened and spectral energy piles up in the range $n > n_R$, to decrease beyond Rhines index. In both simulations, the integrated total energy in the stratosphere is more energetic than in the troposphere (Figure 2), with energy fluxes one order of magnitude higher in the stratosphere. This might result from the growth of baroclinic instabilities that preferentially form in the stratosphere (Cabanes et al., 2020). The integrated total energy also show that the 32-level simulation predicts a flow at stratospheric levels more energetic by a factor of 2 than in the 61-level simulation. In the former simulation, the top of the model is close to the lower stratosphere, therefore an energy accumulation likely produces these high values of total energy – and might also create wave reflection leading to energetic non-axisymmetric modes m = 1, 2, 3.




Figure 4: Comparative spectral analysis of the 32-level simulation (left) and the reference 61-level simulation (right) in the stratospheric level p $\sim 4.9 \times 10^2$ Pa. Spectral quantities are averaged in time, over the tenth to twelfth simulated Saturn years, and in altitude, over pressure levels $(4.7 Pa. The dashed black lines are the KK-law with the energy transfer rate <math display="inline">\epsilon = 5 \times 10^{-5}$ W kg $^{-1}$ (Kraichnan, 1967b). The Rhines typical indices correspond to a typical length scale of $\sim 47,000$ and $\sim 37,000$ km for the 32-level and 61-level simulations respectively. All other spectral quantities are similar to the caption of Figure 3

Finally, we propose in Figure 5 a spectral analysis similar to those of Figure 3 327 and 4 for the stratospheric level 25 Pa of our 61-level simulation, left unresolved 328 in the previous Part II and III papers. At the smallest resolved scales, the 329 zonal kinetic spectrum depicts a -5 slope with estimated values of $\epsilon = 8 \times 10^{-6}$ 330 W kg⁻¹, two orders of magnitude less than the residual kinetic spectrum. As in the troposphere (Figure 3, right top row), the large scales are driven by a 332 strong zonal anisotropy linked to zonostrophic turbulence. In the stratosphere, 333 our simulation indicates that the modes m = 2 and 4 are dominant in the 334 residual spectrum, suggesting that strongly-energetic waves propagate in the 335 zonal direction. The spectral flux of energy depicts huge negative values for moderate n, contrary to tropospheric results in Figure 3. The inverse energy 337 cascade, from the small scales to the large scales, is operating in the stratosphere 338 for most intermediate scales between n=3 and $n=10^2$. At both the largest 339 and the smallest resolved scales, the energy flux becomes positive denoting a direct energy cascade (energy is transferred from the large to the small scales). Aside from the positive peak around n=3, the global trend of energy flux is 342 equivalent in the troposphere and the stratosphere. The enstrophy flux confirms 343 the dynamical regime of the stratosphere (bottom row of Figure 5): it is positive 344 for n higher than 10, which suggests the existence of an inverse cascade.

4. Equatorial stratospheric dynamics with the DYNAMICO-Saturn

347 4.1. Global stratospheric zonal wind

346

350

351

352

353

354

The temporal evolution of the zonal-mean stratospheric zonal wind over the whole 13-year duration of our DYNAMICO-Saturn simulation is shown in Figure 6 at the pressure level of 40 Pa. Before turning to low latitudes, we note that at high and mid-latitudes, zonal jets undergo a poleward migration due to bursts of eddies induced by baroclinic instabilities. This migration was already witnessed by Spiga et al. (2020) in the troposphere and is thought to be partly caused by baroclinicity at the bottom of the model $(3\times10^5 \text{ Pa})$, where the meridional gradient of temperature is slightly overestimated compared to the




Figure 5: Spectral analysis of the reference simulation in the stratospheric level p ~ 25 Pa. Spectral quantities are averaged in time, over the tenth to twelfth simulated Saturn years, and in altitude, over pressure levels $21 Pa. The dashed black lines are the KK-law with the energy transfer rate <math display="inline">\epsilon = 8 \times 10^{-6}$ W kg $^{-1}$ (Kraichnan, 1967b). The Rhines typical indices correspond to a typical length scale of $\sim 42,000$ km. All other spectral quantities are similar to the caption of Figure 3




Figure 6: Time evolution of the zonal-mean zonal wind in Saturn's stratosphere (40 Pa) within the whole 13-years duration of our DYNAMICO-Saturn simulation. The wind structure at this pressure level is typical of conditions between the tropopause and the model top in the upper stratosphere.

observations. Furthermore, Chemke and Kaspi (2015) show that the poleward migration of baroclinic eddy-driven jets is consistent with an asymmetry in the baroclinic growth around the jet's core: the poleward flank of the jet can be slightly more baroclinically unstable than the equatorward flank. The baroclinic growth precedes the increase of the eddy momentum flux convergence, causes the eddy forcing to be shifted slightly poleward of the jet peak, and thus drives the poleward migration of the jets.

Now, turning to the low latitudes simulated in our reference 61-level Saturn simulation, we notice in Figure 6 two key features in the temporal evolution of the stratospheric zonal-mean zonal wind:

- an alternatively eastward and westward wind direction at the equator, with a sub-annual periodicity, appearing in the second simulated year and maintained for the rest of the 13 simulated years;
- an alternatively eastward and westward wind direction at 20°N and 20°S,

with an annual periodicity and a phase opposition between the northern and the southern hemisphere.

These two features are discussed in detail in the following sections.

4.2. Equatorial stratospheric zonal jets

By making an altitude/time section of the zonal-mean zonal wind at the equator (Figure 7), for the four last years of our 13-years simulation, the downward propagation with time of the stacked stratospheric eastward-westward jets is well visible. At a given pressure level, the zonal wind alternates between eastward and westward direction, with a westward phase more intense – about -100 m s⁻¹ (Figure 9 in Showman et al. (2019) shows a similar behaviour) – than the eastward one (only 60 m s⁻¹). In addition, at a given pressure level, the westward phase lasts longer than the eastward one. The equatorial eastward phases of the oscillation seem to be unstable and disturbed compared to westward phases. For this reason, the period of the resulting equatorial oscillation is irregular in time.

As is reminded in the introduction, a pattern of alternatively eastward and westward jets stacked on the vertical, with a downward propagation, reminds both the Quasi-Biennial Oscillation (QBO) on Earth and the QBO-like oscillation evidenced in Cassini observations (Fouchet et al. (2008), Guerlet et al. (2011), Li et al. (2011), Orton et al. (2008), Guerlet et al. (2018)). We tracked the equatorial jets to calculate the periodicity and the downward propagation rate of the modeled QBO-like oscillation. Our DYNAMICO-Saturn produces a QBO-like oscillation with a period in the range 0.3-0.7 Saturn year. The corresponding stacked jets' downward propagation rate is respectively between 73 and 60 km per Saturn month. In Fletcher et al. (2017), Cassini observations were used to estimate a period of 0.50±0.03 Saturn year and a downward propagation speed of (42±2) km per Saturn month. Guerlet et al. (2018) estimated a downward propagation of 24.5 km per Saturn month at 500 Pa and 49 km per Saturn month at 10 Pa. Hence, the DYNAMICO-Saturn simulation exhibit an equatorial oscillation periodicity of the right order of magnitude compared




Figure 7: Altitude/time section at the equator of the zonal-mean zonal wind in Saturn's stratosphere for the 5 last years of our 13-years DYNAMICO-Saturn simulation.

to the observations, but more irregular. Moreover, the stacked zonal jets in our simulation propagate downward 1.5 times too fast compared to the observations. The irregularity in both the oscillating period and the downward rate propagation could be due to the absence of sub-grid-scale waves parameterization, which, as is explained in introduction, contribute to 70% of the eastward phase forcing in the Earth's QBO.

The second notable feature in Figure 6 is the strong alternating eastward and westward jets at around 20° N and 20° S, with a seasonal phase opposition between the northern and southern hemispheres. Compared to a time evolution of the incoming solar radiation (Figure 8), we remark that each eastward jets emerge during the winter and seem to be correlated to the rings' shadowing. Those tropical eastward and westward jets both have an amplitude of about 100 m s^{-1} , contrary to the QBO-like equatorial oscillation which exhibits an eastward phase weaker than the westward phase. This pattern exhibits a regular one-Saturn-year periodicity without downward propagation: the jets shown in Figure 6 at 40 Pa extend from 10^3 Pa to the model top (Figure 9).




Figure 8: Temporal evolution of the incoming solar radiation in Saturn's atmosphere on the whole 12-year DYNAMICO-Saturn simulation

4.3. Equatorial stratospheric thermal structure

In this section, we compare our DYNAMICO-Saturn simulations with the observations of Saturn's equatorial stratosphere by Cassini/CIRS. Stratospheric winds have never been measured; rather, the CIRS instrument on-board the Cassini spacecraft allowed the retrieval of stratospheric temperature vertical profiles and stratospheric winds were calculated using thermal wind balance. It is therefore relevant to compare the observed and simulated stratospheric temperatures. Figure 10 represents altitude/latitude section of temperature simulated by DYNAMICO-Saturn in the stratosphere. Between 8°N and 8°S, this meridional section exhibits a stack of local maxima (around 148 K) and minima (130 K) of temperature from 10² Pa to the top of the model. The pattern of alternating temperature extrema propagate downward with time. Temperature oscillates with a 10 K-magnitude around 140 K with a period and a descent rate equivalent to the wind's. Moreover, temperature extrema at the equator are anti-correlated to those occurring in the tropics. At a given pressure level, the cold equator regions are flanked by warmer tropical regions




Figure 9: Altitude/time section at $20^{\circ}N$ (9(a)) and $20^{\circ}S$ (9(b)) of the zonal-mean zonal wind in Saturn's stratosphere for the 5 last years of our 13-years DYNAMICO-Saturn simulation.

at 10 to 15°N and at 10 to 15°S. Using the thermal-wind equation applied assuming a geostrophically balanced flow, this significant meridional gradient of temperature confirms the presence of a significant vertical shear of the zonal wind at the equator.

To compare our simulation to CIRS observations, we re-mapped altitude vs latitude sections of modeled and observed temperatures with the same temperature range. GCM results are mapped in Figure 11 and CIRS limb observations (acquired in 2005, 2010 and 2015) in Figure 12, focused on high stratospheric levels. To carry out this comparison, we used CIRS data already processed in Guerlet et al. (2018). Our DYNAMICO-Saturn simulation produces a temperature field qualitatively consistent with observations, with alternative maxima and minima of temperature stacked on the vertical in the stratosphere. There are between 3 and 4 temperature extrema in our DYNAMICO-Saturn model whereas there are only 2 (2010) or 3 (2005 and 2015) temperature extrema in CIRS temperature retrievals. Moreover, observations show a temperature oscillation from 170 K to 120 K, with a 20 K-magnitude, hence twice as much as in our Saturn GCM simulations.

To highlight the anomalies temperature resulting of the modeled and observed Saturn equatorial oscillation, we map temperature differences between two half-period-separated dates. Figure 13 displays altitude/latitude sections of temperature differences between the dates 8.53 and 8.5 years (top left) and between the dates 8.6 and 8.53 years (bottom left) of Figure 11. Comparison with CIRS measurements (right rows of Figure 13) shows the similarities and differences in the modeled and observed QBO-like oscillations. Temperature differences underline a stack of positive and negative anomalies of temperature, with Saturn-DYNAMICO underestimating the amplitude by a factor of 2 compared to the observations. The characteristic vertical size of the DYNAMICO-Saturn QBO-like oscillations is two times smaller than the observed one. Our DYNAMICO-Saturn underestimates the temperature maximum by around 20 K and underestimates the magnitude of the temperature anomalies by 10 K. Another difference between the Cassini observations and the GCM-modeled equato-




Figure 10: Altitude/latitude sections of zonal-mean temperature in Saturn's stratosphere at three dates of simulation: 10(a) at 10.45 years, 10(b) at 10.55 years and 10(c) at 10.60 years.




Figure 11: Altitude/latitude sections of zonal-mean temperature in Saturn's stratosphere at the 8.5~(11(a)), 8.53~(11(b)) and 8.6~(11(c)) years to compare with CIRS measurements (Figure 12). Contour lines are separated by 2 Kelvin.




Figure 12: Altitude/latitude sections temperature measured by Cassini CIRS instrument at 2005/2006, 2010 and 2015 (analogous to Guerlet et al. (2018) Figure 3 top row but focused here on high stratospheric levels). Contour lines are separated by 5 Kelvin.

rial oscillation is the vertical extent of the temperature anomalies at the equator.

Cassini radio occultation data showed that the descending temperature minima
and maxima extend down to the tropopause level, around 100 hPa (Schinder
et al., 2011) whereas in the Saturn-DYNAMICO simulations there is no more
equatorial-oscillation signal below the 1-2 hPa level.

We can also compare our simulations to the idealized work of Showman et al. (2019). In their idealized simulation, they obtain a temperature oscillation of about ~ 10 K that migrate downward over time (Figure 8 of Showman et al. (2019)), as in our simulation. Moreover, we obtain a stack of temperature extremes spatially close to each other on the vertical, contrary to their simulation, where the extremes of temperature are half a decade (in pressure) apart from each other by a constant temperature zone. In our and their simulations, opposite extremes of temperature (at a given pressure level), centered between 10 and 15 latitude degrees (both north and south), are generated. There is, in the two simulations, an anti-correlation between temperature extremes at the equator and those occurring off the equator. With DYNAMICO-Saturn, compared to the CIRS observations, we obtain a more realistic patterns of temperature anomalies at the equator than the idealized work of Showman et al. (2019), but there are still some notable differences with the CIRS observations.

Another feature of Saturn's stratosphere observed by Cassini/CIRS is the anomalously high temperatures under the rings' shadows (Fletcher et al., 2010). Previous radiative simulations of Saturn's atmosphere failed to reproduce these temperature anomalies (Guerlet et al., 2014), hence dynamical heating was considered to explain this feature.

In our simulations, there is an interplay between the tropical eastward jets and temperature evolution, displayed in Figure 14. In wintertime, at 20° latitude, the temperature starts by cooling rapidly (from 150K to 140K), which is likely due to the ring's shadow radiative effect. Then, when the eastward jet increases in strength, this low temperature region is significantly reduced, there is an increase of temperature from 140K to 145K. This is true only near the core of the eastward jet, at 20°. Indeed, at 30° latitude, the temperature




Figure 13: Altitude/latitude sections of temperature differences between two half-period-separated dates (left: DYNAMICO-Saturn results and right: as derived from CIRS measurements, analogous to Guerlet et al. (2018) Figure 3 bottom row) in Saturn's stratosphere. The modeled temperature oscillation underlines a vertical characteristic length twice as small as the observed one and a amplitude differences weaker than derived from CIRS measurements.




Figure 14: Time evolution of the zonal-mean temperature (color) and the zonal-mean zonal wind (contours spacing by 25 m s^{-1} between -100 m s⁻¹ and 100 m s⁻¹) in Saturn's stratosphere (40 Pa) of our 13-years DYNAMICO-Saturn simulation.

remains very cold (140K) throughout wintertime. We will assess in more detail
the dynamical impact of ring shadowing in the stratosphere in section 6.

4.4. Equatorial stratospheric planetary-scale waves

According to the terrestrial experience, equatorial oscillation results from both planetary-scale waves and mesoscale waves forcing. In our DYNAMICO-Saturn GCM simulation, the oscillation at the low latitudes can only result from resolved motions, therefore planetary-scale waves, because there is no subgrid scale parameterization or bottom thermal forcing in our model. To study those waves, we performed a two-dimensional Fourier transform of the symmetric and antisymmetric components of temperature and zonal wind fields, following Wheeler and Kiladis (1999) method, as in Spiga et al. (2020) section 3.3.1. We applied the two-dimensional Fourier analysis on a specific 1000-daylong run, with daily output frequency, after 270000 simulated Saturn days as in Spiga et al. (2020). The spectral mapping in the wavenumber s and frequency σ space enables to evidence and characterize the planetary-scale waves

driving the stratospheric equatorial oscillation. Symmetric component of temperature (about the equator) T_S shows Rossby, inertia-gravity and Kelvin waves and antisymmetric component of temperature T_A shows Yanai (Rossby-gravity) waves.

509

510

511

512

514

521

526

52

528

529

530

533


534

535

538

The results of the two-dimensional Fourier transform for the stratospheric temperature and zonal wind fields at the 20-Pa pressure level are shown in Figure 15 and in Table 1. The spectral analysis demonstrates, both in the anti-515 symmetric component of temperature and zonal wind fields, that the dominant 516 wavenumber-2 is a westward-propagating Rossby-gravity wave with a period 517 of 6 days and a frequency of 60° longitude per day. Westward-propagating 518 Rossby and internal-gravity waves with wavenumber s = -1 are the secondary 519 prominent mode in temperature, with a period of 100 Saturn days. There are 520 two other westward-propagating modes with wavenumbers s = -2 and s = -23, and respectively a period of 6 and 34 Saturn days. Finally, there are only two eastward-propagating Kelvin waves (identified both in the temperature and wind field) with s = +3 and s = +4, with a 5 Saturn days and 6 Saturn days 524 periodicity. The zonal wind field indicates westward-propagating Rossby waves 525 with s = -1 to s = -10, exhibiting long periods of several tens of Saturn days and frequencies of about fifteen degrees longitude per day.

It is worth noticing that there are numerous westward-propagating modes versus only two eastward-propagating mode, both in temperature and zonal wind components. The resolved QBO-like oscillation in our DYNAMICO-Saturn reference GCM simulation is thus characterized by an imbalance in eastward- and westward-wave forcing. This may be symptomatic of the absence of sub-grid scale waves parameterization, which contribute of almost 3/4 of the eastward momentum forcing in the equatorial oscillation of Earth. Indeed, the smaller the eastward-wave forcing is, the smaller the eastward momentum carried by waves to critical levels is. This lack of eastward momentum in the resolved dynamics could explain why, as noticed in section 4.2, the eastward phase of the equatorial oscillation seems to be unstable in time compared to the westward phase. A plausible explanation is that the eastward momentum






Figure 15: Two-dimensional Fourier transforms of the symmetric component of temperature field, following Wheeler and Kiladis (1999) method, to highlight the equatorial waves produced by our DYNAMICO-Saturn in dynamical steady-state at the 40th pressure-level (43 Pa). Grey shaded areas depict the waves identified by the spectral analysis. The colored curves correspond to the dispersion relation from the linear theory. Four values of equivalent depths are included into the linear theory: 5 km in blue, 10 km in purple, 20 km in magenta and 50 km in red.

Dominant	modes	${\rm in}$	T_s
----------	-------	------------	-------

			o .
s	σ (°/d)	period (d)	$\log(SP)$
-1	3.6	100	9.6
-2	60.5	6	9.4
-3	10.4	34	9.2
+3	73.8	5	8.9
-4	7.9	45	8.7
+4	61.2	6	8.7
-5	16.2	22	8.7

Dominant modes in u_s

s	$\sigma\left(^{\circ}/\mathrm{d}\right)$	period (d)	$\log(\mathrm{SP})$
-1	4.0	91	11.9
-2	7.9	45	11.9
-3	11.2	32	11.3
-7	13.7	26	11.3
+3	73.8	5	11.3
-4	8.3	43	11.2
-5	10.4	34	11.1
-10	17.3	21	11.0
-6	16.2	22	11.0
+4	61.2	6	11.0

Dominant modes in T_A , u_A , v_S

s	σ (°/d)	period (d)	$\log(SP)$
-2	60.5	6	11.3

Table 1: Spectral modes detected by Fourier analysis and depicted in Figure 15. SP means spectral power and d Saturn days.

deposition of Kelvin wave is too low on its own to balance the westward phase induced by the Rossby-gravity, Rossby and inertia-gravity waves.

542 4.5. Eddy-to-mean interactions driving the equatorial stratospheric oscillation

543

544

545

549

550

To determine the eddy-to-mean interactions within the flow, we use the Transformed Eulerian Mean (TEM) formalism. In terrestrial atmospheric studies, it is commonly employed to investigate momentum and heat transfers by wave-mean flow interactions (Andrews et al., 1983).

In all the following equations (1 to 4), the overline denotes the zonal-mean of each field, the prime symbol denotes the eddy component, i.e. departures from the zonal mean. By defining the transformed zonal-mean velocities as follows

$$\overline{v^*} = \overline{v} - \frac{\partial}{\partial P} \left(\frac{\overline{v'\theta'}}{\overline{\theta}_P} \right) \tag{1}$$

$$\overline{\omega^*} = \overline{\omega} + \frac{1}{a\cos\phi} \frac{\partial}{\partial\phi} \left(\frac{\cos\phi\overline{v'\theta'}}{\overline{\theta}_P} \right) \tag{2}$$

we obtain the momentum equation in the Transformed Eulerian Mean formalism:

$$\frac{\partial \overline{u}}{\partial t} = \overline{X} - \underbrace{\left[\frac{1}{a\cos\phi} \frac{\partial (\overline{u}\cos(\phi))}{\partial \phi} - f\right] \overline{v}^* - \overline{\omega}^* \frac{\partial \overline{u}}{\partial P}}_{I} + \underbrace{\frac{1}{a\cos\phi} \overrightarrow{\nabla} \cdot \overrightarrow{F}}_{II}$$
(3)

where \overline{X} is the zonal-mean non-conservative friction and $\overrightarrow{F} = (F^{\phi}, F^{P})$ is the Eliassen-Palm flux, which components are defined in equation 4 below.

$$F^{\phi} = \rho_0 a \cos \phi \left(\overline{v'\theta'} \frac{\partial \overline{u}}{\partial \overline{P}} - \overline{u'v'} \right)$$

$$F^{P} = \rho_0 a \cos \phi \left(\overline{\frac{v'\theta'}{\partial \overline{P}}} \left(f - \frac{1}{a \cos \phi} \frac{\partial (\overline{u} \cos \phi)}{\partial \phi} \right) - \overline{u'\omega'} \right)$$
(4)

The Eliassen-Palm flux is defined as a wave momentum flux: it depicts both interactions between eddies and the mean flow (a momentum stress on the mean flow) and eddy propagation, as a wave activity. It allows one to link the meridional flux of heat $\overline{v'\theta'}$ and zonal momentum $\overline{u'v'}$ (due to waves forcing) to a horizontal F^{ϕ} and vertical F^{P} flux of momentum on the mean flow (into Equation 3). In equation 3, the term I is the residual-mean acceleration and the term

II is the Eliassen-Palm flux divergence, i.e. the eddy forcing in momentum on the mean flow acceleration (named eddy-induced acceleration in the following). 562 Studying the Eliassen-Palm flux, as well as its divergence, makes it possible to 563 identify the regions of greatest interaction between the eddies and the mean 564 flow, and to visually determine the propagation of eddy-induced momentum from one region of the atmosphere to another. 566

567

568

569

571

577

581


587

591

In the following analysis, we separate the lower stratosphere $(2\times10^4 \text{ Pa to})$ 6×10^1 Pa) and the upper stratosphere $(6\times10^1$ Pa to 5×10^{-1} Pa) to clarify the analysis. For each stratospheric regions, the two components of the Eliassen-Palm vectors are scaled by their own averaged values which are distinct in the two stratospheric regions.

We ran an additional, specific 1000-day-long GCM simulations with a daily 572 output frequency, restarted at a time of a strong reversal of wind direction from 573 the westward to the eastward direction (at Ls = 140° during the eighth simulated Saturn years). Figure 16 displays the time-average of the Eliassen-Palm flux diagram (vectors) superimposed on the zonal-mean zonal wind (color). The 576 Eliassen-Palm flux essentially comes from the high troposphere in tropical regions, particularly the strong eastward jets located at $\pm 20^{\circ}$ of latitude. In 578 the southern hemisphere, the Eliassen-Palm flux vectors is significant between 2×10^4 Pa and 6×10^2 Pa in the lower stratosphere (Figure 16(b)) and between 5×10^1 Pa and 1×10^1 in the upper stratosphere (Figure 16(a)). The eddy momentum transferred to the upper stratospheric layers mainly comes from the 582 strong eastward jet correlated to the rings shadow (centered at 25°S). Comparison between northern and southern tropical regions shows that the largest eddy momentum forcing is correlated to this strong eastward jet, even in the highest 585 stratospheric layers, where the forcing is greatly reduced. Furthermore, there 586 is an inversion of the Eliassen-Palm vectors' direction at the equator (downward) compared to the two tropical regions (upward). We deduce that there is a conceivable cell of eddy flux on both sides of the equatorial stacked jets, which suggests an eddy forcing of the equatorial oscillation. 590

Eddy-to-mean interactions are indeed involved in the downward propagation






Figure 16: Altitude/latitude sections of the zonal mean zonal-wind (color) and the Eliassen-Palm flux in equatorial regions at Ls = 140° during the eighth simulated Saturn years, focused on high stratospheric levels (16(a)) and low stratospheric levels (16(b)). Vectors scale is arbitrary for each section.

of the terrestrial equatorial oscillation. We investigate those interactions in the case of our simulated Saturn equatorial oscillation by choosing a representative 593 case study, the downward propagation of the equatorial eastward zonal jets between Ls = 185° and Ls = 188° on simulated year 8. For this test case, to 595 diagnose the wave-induced forcing on the mean flow, we report the temporal evolution of zonal wind profiles, waves and the divergence of the Eliassen-Palm flux in Figure 17. Additionally, to investigate the types of waves involved in this 598 forcing, we perform two related spectral analysis, one in the interval Ls = 181-599 185° and the other in the interval Ls = $185-188^{\circ}$, each one over 250 simulated 600 Saturn days. 60

At Ls = 185°, zonal wind profile shows an intense westward jet (almost -602 75 m s⁻¹) between 50 and 15 Pa, a weak eastward jet between 15 and 9 Pa 603 (only 10 m s⁻¹) and the lower part of a second intense westward jet (from 604 9 Pa to the top of the figure). At 21 Pa, between Ls=181° and 188°, there is a small eastward eddy-induced acceleration, of about 0.3 m s⁻². Our spectral analysis shows that this is associated to a decrease of both Rossby and Kelvin 607 waves activity at this pressure level. The eastward eddy-induced acceleration, 608 correlated to the Kelvin waves activity at 21 Pa, forces the wind direction to 600 eastward propagation and tends to "push" the eastward jet down. So, at Ls = 610 188°, this eastward jet is located from 20 to 12 Pa, close to the weak eastward 611 eddy-induced acceleration. At 10 Pa, the temporal average of the Eliassen-Palm 612 flux divergence demonstrates a significant westward eddy-induced acceleration, 613 associated to a great enhancement of Rossby waves and a vanishing of Kelvin waves activity in spectral analysis. During the 500 Saturn days around the date 615 Ls = 185°, at 10 Pa, the westward waves transfer westward momentum to the 616 mean flow, the large westward acceleration changes the wind direction and at-617 tenuates the eastward jet. As a result, the westward jet, located between 9 Pa 618 to the top of the figure at $Ls = 185^{\circ}$, downs to 11 Pa at $Ls = 188^{\circ}$. At this pressure level, we observe the transition form the eastward phase to the westward phase of the equatorial oscillation. Eastward and westward accelerations 621 occur just below eastward and westward jets, respectively: this may be due 622

to the location of critical levels. Approaching a critical level from below, the
wave vertical group velocity and vertical wavelength both decrease, facilitating
the momentum exchange with the mean flow, although the maximum transfer
of momentum can occur somewhere before encountering the critical level (e.g.
through radiative damping). This could explain the downward propagation of
the stacked jets causing the QBO-like oscillation.

5. Saturn seasonal cycle to synchronize its equatorial oscillation

Idealized terrestrial QBO simulations show that the seasonal cycle could lock 630 the equatorial oscillation period to an integer multiple of the annual cycle period 631 (Rajendran et al., 2016). In our reference simulation, the QBO-like oscillation 632 period is nearly the observed mean period, namely about half a Saturn year. 633 This raises a new question: does Saturn's annual seasonal cycle synchronize the 634 period of the equatorial oscillation? To address this question, we performed an alternate simulation (named hereinafter the "no-season" simulation) in which 636 the seasonal cycle of the incoming solar radiation is neglected: the planet's po-637 sition around the Sun is fixed at Ls=0°. As a consequence, there is no ring 638 shadowing in this simulation to avoid any singularities in the radiation at the equator. All other settings are similar to the DYNAMICO-Saturn reference simulation described previously. This "no-season" simulation starts with an initial 641 state derived from the reference simulation after 7 simulated Saturn years. In 642 this alternate simulation, the DYNAMICO-Saturn GCM is run for six simulated 643 years: three years to reach a dynamical steady-state (a spin-up phase) and three additional years to compare the results with the eleventh to the thirteenth years 645 of our reference simulation. 646

Figure 18 shows the time evolution of the zonal-mean zonal wind vertical structure at the equator for the six simulated Saturn years of the "no-season" simulation. Compared to the reference simulation (Figure 7), two conclusions emerge from the "no-season" simulation:

647

650

651

• During the spin-up phase, the eastward wind intensity is higher and the




Figure 17: Left panel: Zonal-mean zonal wind profiles at Ls = 185° (blue line) and Ls = 188° (orange line). Middle panel: zonal-mean eddy-induced acceleration (term II of Equation 3, black line), average over 500 days around Ls = 185° . Each profiles are average over \pm 5 degrees of latitude. Right panel: two-dimensional Fourier transforms of the symmetric component of temperature field, following Wheeler and Kiladis (1999) method, over two time intervals (Ls = $181-185^{\circ}$ and Ls = $185-188^{\circ}$) and at 21 and 10 Pa.




Figure 18: Altitude/time section at the equator of the zonal-mean zonal wind in Saturn's stratosphere for the no-season DYNAMICO-Saturn simulation.

eastward phase of the equatorial oscillation is more regular and longer duration than in the reference simulation.

 after three simulated Saturn years, the oscillation begins to disappear in the lower stratosphere, toward 5×10¹ Pa.

There is an interconnection between the stratospheric jets (mean flow) and the eddies that force the equatorial oscillation. The presence of established jets, coming from the reference simulation, at the beginning of the "no-season" simulation influences the eddies activity, maintaining a seasonal signature for about three years. Jets and eddies are intimately coupled: once the seasonal cycle is removed, the equilibrium between jets and eddies is slightly disturbed, the effect of which is only noticeable after three simulated years.

After spin-up, the equatorial oscillation disappears in the lower stratosphere, between 10^3 and 5×10^1 Pa, but it is maintained between 5×10^1 Pa to the model top with a different periodicity than in the reference simulation. At any pressure level, from the fourth simulated Saturn year to the end of the "no-season" simulation, we notice only 3 or 4 stratospheric eastward jets. We obtain, in this "no-season" simulation, a periodicity of about 0.7 simulated Saturn year which is less consistent with observations than the reference simulation. This is con-

sistent with one of the conclusions of Rajendran et al. (2016): the annual cycle can regulate an equatorial oscillation by enhancing the eddies forcing induced by the seasonality of atmospheric waves.

We conclude from our "no-season" simulation that the seasonal cycle of Saturn is a key parameter to establish and regulate the stratospheric equatorial oscillation modeled by our DYNAMICO-Saturn GCM. Both eddy activity and residual-mean circulations are impacted by seasons in such a way that the periodicity of the equatorial oscillations is "locked" close to a semi-annual periodicity. How much which effect dominates over the other is left for a future study.

680 6. Impact of the rings on Saturn's stratospheric dynamics

6.1. Zonal wind in the tropical regions

To determine Saturn's rings contribution to the atmospheric dynamics in the tropical channel, we performed an alternate simulation named the "noring" simulation, in which the rings' shadowing of the incoming solar radiation is neglected, all other settings being equal with the DYNAMICO-Saturn reference simulation described previously. Contrary to the "no-season" simulation, a seasonal cycle is simulated in the "no-ring" simulation: it is different from the reference simulation since the shadow of the rings is removed. This "no-ring" simulation starts with an initial state derived from the reference simulation after 8 simulated Saturn years. The DYNAMICO-Saturn GCM is run for five simulated years: three years devoted to spin-up to reach a dynamical steady-state (see section 5) and two additional years to compare the results with the eleventh and the twelfth years of our reference simulation.

Figure 19 compares the two Saturn GCM simulations. In the no-ring simulation compared to the reference simulation, we note a disturbance of the structure of the zonal-mean zonal wind at the tropics, as well as an enhancement of the zonal wind intensity at the equator. Eastward jets at the tropics in the no-ring simulation split in several weaker eastward jets in the northern hemisphere. In

the southern tropics, eastward jets even disappear after 3.5 Saturn years of simulation. Hence, rings' shadowing (or the absence thereof) impacts equatorial 700 and tropical dynamics.

We present in Figure 20 the vertical structure of the stratospheric equatorial oscillation resulting from the no-ring simulation. As in the reference simulation, the eastward phase of this QBO-like oscillation is irregular compared to the westward phase. However, eastward stratospheric jets in the no-ring simulation are larger in amplitude compared to the reference simulation (see Figure 7), and the eastward phase of the equatorial oscillation lasts longer in the no-ring simulation than in the reference simulation. Eastward and westward phases are less contrasted. Neglecting the ring shadowing, we obtain an eastward phase of the simulated Saturn QBO-like oscillation enhanced by around $25~\mathrm{m~s^{-1}}$ and a periodicity between 0.4 and 0.5 simulated Saturn years.

6.2. Temperature field in the tropical region

701

702

704

705

706

707

709

710

711

712

713

714

715

717

718

719

720


722

723

724

727

Figure 21 compares at the 40-Pa pressure level the reference DYNAMICO-Saturn simulation, the no-ring DYNAMICO-Saturn simulation, with radiativeconvective 2D seasonal modeling à la Guerlet et al. (2014), and the 2005 CIRS limb observations (Guerlet et al., 2009). This comparison is carried out at $Ls = 300^{\circ}$ in southern summer, when rings shadowing occurs at 20-25°N. As mentioned previously, the radiative-convective model fails to reproduce the local temperature maximum under the rings' shadow (between 20 and 30°N). It predicts instead a temperature \sim 12 K colder than the CIRS observations. Besides, the reference GCM simulation presents higher temperatures at these latitudes, which are still ~5 K too cold compared to measurements. At northern mid-latitudes in the winter hemisphere, the modeled temperature decreases from 20°N to 40°N, that we can associate with the signature of the rings shadow. Even if the dynamics of the DYNAMICO-Saturn GCM raises temperature underneath the ring, there remains a failure to replicate hot anomalies in the shadows. The no-ring simulation also exhibits warm temperature between 20°N and 30°N; however, these temperatures are higher than the reference simulation






Figure 19: Two-month running mean evolution of the zonal-mean zonal wind in Saturn's stratosphere (40 Pa) between 30°N and 30°S of our DYNAMICO-Saturn comparative simulations: 19(a) with rings' shadow (reference simulation) and 19(b) without rings' shadow. The two first simulated years of the alternate simulation are not shown (model spin-up).




Figure 20: Altitude/time section at the equator of the zonal-mean zonal wind in Saturn's stratosphere for the no-ring DYNAMICO-Saturn simulation.

(probably because the tropical eastward jets are impacted by the lack of ring shadowing) and too warm compared to the observations for the whole northern hemisphere except between 30-35°N. Hence Figure 21 suggests a possible dynamical origin of the unexpected high temperature below Saturn's rings, but this dynamics is not fully addressed by DYNAMICO-Saturn with rings shadow. We defer the detailed study of the seasonal circulation to a future work.

6.3. Eddy-to-mean interactions in the tropical region

729

730

733

734

735

736

737

740

741

742

745

Ring shadowing impacts the tropical eastward jets. Those jets are forced by the residual-mean circulation and the eddy-to-mean interactions. To further characterize the impact of ring shadowing on those two contributions, we use the TEM formalism (Equation 3).

In the two simulations, eddy-induced (term II of Equation 3) and meancirculation-induced (term I of Equation 3) accelerations are of the same order of magnitude. It is also of the same order of magnitude between both simulations (Figure 22). The presence of the tropical southern eastward jet in the reference simulation is associated with a significant eddy-induced acceleration that disappears completely when ring shadowing is not included (Figure 22 top rows). The equatorial behavior of eddy-induced acceleration is of opposite




Figure 21: Temperature comparison between CIRS 2005 limb data (blue dots), reference simulation (blue line), NO-RING simulation (red line) and the radiative-convective model \dot{a} la Guerlet et al. (2014) (blue dashed line) at the 40 Pa pressure level. Errorbars for the CIRS data contain the error due to the measurement noise and also related to the uncertainty of the CH₄ abundance.

sign at the top of the stratosphere in the no-ring simulation compared to the reference simulation.

The acceleration due to the mean circulation is shown at the bottom of Figure 22. Without rings shadowing, acceleration induced by the mean circulation is mainly positive in the north and negative in the south. With ring shadowing, this pattern is disturbed both in the southern hemisphere (where a reduced acceleration is seen at the location of the tropical eastward jet) and in the opposite hemisphere as well. Indeed, in the northern hemisphere, the acceleration is now mainly negative in the range 2-100 Pa when ring shadowing is taken into account. A similar behavior is observed during southern summer (not shown).

The amplification of the eddy-induced acceleration just below rings shadowing presents the same periodicity than the Saturn seasonal cycle. We map the time evolution of the acceleration due to eddies in the reference simulation (Figure 23(a)) and the no-ring simulation (Figure 23(b)). In the reference simulation, eddy-induced acceleration is enhanced at the tropics when eastward tropical jets are present. There is a strong deceleration due to eddies at the





Figure 22: Comparative meridional sections of zonal-mean zonal wind (contours, solid lines depict eastward jets and dashed lines depict westward jets), eddy-induced acceleration (color, top rows) and mean-circulation-induced acceleration (color, bottom rows) in TEM formalism between rings- (left columns) and no-ring- (right columns) simulations at the 3.5 simulated Saturn year since restart. This dates correspond to the northern summer: rings' shadow takes place at around $20^{\circ}\mathrm{S}$ and produces a strong eastward jet centered at $25^{\circ}\mathrm{S}$.

location of the tropical eastward jets (except for the jets located at 20° S at 2.5 simulated Saturn year). The winter tropics, where the rings' shadow occurs and eastward jets are produced, are associated with an intense interaction between eddies and the mean circulation, which induces a significant deceleration due to eddy activity. Regarding the no-ring simulation, the eddy-induced acceleration is halved compared to the reference simulation at the location of the eastward jets. The seasonality of the eddy-to-mean interaction persists at the tropics without the rings shadowing, but the intensity of the eddy forcing in the mean flow is reduced. In this case, the whole tropical channel is driven by homogeneous absolute values of acceleration and deceleration (about 1.5×10^{-5} m s⁻²).

To summarize the conclusions of this section 6, rings' shadowing affects the stratospheric dynamics of Saturn. Rings shadowing impacts the thermal structure of the tropical regions with a seasonal periodicity. This causes seasonally-varying tropical eastward jets underneath the shadows, through two distinct dynamical interactions. First of all, there is a enhancement of the eddy-induced acceleration at the location of the shadow. Secondly, there is a reversal of sign of the acceleration (positive in the case without ring shadow to negative sign in the case with rings shadow) due to the residual-mean circulation in summer hemisphere (opposite of the "rings shadow" hemisphere). Moreover, the strong meridional gradients of wave activity disturb the eastward phase of the equatorial oscillation (and the overall periodicity of it) by producing low-intensity eastward jets.

A putative impact of the ring's shadow on Saturn's stratospheric dynamics was already suspected by previous authors, based on the observation of a local maximum in hydrocarbons and anomalously high temperatures under the ring's shadow in northern winter, disappearing at the spring equinox (Guerlet et al., 2009; Sylvestre et al., 2015). Upward motion at summer mid-latitudes associated with a tropical adiabatic subsidence in the winter hemisphere could explain heat transport under the ring shadowing, as well as the observed hydrocarbon abundances asymmetries (Guerlet et al. (2009), Guerlet et al. (2010)).






Figure 23: Two-month running mean evolution of the zonal-mean eddy-induced acceleration (colors) and the zonal wind (contours) in Saturn's stratosphere (40 Pa) between 30° N and 30° S of our DYNAMICO-Saturn comparative simulations: 23(a) with rings' shadow (reference simulation) and 23(b) without rings' shadow.

With our study, we show that such interpretations of anomalies seen in observations invoking upward and downward motions may reflect a too simplistic view. Rather, eddy forcings might play a role as much as significant as the residual-mean circulation in shaping Saturn's stratospheric temperatures and dynamics.

7. Conclusions and perspectives

800

801

802

804

805

808

809

810

811

812

813

814

815

816

817

818

819

820

822

823

824

827

We use a troposphere-to-stratosphere Saturn GCM without any prescribed wave parameterization to study the equatorial stratospheric dynamics, especially the stratospheric equatorial oscillation. Concerning the global atmospheric dynamics, spherical harmonic decomposition of the horizontal velocity shows that statistical properties are similar in the tropospheric and stratospheric levels. These properties differ when we extend the model top toward higher stratospheric levels, but still predict a stratosphere more energetic than the troposphere. However, the 32-level simulation shows energetic non-axisymmetric modes m = 1, 2, 3 at large scale (i.e. small indices n) that vanish in our reference simulation. These modes likely results from energy accumulation at the model top which artificially enforces large-scale waves in the 32-level simulation of Spiga et al. (2020). Our spectral analysis emphasizes a currently open question: does the statistical framework of 2D-turbulence with a β -effect apply to energy spectra of Saturn's atmosphere, and more generally to 3D planetary macroturbulence? If Spiga et al. (2020) simulation retrieves the well-known KK-law of quasi-2D turbulence, the -5/3 slope does not apply when we raise the model top in our reference simulation. These statistical predictions of our Saturn climate model have now to be validated by direct observations of the Saturn's atmospheric flow.

Regarding the lower latitudes, our DYNAMICO-Saturn GCM reproduces an almost semi-annual equatorial oscillation with contrasted eastward and westward phases. This oscillation shows a similar behavior in temperature than the Cassini/CIRS retrievals, with alternatively local maxima and minima of temperature stacked on the vertical at the equator. The DYNAMICO-Saturn signal exhibits a two times smaller vertical characteristic size of the oscillation and underestimates by a factor of two the amplitude of the temperature anomalies, compared with CIRS observations. Regarding the zonal-mean zonal wind, we determined an irregular period of wind reversal and a downward propagation rate faster than observations. Spectral analysis at the equator demonstrated

that this QBO-like oscillation is produced by planetary-scale waves. The equatorial oscillation in the DYNAMICO-Saturn GCM is mainly driven by strong westward-propagating waves, such as Rossby, Rossby-gravity and inertia-gravity waves, which deposit westward momentum in the stratosphere. There are only two eastward-propagating modes (Kelvin waves) in the spectral analysis with a weaker impact in the stratospheric dynamics than the westward-propagating waves. This lack of eastward waves prevents the eastward momentum deposition in the mean zonal wind and explains the erratic behavior of the eastward phase of the modeled QBO-like oscillation. Using the Transformed Eulerian Mean formalism to determine how the eddy-to-mean interactions drives the Saturn equatorial oscillation, we are able to conclude that the maximum of eddy forcing comes from the high-troposphere tropical regions. Moreover, we demonstrate the wave forcing origin of the vertically-stacked stratospheric eastward and westward jets that propagate downward with time to form the equatorial oscillation. At the equator, in the stratosphere, the eddy-induced eastward acceleration maximum is located just under the eastward jets and the eddy-induced westward acceleration maximum is located just under the westward jets at every step of the downward propagation of this Saturn QBO-like equatorial oscillation. A control experiment, using a perpetual equinox radiaitve forcing, demonstrate that the seasonal cycle of Saturn plays a significant role to establish and regulate the stratospheric equatorial oscillation modeled by our DYNAMICO-Saturn GCM. Both eddy activity and residual-mean circulations are impacted by seasons in such a way that the periodicity of the equatorial oscillations is "locked" close to a semi-annual periodicity.

830

831

832

834

835

836

837

839

840

841

844

845

846

848

849

850

853

854

855

858

For future improvements of the modeling of the QBO-like oscillation in Saturn's equatorial stratosphere, we will draw inspiration from Earth's atmospheric modeling. Adequate vertical resolution is needed to obtain a more realistic Quasi-Biennial Oscillation in Earth models (Richter et al. (2014), Hamilton et al. (2001)). We plan to refine the vertical resolution in the stratosphere both to lead to a downward propagation rate of the oscillating zonal wind consistent with the observations, and a large-enough amplitude of Kelvin and Rossby-gravity

waves to enhance the westward and eastward forcing of the Saturn equatorial oscillation phases. Furthermore, the Earth's QBO eastward phase is primarily induced by gravity waves, triggered by tropospheric convection (around 70% of the total eastward forcing) and Kelvin waves for the remaining 30% (Baldwin et al., 2001). To overcome the lack of eastward momentum in our Saturn stratospheric modeling, we plan to add a stochastic gravity wave drag parameterization (Lott et al., 2012) in our DYNAMICO-Saturn GCM. This is expected to produce a more realistic wave spectrum (with equivalent eastward-and westward-propagating waves), which would strongly impact the simulation of the equatorial oscillation and the downward propagation of winds.

861

862

863

866

867

870

871

872

875

876

877

879

880

881

884

885

886

889

890

Another main result of this study is the impact of ring shadowing on the stratospheric dynamics. In our DYNAMICO-Saturn reference simulation we obtained strong tropical eastward jets, which are seasonally periodic, and correlated with Saturn rings' shadow. With an additional simulation not including rings' shadowing, we show that the tropical eastward jets are caused by rings' shadowing in the stratosphere. Without rings' shadowing, the tropical eastward jets disappear after 3 simulated Saturn years. Comparisons between temperature predicted by our dynamical GCM simulations, computed with radiative-convective equilibrium, and measured from Cassini/CIRS observations also suggests a dynamical impact of rings' shadowing in the stratosphere. The transformed Eulerian mean formalism shows that the dynamical impact of ring shadowing on tropical eastward jets is strong both on the eddy-induced acceleration and the residual-mean-induced acceleration. In presence of rings' shadowing, eddy-induced acceleration is increased in the tropical channel and there is a reversal of the residual-mean-induced acceleration in the opposite hemisphere to the rings. Wave activity is correlated with rings' shadowing: the seasonality of the eddies is enhanced by rings' shadowing, which contributes to the annual periodicity of the strong eastward tropical jets. Dynamics in the equatorial region, in particular the QBO-like oscillation, is also influenced by rings' shadowing.

Stratospheric winds have never been measured on Saturn and were deter-

mined using the thermal wind balance from the CIRS retrievals of stratospheric temperatures. Obviously, the tropical eastward jets could be a particularity of our DYNAMICO-Saturn GCM. Because of the small vertical wind shear associated with these tropical jets, there is no specific temperature signature associated to it. In other words, we cannot invalidate their existence with the available observations of the temperature field. Future measurements of winds in Saturn's stratosphere would help to validate the predictive scenario drawn by our model.

ดกร

Future studies using the DYNAMICO-Saturn GCM could adopt a wider analysis scope and study the global meridional circulation in the stratosphere. Results presented here are focused on the tropical regions, while the GCM extent is global. For instance, we could further characterize heat transport under the ring shadows, as well as the observed asymmetries of hydrocarbon abundances (Guerlet et al. (2009), Guerlet et al. (2010)). More generally, a complete study on the possible Brewer-Dobson-like circulation in the stratosphere of Saturn, and its impact on the hydrocarbons distribution, is warranted. A subsequent coupling of DYNAMICO-Saturn with photochemical models would then allow to refine this picture.

Sudden stratospheric warming on Earth's high and mid-latitude regions are associated with downward wind propagation anomalies of the Quasi-Biennial Oscillation (Lu et al., 2008). Is it possible that the extremely warm stratospheric disturbance in the aftermath of the Great White Storm of 2010-2011 (Fletcher et al., 2011, 2012; Fouchet et al., 2016) is due to a disruption of the downward propagation of the equatorial oscillation on Saturn? Conversely, Cassini observations showed that the occurrence of this huge storm disturbed the equatorial oscillations (Fletcher et al., 2017). Global stratospheric dynamical simulations by DYNAMICO-Saturn could help to address these questions in future studies.

18 Acknowledgments

927

928

The authors acknowledge the exceptional computing support from Grand
Equipement National de Calcul Intensif (GENCI) and Centre Informatique National de l'Enseignement Supérieur (CINES). All the simulations presented here
were carried out on the Occigen cluster hosted at CINES. Bardet, Spiga, Guerlet acknowledge funding from Agence National de la Recherche (ANR), project
EMERGIANT ANR-17-CE31-0007. We also acknowledge funding by CNES as
support of interpretation of Cassini/CIRS data analysis.

This paper is dedicated to the memory of Adam Showman who reviewed

This paper is dedicated to the memory of Adam Showman who reviewed our paper with his perfect balance of expertise and open-mindedness that our entire field will sorely miss.

References

- 930 Andrews, D.G., Mahlman, J.D., Sinclair, R.W., 1983. Eliassen-Palm Diag-
- nostics of Wave-Mean Flow Interaction in the GFDL "SKYHI" General
- 932 Circulation Model. Journal of the Atmospheric Sciences 40, 2768–2784.
- doi:10.1175/1520-0469(1983)040<2768:ETWATM>2.0.CO;2.
- Baldwin, M.P., Gray, L.J., Dunkerton, T.J., Hamilton, K., Haynes, P.H.,
- Randel, W.J., Holton, J.R., Alexander, M.J., Hirota, I., Horinouchi, T.,
- Jones, D.B.A., Kinnersley, J.S., Marquardt, C., Sato, K., Takahashi, M.,
- 2001. The quasi-biennial oscillation. Reviews of Geophysics 39, 179–229.
- 938 doi:10.1029/1999RG000073.
- Boer, G.J., 1983. Homogeneous and isotropic turbulence on the sphere. Journal
- of the Atmospheric Sciences 40, 154–163. doi:10.1175/1520-0469(1983)
- 040\$<\$0154:HAITOT\$>\$2.0.CO;2.
- 942 Butchart, N., 2014. The Brewer-Dobson circulation. Reviews of Geophysics 52,
- 943 157-184. doi:10.1002/2013RG000448.
- ⁹⁴⁴ Cabanes, S., Spiga, A., Young, R.M.B., 2020. Global Climate Modelling of
- Saturn's atmosphere. Part III: Global statistical picture of zonostrophic tur-
- bulence in high-resolution 3D-turbulent simulations. Icarus 345, 113705.
- doi:10.1016/j.icarus.2020.113705.
- ⁹⁴⁸ Chemke, R., Kaspi, Y., 2015. Poleward migration of eddy-driven jets. Jour-
- nal of Advances in Modeling Earth Systems 7, 1457–1471. doi:10.1002/
- 950 2015MS000481.
- ⁹⁵¹ Cosentino, R.G., Morales-Juberías, R., Greathouse, T., Orton, G., Johnson, P.,
- 952 Fletcher, L.N., Simon, A., 2017. New Observations and Modeling of Jupiter's
- 953 Quasi-Quadrennial Oscillation. Journal of Geophysical Research (Planets)
- 954 122, 2719–2744. doi:10.1002/2017JE005342.
- Dowling, T.E., 2008. Planetary science: Music of the stratospheres. Nature
- 956 453, 163–164. doi:10.1038/453163a.

- Dubos, T., Dubey, S., Tort, M., Mittal, R., Meurdesoif, Y., Hourdin, F., 2015. DYNAMICO-1.0, an icosahedral hydrostatic dynamical core designed for consistency and versatility. Geoscientific Model Development 8, 3131– 3150. doi:10.5194/gmd-8-3131-2015.
- Dunkerton, T.J., 1997. The role of gravity waves in the quasi-biennial oscillation.
 Journal of Geophysical Research 102, 26053–26076. doi:10.1029/96JD02999.
- Dunkertton, T., 1979. On the Mean Meridional Mass Motions of the Stratosphere and Mesosphere. Journal of the Atmospheric Sciences .
- Ern, M., Preusse, P., 2009. Quantification of the contribution of equatorial Kelvin waves to the QBO wind reversal in the stratosphere. Geophysical Research Letters 36, L21801. doi:10.1029/2009GL040493.
- Fletcher, L.N., Achterberg, R.K., Greathouse, T.K., Orton, G.S., Conrath, B.J.,
 Simon-Miller, A.A., Teanby, N., Guerlet, S., Irwin, P.G., Flasar", F., 2010.
 "seasonal change on saturn from cassini/cirs observations, 2004–2009". Icarus
 208, 337 352. URL: http://www.sciencedirect.com/science/article/
 pii/S0019103510000412, doi:https://doi.org/10.1016/j.icarus.2010.
 01.022.
- Fletcher, L.N., Guerlet, S., Orton, G.S., Cosentino, R.G., Fouchet, T., Irwin,
 P.G.J., Li, L., Flasar, F.M., Gorius, N., Morales-Juberías, R., 2017. Disruption of Saturn's quasi-periodic equatorial oscillation by the great northern
 storm. Nature Astronomy 1, 765–770. doi:10.1038/s41550-017-0271-5,
 arXiv:1803.07875.
- Fletcher, L.N., Hesman, B.E., Achterberg, R.K., Irwin, P.G.J., Bjoraker, G.,
 Gorius, N., Hurley, J., Sinclair, J., Orton, G.S., Legarreta, J., GarcíaMelendo, E., Sánchez-Lavega, A., Read, P.L., Simon-Miller, A.A., Flasar,
 F.M., 2012. The origin and evolution of Saturn's 2011-2012 stratospheric
 vortex. Icarus 221, 560–586. doi:10.1016/j.icarus.2012.08.024.

- Fletcher, L.N., Hesman, B.E., Irwin, P.G.J., Baines, K.H., Momary, T.W.,
- Sanchez-Lavega, A., Flasar, F.M., Read, P.L., Orton, G.S., Simon-Miller,
- A., Hueso, R., Bjoraker, G.L., Mamoutkine, A., del Rio-Gaztelurrutia, T.,
- Gomez, J.M., Buratti, B., Clark, R.N., Nicholson, P.D., Sotin, C., 2011. Ther-
- mal Structure and Dynamics of Saturn's Northern Springtime Disturbance.
- 989 Science 332, 1413. doi:10.1126/science.1204774.
- 990 Fletcher, L.N., Irwin, P.G.J., Sinclair, J.A., Orton, G.S., Giles, R.S., Hurley, J.,
- Gorius, N., Achterberg, R.K., Hesman, B.E., Bjoraker, G.L., 2015. Seasonal
- evolution of Saturn's polar temperatures and composition. Icarus 250, 131–
- 993 153. doi:10.1016/j.icarus.2014.11.022.
- 994 Fletcher, L.N., Kaspi, Y., Guillot, T., Showman, A.P., 2019. How well do we
- 995 understand the belt/zone circulation of Giant Planet atmospheres? arXiv
- e-prints, arXiv:1907.01822arXiv:1907.01822.
- 997 Fouchet, T., Greathouse, T.K., Spiga, A., Fletcher, L.N., Guerlet, S., Leconte,
- ⁹⁹⁸ J., Orton, G.S., 2016. Stratospheric aftermath of the 2010 Storm on Saturn
- as observed by the TEXES instrument. I. Temperature structure. Icarus 277,
- 196-214. doi:10.1016/j.icarus.2016.04.030, arXiv:1604.06479.
- Fouchet, T., Guerlet, S., Strobel, D.F., Simon-Miller, A.A., Bézard, B., Flasar,
- F.M., 2008. An equatorial oscillation in Saturn's middle atmosphere. Nature
- 453, 200-202. doi:10.1038/nature06912.
- Friedson, A.J., 1999. New Observations and Modelling of a QBO-Like Oscilla-
- tion in Jupiter's Stratosphere. Icarus 137, 34–55. doi:10.1006/icar.1998.
- 1006 6038.
- 1007 Friedson, A.J., Moses, J.I., 2012. General circulation and transport in Saturn's
- upper troposphere and stratosphere. Icarus 218, 861–875. doi:10.1016/j.
- icarus.2012.02.004.
- Galperin, B., Young, R.M.B., Sukoriansky, S., Dikovskaya, N., Read, P.L., Lan-
- caster, A.J., Armstrong, D., 2014. Cassini observations reveal a regime of

- zonostrophic macroturbulence on Jupiter. Icarus 229, 295–320. doi:10.1016/ j.icarus.2013.08.030.
- Giorgetta, M.A., Manzini, E., Roeckner, E., 2002. Forcing of the quasi-biennial oscillation from a broad spectrum of atmospheric waves. Geophysical Research Letters 29, 86–1–86–4. doi:10.1029/2002GL014756.
- Guerlet, S., Fouchet, T., Bézard, B., Flasar, F.M., Simon-Miller, A.A., 2011.
 Evolution of the equatorial oscillation in Saturn's stratosphere between 2005
 and 2010 from Cassini/CIRS limb data analysis. Geophysical Research Letters
 38, L09201. doi:10.1029/2011GL047192.
- Guerlet, S., Fouchet, T., Bézard, B., Moses, J.I., Fletcher, L.N., Simon-Miller,

 A.A., Michael Flasar, F., 2010. Meridional distribution of CH₃C₂H and

 C₄H₂ in Saturn's stratosphere from CIRS/Cassini limb and nadir observations. Icarus 209, 682–695. doi:10.1016/j.icarus.2010.03.033.
- Guerlet, S., Fouchet, T., Bézard, B., Simon-Miller, A.A., Michael Flasar, F., 2009. Vertical and meridional distribution of ethane, acetylene and propane in Saturn's stratosphere from CIRS/Cassini limb observations. Icarus 203, 214–232. doi:10.1016/j.icarus.2009.04.002.
- Guerlet, S., Fouchet, T., Spiga, A., Flasar, F., Fletcher, L.N., Hesman, B.E.,
 Gorius, N., 2018. Equatorial Oscillation and Planetary Wave Activity in
 Saturn's Stratosphere throught the Cassini Epoch. Journal of Geophysical
 Research: Planets.
- Guerlet, S., Spiga, A., Sylvestre, M., Indurain, M., Fouchet, T., Leconte, J.,
 Millour, E., Wordsworth, R., Capderou, M., Bézard, B., Forget, F., 2014.
 Global climate modeling of Saturn's atmosphere. Part I: Evaluation of the
 radiative transfer model. Icarus 238, 110–124. doi:10.1016/j.icarus.2014.
 05.010.
- Hamilton, K., Wilson, R.J., Hemler, R.S., 2001. Spontaneous Stratospheric QBO-like Oscillations Simulated by the GFDL SKYHI General Circula-

- tion Model. Journal of Atmospheric Sciences 58, 3271-3292. doi:10.1175/ 1040 1520-0469(2001)058<3271:SSQLOS>2.0.CO;2. 1041
- Holton, J.R., Lindzen, R.S., 1972. An Updated Theory for the Quasi-Biennial 1042 Cycle of the Tropical Stratosphere. Journal of Atmospheric Sciences 29, 1076-
- 1080. doi:10.1175/1520-0469(1972)029<1076:AUTFTQ>2.0.CD;2. 1044

1043

- Kraichnan, R.H., 1967a. Inertial Ranges in Two Dimensional Turbulence. 1045 Physics of Fluids 10, 1417–1423. 1046
- Kraichnan, R.H., 1967b. Inertial ranges in two-dimensional turbulence. The 1047 Physics of Fluids 10, 1417-1423. doi:10.1063/1.1762301. 104
- Kuroda, T., Medvedev, A.S., Hartogh, P., Takahashi, M., 2008. Correction to "Semiannual oscillations in the atmosphere of Mars". Geophysical Research 1050 Letters 35, L23202. doi:10.1029/2008GL036061. 1051
- Leovy, C.B., Friedson, A.J., Orton, G.S., 1991. The quasiquadrennial oscilla-1052 tion of Jupiter's equatorial stratosphere. Nature 354, 380–382. doi:10.1038/ 1053 354380a0.
- Li, L., Jiang, X., Ingersoll, A.P., Del Genio, A.D., Porco, C.C., West, R.A., 1055 Vasavada, A.R., Ewald, S.P., Conrath, B.J., Gierasch, P.J., Simon-Miller, 1056 A.A., Nixon, C.A., Achterberg, R.K., Orton, G.S., Fletcher, L.N., Baines, 1057 K.H., 2011. Equatorial winds on Saturn and the stratospheric oscillation. 1058 Nature Geoscience 4, 750-752. doi:10.1038/ngeo1292. 1059
- Li, X., Read, P.L., 2000. A mechanistic model of the quasi-quadrennial oscilla-1060 tion in Jupiter's stratosphere. Planetary and Space Science . 106
- Lian, Y., Showman, A.P., 2008. Deep jets on gas-giant planets. Icarus 194, 1062 597-615. doi:10.1016/j.icarus.2007.10.014. 1063
- Lian, Y., Showman, A.P., 2010. Generation of equatorial jets by large-scale 1064 latent heating on the giant planets. Icarus 207, 373–393. doi:10.1016/j. 1065 icarus.2009.10.006. 1066

- Lindzen, R.S., Holton, J.R., 1968. A Theory of the Quasi-Biennial Oscillation. Journal of Atmospheric Sciences 25, 1095–1107. doi:10.1175/
- Liu, J., Schneider, T., 2010. Mechanisms of Jet Formation on the Giant Planets.

 Journal of Atmospheric Sciences 67, 3652–3672. doi:10.1175/2010JAS3492.

 1, arXiv:0910.3682.
- Lott, F., Guez, L., Maury, P., 2012. A stochastic parameterization of non-orographic gravity waves: Formalism and impact on the equatorial stratosphere. Geophysical Research Letters 39, L06807. doi:10.1029/
- Lu, H., Baldwin, M.P., Gray, L.J., Jarvis, M.J., 2008. Decadal-scale changes in the effect of the qbo on the northern stratospheric polar vortex. Journal of Geophysical Research: Atmospheres 113. doi:10.1029/2007JD009647.
- Mayr, H.G., Lee, J.N., 2016. Downward propagating Equatorial Annual Oscillation and QBO generated multi-year oscillations in stratospheric NCEP reanalysis data. Journal of Atmospheric and Solar-Terrestrial Physics 138, 1–8. doi:10.1016/j.jastp.2015.11.016.
- Murgatroyd, R.J., Singleton, F., 1961. Possible meridional circulation in the
 Stratosphere and Mesosphere. Quaterly Journal of the Royal Meteorological
 Society .
- Orton, G.S., Friedson, A.J., Caldwell, J., Hammel, H.B., Baines, K.H.,
 Bergstralh, J.T., Martin, T.Z., Malcom, M.E., West, R.A., Golisch, W.F.,
 Griep, D.M., Kaminski, C.D., Tokunaga, A.T., Baron, R., Shure, M.,
 1991. Thermal maps of Jupiter Spatial organization and time dependence of stratospheric temperatures, 1980 to 1990. Science 252, 537–542.
 doi:10.1126/science.252.5005.537.
- Orton, G.S., Yanamandra-Fisher, P.A., Fisher, B.M., Friedson, A.J., Parrish,
 P.D., Nelson, J.F., Bauermeister, A.S., Fletcher, L., Gezari, D.Y., Varosi, F.,

- Tokunaga, A.T., Caldwell, J., Baines, K.H., Hora, J.L., Ressler, M.E., Fu-
- jiyoshi, T., Fuse, T., Hagopian, H., Martin, T.Z., Bergstralh, J.T., Howett, C.,
- Hoffmann, W.F., Deutsch, L.K., van Cleve, J.E., Noe, E., Adams, J.D., Kas-
- sis, M., Tollestrup, E., 2008. Semi-annual oscillations in Saturn's low-latitude
- stratospheric temperatures. Nature 453, 196–199. doi:10.1038/nature06897.
- Plumb, A.R., Bell, R.C., 1982. A model of the quasi-biennial oscillation on an
- equatorial beta-plane. Quarterly Journal of the Royal Meteorological Society
- 108, 335-352. doi:10.1002/qj.49710845604.
- Pouquet, A., Marino, R., 2013. Geophysical turbulence and the duality of the
- energy flow across scales. Physical Review Letters 111, 234501. doi:10.1103/
- 1105 PhysRevLett.111.234501.
- Rajendran, K., Moroz, I.M., Read, P.L., Osprey, S.M., 2016. Synchronisation
- of the equatorial QBO by the annual cycle in tropical upwelling in a warming
- climate. Quarterly Journal of the Royal Meteorological Society 142, 1111–
- 1120. doi:10.1002/qj.2714.
- Reed, R.J., Campbell, W.J., Rasmussen, L.A., Rogers, D.G., 1961. Ev
 - idence of downward propagating annual wind reversal in the equatorial
- stratosphere. Journal of Geophysical Research 66, 813–818. doi:10.1029/
- JZ066i003p00813.

1111

- Rhines, P.B., 1977. The dynamics of unsteady currents. The sea 6, 189–318.
- Richter, J.H., Solomon, A., Bacmeister, J.T., 2014. On the simulation of
- the Quasi-Biennial Oscillation in the Community Atmosphere Model, ver-
- sion 5. Journal of Geophysical Research (Atmospheres) 119, 3045–3062.
- doi:10.1002/2013JD021122.
- Ruan, T., Lewis, N.T., Lewis, S.R., Montabone, L., Read, P.L., 2019. Inves-
- tigating the semiannual oscillation on mars using data assimilation. Icarus
- 333, 404 414. URL: http://www.sciencedirect.com/science/article/

- pii/S0019103518306055, doi:https://doi.org/10.1016/j.icarus.2019.
- Schinder, P.J., Flasar, F.M., Marouf, E.A., French, R.G., McGhee, C.A., Kliore,
- A.J., Rappaport, N.J., Barbinis, E., Fleischman, D., Anabtawi, A., 2011.
- Saturn's equatorial oscillation: Evidence of descending thermal structure from
- Cassini radio occultations. Geophysical Research Letters 38, L08205. doi:10.
- 1029/2011GL047191.
- Schneider, T., Liu, J., 2009. Formation of Jets and Equatorial Superrotation on
- Jupiter. Journal of Atmospheric Sciences 66, 579. doi:10.1175/2008JAS2798.
- 1, arXiv:0809.4302.
- Shaw, T.A., Shepherd, T.G., 2007. Angular Momentum Conservation and Grav-
- ity Wave Drag Parameterization: Implications for Climate Models. Journal
- of Atmospheric Sciences 64, 190. doi:10.1175/JAS3823.1.
- Showman, A.P., Tan, X., Zhang, X., 2019. Atmospheric Circulation of Brown
- Dwarfs and Jupiter and Saturn-like Planets: Zonal Jets, Long-term Vari-
- ability, and QBO-type Oscillations. The Astrophysical Journal 883, 4.
- doi:10.3847/1538-4357/ab384a, arXiv:1807.08433.
- Simon-Miller, A.A., Poston, B.W., Orton, G.S., Fisher, B., 2007. Wind varia-
- tions in Jupiter's equatorial atmosphere: A QQO counterpart? Icarus 186,
- 192-203. doi:10.1016/j.icarus.2006.08.009.
- Sinclair, J.A., Irwin, P.G.J., Fletcher, L.N., Moses, J.I., Greathouse, T.K.,
- Friedson, A.J., Hesman, B., Hurley, J., Merlet, C., 2013. Seasonal varia-
- tions of temperature, acetylene and ethane in Saturn's atmosphere from 2005
- to 2010, as observed by Cassini-CIRS. Icarus 225, 257–271. doi:10.1016/j.
- icarus.2013.03.011.
- Solomon, S., Kiehl, J.T., Garcia, R.R., Grose, W., 1986. Tracer Transport by
- the Diabatic Circulation Deduced from Satellite Oservations. Journal of the
- 1149 Atmospheric Sciences .

- Spiga, A., Guerlet, S., Millour, E., Indurain, M., Meurdesoif, Y., Cabanes, S.,
 Dubos, T., Leconte, J., Boissinot, A., Lebonnois, S., Sylvestre, M., Fouchet,
 T., 2020. Global climate modeling of Saturn's atmosphere. Part II: Multiannual high-resolution dynamical simulations. Icarus 335, 113377. doi:10.
 1016/j.icarus.2019.07.011.
- Sukoriansky, S., Galperin, B., Dikovskaya, N., 2002. Universal spectrum of
 two-dimensional turbulence on a rotating sphere and some basic features of
 atmospheric circulation on giant planets. Physical review letters 89, 124501.
- Sylvestre, M., Guerlet, S., Fouchet, T., Spiga, A., Flasar, F.M., Hesman, B.,
 Bjoraker, G.L., 2015. Seasonal changes in Saturn's stratosphere inferred
 from Cassini/CIRS limb observations. Icarus 258, 224–238. doi:10.1016/
- Wheeler, M., Kiladis, G.N., 1999. Convectively Coupled Equatorial Waves:
 Analysis of Clouds and Temperature in the Wavenumber-Frequency Domain.
 Journal of Atmospheric Sciences 56, 374–399. doi:10.1175/1520-0469(1999)
 056<0374:CCEWAO>2.0.CO;2.
- Young, R.M., Read, P.L., 2017. Forward and inverse kinetic energy cascades in jupiter's turbulent weather layer. Nature Physics 13, 1135.

•

compared to observation

• Saturn's ring shadowing impacts the stratospheric equatorial dynamics, the equatorial scillation periodicity and equatorial winds intensity