



HAL
open science

Variations in surface area of six ice aprons in the Mont-Blanc massif since the Little Ice Age

Grégoire Guillet, Ludovic Ravanel

► **To cite this version:**

Grégoire Guillet, Ludovic Ravanel. Variations in surface area of six ice aprons in the Mont-Blanc massif since the Little Ice Age. *Journal of Glaciology*, 2020, 66 (259), pp.777-789. 10.1017/jog.2020.46 . hal-03090073

HAL Id: hal-03090073

<https://hal.science/hal-03090073v1>

Submitted on 29 Dec 2020

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.



Paper

Cite this article: Guillet G, Ravel L (2020). Variations in surface area of six ice aprons in the Mont-Blanc massif since the Little Ice Age. *Journal of Glaciology* 1–13. <https://doi.org/10.1017/jog.2020.46>

Received: 28 November 2019

Revised: 29 May 2020

Accepted: 1 June 2020

Key words:

Glacier monitoring; ice and climate; mountain glaciers

Author for correspondence:

Grégoire Guillet,

E-mail: gregoire.guillet@univ-smb.fr

Variations in surface area of six ice aprons in the Mont-Blanc massif since the Little Ice Age

Grégoire Guillet  and Ludovic Ravel

Université Grenoble Alpes, Université Savoie Mont Blanc, CNRS, EDYTEM (UMR 5204), Chambéry, France

Abstract

Deglaciation of high mountain rockwalls alters slope stability as rockwalls become more sensitive to modifications in environmental factors (e.g. seasonal temperature variations). In the past decades, increasing efforts focused on studying deglaciated Alpine rockwalls. Yet, currently deglaciating rockfaces remain unstudied. Here, we quantify surface area variations of massive ice bodies lying on high mountain rockwalls (ice aprons) in the French sector of the Mont Blanc massif between the end of the Little Ice Age (LIA) and 2018. Surface area estimates are computed from terrestrial and aerial oblique photographs via photogrammetry. This technique allows using photographs taken without scientific intent, and to tap into diverse historical or recent photographic catalogs. We derive an ice apron surface area model from precipitation records and the positive degree-days. The studied ice aprons shrank from 1854 to the 1950s, before expanding until the end of the 1990s. The beginning of the 21st century shows a decrease in surface area, leading to the complete melt of one of the studied ice aprons in 2017. Observed variations correlate with modeled surface area, suggesting strong sensitivity of ice aprons to changes in climatic variables. By studying site-specific correlations, we explore the importance of local drivers over the balance of ice aprons.

1. Introduction

Over the past decades, glacial shrinkage and permafrost warming have been identified as drivers for the physical and socio-economical changes observed in high mountain areas. Numerous geomorphological processes acting on landscape dynamics are indeed related to changes in the mechanical stability of recently deglaciated rockwalls/slopes (Deline and others, 2012, 2015; McColl, 2012; Ravel and others, 2013). Among them, the greatest sensitivity of deglaciated rock masses to variations in hydrological and thermal stresses is a well-documented preparatory and triggering mechanism for paraglacial rock mass failure (Ballantyne, 2002; Mercier and Etienne, 2008; Slaymaker, 2009). In the latter, fatigue of the rock mass, driven by long-term addition of diurnal to seasonal stress modifications, is the main driver for fracture development and growth (Krautblatter and Leith, 2015; McColl and Draebing, 2019). For example, climate change-related permafrost warming has been documented as a preparatory and triggering phenomenon for an increasing number of high mountain rock mass failures (Gruber and others, 2004; Fischer and others, 2006; Gruber and Haerberli, 2007; Caplan-Auerbach and others, 2008; Gruber, 2012; Deline and others, 2015; Ravel and others, 2017; Duvillard and others, 2019). The continued glacial shrinkage (Beniston and others, 2018; Jouvét and Huss, 2019; Zekollari and others, 2019), rising of the snowline elevation (Gobiet and others, 2014; Radić and others, 2014), reduction in frost frequency (Pohl and others, 2019) and overall snowfall (Klein and others, 2016) expected in the near future spark concern over the integrity of high mountain cryospheric bodies, and the stability of the underlying rockwalls (Krautblatter and others, 2010; Kenner and others, 2011; Stoffel and Huggel, 2012; Deline and others, 2015; Phillips and others, 2017).

While considerable efforts have been deployed to document and model the conditions leading to high mountain cryosphere-related failures (avalanching glaciers and permafrost; see Pralong and Funk, 2006; Huggel, 2009; Hasler, 2011; Faillettaz and others, 2015; Krautblatter and Leith, 2015), very few studies have focused on the ice of currently deglaciating rockwalls. Ice-covered rockfaces have received hardly any attention but are likely undergoing drastic changes in thermal and mechanical conditions as the ice cover disappears. To our knowledge, only the studies of Galibert (1960, 1964) provided qualitative descriptions of steep and thin ice covering high mountain rockfaces. As part of the mountain cryosphere, ice aprons are thought to have a negligible impact on sea-level rise and water resource availability. Nonetheless, as small-sized ice bodies, ice aprons are likely to be reliable indicators of climate change (Kuhn, 1995; Dyurgerov and Meier, 2000; Huss and Fischer, 2016) and to locally affect the stability of rockwalls (Kenner and others, 2011). Furthermore, ice aprons are mandatory passing points for numerous mountaineering routes (Mourey and others, 2019). Their change with time and climate as well as their relationships with other cryospheric objects in their vicinity (glaciers and permafrost) are still poorly understood. Ice apron/climate interactions and their relation to high mountain rockwall deglaciation need to be further investigated.

Our paper first aims at quantifying variations in surface area of six ice aprons located in the Mont-Blanc massif (France) since the end of the latest Little Ice Age (LIA) Alpine glaciers

© The Author(s), 2020 Published by Cambridge University Press. This is an Open Access article, distributed under the terms of the Creative Commons Attribution licence (<http://creativecommons.org/licenses/by/4.0/>), which permits unrestricted re-use, distribution, and reproduction in any medium, provided the original work is properly cited.

cambridge.org/jog

highstand (i.e. ≈ 1850 , Matthews and Briffa, 2005). In a second step, we assess potential relationships between the studied ice aprons and ongoing climate change. Section 2 reviews existing ice apron definitions. In Section 3, we detail the different study sites before further describing materials and methods used to quantify past variations in surface area in Section 4. According to the reported variations in surface area and with regards to meteorological data, we analyze the relationships between the studied ice aprons and climate in Section 5. A summary of the paper is presented in Section 6.

2. Definition and terminology

The definition of *ice apron* is not straightforward. According to Armstrong and others (1969), Benn and Evans (2010) and Bhutiyani (2011), ice aprons represent ‘small accumulations of snow and ice masses that stick to the topography of the glacierized basin’ and are ‘usually found above the equilibrium line’. Conversely, Cogley and others (2011) state that the term ‘ice apron’ is synonymous to ‘mountain apron glacier’ and defined as ‘a small *glacier* of irregular outline, elongate along slope, in mountainous terrain’. While the definitions proposed by Armstrong and others (1969), Benn and Evans (2010) and Bhutiyani (2011) imply low, if any, flow of the ice mass, Cogley and others (2011) explicitly state the existence of a past or present active ice motion in ice aprons. These two conflicting definitions reflect the lack of consensus on how to define ice aprons and the knowledge gap existing over the dynamics of such ice masses.

In the present study, we use the term ice apron to define very small (typically smaller than 0.1 km^2 in extent) ice bodies of irregular outline, lying on slopes $>40^\circ$, regardless of whether they are thick enough to deform under their own weight. To qualify as an ice apron, an ice body must persist for at least two consecutive years. We do not use the widespread maximum extent threshold for very small glaciers of 0.5 km^2 (see Leigh and others (2019) for more details) as we believe ice aprons of such dimension are very unlikely. Nonetheless, we doubt the studied sites (see Sections 3 and 5 for more) to be representative of the spectrum of possible ice apron extent and do not exclude the possibility of ice aprons with greater dimensions in other mountain ranges. The chosen slope angle is a common threshold in the material sciences community. It corresponds to the upper boundary limit of the stability angle for granular material (see e.g. Perla, 1978; Barabási and others, 1999). Our adopted definition for ice apron covers ice masses from different settings such as entirely glaciated rockfaces (e.g. north face of Obergabelhorn, Pennine Alps), isolated massive ice patches on rockwalls (e.g. north face of Mt. Alberta, Canadian Rocky Mountains) and any steep ice body lying over a glacial bergschrund (Mair and Kuhn, 1994), among others. Our study sites typically fall within the latter two settings (see Section 3).

3. Study sites

The Mont Blanc massif forms the border between Italy, France and Switzerland. Spanning 550 km^2 , the Mont Blanc massif concentrates the highest peaks in the Western European Alps and displays very irregular terrain, with altitudes ranging from 581 m a.s.l. (town of Saint-Gervais-les-Bains) to 4809 m a.s.l. (summit of Mont Blanc). This terrain irregularity provides favorable conditions for the development of steep glacial bodies such as avalanching glaciers (Pralong and Funk, 2006) or ice aprons on north-facing bedrock slopes.

This study focuses on six ice aprons located on north-oriented steep rockwalls within the Mont Blanc massif (see Fig. 1):

- (1) the north face of Triangle du Tacul (3970 m a.s.l.)
- (2) the north face of Tour Ronde (3792 m a.s.l.)
- (3) the north face of Grandes Jorasses (4208 m a.s.l.)
- (4) the north face of Aiguille des Grands Charmoz (3445 m a.s.l.)

As our study relies heavily on the use of oblique historical imagery for extracting physical landscape measurements (see Section 4.1.1 for more details), the choice was made to select the most accessible ice aprons, as they are likely the best represented in mountain photography. The north faces of Grandes Jorasses and Aiguille des Grands Charmoz are easily observable from the Montanvers (Fig. 1), a panoramic viewpoint on the whole Mer-de-Glace basin, where the first hotel was opened in 1840 (Ballu, 2002). This broadens the studied time range as we were able to include photographs taken in the 1850s. The north faces of Triangle du Tacul and Tour Ronde are mainly documented since the 1950s, as the construction of the Aiguille du Midi cable-car enabled easy access to these remote sites. They have since become classical routes for mountaineers and are thus regularly documented.

The north face of Triangle du Tacul (Fig. 2a) lies in the accumulation zone of the Géant glacier. The mountain face is divided into two different ice aprons. We will hereafter focus on the lower one which extends from 3570 to 3690 m a.s.l. of elevation (0.004 km^2 in 2018) and shows a mean slope of $59 \pm 2^\circ$.

Similarly situated in the accumulation zone of the Géant glacier, Tour Ronde (Fig. 2b) forms the border between France and Italy. Its north face displays two ice aprons separated by a gully. The lower one, ranging from 3343 m a.s.l. at the bergschrund to 3594 m a.s.l. at its top (2015), will hereafter be called Lower Tour Ronde. The upper one, ranging from 3600 to 3750 m a.s.l. (2015), will be referred to as Upper Tour Ronde (0.005 km^2 in 2012). Both ice aprons exhibit a mean slope of $55 \pm 2^\circ$.

The north face of Grandes Jorasses (Fig. 2c), is a 1200 m-high rock face located in the Mont Mallet basin, in the accumulation zone of the eponymous glacier. Most of the rockwall, up to an elevation of 4000 m a.s.l., is covered by a 500 m-high and 170 m-wide ice apron (0.028 km^2 in 2017). Overall, the Upper Grandes Jorasses ice apron displays a mean slope close to $63 \pm 3^\circ$. The second studied ice apron located in the north face of Grandes Jorasses lies at the bottom of the face, between 3220 and 3650 m a.s.l., and will be further referred to as Lower Grandes Jorasses. Its average slope is similar to that of Upper Grandes Jorasses.

The north face of Aiguille des Grands Charmoz lies over the Mer-de-Glace basin (Fig. 2d). The ice apron lies between 2907 and 3185 m a.s.l. of elevation (2015). Contrary to the other studied ice aprons, the Grands Charmoz ice apron is not located within the accumulation zone of a large valley glacier. The ice apron shows a mean slope of $\sim 52 \pm 2^\circ$.

4. Materials and methods

In the present study, we estimate the evolution of surface area for six different ice aprons from photographs taken between 1854 and 2018. To this end, we rely on a photogrammetric inverse perspective method, presented in detail in Guillet and others (2020). This particular technique aims at extracting referenced landscape feature measurements from a single image by estimating the parameters of the imaging camera using ground control points (GCPs), such as peaks or noticeable buildings (e.g. Förstner and Wrobel, 2016). Extracted measurements are then back-projected onto a Digital Elevation Model (DEM), thus providing an estimate of the ice apron surface area. Similar methods have already been used to document and reconstruct changes in glacier states




Fig. 1. Localization map of the Mont Blanc massif and the study sites.

in the Himalayas (Byers, 2007), the Swiss (Wiesmann and others, 2012) and Julian Alps (Triglav-Čekada and Gabrovec, 2013), among others.

In this section, we start by detailing the data used for this study (Section 4.1). We then briefly describe our inverse perspective method, which provides our surface area estimates and uncertainties (Section 4.2). We finally derive a model of surface area evolution based on meteorological data (Sections 4.3 and 4.4).

4.1 Data description

4.1.1 Photographs

This study relies on the joint use of terrestrial oblique photographs and aerial single images for extracting discrete ice apron surface area estimates. Working with single photographs allows one to tap into a wealth of available data readily accessible from the Internet such as aerial surveys, historical records or user-contributed photographs. Ice apron surface area estimates can hence be extracted from photographs taken with no prior scientific intention and in this instance allowing us to cover a 164-year time range.

For this study, we used photographs from diverse sources:

- Aerial photographs come from various photographic surveys carried out by the IGN (Institut Géographique National, French National Geographic Institute) and are publicly available

(Institut Géographique National, 2019). Such photographs cover a time span of 64 years, from 1949 to 2012. The list of aerial photographs used in this study is provided in the Appendix.

- Terrestrial oblique photographs originate from private collections. Photographs originating from the 19th and 20th centuries were taken by professional photographers. Photographs taken after that period originate from the authors' and their relatives' private collections.

Seasonal variations in snow cover are likely to impact the estimated ice apron surface area. To ensure comparable estimates, we selected only photographs taken in late summer, and preferably, in September. All IGN aerial photographs provide accurate time-stamps. Most recent terrestrial digital photographs provide date and time information, for example, in embedded EXIF metadata. For historical photographs, while generally only the year is known, the season in the year can easily be identified by the presence of seasonal snow at low- to mid-altitudes (winter and spring or fall), and we exclude any photograph shot in the winter or spring. Finally, all photographs taken in summer which show evidence of recent snowfall are rejected. In this process, we are typically looking for sparse snow patches on nearby rockfaces, and recent avalanche activity overlaying the bergschrunds. After the selection process, our final corpus is composed of a total of 55 photographs.




Fig. 2. The studied ice aprons. Yellow outline represents the ice apron boundary. (a) Triangle du Tacul (3970 m a.s.l.). (b) Tour Ronde (3792 m a.s.l.). (c) Grandes Jorasses (4208 m a.s.l.). (d) Aiguille des Grands Charmoz (3445 m a.s.l.). None of these pictures were used to produce surface area estimates.

4.1.2 Digital elevation model

The DEM used is provided by a regional French agency (Régie de Gestion des Données des Pays de Savoie). It was constructed from 1998 aerial photographs, revised in 2004 through photogrammetric GCPs, and further updated in 2008 and 2010. The DEM is provided to us as rectilinear gridded data with 4 m node spacing (horizontal resolution) in both easting and northing, in the Lambert-93 projection. The documentation reports an estimated vertical root mean square error (RMSE) ranging from 1 m in plains to 4 m in rugged and alpine high altitude areas. The back-projection model accounts for errors in the DEM based on an RMSE comparable to published specifications; our uncertainty model accounts for spatially correlated vertical errors which can easily exceed 4 m in steep terrain (see Guillet and others (2020) for details). It should be noted that the DEM is likely to change in time, as a consequence of variations in ice apron volume. Considering the small dimensions of the studied objects, we assume such changes in the DEM to be in the same order of magnitude as the DEM resolution.

4.1.3 Ground control points

We manually determine 2D/3D control point matches. We proceed by identifying well-defined features on the photograph, such as road crossings, mountain peaks, corners of noticeable buildings, and match them to their known position in 3D world coordinates. 3D world positions are determined by detailed topographical maps and completed, if needed, with planimetric and altimetric databases such as OpenStreetMap (OpenStreetMap contributors, 2019). As 3D GCPs coordinates do not come from high-precision geodetic surveys, their typical accuracy is of the order of a few meters.

4.2 From single photographs to ice apron surface area: camera calibration and inverse perspective with uncertainties

For this study, we use the Bayesian framework developed in Guillet and others (2020) to reconstruct the surface areas and their uncertainties from individual photographs.

In photogrammetric applications, measurements are usually extracted from single photographs using camera models with known camera parameters. In our study, photographs come from various sources; for most photographs, the camera parameters and the imaging system used are unknown. It is therefore necessary to compute an estimate of the camera parameters used to take each picture.

This process, called camera calibration, aims at finding a set of admissible camera parameters that can reproduce the observed 2D control points by projection of the 3D points, given a chosen camera projection model (Fig. 3). Once the camera is calibrated, the outline of the ice apron is manually traced on the picture as a polygon. Using the estimated camera parameters, we finally invert the perspective of the calibrated camera and project the 2D polygon onto the DEM.

There are four main sources of uncertainties that we account for in our reconstruction of the surface area:

- (1) Finding the 2D location of a control point on the image involves some level of uncertainty. The accuracy of 2D point picking depends on several factors such as image resolution, blurriness, contrast or perspective among others. For low-resolution imagery, we can expect uncertainties of <5 pixels, while high-resolution aerial pictures typically allow for lower GCP location uncertainties, typically between 1 and 2 pixels.
- (2) The positions of the GCPs in 3D world coordinates are known up to a certain level of accuracy. The uncertainty over the *true* 3D GCP location varies with surveying method. While GPS-surveyed GCPs could be located with centimetric accuracy, coordinates derived from maps typically only provide an accuracy of a few meters, at best.
- (3) Similarly to 2D GCPs, the manual polygon tracing step introduces systematic errors originating from the precision with which ice apron margins can be identified.
- (4) Finally, errors arise from the accuracy of the DEM itself.




Fig. 3. Overview of the inverse perspective problem. 2D control points (blue) are defined on the picture and matched with their corresponding 3D world coordinates (red). The matches are used to estimate the parameters of the imaging camera. The 2D polygon (blue) is then backprojected onto the DEM in order to obtain the surface area estimate (red). Shaded areas typically illustrate the uncertainties on true location (see text for further details). Modified from Guillet and others (2020).

The method proposed in Guillet and others (2020) allows one to compute the camera parameters as a probability distribution of admissible camera parameters, rather than a single value estimate. From the probability distribution on camera parameters, a number N of samples is randomly drawn. Each of the samples is then used to back-project the polygon onto the DEM. Here, we typically use $N = 5000$. For each photograph, the extracted ice apron surface area thus corresponds to a probability distribution, originating from 5000 different back-projections of the polygon.

4.3 Meteorological data

In our study, our goal is to correlate variations in surface area estimates with accumulation and ablation proxies. For our study sites, the closest permanent weather station is the MeteoFrance Aiguille du Midi station (3842 m a.s.l., abbreviated AdM, see Fig. 1). However, no precipitation records are available for the AdM station. We thus consider monthly temperature and precipitation records from the Col du Grand-Saint-Bernard (2469 m a.s.l., abbreviated GSB) weather station (MeteoSwiss), over the 1860–2018 period. Located 15 km eastward from Grandes Jorasses (4208 m a.s.l.) and Aiguille du Midi, the Col du Grand-Saint-Bernard presents a similar climatological regime.

With the aim of modeling the monthly averaged temperature at elevations closer to our study sites, we study the correlation between AdM and GSB datasets. Because of the strong correlation between monthly averaged AdM and GSB temperature records (Pearson's $r = 0.98$, p -value < 0.001 , see Fig. 4), we model the monthly averaged AdM temperature from the GSB temperature using a linear model:

$$T_{\text{ADM}_i} = aT_{\text{GSB}_i} + b + r_i, \quad (1)$$

where $a = 0.87$, $b = -7.7^\circ\text{C}$, r are, respectively, the slope, intercept and residuals with zero mean.




Fig. 4. Correlation (Pearson's $r = 0.98$, $p < 0.001$) between the monthly averaged temperature measurements at the Aiguille du Midi (AdM) and the Col du Grand Saint Bernard (GSB) for the 2007–2018 period.

From the AdM data reconstructed using 1, we estimate an annual sum of positive degree-days (PDD), using the method proposed by Calov and Greve (2005). This method, based on the ideas of Reeh (1991) and Braithwaite (1995), proposes a probabilistic approach to the computation of the PDD. The annual sum of PDD is thus computed from the normal probability distribution centered on the mean monthly temperature. Calov and Greve (2005) also account for stochastic variations in temperature in the computation of the PDD. We then calculate the cumulative




Fig. 5. Evolution of surface area for the six studied ice aprons of the Mont Blanc massif. Error bars represent the 90% confidence interval obtained from the polygon back projection process.

Table 1. Summary of the variations of surface area for the six study sites. $S(t)/S(t_0)$ represents normalization of the surface area measurement at time t by the first estimate

Site	First estimate (m ²) (year) ($S(t)/S(t_0)$)	1940s–1950s (m ²)	End of 1960s (m ²)	1980s (m ²)	Early 2000s (m ²)	Last (m ²)
U. Gdes Jorasses	35 514 ± 1711 (1854) 1.0	30 411 ± 1011 (1952) 0.85	35 298 ± 1134 (1967) 0.99	36 807 ± 1620 (1988) 1.03	33 179 ± 1608 (2004) 0.93	28 128 ± 1288 (2017) 0.79
L. Gdes Jorasses	44 607 ± 2019 (1902) 1.0	27 124 ± 1838 (1952) 0.60	32 844 ± 867 (1967) 0.73	29 319 ± 1141 (1984) 0.65	18 749 ± 561 (2004) 0.42	16 163 ± 1137 (2016) 0.36
U. Tour Ronde	10 110 ± 195 (1880) 1.0	8602 ± 265 (1952) 0.8	9830 ± 183 (1966) 0.94	8941 ± 541 (1988) 0.88	5467 ± 147 (2004) 0.43	5129 ± 153 (2012) 0.39
L. Tour Ronde	22 045 ± 1954 (1880) 1.0	15 319 ± 497 (1952) 0.69	15 890 ± 984 (1966) 0.72	16 151 ± 916 (1988) 0.73	14 000 ± 197 (2004) 0.63	11 000 ± 214 (2018) 0.49
Triangle du Tacul	5954 ± 429 (1939) 1.0	5087 ± 475 (1959) 0.85	4885 ± 314 (1967) 0.82	5413 ± 225 (1988) 0.90	4588 ± 278 (2004) 0.76	4013 ± 309 (2018) 0.67
Grands Charmoz	34 702 ± 2700 (1900) 1.0	24 237 ± 607 (1958) 0.69	21 647 ± 441 (1967) 0.62	21 307 ± 413 (1988) 0.61	10 625 ± 283 (2012) 0.11	0 (2017) 0.0

PDD and use it as a proxy for ablation (Braithwaite and Olesen, 1989; Vincent and Vallon, 1997).

Accumulation is approximated as the yearly sum of precipitation occurring at a temperature between -5 and 0°C , as only snowfall within this temperature range is believed to accumulate in steep terrain (Kuroiwa and others, 1967). Other local mass-balance drivers such as wind redistribution and erosion, gravitational transport and probable feedback – positive or negative – between surface slope variations and accumulation or ablation, among others, are neglected.

4.4 Surface area model

We finally derive the surface area model for the studied ice aprons. We propose to model the differences between surface area

measurements at different time steps, as the result of time-integrated changes in climatic forcing. Here, we are typically looking for a potential linear relationship between variations in ice apron surface area and the defined climate forcing by using a multivariate regression model. More formally, it can be written as follows:

$$S_m(t) = S(t_0) - \int_{t_0}^t (\alpha_1 \text{CPDD}(t) - \chi_i(T(t))\alpha_2 A(t)) dt + \beta + \epsilon(t), \quad (2)$$

where $S_m(t)$ corresponds to the modeled surface area at time t . Similarly, $\text{CPDD}(t)$ and $A(t)$ represent our proxies for ablation and accumulation. $S(t=0)$ is the first measurement available for




Fig. 6. Evolution of the Grand Charmoiz ice apron between 1989 and 2017. Between 1989 and 1993, the lower part of the ice apron (blue) is fragmented from the two ice gullies (red). As often observed, the ice apron is successively fragmented in smaller ice bodies before total melt in 2017.




Fig. 7. Comparison of photographs for: (a) Triangle du Tacul (upper and lower), (b) Tour Ronde (upper and lower) and (c) Grandes Jorasses. Yellow dashed line represents ice apron outlines from the left picture. The steepest sections of the ice aprons are the first parts to display shrinkage. Note that the presented Tour Ronde pictures were not used to extract surface area measurement of the Upper Tour Ronde ice apron hence, the black outline of Upper Tour Ronde (b) is a crude representation of 1880 ice apron extent.




Fig. 8. Correlation between the mean normalized surface area estimates and the modeled surface areas. $S(t)/S(t_0)$ represents normalization of the surface area measurement at time t by the first estimate. Similarly, $S_m(t)/S(t_0)$ represents normalization of the modeled surface area at time t . The dashed lines represent the best fit line of equation $y=x$ (see text for further details).

each individual ice apron. α_1 and α_2 are the coefficients of linear regression, β is the intercept, and ϵ the residuals. $\chi(T, t)$ accounts for precipitation occurring in the $[-5^\circ\text{C}, 0^\circ\text{C}]$ temperature range. It is written as the temperature-dependent indicator function of the form:

$$\chi_i(T(t)) = \begin{cases} 1 & \text{if } -5^\circ\text{C} \leq T(t) \leq 0^\circ\text{C} \\ 0 & \text{otherwise} \end{cases}. \quad (3)$$

5. Results and discussion

In this section, we first present the time series of surface area estimates. We then review the potential correlation between extracted and modeled ice apron surface areas. Finally, we discuss the sensitivity of the studied ice aprons to small-scale processes and local mass-balance drivers.

5.1 Changes in ice apron extent: the decrease in surface area

Time series of surface area estimates are presented in Figure 5, and summarized in Table 1. The studied sites show similar trends in surface area evolution, with details varying between individual ice aprons. Despite significant data gaps, results indicate that the largest ice aprons expansion occurs at the end of the 19th century. We observe a decrease in relative surface area from the beginning of the 20th century to the end of the 1960s. The Grands Charmoz ice apron shows the most substantial surface loss, decreasing 40% ($\approx -13000 \text{ m}^2$) between 1900 and 1966. Lower Tour Ronde and Lower Grandes Jorasses exhibit similar trends, with a relative surface area loss $\sim 30\%$ ($\approx -6100 \text{ m}^2$) for the 1880–1966 period. Relative surface losses are lower for the Triangle du Tacul and Upper Grandes Jorasses ice aprons, with 18% ($\approx 770 \text{ m}^2$) and 13% ($\approx -5000 \text{ m}^2$) observed shrinkage, respectively. Overall decrease (1850s to late 1960s) is followed by a period of ~ 20 years of expansion, reaching its maximum by the end of the 1980s for the Grands Charmoz, Tour Ronde (upper and lower) and Triangle du Tacul ice aprons. In 1988, the Upper Grandes Jorasses ice apron attains a surface area close to its 1854 extent.

Table 2. Linear regression parameters and correlation metrics for each individual study site

Site	Altitude range (m a.s.l.)	Slope	Intercept	Pearson's r	p value
Upper Grandes Jorasses	3500–4000	0.36	0.56	0.6	0.02
Lower Grandes Jorasses	3200–3600	0.74	0.16	0.86	0.002
Upper Tour Ronde	3600–3700	0.89	-0.12	0.90	<0.001
Lower Tour Ronde	3400–3600	0.90	0.05	0.86	<0.001
Triangle du Tacul	3600–3700	0.70	0.19	0.86	<0.001
Grands Charmoz	2900–3200	1.01	0.06	0.95	<0.001

Between 1988 and 1993, we observe an important decrease in the Grands Charmoz and Upper Tour Ronde time series. The ice apron was fragmented in smaller ice bodies as the steepest parts of the ice apron are separated from the underlying main body (Fig. 6). Since the 1990s, shrinkage is observed over all the investigated ice aprons.

Both Lower Tour Ronde and Triangle du Tacul exhibit an average shrinking rate in surface area of $1\% \text{ a}^{-1}$ between 1984 and 2018. Over the same period, the decrease for Upper Grandes Jorasses is close to $0.7\% \text{ a}^{-1}$. Again, the Lower Grandes Jorasses, Upper Tour Ronde and Grands Charmoz ice aprons record the highest decrease rates, with $2.6\% \text{ a}^{-1}$, $3.6\% \text{ a}^{-1}$ and $4.8\% \text{ a}^{-1}$, respectively. Ice apron shrinkage from the 19th and 20th centuries to 2018 is further illustrated in Figure 7.

Overall, our records of surface area and of their estimated shrinking rates of a total of $\sim 90\,000 \text{ m}^2$ over the period 1854–2018 are consistent with previous results from similar studies (Hoffman and others, 2007; Andreassen and others, 2008; Bolch and others, 2011; Serrano and others, 2011; Shahgedanova and others, 2012; Marti and others, 2015; Zemp and others, 2015).

5.2 Climate change as a driver for ice apron shrinkage

Figure 8 illustrates the correlation between measured and modeled normalized surface area estimates for all the studied ice aprons. We observe a strong linear correlation (Pearson's $r = 0.92$, p -value = 0.001) between the mean normalized surface area estimates extracted from the photographs and the modeled normalized surface areas (Fig. 8). The best-fitting line presents a slope of 1.0 and an intercept of 0.0. These results demonstrate the proficiency of the proposed surface area model in computing new ice apron states from the accumulation and ablation proxies. It is, however, important to note that we observe substantial scatter in the data, with a std dev. of 0.23.

We will now review site-specific ice apron/climate relationships for each individual ice apron. Table 2 summarizes regression parameters and correlation metrics for each study site. Figure 9 illustrates the correlation between measured and modeled normalized surface area estimates for each independent ice apron. As before, we observed linear relationships between modeled and extracted surface areas. Our results however show discrepancies between the different ice aprons. The most notable one is the Upper Grandes Jorasses ice apron for which the linear relationship is the weakest (Table 2). Due to their small dimensions, all the studied ice aprons do not display standard accumulation and ablation zones. Mass gain and loss mainly occur across the ice apron in its entirety, with a major impact near the ice margins (Fig. 7). No evidence of ice flow at the surface could be observed between photographs. The latter suggests that downward mass transfer has very small, if any, impact on the ice aprons and that such ice masses should respond rapidly to climate change (Kuhn, 1995). A simple approach to modeling surface area variations, based exclusively on PDD and precipitation as proxies for ablation and accumulation, appears suitable for the study of ice




Fig. 9. Correlation between the mean normalized surface area estimates and the modeled surface areas for each individual study site. Shaded areas represent 95% confidence interval of the linear fit. $S(t)/S(t_0)$ represents normalization of the surface area measurement at time t by the first estimate. Similarly, $S_m(t)/S(t_0)$ represents similar normalization of the modeled surface area at time t . Pearson's correlation coefficient and other regression metrics are further detailed in Table 2.

aprons over several study sites. However, the proposed model failed to constrain site-specific surface area variations, especially for the Upper Grandes Jorasses ice apron.

5.3 The importance of local mass-balance drivers

Discrepancies in surface area evolution between individual ice aprons can primarily be related to elevation differences. The works of Hantel and others (2012) documented the median summer snowline (snow probability 0.50) of the Alps 1961–2010 to be 3083 ± 121 m a.s.l. Similarly, Rabatel and others (2013) proposed a regional equilibrium line altitude (ELA) of 3035 ± 120 m a.s.l. for the western Alps (1984–2010). As mentioned above, ice aprons do not display standard accumulation and ablation zones. ELA approaches are therefore not well-suited to study the mass balance of ice aprons. Nonetheless, in the present case, both the ELA and the snowline are mentioned as reference altitudes at which we are to expect conservation of snow cover during summer. With altitudes ranging from 2900 to 3200 m a.s.l., a substantial part of the Grand Charmoz ice apron lies below the ELA and the snowline. In addition, Rabatel and others (2013) describe rising of the ELA to 3250 ± 135 m a.s.l. during the 2003 heat wave, bringing the ELA higher than the upper margin of the ice apron (3200 m a.s.l.). Similar scenarios likely happened during the subsequent heat waves of 2006, 2015 and 2017 (Della-Marta and others, 2007; Hoy and others, 2017), leading to complete melting of the Grands Charmoz ice apron in August 2017 (Fig. 6).

Differences in elevation between ice aprons cannot however explain the rates of yearly loss recorded by the Lower Grandes Jorasses and Upper Tour Ronde ice aprons since the end of the 1990s. Hoffman and others (2007) and DeBeer and Sharp (2009), among others, demonstrated the importance of accounting for local mass-balance drivers in variations of ice masses. Local topography is a documented factor contributing to the persistence of small glaciers lying under the regional ELA (Florentine and others, 2018). Here, we suggest that local topography mitigates ice apron persistence, especially for Lower Grandes Jorasses and Upper Tour Ronde. Figure 7 shows that for these two ice aprons, most of the recorded loss occurs on a topographical ridge. Ridge-like topographies lead to unobstructed surfaces and

introduce local changes in slope aspect, altering the energy balance of ice masses lying on the ridge (Gratton and others, 1993; Evans, 2006). Furthermore, it can be inferred that thermal radiation emitted from recently deglaciated zones will further accelerate the melt of nearby ice aprons (Paul and others, 2004). It is also worth noting that the Upper Tour Ronde ice apron lies on the summit ridge; therefore, we believe that summer horizontal (south to north) heat fluxes likely affect the energy balance of the summital part of Upper Tour Ronde ice apron (Noetzli and others, 2007). We further suggest that the steepness of the studied ice aprons is severely limiting accumulation. In this type of complex topography, avalanching will scour snow away from the ice apron, exposing the bare ice and the same is to be expected from wind, which can relocate or sublimate snow (Vionnet and others, 2014).

Several studies discussed the need to account for decadal variations in radiation (secondary to changes in cloudiness or solar dimming/brightening) in mass-balance modeling (Gerbaux and others, 2005; Huss and others, 2009; Thibert and others, 2018). Here, we chose to use a simple temperature-index model as a first approach to simulate surface area variations of the studied ice aprons (Reveillet and others, 2017). While our results demonstrate the importance of air temperature and precipitation on the observed surface area variations, we expect global radiation to play a role in the mass and energy balance of ice aprons. Clarifying the sensitivity of ice aprons to long-term changes in global radiation is of importance to allow meaningful projections of ice aprons evolution during the 21st century, and should be addressed in future studies.

Our results show that ice aprons react rapidly to changes in climate forcing (see Figs 8, 9 and Table 2). Most local mass-balance drivers mitigate the accumulation of snow and thus enhance the impact of air temperature on ice aprons. This poses the question of the sensitivity of ice aprons to extreme weather events. Given the sampling rate of our surface area measurements, it is not possible to quantify the contribution of individual extreme weather events, such as the 2003 heat wave. Yet, we believe that heat waves occurring when the ice apron is free of snow (in winter and midsummer) will have the greatest effect. With regards to the foreseeable increase in intensity, frequency and length of heat waves in the 21st century (Meehl and Tebaldi, 2004), there

is a pressing need for a better understanding of ice apron sensitivity to extreme weather events.

6. Conclusions and outlooks

In this paper, we presented time series of surface area estimates for six ice aprons located in the Mont Blanc massif over the period 1854–2018 using 55 terrestrial and aerial oblique photographs to produce estimates of end-of-summer surface area (Table 1).

The studied ice aprons shrank between the end of 1850s and the mid- to late-1960s. While a short period of ice apron expansion occurred from the early 1970s to the early 1990s, we observe an accelerated recession of all ice aprons since the beginning of the 21st century. Over the studied time period (e.g. 1850s–2018), the Upper Grandes Jorasses display shrinkage $\sim 20\%$ ($-7400 \pm 200 \text{ m}^2$, see Table 1) while the Triangle du Tacul, Upper Tour Ronde and Lower Tour Ronde ice aprons lost 35% ($-1940 \pm 158 \text{ m}^2$), 40% ($-3500 \pm 147 \text{ m}^2$) and 50% ($-1100 \pm 127 \text{ m}^2$, see Fig. 5 and Table 1). The Lower Grandes Jorasses ice apron exhibits shrinkage $\sim 60\%$ ($-28440 \pm 550 \text{ m}^2$, see Fig. 5 and Table 1). The most dramatic example of ice apron shrinkage is the Grands Charmoz ice apron which melted completely during the summer of 2017.

In parallel, we derived an ice apron surface area model based on meteorological data. We used the precipitation record, focusing on snowfall occurring between -5 and 0°C , and a simple PDD approach, as proxies for accumulation and ablation, respectively. Combining time-integrated accumulation with a temperature-index, the model consistently estimated variations in ice apron surface area. Applied to our sites of interest, our study showed discrepancies in surface area variations between individual ice aprons. While discrepancies in surface area variations could primarily be related to differences in elevation, we also noted the importance of local topography on both the energy and mass balances of ice aprons.

Ice aprons stand out as an important component of the high-alpine cryospheric system; given the observed shrinking rates and existing climate scenarios, severe concerns exist over the fate of the studied ice aprons. Climate change-related modifications in ice aprons are likely to alter the whole high mountain environment; most notably, the loss of ice aprons is thought to have major consequences over the mechanical and thermodynamical stability of the underlying steep rockfaces. We believe the impact of ice apron loss over the underlying steep high mountain rockwalls needs to be further addressed.

Acknowledgements. This study is part of the ANR 14-CE03-0006 VIP Mont Blanc and the ALCOTRA n342 PrevRisk Haute Montagne projects. We thank the editor and two anonymous reviewers for their constructive remarks on the manuscript.

References

- Andreassen LM, Paul F, Kääb A and Hausberg JE (2008) Landsat-derived glacier inventory for Jotunheimen, Norway, and deduced glacier changes since the 1930s. *The Cryosphere* 2(2), 131–145. ISSN 1994-0424, doi: [10.5194/tc-2-131-2008](https://doi.org/10.5194/tc-2-131-2008).
- Armstrong TE, Roberts BB and Swithinbank C (1969) *Illustrated Glossary of Snow and Ice*. Cambridge: Scott Polar Research Institute.
- Ballantyne CK (2002) Paraglacial geomorphology. *Quaternary Science Reviews* 21(18), 1935–2017. ISSN 0277-3791, doi: [10.1016/S0277-3791\(02\)00005-7](https://doi.org/10.1016/S0277-3791(02)00005-7).
- Ballu Y (2002) *Drus, Montvers et mer de Glace*. Paris: Hoëbeke edition.
- Barabási AL, Albert R and Schiffer P (1999) The physics of sand castles: maximum angle of stability in wet and dry granular media. *Physica A: Statistical Mechanics and its Applications* 266(1), 366–371, ISSN 0378-4371, doi: [10.1016/S0378-4371\(98\)00618-9](https://doi.org/10.1016/S0378-4371(98)00618-9).
- Beniston M and 24 others (2018) The European mountain cryosphere: a review of its current state, trends, and future challenges. *The Cryosphere* 12(2), 759–794. ISSN 1994-0416, doi: <https://doi.org/10.5194/tc-12-759-2018>.
- Benn DI and Evans DJA (2010) *Glaciers and Glaciation*. London: Hodder Education. ISBN 978-0-340-90579-1.
- Bhutiyani MR (2011) Ice apron. In Singh VP, Singh P and Haritashya UK (eds), *Encyclopedia of Snow, Ice and Glaciers*. Dordrecht: Springer Netherlands, pp. 581–582. ISBN 978-90-481-2642-2.
- Bolch T, Pieczonka T and Benn DI (2011) Multi-decadal mass loss of glaciers in the Everest area (Nepal Himalaya) derived from stereo imagery. *The Cryosphere* 5(2), 349–358. ISSN 1994-0416. doi: <https://doi.org/10.5194/tc-5-349-2011>.
- Braithwaite RJ (1995) Positive degree-day factors for ablation on the Greenland ice sheet studied by energy-balance modelling. *Journal of Glaciology* 41(137), 153–160. ISSN 0022-1430, 1727-5652. doi: [10.3189/S0022143000017846](https://doi.org/10.3189/S0022143000017846).
- Braithwaite RJ and Olesen OB (1989) Calculation of glacier ablation from air temperature, West Greenland. In Oerlemans J ed. *Glacier Fluctuations and Climatic Change, Glaciology and Quaternary Geology*. Dordrecht: Springer Netherlands, pp. 219–233. ISBN 978-94-015-7823-3.
- Byers AC (2007) An assessment of contemporary glacier fluctuations in Nepal's Khumbu Himal using repeat photography. *Himalayan Journal of Sciences* 4(6), 21–26. ISSN 1727-5229. doi: [10.3126/hjs.v4i6.979](https://doi.org/10.3126/hjs.v4i6.979).
- Calov R and Greve R (2005) A semi-analytical solution for the positive degree-day model with stochastic temperature variations. *Journal of Glaciology* 51(172), 173–175. ISSN 0022-1430, 1727-5652. doi: [10.3189/172756505781829601](https://doi.org/10.3189/172756505781829601).
- Caplan-Auerbach S, Gruber S, Molnia BF, Huggel C and Wessels RL (2008) The 2005 Mt. Steller, Alaska, rock-ice avalanche: a large slope failure in cold permafrost. *9th International Conference on Permafrost*, Fairbanks, Alaska, USA, pp. 747–752. doi: [10.5167/uzh-3097](https://doi.org/10.5167/uzh-3097).
- Cogley JG and 10 others (2011) Glossary of glacier mass balance and related terms. *IHP-VII Technical Documents in Hydrology* 86, 965. doi: [info:doi/10.5167/uzh-53475](https://doi.org/10.5167/uzh-53475).
- DeBeer CM and Sharp MJ (2009) Topographic influences on recent changes of very small glaciers in the Monashee Mountains, British Columbia, Canada. *Journal of Glaciology* 55(192), 691–700. ISSN 0022-1430, 1727-5652. doi: [10.3189/002214309789470851](https://doi.org/10.3189/002214309789470851).
- Deline P and 12 others (2015) Chapter 15 – ice loss and slope stability in high-mountain regions. In Shroder JF, Haeberli W and Whiteman C (eds), *Snow and Ice-Related Hazards, Risks and Disasters*. Boston: Academic Press, pp. 521–561. ISBN 978-0-12-394849-6. doi: [10.1016/B978-0-12-394849-6.00015-9](https://doi.org/10.1016/B978-0-12-394849-6.00015-9).
- Deline P, Gardent M, Magnin F and Ravel L (2012) The morphodynamics of the mont blanc massif in a changing cryosphere: a comprehensive review. *Geografiska Annaler: Series A, Physical Geography* 94(2), 265–283. ISSN 0435-3676. doi: [10.1111/j.1468-0459.2012.00467.x](https://doi.org/10.1111/j.1468-0459.2012.00467.x).
- Della-Marta PM, Haylock MR, Luterbacher J and Wanner H (2007) Doubled length of western European summer heat waves since 1880. *Journal of Geophysical Research: Atmospheres* 112(D15). ISSN 2156-2201–11. doi: [10.1029/2007JD008510](https://doi.org/10.1029/2007JD008510).
- Duvillard PA, Ravel L, Marcer M and Schoeneich P (2019) Recent evolution of damage to infrastructure on permafrost in the French Alps. *Regional Environmental Change* 19(5), 1281–1293. ISSN 1436-378X. doi: [10.1007/s10113-019-01465-z](https://doi.org/10.1007/s10113-019-01465-z).
- Dyurgerov MB and Meier MF (2000) Twentieth century climate change: evidence from small glaciers. *Proceedings of the National Academy of Sciences* 97(4), 1406–1411. ISSN 0027-8424, 1091-6490. doi: [10.1073/pnas.97.4.1406](https://doi.org/10.1073/pnas.97.4.1406).
- Evans IS (2006) Local aspect asymmetry of mountain glaciation: a global survey of consistency of favoured directions for glacier numbers and altitudes. *Geomorphology* 73(1), 166–184. ISSN 0169-555X. doi: [10.1016/j.geomorph.2005.07.009](https://doi.org/10.1016/j.geomorph.2005.07.009).
- Faillat J, Funk M and Vincent C (2015) Avalanching glacier instabilities: review on processes and early warning perspectives. *Reviews of Geophysics* 53(2), 203–224. ISSN 1944-9208. doi: <https://doi.org/10.1002/2014RG000466>.
- Fischer L, Kääb A, Huggel C and Noetzi J (2006) Geology, glacier retreat and permafrost degradation as controlling factors of slope instabilities in a high-mountain rock wall: the Monte Rosa east face. *Natural Hazards and Earth System Sciences* 6(5), 761–772. ISSN 1561-8633. doi: <https://doi.org/10.5194/nhess-6-761-2006>.

- Florentine C, Harper J, Fagre D, Moore J and Peitzsch E (2018) Local topography increasingly influences the mass balance of a retreating cirque glacier. *The Cryosphere* 12(6), 2109–2122. ISSN 1994-0416. doi: [10.5194/tc-12-2109-2018](https://doi.org/10.5194/tc-12-2109-2018).
- Förstner W and Wrobel BP (2016) *Photogrammetric Computer Vision, Volume 11 of Geometry and Computing*. Cham: Springer International Publishing. ISBN 978-3-319-11549-8 978-3-319-11550-4. doi: [10.1007/978-3-319-11550-4](https://doi.org/10.1007/978-3-319-11550-4).
- Galibert G (1960) Les processus actuels d'évolution du relief de Haute Montagne dans le massif de Zermatt (Alpes Valaisannes) – Persée. *Bulletin de l'Association de Géographes Français* 290-291, 70–86.
- Galibert G (1964) Mécanique de versant et stabilité des pentes dans les Massifs du Mont Blanc et des Mischabel. *Bulletin de l'Association de Géographes Français* 41(324), 2–23. doi: [10.3406/bagf.1964.5683](https://doi.org/10.3406/bagf.1964.5683).
- Gerbaux M, Genthon C, Etchevers P, Vincent C and Dedieu J (2005) Surface mass balance of glaciers in the French Alps: distributed modeling and sensitivity to climate change. *Journal of Glaciology* 51(175), 561–572.
- Gobiet A and 5 others (2014) 21st Century climate change in the European Alps – a review. *Science of the Total Environment* 493, 1138–1151. ISSN 0048-9697. doi: [10.1016/j.scitotenv.2013.07.050](https://doi.org/10.1016/j.scitotenv.2013.07.050).
- Gratton DJ, Howarth PJ and Marceau DJ (1993) Using Landsat-5 thematic mapper and digital elevation data to determine the net radiation field of a Mountain Glacier. *Remote Sensing of Environment* 43(3), 315–331. ISSN 0034-4257. doi: [10.1016/0034-4257\(93\)90073-7](https://doi.org/10.1016/0034-4257(93)90073-7).
- Gruber S (2012) A global view on permafrost in steep bedrock. Proceedings of the 10th International Conference on Permafrost, Salekhard, Russia. 2012. doi: [10.5167/uzh-68861](https://doi.org/10.5167/uzh-68861).
- Gruber S and Haerberli W (2007) Permafrost in steep bedrock slopes and its temperature-related destabilization following climate change. *Journal of Geophysical Research* 112(F2). ISSN 0148-02271–10. doi: [10.1029/2006JF000547](https://doi.org/10.1029/2006JF000547).
- Gruber S, Hoelzle M and Haerberli W (2004) Permafrost thaw and destabilization of Alpine rock walls in the hot summer of 2003. *Geophysical Research Letters* 31(13). ISSN 1944-80071–4. doi: [10.1029/2004GL020051](https://doi.org/10.1029/2004GL020051).
- Guillet G, Guillet T and Ravanel L (2020) Camera orientation, calibration and inverse perspective with uncertainties: a Bayesian method applied to area estimation from diverse photographs. *ISPRS Journal of Photogrammetry and Remote Sensing* 159, 237–255.
- Hantel M, Maurer C and Mayer D (2012) The snowline climate of the Alps 1961–2010. *Theoretical and Applied Climatology* 110(4), 517–537. ISSN 1434-4483. doi: [10.1007/s00704-012-0688-9](https://doi.org/10.1007/s00704-012-0688-9).
- Hasler A (2011) *Thermal Conditions and Kinematics of Steep Bedrock Permafrost* (PhD). University of Zurich, Faculty of Science, Zurich.
- Hoffman MJ, Fountain AG and Achuff JM (2007) 20th-century Variations in area of cirque glaciers and glacierets, Rocky Mountain National Park, Rocky Mountains, Colorado, USA. *Annals of Glaciology* 46, 349–354. ISSN 0260-3055, 1727-5644. doi: [10.3189/172756407782871233](https://doi.org/10.3189/172756407782871233).
- Hoy A, Hänsel S, Skalak P, Ustrnul Z and Bochniček O (2017) The extreme European summer of 2015 in a long-term perspective. *International Journal of Climatology* 37(2), 943–962. ISSN 1097-0088. doi: [10.1002/joc.4751](https://doi.org/10.1002/joc.4751).
- Huggel C (2009) Recent extreme slope failures in glacial environments: effects of thermal perturbation. *Quaternary Science Reviews* 28(11), 1119–1130. ISSN 0277-3791. doi: [10.1016/j.quascirev.2008.06.007](https://doi.org/10.1016/j.quascirev.2008.06.007).
- Huss M and Fischer M (2016) Sensitivity of very small glaciers in the Swiss Alps to future climate change. *Frontiers in Earth Science* 4. ISSN 2296-64631–15. doi: [10.3389/feart.2016.00034](https://doi.org/10.3389/feart.2016.00034).
- Huss M, Funk M and Ohmura A (2009) Strong alpine glacier melt in the 1940s due to enhanced solar radiation. *Geophysical Research Letters* 36(23), 1–5.
- Institut Géographique National (2019) Remonter le temps. <https://remonter-letemps.ign.fr/>.
- Jouvet G and Huss M (2019) Future retreat of Great Aletsch Glacier. *Journal of Glaciology* 65(253), 869–872.
- Kenner R and 5 others (2011) Investigation of rock and ice loss in a recently deglaciated mountain rock wall using terrestrial laser scanning: Gemsstock, Swiss Alps. *Cold Regions Science and Technology* 67(3), 157–164. ISSN 0165-232X. doi: [10.1016/j.coldregions.2011.04.006](https://doi.org/10.1016/j.coldregions.2011.04.006).
- Klein G, Vitasse Y, Rixen C, Marty C and Rebetez M (2016) Shorter snow cover duration since 1970 in the Swiss Alps due to earlier snowmelt more than to later snow onset. *Climatic Change* 139(3), 637–649. ISSN 1573-1480. doi: [10.1007/s10584-016-1806-y](https://doi.org/10.1007/s10584-016-1806-y).
- Krautblatter M and 5 others (2010) Climate change and enhanced rockfall activity in the European Alps. In *GeoDarmstadt 2010*, 68. *Schriftenreihe Der Deut. Ges. Für Geowissenschaften*, pp. 331–332.
- Krautblatter M and Leith K (2015) Glacier- and permafrost-related slope instabilities. The High-Mountain Cryosphere: Environmental Changes and Human Risks, 147–165. doi: [10.1017/CBO9781107588653.009](https://doi.org/10.1017/CBO9781107588653.009).
- Kuhn M (1995) The mass balance of very small glaciers. *Zeitschrift für Gletscherkunde und Glazialgeologie* 31(1), 171–179.
- Kuroiwa D, Mizuno Y and Takeuchi M (1967) Micromeritical properties of snow. *Physics of Snow and Ice* 1(2), 751–772.
- Leigh JR and 5 others (2019) Identifying and mapping very small (<0.5 km²) mountain glaciers on coarse to high-resolution imagery. *Journal of Glaciology* 65(254), 873–888. doi: [10.1017/jog.2019.50](https://doi.org/10.1017/jog.2019.50).
- Mair R and Kuhn M (1994) Temperature and movement measurements at a bergschrund. *Journal of Glaciology* 40(136), 561–565. ISSN 0022-1430, 1727-5652. doi: [10.3189/S0022143000012442](https://doi.org/10.3189/S0022143000012442).
- Marti R and 11 others (2015) Evolution of Ossoue Glacier (French Pyrenees) since the end of the Little Ice Age. *The Cryosphere* 9(5), 1773–1795. doi: [10.5194/tc-9-1773-2015](https://doi.org/10.5194/tc-9-1773-2015).
- Matthews JA and Briffa KR (2005) The 'little ice age': re-evaluation of an evolving concept. *Geografiska Annaler: Series A, Physical Geography* 87(1), 17–36. ISSN 0435-3676. doi: [10.1111/j.0435-3676.2005.00242.x](https://doi.org/10.1111/j.0435-3676.2005.00242.x).
- McCull ST (2012) Paraglacial rock-slope stability. *Geomorphology* 153–154, 1–16. ISSN 0169-555X. doi: [10.1016/j.geomorph.2012.02.015](https://doi.org/10.1016/j.geomorph.2012.02.015).
- McCull ST and Draebing D (2019) Rock slope instability in the proglacial zone: state of the art. In Heckmann T and Morche D (eds), *Geomorphology of Proglacial Systems: Landform and Sediment Dynamics in Recently Deglaciated Alpine Landscapes, Geography of the Physical Environment*. Cham: Springer International Publishing, pp. 119–141. ISBN 978-3-319-94184-4.
- Meehl GA and Tebaldi C (2004) More intense, more frequent, and longer lasting heat waves in the 21st century. *Science (New York, N.Y.)* 305(5686), 994–997. ISSN 0036-8075, 1095-9203. doi: [10.1126/science.1098704](https://doi.org/10.1126/science.1098704).
- Mercier D and Etienne S (2008) Paraglacial geomorphology: processes and paraglacial context. *Geomorphology* 95(1–2), 1–2. ISSN 0169555X. doi: [10.1016/j.geomorph.2006.07.029](https://doi.org/10.1016/j.geomorph.2006.07.029).
- Mourey J, Marcuzzi M, Ravanel L and Pallandre F (2019) Effects of climate change on high Alpine mountain environments: evolution of mountaineering routes in the Mont Blanc massif (Western Alps) over half a century. *Arctic, Antarctic, and Alpine Research* 51(1), 176–189. ISSN 1523-0430. doi: [10.1080/15230430.2019.1612216](https://doi.org/10.1080/15230430.2019.1612216).
- Noetzi J, Gruber S, Kohl T, Salzmann N and Haerberli W (2007) Three-dimensional distribution and evolution of permafrost temperatures in idealized high-mountain topography. *Journal of Geophysical Research: Earth Surface* 112, 1–15. ISSN 2169-9003. doi: [10.1029/2006JF000545](https://doi.org/10.1029/2006JF000545).
- OpenStreetMap contributors (2019) Planet Dump Retrieved from <https://planet.osm.org>.
- Paul F, Käab A, Maisch M, Kellenberger T and Haerberli W (2004) Rapid disintegration of Alpine glaciers observed with satellite data. *Geophysical Research Letters* 31(21). ISSN 1944-80071–4. doi: [10.1029/2004GL020816](https://doi.org/10.1029/2004GL020816).
- Perla RI (1978) Chapter 22 – failure of snow slopes. In Voight B (ed.), *Developments in Geotechnical Engineering, Volume 14 of Rockslides and Avalanches, 1*. Elsevier, pp. 731–752. doi: [10.1016/B978-0-444-41507-3.50030-1](https://doi.org/10.1016/B978-0-444-41507-3.50030-1).
- Phillips M and 5 others (2017) Rock slope failure in a recently deglaciated permafrost rock wall at Piz Kesch (Eastern Swiss Alps), February 2014. *Earth Surface Processes and Landforms* 42(3), 426–438. ISSN 1096-9837. doi: [10.1002/esp.3992](https://doi.org/10.1002/esp.3992).
- Pohl B and 5 others (2019) Huge decrease of frost frequency in the Mont-Blanc Massif under climate change. *Scientific Reports* 9(1), 1–7. ISSN 2045-2322. doi: [10.1038/s41598-019-41398-5](https://doi.org/10.1038/s41598-019-41398-5).
- Pralong A and Funk M (2006) On the instability of avalanching glaciers. *Journal of Glaciology* 52(176), 31–48. ISSN 0022-1430, 1727-5652. doi: [10.3189/172756506781828980](https://doi.org/10.3189/172756506781828980).
- Rabatel A, Letréguilly A, Dedieu JP and Eckert N (2013) Changes in glacier equilibrium-line altitude in the western Alps from 1984 to 2010: evaluation by remote sensing and modeling of the morpho-topographic and climate controls. *The Cryosphere* 7(5), 1455–1471. ISSN 1994-0416. doi: <https://doi.org/10.5194/tc-7-1455-2013>.
- Radić V and 5 others (2014) Regional and global projections of twenty-first century glacier mass changes in response to climate scenarios from global climate models. *Climate Dynamics* 42(1), 37–58. ISSN 1432-0894. doi: [10.1007/s00382-013-1719-7](https://doi.org/10.1007/s00382-013-1719-7).
- Ravanel L, Deline P, Lambiel C and Vincent C (2013) Instability of a high alpine rock ridge: the Lower Arête Des Cosmiques, Mont Blanc Massif, France. *Geografiska Annaler: Series A, Physical Geography* 95(1), 51–66. ISSN 0435-3676. doi: [10.1111/geoa.12000](https://doi.org/10.1111/geoa.12000).

- Ravel L, Magnin F and Deline P (2017) Impacts of the 2003 and 2015 summer heatwaves on permafrost-affected rock-walls in the Mont Blanc massif. *Science of the Total Environment* **609**, 132–143. ISSN 0048-9697. doi: [10.1016/j.scitotenv.2017.07.055](https://doi.org/10.1016/j.scitotenv.2017.07.055).
- Reeh N (1991) Parameterization of melt rate and surface temperature in the Greenland ice sheet. *Polarforschung* **59**(3), 113–128.
- Revellet M, Vincent C, Six D and Rabatel A (2017) Which empirical model is best suited to simulate glacier mass balances? *Journal of Glaciology* **63** (237), 39–54.
- Serrano E, González-trueba JJ, Sanjosé JJ and Del río LM (2011) Ice patch origin, evolution and dynamics in a temperate high mountain environment: the jou negro, picos de europa (nw Spain). *Geografiska Annaler: Series A, Physical Geography* **93**(2), 57–70. ISSN 0435-3676. doi: [10.1111/j.1468-0459.2011.00006.x](https://doi.org/10.1111/j.1468-0459.2011.00006.x).
- Shahgedanova M, Nosenko G, Bushueva I and Ivanov M (2012) Changes in area and geodetic mass balance of small glaciers, Polar Urals, Russia, 1950–2008. *Journal of Glaciology* **58**(211), 953–964. ISSN 0022-1430, 1727-5652. doi: [10.3189/2012JoG11J233](https://doi.org/10.3189/2012JoG11J233).
- Slaymaker O (2009) Proglacial, periglacial or paraglacial? *Geological Society, London, Special Publications* **320**(1), 71–84. ISSN 0305-8719, 2041-4927. doi: [10.1144/SP320.6](https://doi.org/10.1144/SP320.6).
- Stoffel M and Huggel C (2012) Effects of climate change on mass movements in mountain environments. *Progress in Physical Geography: Earth and Environment* **36**(3), 421–439. ISSN 0309-1333. doi: [10.1177/0309133312441010](https://doi.org/10.1177/0309133312441010).
- Thibert E, Dkengne Sielenou P, Vionnet V, Eckert N and Vincent C (2018) Causes of glacier melt extremes in the Alps since 1949. *Geophysical Research Letters* **45**(2), 817–825.
- Triglav-Cekada M and Gabrovce M (2013) Documentation of Triglav glacier, Slovenia, using non-metric panoramic images. *Annals of Glaciology* **54**(62), 80–86. ISSN 0260-3055, 1727-5644. doi: [10.3189/2013AoG62A095](https://doi.org/10.3189/2013AoG62A095).
- Vincent C and Vallon M (1997) Meteorological controls on glacier mass balance: empirical relations suggested by measurements on glacier de Sarennes, France. *Journal of Glaciology* **43**(143), 131–137. ISSN 0022-1430, 1727-5652. doi: [10.3189/S0022143000002896](https://doi.org/10.3189/S0022143000002896).
- Vionnet V and 7 others (2014) Simulation of wind-induced snow transport and sublimation in alpine terrain using a fully coupled snowpack/atmosphere model. *The Cryosphere* **8**, 395–415. doi: [10.5194/tc-8-395-2014](https://doi.org/10.5194/tc-8-395-2014).
- Wiesmann S and 5 others (2012) Reconstructing historic glacier states based on terrestrial oblique photographs. Proceedings of the AutoCarto International Symposium on Automated Cartography, Columbus, OH, USA. Vol. 1618. 14.
- Zekollari H, Huss M and Farinotti D (2019) Modelling the future evolution of glaciers in the European Alps under the EURO-CORDEX RCM ensemble. *The Cryosphere* **13**(4), 1125–1146. ISSN 1994-0416. doi: <https://doi.org/10.5194/tc-13-1125-2019>.
- Zemp M and 38 others (2015) Historically unprecedented global glacier decline in the early 21st century. *Journal of Glaciology* **61**(228), 745–762. ISSN 0022-1430, 1727-5652. doi: [10.3189/2015JoG15J017](https://doi.org/10.3189/2015JoG15J017).

Appendix

Table A1. Table of aerial IGN photographs used in this study

North face of Tour Ronde	Mission ID	Picture number	Scale	Date taken
	C3528-0051-1952-F3630-3631-0019	19	1/23 628	27/07/1952
	C3530-0081-1959-FR166-0058	58	1/26 151	09/09/1959
	C3531-0061-1966-F3531-0013	13	1/19 924	08/09/1966
	C0600-0311-1979-FR7031-0147	147	1/43 646	18/07/1979
	C3428-0021-1984-IFN74-0574	574	1/19 856	09/07/1984
	C3529-0011-1988-FD74-0048	48	1/32 403	26/07/1988
	C93SAA0881-1993-FD7-0419	419	1/33 249	11/08/1993
	CN 95000014-1995-IFN74-IRC-1398	1398	1/21 252	20/07/1995
	CA00S00931-2000-FD01-74-1250	1250	1/31 024	01/08/2000
	CP04000702-2004-fd74-c-20000-2559	2559	1/21 631	18/07/2004
North face of Grandes Jorasses	–	–	–	–
	C3528-0051-1952-F3630-3631-0049	49	1/35 184	27/07/1952
	C3630-0031-1958-FR120-0009	9	1/26 151	31/07/1958
	C3531-0061-1966-F3531-0018	18	1/24 496	08/09/1966
	C3531-0031-1979-F3531-3631-0113	113	1/43 646	05/09/1979
	C3428-0021-1984-IFN74-0630	630	1/19 856	09/07/1984
	C3529-0011-1988-FD74-0036	36	1/33 191	26/07/1988
	C93SAA0881-1993-FD7-0419	419	1/33 249	11/08/1993
	CP 04000702-2004-fd74-c-20000-1658	1658	1/16 112	30/06/2004
Triangle du Tacul	–	–	–	–
	C3630-0141-1939-F3630-3631-0022	22	1/17 693	23/06/1939
	C3630-0121-1949-F3630-3631-0091	91	1/31 938	04/09/1949
	C3530-0081-1959-FR166-0058	58	1/26 151	09/09/1959
	C3531-0031-1979-F3531-3631-0018	18	1/18 386	05/09/1979
	C3428-0021-1984-IFN74-0575	575	1/20 274	09/07/1984
	C3529-0011-1988-FD74-0185	185	1/25 258	26/07/1988
	C93SAA0881-1993-FD74-0480	480	1/26 663	18/08/1993
Grands Charmoz	–	–	–	–
	C3630-0011-1967-F3630-0057	57	1/22 983	08/08/1967
	C4256-0011-1970-F3630-0025	25	1/30 487	15/09/1970
	C0600-0321-1979-FR7032-0091	91	1/47 578	17/07/1979
	C3529-0011-1988-FD74-0228	228	1/27 312	26/07/1988
	C93SAA0881-1993-FD74-0491	491	1/30 549	18/08/1993
	CA02S 00 032-2001-fd0073-250-c-3727	3727	1/19 854	12/08/2001
	CP12000122-FD74x00063-02273	2273	17 cm	08/08/2012

Table A2. Table of terrestrial oblique photographs used in this study

North face of Tour Ronde	Source	Picture/scan res.	Date taken
	Bisson Frères	943 × 625 px	1880
	Authors	7290 × 5325 px	2012
	Authors	1431 × 805 px	2016
	Authors	1500 × 1000 px	2018
North face of Grandes Jorasses	–	–	–
	Bisson Frères	1239 × 673 px	1854
	Unknown	800 × 800 px	1902
	Authors	1000 × 665 px	30/06/ 2012
	Authors	800 × 600 px	2014
	Authors	800 × 600 px	06/09/ 2016
Triangle du Tacul	–	–	–
	Relatives	4620 × 4643 px	2004
	Relatives	3008 × 2000 px	2007
	Authors	2731 × 2048 px	03/09/ 2014
	Authors	1290 × 1080 px	2016
	Cie. du Mont-Blanc	1810 × 750 px	10/09/ 2018
Grands Charmoz	–	–	–
	Unknown	1500 × 1136 px	1900
	Unknown	1685 × 1097 px	1920
	Unknown	994 × 604 px	1948
	Authors	1500 × 1125 px	28/07/ 2010
	Authors	5472 × 3648 px	08/08/ 2015
	Authors	3200 × 4232 px	09/2017