



Enhanced C₂H₂ Absorption Within Jupiter's Southern Auroral Oval From Juno UVS Observations

Rohini Giles, Vincent Hue, Thomas Greathouse, G. Randall Gladstone, Joshua Kammer, Maarten Versteeg, Bertrand Bonfond, Denis Grodent, Jean-claude Gérard, James Sinclair, et al.

► To cite this version:

Rohini Giles, Vincent Hue, Thomas Greathouse, G. Randall Gladstone, Joshua Kammer, et al.. Enhanced C₂H₂ Absorption Within Jupiter's Southern Auroral Oval From Juno UVS Observations. Journal of Geophysical Research. Planets, 2023, 128 (2), 10.1029/2022JE007610 . hal-04505857

HAL Id: hal-04505857

<https://hal.science/hal-04505857>

Submitted on 24 Mar 2024

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

JGR Planets

RESEARCH ARTICLE

10.1029/2022JE007610

Key Points:

- Ultraviolet reflected sunlight observations from Juno Ultraviolet Spectrograph were used to study the distribution of C_2H_2 at Jupiter's south pole
- From the changes in the spectral shape, we infer enhanced C_2H_2 absorption within the southern auroral oval
- Jupiter's atmospheric chemistry at the poles is strongly influenced by the influx of charged auroral particles

Correspondence to:













R. S. Giles,
rgiles@swri.edu

Citation:

Giles, R. S., Hue, V., Greathouse, T. K., Gladstone, G. R., Kammer, J. A., Versteeg, M. H., et al. (2023). Enhanced C_2H_2 absorption within Jupiter's southern auroral oval from Juno UVS observations. *Journal of Geophysical Research: Planets*, 128, e2022JE007610. <https://doi.org/10.1029/2022JE007610>

Received 4 OCT 2022
Accepted 8 FEB 2023

Enhanced C_2H_2 Absorption Within Jupiter's Southern Auroral Oval From Juno UVS Observations

Rohini S. Giles¹ , Vincent Hue^{1,2} , Thomas K. Greathouse¹ , G. Randall Gladstone^{1,3} , Joshua A. Kammer¹ , Maarten H. Versteeg¹ , Bertrand Bonfond⁴ , Denis C. Grodent⁴ , Jean-Claude Gérard⁴ , James A. Sinclair⁵ , Scott J. Bolton¹ , and Steven M. Levin⁵ 

¹Space Science and Engineering Division, Southwest Research Institute, San Antonio, TX, USA, ²Aix-Marseille Université, CNRS, CNES, Institut Origines, LAM, Marseille, France, ³Department of Physics and Astronomy, University of Texas at San Antonio, San Antonio, TX, USA, ⁴Laboratoire de Physique Atmosphérique et Planétaire, STAR Institute, Université de Liège, Liège, Belgium, ⁵Jet Propulsion Laboratory, Pasadena, CA, USA

Abstract Reflected sunlight observations from the Ultraviolet Spectrograph (UVS) on the Juno spacecraft were used to study the distribution of acetylene (C_2H_2) at Jupiter's south pole. We find that the shape of the C_2H_2 absorption feature varies significantly across the polar region, and this can be used to infer spatial variability in the C_2H_2 abundance. There is a localized region of enhanced C_2H_2 absorption which coincides with the location of Jupiter's southern polar aurora; the C_2H_2 abundance poleward of the auroral oval is a factor of 3 higher than adjacent quiescent, non-auroral longitudes. This builds on previous infrared studies, which found enhanced C_2H_2 abundances within the northern auroral oval. This suggests that Jupiter's upper-atmosphere chemistry is being strongly influenced by the influx of charged auroral particles and demonstrates the necessity of developing ion-neutral photochemical models of Jupiter's polar regions.

Plain Language Summary The Ultraviolet Spectrograph on the Juno mission to Jupiter measures ultraviolet sunlight that is reflected from the planet's upper atmosphere and these observations can be used to measure the abundances of different gases in the stratosphere. In this paper, we study the spatial distribution of the molecule acetylene at Jupiter's south pole. We find that there is a significant increase in the acetylene abundance at the location of Jupiter's southern aurora. This suggests that the charged particles that travel along magnetic field lines toward Jupiter's poles and produce bright auroral emission also have a strong influence on the chemistry of Jupiter's upper atmosphere.

1. Introduction

Jupiter's strong magnetic field gives rise to the brightest and most energetic auroras in the solar system. These auroras comprise main auroral emissions, which form a distorted and often discontinuous oval around the magnetic pole; complex polar emissions within the auroral ovals; and diffuse equatorward emissions, including the auroral satellite footprints (Grodent, 2015).

Auroral processes lead to localized heating of the atmosphere within the auroral regions (Caldwell et al., 1980; Drossart et al., 1993; Sinclair et al., 2017) and may also be responsible for the high upper atmosphere temperatures across the entire planet (O'Donoghue et al., 2021; Waite et al., 1983). Several previous studies have also suggested that the precipitation of high-energy charged particles may lead to the modification of Jupiter's stratospheric chemistry in the auroral regions. Using infrared observations from the Voyager IRIS, S. J. Kim et al. (1985) observed enhanced emission from a range of hydrocarbons, including C_2H_2 , C_2H_4 , and C_2H_6 , within Jupiter's northern auroral oval. They concluded that the enhanced emission was due to increased abundances of these species, although in the infrared spectral region they focus on, there is a significant degeneracy between chemical abundances and stratospheric temperatures. Drossart et al. (1986) obtained ground-based mid-infrared observations of Jupiter and similarly observed a C_2H_2 emission hot-spot that coincided with the northern aurora, which they noted could be caused either by an enhancement in the C_2H_2 abundance or an alteration in the thermal profile.

More recently, Sinclair et al. (2017, 2018, 2019) have sought to break the degeneracy between chemistry and temperature in order to map the distribution of hydrocarbons in Jupiter's polar regions. Sinclair et al. (2017) used a radiative transfer model to simultaneously constrain the temperature profile and chemical abundances

using Voyager IRIS and Cassini CIRS infrared observations. Sinclair et al. (2018) performed a similar analysis using high spectral resolution mid-infrared observations obtained from a ground-based telescope, making use of a two-step retrieval process that first used CH_4 and $\text{H}_2\text{S}(1)$ emission to constrain the temperature and then retrieved the hydrocarbon abundances. These studies found that C_2H_2 and C_2H_4 are enhanced within Jupiter's northern auroral oval and Sinclair et al. (2017) suggested that the precipitation of charged particles leads to an increase in ion-neutral and electron recombination reactions which, by analogy with Titan's hydrocarbon chemistry, would favor the production of unsaturated hydrocarbons, including C_2H_2 (De La Haye et al., 2008). Sinclair et al. (2019) extended this analysis to study additional hydrocarbons and found that C_2H_4 , $\text{CH}_3\text{C}_2\text{H}$, and C_6H_6 are also enhanced within the auroral region.

In this paper, we build on these previous studies by using ultraviolet reflected sunlight observations from the Ultraviolet Spectrograph (UVS) on the Juno mission to study the distribution of C_2H_2 in Jupiter's polar regions. C_2H_2 is the hydrocarbon with the strongest spectral signature in the reflected sunlight portion of the UVS spectrum and ultraviolet observations have the advantage of being insensitive to the thermal structure, and therefore complement the earlier infrared studies. The polar orbit of the Juno spacecraft provides a unique viewpoint of Jupiter's auroral regions, particularly the southern aurora, which cannot be easily seen from Earth or from equatorial-orbit spacecraft. In Section 3, we present reflectance maps of Jupiter's poles and show how the shape of the reflectance spectra varies across the polar region. By comparing reflectance maps made at different wavelength intervals, we can infer the C_2H_2 distribution and we discuss how these results are impacted by uncertainty in the haze opacity and C_6H_6 abundance. In Section 4, we compare the proxy C_2H_2 abundance maps with previous results obtained using infrared observations and discuss the possible mechanisms that drive the C_2H_2 distribution.

2. Juno UVS Observations

UVS (Gladstone et al., 2017) is a far-ultraviolet imaging spectrograph on NASA's Juno mission, which has been in a highly elliptical polar orbit around Jupiter since July 2016 (Bolton et al., 2017). UVS covers the 68–210 nm spectral range with a spectral resolution that varies between 1.3 and 3.0 nm depending on the position along the instrument's slit (Greathouse et al., 2013). The primary scientific goal of the UVS instrument is to characterize Jupiter's far-ultraviolet auroral emissions and this spectral range was selected to include the H Lyman series and the Lyman, Werner, and Rydberg band systems of H_2 . However, the longer wavelengths covered by UVS extend into a spectral region that is dominated by reflected sunlight and this part of the spectrum is sensitive to hydrocarbons and aerosols (Gladstone et al., 2017). In this paper, we focus on the 175–205 nm reflected sunlight segment of the UVS spectrum.

Juno is a spin-stabilized spacecraft with a rotation period of ~ 30 s. The UVS instrument slit is nominally parallel to the spacecraft's spin axis, allowing the slit to sweep across a swath of planet as the spacecraft rotates. In this paper, we exclusively use data from the wide part of the dog-bone-shaped slit, as it has a better signal-to-noise ratio, particularly at the longer wavelengths where the instrument detector is less sensitive (Hue et al., 2019, 2021). UVS data are recorded in a pixel-list time-tagged format; by considering the position along the slit and the spin phase of the spacecraft at the time of observation, each photon can be assigned to a latitude and longitude on the planet. This geometric information can then be used to produce spatial maps of the ultraviolet radiation (Gladstone et al., 2017). In-flight radiometric calibration is achieved by observation of UV-bright O, B, and A stars (Hue et al., 2019), and radiances can be converted to reflectances by dividing by the solar spectrum (Woods et al., 2009), corrected for the solar incidence angle.

UVS obtains observations of Jupiter for several hours on either side of each perijove (the point of closest approach for the spacecraft), covering both the approach over Jupiter's north pole and the subsequent departure over the south pole. When the spacecraft passes through Jupiter's radiation belts, the UVS instrument records high background noise from high energy electrons and ions. Data acquisition is therefore temporarily paused to protect the instrument from enhanced degradation (Kammer et al., 2019) and to limit the volume of low-quality noisy data. Due to the precession of the Juno orbit over the course of the mission, the location of the perijove has gradually moved northwards over time, which has moved the approach observations further into the radiation belts. This means that the amount of UVS data obtained from the northern polar region has decreased over time (Gladstone et al., 2019) and when we co-add reflected sunlight data from many perijoves, as described in Section 3.2, the signal-to-noise ratio and spatial coverage is significantly better for the south pole.




Figure 1. Absorption spectra for six molecules with significant absorption in the 140–205 nm spectral range. Transmission is defined as the transmission between an altitude of 100 km (5 mbar) and the top of the atmosphere. The absorption cross-sections have been smoothed to match the spectral resolution of the Ultraviolet Spectrograph-wide slit. Two abundances are shown for C_6H_6 : the a priori value (solid line) and 8× the a priori value (dashed line).

3. Analysis and Results

3.1. Molecular Absorption

Figure 1 shows the absorption spectrum for C_2H_2 , as well as five other molecular species in Jupiter's stratosphere that produce non-negligible absorption in the 140–205 nm spectral range. Transmission is defined as the transmission between an altitude of 100 km (5 mbar) and the top of the atmosphere. The column density for each gas was calculated using the atmospheric composition model described by Model C in Moses et al. (2005), with the exception of C_6H_6 . As noted in Sinclair et al. (2019), the peak of the C_6H_6 distribution is likely to be higher in the atmosphere than predicted in Moses et al. (2005) due to additional ion sources. We therefore follow a similar approach to Sinclair et al. (2019) and use an a priori vertical profile for C_6H_6 that is 0.1% of the a priori vertical profile for C_2H_2 ; this C_6H_6 a priori vertical profile matches the Moses et al. (2005) Model C C_6H_6 profile at 3–5 mbar but has significantly higher densities at higher altitudes. Absorption cross-sections were obtained from Keller-Rudek et al. (2013) and were smoothed to match the 2.2 nm spectral resolution of the UVS-wide slit.

Figure 1 shows that while there are multiple highly absorbing species at <160 nm, C_2H_2 and C_6H_6 are the only species with non-negligible absorption at >175 nm. C_2H_2 has a broad absorption feature that has a local maximum at ~172 nm, while C_6H_6 has a narrower feature that peaks at ~179 nm. The solid purple line shows the absorption produced by the a priori C_6H_6 distribution, which is considerably weaker than the C_2H_2 absorption. However, the C_6H_6 abundance is highly uncertain, and Sinclair et al. (2019) showed that within the northern auroral oval the abundance can be as high as 0.8% of the C_2H_2 abundance, a factor of 8 higher than our a priori. The transmission curve for this higher value is shown by the dashed purple line in Figure 1, showing that C_6H_6 can also have a significant impact on the shape of Jupiter's 175–205 nm spectrum and must therefore be considered in the following analysis.

3.2. Reflectance Maps

Figure 2 shows reflectance maps of Jupiter's southern and northern polar regions at wavelengths of 175–190 nm. As described in Section 2, Juno UVS observations were converted from radiance to reflectance by correcting for the solar incidence angle and dividing by the solar spectrum (Woods et al., 2009). The maps shown in Figure 2 combine all dayside (local time of 8 a.m. to 4 p.m., solar zenith angle less than 85°) data obtained during the first 46 perijoves of the Juno mission (July 2016–November 2022). The maps comprise observations made at a range of different spacecraft positions spanning radial distances of 1.3–9.7 R_J .

Because of the precession of the spacecraft orbit, the southern hemisphere (Figures 2a and 2b) has significantly better spatial coverage and signal-to-noise ratios than the northern hemisphere (Figures 2c and 2d). The higher noise level means that some “striping” is visible in the northern data. Figures in the right column are identical to figures in the left column but have a different grayscale stretch to highlight different morphologies. The average locations of the expanded and contracted auroral ovals (Bonfond et al., 2017) are shown in red.

The wavelength range of 175–190 nm was chosen because this is a spectral region that is sensitive to absorption by C_2H_2 , as shown in Figure 1. While slightly shorter wavelengths would be even more sensitive (C_2H_2 has a local absorption maximum at ~172 nm), shorter wavelengths are also increasingly sensitive to H_2 auroral emissions that peak near 160 nm and lead to misleadingly high reflectances along the auroral ovals; 175–190 nm represents a spectral region that is sensitive to C_2H_2 while minimizing the contamination from the auroral emission.

Figure 2a shows that the reflectance at all longitudes decreases toward the south pole. This is a well-known phenomenon and is caused by the presence of stratospheric hazes at both poles; these hazes lead to a distinctive appearance in both the infrared and the ultraviolet (West et al., 2004). In the infrared, there is a bright “polar hood” in methane-band observations due to the fact that the stratospheric haze particles scatter light before it has the chance to be absorbed by methane. In contrast, the UV polar hood is dark, as seen in Figure 2a, because the haze particles are less reflective than the Rayleigh-scattering molecular atmosphere.




Figure 2. Ultraviolet reflectance maps of Jupiter's south pole (a and b) and north pole (c and d). The figures show the mean reflectance in the 175–190 nm spectral range, which is sensitive to C_2H_2 absorption. Panels (b and d) show the same data as panels (a and c), but have a different grayscale stretch to highlight different morphologies. The average locations of the expanded and contracted auroral ovals (Bonfond et al., 2017) are shown in red.

Although the entire polar region in Figure 2a is relatively dark, the segment within the southern auroral oval (marked by the red lines) is darker than the adjacent longitudes. This can be seen more clearly in Figure 2b, which presents the same data as Figure 2a but with a different grayscale stretch to highlight morphology within the darkest regions. There is a distinct dark patch which aligns closely with the location of the auroral oval; the reflectance within the auroral oval is 0.02, while the mean reflectance at similar latitudes outside the oval is 0.05. A similar effect can be seen at the north pole, as shown in Figures 2c and 2d. These observations are noisier and have decreased coverage, but the same approximate trend can be seen; the region within the auroral oval has an even lower reflectance than the rest of the pole. These observations could be due to an increase in the haze concentration within the auroral ovals, which would lead to a local enhancement of the effect that causes the broader polar hood. Alternatively, it could be due to an increase in the C_2H_2 and/or C_6H_6 abundances, both of which would lead to increased absorption at 175–190 nm and therefore lower reflectance. In order to distinguish between these scenarios, we consider the full UVS spectra in Section 3.3.




Figure 3. Comparison of ultraviolet spectra from the polar auroral and quiescent regions of Jupiter's southern pole. The polar auroral region is defined as within the contracted auroral oval and the polar quiescent region is defined as outside the expanded auroral oval but poleward of 67.2°S . Panels (a) and (b) show dayside spectra from the two regions (black) alongside a pure auroral emission spectrum (red). Panels (c) and (d) show the reflectance spectra from the two regions once the auroral emission component has been removed; the spectral range dominated by the auroral emission is shaded out. Panel (e) shows the ratio of the two spectra shown in panels (c) and (d). The wavelength range where an absorption feature is present is highlighted by the arrows.

3.3. Spectra

To further explore how the UV reflectance varies across the polar region, we now consider the full UVS spectra. In order to obtain a sufficient signal-to-noise ratio, we focus solely on the southern polar region and co-add data to produce two representative spectra: (a) the polar auroral region, defined as within the contracted auroral oval, and (b) the polar quiescent region, defined as outside the expanded auroral oval, but still poleward of 67.2°S (the most-equatorward point of the expanded oval). In both cases, the data is limited to local times of 8 a.m. to 4 p.m. and is corrected for the solar incidence angle, as in Figure 2.

The representative spectra from inside and outside the southern auroral oval are shown in black in Figures 3a and 3b, respectively. Because these spectra are obtained from the dayside of the planet in a spatial region with significant auroral emission, they consist of a combination of reflected sunlight and auroral emission. At longer wavelengths ($>175\text{ nm}$), the reflected sunlight component dominates, and at shorter wavelengths ($<165\text{ nm}$), the auroral emission dominates. The spectrum from the polar “quiescent” region still has a strong auroral emission component due to the diffuse equatorward emissions from the regions closest to the auroral oval.




Figure 4. (a) Synthetic reflectance spectra of Jupiter assuming a solar incidence angle of 80° and haze-free atmosphere. The spectrum without either C_2H_2 or C_6H_6 is shown in black, the spectrum with the nominal C_2H_2 abundance is shown in red and the spectrum with the nominal C_6H_6 abundance is shown in blue. The two spectral regions used to calculate the reflectance ratio in panels (b and c) are shown by the arrows. (b) The relationship between the C_2H_2 scaling factor relative to the nominal vertical profile and the reflectance ratio for four different cloud models. (c) The relationship between the C_6H_6 scaling factor relative to the nominal vertical profile and the reflectance ratio for four different cloud models.

abundance) is included. Both species can clearly have an impact on the ratio between the mean reflectance at 175–190 nm and the mean reflectance at 190–205 nm; the ratio with no C_2H_2 or C_6H_6 is 1.00, the ratio with C_2H_2 alone is 0.52 and the ratio with the C_6H_6 alone is 0.89.

Similar reflectance spectra were generated for a range of C_2H_2 vertical profiles, each consisting of the nominal vertical profile multiplied by a scaling factor between 0 and 3. For each C_2H_2 scaling factor, the ratio between the mean reflectance at 175–190 nm and the mean reflectance at 190–205 nm was measured. The relationship

In order to obtain a spectrum that consists of purely reflected sunlight, we first obtained a pure auroral spectrum by coadding polar data obtained during the night. This pure auroral spectrum is shown in red in Figures 3a and 3b, and in each case, has been scaled to match the average radiance of the dayside spectrum at 157–160 nm. By subtracting these auroral spectra from the dayside spectra, and then dividing by the solar spectrum, we were able to produce the “clean” reflectance spectra shown in Figures 3c and 3d.

Figures 3c and 3d have noticeably different spectral shapes. Figure 3c, the reflectance spectrum from the polar auroral region, has a steep slope between 175 and 195 nm, while Figure 3d, the spectrum from the quiescent region, is significantly flatter. Figure 3e further compares the two reflectance spectra by showing the ratio of the polar auroral region to the quiescent region. At 195–205 nm, the relative reflectance from the polar auroral region is relatively constant and $\sim 50\%$ of the reflectance at quiescent longitudes. This then decreases to $\sim 20\%$ by 175 nm before increasing again at shorter wavelengths. The shape shown in Figure 3e is very similar to the shape of the C_2H_2 absorption feature shown in Figure 1, and is also consistent with the presence of C_6H_6 . This suggests that the decreased reflectance at 175–190 nm in the polar auroral region is at least partially driven by an increase in these hydrocarbons.

3.4. Proxy C_2H_2 and C_6H_6 Abundance Maps

In Giles et al. (2021), we used a radiative transfer and retrieval algorithm to model Juno UVS reflected sunlight spectra from Jupiter's low- and mid-latitudes in order to retrieve the zonally averaged C_2H_2 abundances. Ideally, we would perform a similar analysis for the polar region, in order to produce spatially resolved C_2H_2 maps and to determine the extent to which any variability in the C_6H_6 abundance may affect these results. However, the high solar incidence angle at the poles means that the signal-to-noise ratios of the reflected sunlight spectra are significantly lower than they were at low latitudes, and this is compounded by the fact that we are interested in spatial variability on relatively small scales and therefore cannot co-add large spatial regions to reduce the noise. Instead, we can use the ratio between the reflectance at 175–190 nm and the reflectance at 190–205 nm as a proxy for the C_2H_2 and C_6H_6 abundances.

Figure 4a shows three synthetic reflectance spectra generated using the NEMESIS radiative transfer code (Irwin et al., 2008) and smoothed to match the spectral resolution of Juno UVS. The adaptation of NEMESIS for use in the UV spectral region is described in Melin et al. (2020) and Giles et al. (2021). As described in Section 3.1, we use the Model C atmosphere from Moses et al. (2005) as the nominal atmospheric model for Jupiter. The black line in Figure 4a shows the reflectance spectrum of Jupiter if C_2H_2 and C_6H_6 are removed from the atmosphere, in the absence of any hazes and assuming a solar incidence angle of 80° . The red line shows how the spectrum changes when the nominal C_2H_2 abundance is included and the blue line shows the spectrum when the nominal C_6H_6 abundance (0.1% of the C_2H_2

between the C_2H_2 scaling factor and the reflectance ratio is shown by the black curve in Figure 4b; as the C_2H_2 abundance increases, the reflectance at 175–190 nm decreases relative to the reflectance at 190–205 nm and thus the reflectance ratio decreases.

The presence of polar hazes can impact the spectral shape. Jupiter's polar hazes are thought to include a range of particle sizes, with mean radii of approximately 0.09–1.1 μm (Wong et al., 2003). This distribution of particle sizes leads to absorption that is expected to be approximately spectrally flat over the 165–205 nm wavelength range. However, even a spectrally flat haze can affect the shape of the spectrum if it is located within the altitude region of peak sensitivity; as discussed in Giles et al. (2021), the longer wavelength end of the UVS spectrum probes deeper into the atmosphere and therefore can be more impacted by the presence of haze, leading to a tilt in the spectrum and increasing the reflectance ratio.

This can be seen by the colored lines in Figure 4b, which show the C_2H_2 –reflectance ratio curves for the three different haze models used in Giles et al. (2021): a compact layer at 10 μbar , a compact layer at 5 mbar and an extended haze with constant density in the 100–1 mbar range, based on Wong et al. (2003). In each case, the optical thickness of the haze layer was scaled to match the optical thickness retrieved at a latitude of 75°S in Giles et al. (2021). For a given C_2H_2 abundance, the presence of haze acts to increase the reflectance ratio of the synthetic spectrum and for a given observed reflectance ratio, the black no-haze curve shows the corresponding minimum C_2H_2 scaling factor. However, despite the quantitative differences, the results from all four models shown in Figure 4b are qualitatively similar, showing that as the C_2H_2 scaling factor increases, the reflectance ratio decreases.

The same method was used to study the effect of varying the C_6H_6 abundance on the reflectance ratio. Figure 4c shows the relationship between the C_6H_6 scaling factor and the reflectance ratio for each of the same four haze models. We present a larger range of scaling factors for C_6H_6 (0–50) than we did for C_2H_2 (0–3) for two reasons: first, the a priori C_6H_6 abundance is not well constrained, and second, a much higher scaling factor is required to significantly decrease the reflectance ratio. Figure 4c shows that a scaling factor of 8, which is the abundance found by Sinclair et al. (2019) at Jupiter's northern auroral oval, produces a reflectance ratio of 0.88 using the most realistic extended haze model. The reflectance ratio begins to level off beyond this, and even a scaling factor of 50 can only achieve a reflectance ratio of 0.73. Continuing to increase the C_6H_6 abundance even further ultimately increases the reflectance ratio instead, as the small C_6H_6 absorption features at ~ 200 nm begin to have a greater effect; for the extended haze model, the minimum reflectance ratio that can be achieved using C_6H_6 alone is 0.61, with a scaling factor of 225 \times the nominal value. This shows that while C_6H_6 does influence the reflectance spectrum 175–205 nm, C_2H_2 absorption must be primarily responsible for any regions of the planet with very low reflectance ratios.

Figures 5a and 5b show reflectance ratio maps of Jupiter's north and south poles. The 175–190 nm reflectance maps shown in Figure 2 were divided by equivalent maps covering the 190–205 nm spectral range. As expected from Figure 3, Figure 5a shows that there is a region of low reflectance ratio which coincides with the polar aurora within the southern auroral oval. This low reflectance ratio within the auroral oval is markedly different from the adjacent, quiescent longitudes. Figure 5b shows a hint of a similar trend, with a lower reflectance ratio within the northern auroral oval, but the decreased spatial coverage and noisier data make this less clear-cut.

Figure 5c shows the southern reflectance ratio map converted into a C_2H_2 scaling factor in the absence of C_6H_6 . For each latitude, we use the appropriate haze opacity retrieved in Giles et al. (2021) using the extended haze model. The haze retrievals do not extend beyond $\pm 75^\circ$, so poleward of this latitude, a constant haze opacity is assumed. For these polar latitudes, the conversion relationship between reflectance ratio and C_2H_2 scaling factor is shown by the orange line in Figure 4b; for regions of the planet equatorward of $\pm 75^\circ$, the conversion relationship falls between the orange line and black, haze-free line. As expected from Giles et al. (2021), Figure 5c shows that outside the auroral region, the C_2H_2 abundance decreases toward higher latitudes. In the polar auroral region, however, this trend is reversed. Figure 5c shows that the low reflectance within the auroral oval can be explained by a significant enhancement in the C_2H_2 abundance; the mean C_2H_2 scaling factor for the polar auroral region within the auroral oval is 2.5 compared to 0.8 at comparable latitudes outside the auroral oval. Just as the northern auroral oval showed a hint of the same reflectance ratio trend as the southern auroral oval (Figures 5a and 5b), the northern auroral oval also shows a hint of this same C_2H_2 enhancement (Figure 5d) but the noisy data prevents any firm conclusions from being drawn.




Figure 5. (a and b) The ratio of the mean reflectance at 175–190 nm to the mean reflectance at 190–205 nm for Jupiter's south and north poles. (c and d) Proxy C_2H_2 abundance maps assuming no C_6H_6 absorption. (e and f) Proxy C_6H_6 abundance maps assuming no C_2H_2 absorption. The average locations of the expanded and contracted auroral ovals (Bonfond et al., 2017) are shown in black.




Figure 6. The combination of C_2H_2 and C_6H_6 scaling factors that are able to reproduce a reflectance ratio of 0.52 is the mean value within the southern auroral oval. The minimum and maximum C_2H_2 scaling factors are marked by the dashed lines.

Figures 5e and 5f shows the reflectance ratio maps converted into C_6H_6 scaling factors instead, in the absence of C_2H_2 . Figure 5e shows that outside the auroral oval, absorption from C_6H_6 is technically able to reproduce the observed reflectance ratios, although it should be noted that we know from the full radiative transfer retrievals in Giles et al. (2021) that the low-latitude spectral shape is actually due to C_2H_2 absorption. However, within the southern auroral oval, there is no amount of C_6H_6 that can reproduce the low reflectance ratios observed, which is why that region of the map in Figure 5e is empty. This can be further seen in Figure 6, which shows the combination of C_2H_2 and C_6H_6 scaling factors that are together able to produce a synthetic spectrum reflectance ratio of 0.52, the mean value within the southern auroral oval. As the C_6H_6 increases, slightly less C_2H_2 is required, but at extremely high levels of C_6H_6 ($>23\times$ the a priori) the corresponding C_2H_2 abundance starts to increase again. For this specific reflectance ratio, the C_2H_2 scaling factor must fall in the 1.8–2.3 range, marked by the dashed lines. Since C_6H_6 is unable to reproduce the low reflectance ratios within Jupiter's southern auroral oval, we can conclude that this effect must be primarily driven by a C_2H_2 enhancement, with any possible enhancement in C_6H_6 decreasing the C_2H_2 abundances by up to 20%.

It should also be noted that there is some error associated with the haze opacity. In Sections 3.2 and 3.3, we noted that the decreased reflectance within the auroral oval could be partially caused by an increase in the haze opacity as well as an increase in the hydrocarbon abundances, but in Figure 5 we assume a constant haze opacity poleward of $\pm 75^\circ$. However, if the hazes were more opaque within the polar auroral region, the contrast in the C_2H_2 scaling factor within the oval relative to the scaling factor at quiescent longitudes would actually be even greater than what is shown in Figures 5c and 5d. Figure 4b shows that when additional hazes are present in a model, an even higher C_2H_2 abundance is required to produce a given reflectance ratio. The presence of additional hazes can therefore only intensify the polar auroral phenomenon shown in Figure 5.

A similar effect exists with respect to the auroral emissions within the polar region. The wavelength interval of 175–190 nm was chosen in order to minimize the contribution of the auroral emissions, which peak at ~ 160 nm (see Figures 3a and 3b). However, the edge of this emission feature may still contribute a small amount of flux, which would act to slightly increase the apparent reflectance within this interval, and therefore increase the ratio of the 175–190 nm reflectance to the 190–205 nm reflectance. Accounting for any such emission component would therefore further decrease the reflectance ratio within and in the immediate vicinity of the auroral ovals, while the reflectance ratio in the quiescent auroral regions would remain the same. Accounting for any residual auroral emission would therefore only act to intensify the polar auroral phenomenon shown in Figure 5.

In summary, we can conclude that the C_2H_2 abundance is significantly enhanced within Jupiter's southern auroral oval. There are three factors that can modify the C_2H_2 scaling factors presented in Figure 4c: the presence of C_6H_6 , the presence of additional hazes and residual auroral emissions. While the first of these can decrease the auroral C_2H_2 abundance by up to $\sim 20\%$, the latter two would both act to actually further increase the auroral C_2H_2 abundance. A similar trend may exist for the northern auroral oval, but the poor spatial coverage and signal-to-noise ratio prevent us from drawing any firm conclusions from the Juno UVS data.

4. Discussion

In Section 3, we showed that the shape of Jupiter's reflectance spectrum varies significantly across the polar regions of the planet, and that this change in shape can be used to infer spatial variability in the C_2H_2 abundance. As described in Giles et al. (2021), the UVS reflected sunlight spectrum is sensitive to the total column abundance down to the 5–50 mbar region, but the C_2H_2 number density peaks at 0.55 mbar (Moses et al., 2005) and it is therefore this part of the atmosphere that has the strongest influence on the spectral shape. In the south pole, the C_2H_2 abundance generally decreases toward higher latitudes, with the exception of the auroral region; within the southern auroral oval, the C_2H_2 abundance is higher than the abundance at low latitudes and is a factor of ~ 3 higher than adjacent quiescent, non-auroral longitudes. It is possible that there is also an enhancement in the C_6H_6

abundance within the auroral ovals, as shown from infrared observations by Sinclair et al. (2019), but the UVS data cannot independently confirm this.


The decrease in the C_2H_2 abundance toward higher latitudes is consistent with previous studies that have performed full radiative transfer retrievals as a function of latitude. Giles et al. (2021) used zonally averaged Juno UVS data to study the latitudinal variability of C_2H_2 and found that the abundance decreased by a factor of 2–4 toward the poles. Similar results were also obtained using infrared observations from the Cassini spacecraft (Nixon et al., 2007) and from ground-based telescopes (Fletcher et al., 2016; Melin et al., 2018).

The enhancement of C_2H_2 within the southern polar auroral region is similar to results from Drossart et al. (1986) and Sinclair et al. (2017, 2018). Drossart et al. (1986) analyzed FPGS data from NASA's Infrared Telescope Facility (IRTF) and found that there was a localized region of strong C_2H_2 emission that coincided with the location of Jupiter's northern auroral oval. They concluded that this could be due to either a thermal anomaly or an enhancement in C_2H_2 . More recently, Sinclair et al. (2017, 2018) used infrared observations from spacecraft and ground-based telescopes to simultaneously retrieve temperatures and hydrocarbon abundances in Jupiter's polar regions. Sinclair et al. (2017) used data from the Voyager IRIS and Cassini CIRS, while Sinclair et al. (2018) performed similar analyses using data from the TEXES spectrograph at the IRTF. All three sets of infrared observations showed an enhancement in the C_2H_2 abundance within the northern auroral oval relative to the quiescent, non-auroral longitudes, although Sinclair et al. (2017, 2018) do note that there is some degeneracy between the thermal profile and the C_2H_2 abundance.



The results presented in this study build upon the previous works in two ways. First, Drossart et al. (1986) and Sinclair et al. (2017, 2018) found C_2H_2 enhancements in the northern polar auroral region, but the southern aurora could not be clearly seen in the observations because the viewing geometry in each case was close to equatorial and the southern auroral oval is restricted to high latitudes. In contrast, Juno UVS has significantly better coverage at the south pole than the north. Second, this study makes use of observations from a completely different spectral region; unlike previous infrared observations, the UV spectra used in this study are not sensitive to the temperature of the atmosphere, so there is no degeneracy between the inferred C_2H_2 abundance and the thermal profile. The striking similarity between the south polar map shown in Figure 5a and the north polar maps presented in Sinclair et al. (2017, 2018) acts to both confirm the latter's results using an independent spectral region and also shows that the same phenomenon exists at both poles.

Stratospheric C_2H_2 is thought to mainly form on Jupiter from photochemical by-products following methane photolysis (e.g., Gladstone et al., 1996). The peak C_2H_2 production regions are 4×10^{-3} mbar and 0.4 mbar, and the freshly formed acetylene then diffuses downward to higher pressure levels (Hue et al., 2018). The decrease in the C_2H_2 abundance from the equator to the poles can be explained by the decrease in the solar insolation at high latitudes, and this observed latitudinal trend agrees with the results of photochemical models (Gladstone et al., 1996; Hue et al., 2018). However, the low solar insolation rates at Jupiter's poles mean that an alternative mechanism is required to explain the high C_2H_2 abundances within the auroral regions that were observed in both this work and in the previous infrared studies. The clear correlation between the location of Jupiter's polar aurora, which are located poleward of the main auroral oval, and the region of enhanced C_2H_2 absorption suggests that the upper-atmosphere chemistry is being modified by the influx of charged auroral particles and the increase in ion-neutral and electron recombination reactions favors the production of C_2H_2 (Sinclair et al., 2017).

The majority of Jovian photochemical models neglect ion-neutral chemistry and while Y. H. Kim and Fox (1994) did study the effect of hydrocarbon ions on the neutral ones, they focus on photoionization from solar extreme ultraviolet photons in the low- and mid-latitudes and make use of chemical networks that have since been updated, including updated reaction rates, additional chemical pathways, and updated branching ratios. In order to explore the exact mechanism by which auroral chemistry may favor C_2H_2 production, we can instead consider an analogy with Titan's hydrocarbon chemistry, as discussed in Sinclair et al. (2017). Several ion-neutral photochemical models of Titan's atmosphere have found that electron precipitation triggers the formation of the key ion CH_3^+ , which in turn leads to the formation of $C_2H_5^+$ (De La Haye et al., 2008; Dobrijevic et al., 2016; Loison et al., 2015). $C_2H_5^+$ can then lead to the formation of C_2H_2 directly, through




or indirectly, by first forming C_2H_4



which is then photolyzed to produce C_2H_2 and H_2 . A similar pathway could lead to the enhanced production of C_2H_2 within Jupiter's auroral regions.

Y. H. Kim and Fox (1994) suggested that C_2H_2 would be easily destroyed in Jupiter's auroral regions due to ion chemistry, due to the reaction



In Dobrijevic et al. (2016), the rate used for this reaction was 5% slower than the rate used in Y. H. Kim and Fox (1994), leading to a slightly slower C_2H_2 destruction rate. However, the reaction leading to the formation of CH_3^+ , the main building block of C_2H_5^+ , was taken to be 9% slower in Dobrijevic et al. (2016), which might also decrease the C_2H_2 production rate relative to Y. H. Kim and Fox (1994). While enhanced electron precipitation is a plausible driving mechanism for the enhanced C_2H_2 abundances, the development of an ion-neutral photochemical model of Jupiter's polar regions using the most recent reaction rates is needed in order to reach a firm conclusion.

Both this study and Sinclair et al. (2017, 2018) have shown that the C_2H_2 enhancement at Jupiter's poles is longitudinally restricted to the auroras, instead of being well-mixed across the entire polar region. Jupiter's main auroral regions are encircled by electrojets (Rego et al., 1999), which have speeds of 1–2 kms^{-1} and extend from the sub- μbar level (Chaufray et al., 2011) down to at least the middle stratosphere (Cavalié et al., 2021). One possibility is that these electrojets act as a dynamic barrier to limit the loss of materials produced within the auroras. Alternatively, C_2H_2 may be efficiently transported outside the auroral region into the quiescent region, but once in a location where neutral chemistry dominates, it may be rapidly converted into other chemical species such as C_2H_6 before it can become homogenized across the entire polar region (Sinclair et al., 2017). This latter scenario would also explain the increasing C_2H_6 abundance from the equator to the poles observed by Cassini CIRS (Nixon et al., 2007), which cannot be explained by a combination of neutral photochemistry and dynamics alone (Hue et al., 2018).

In order to obtain sufficient signal-to-noise ratio for this study, we combined observations from the entire Juno mission to date, a period of over 6 years. This means that we are unable to study any temporal variability in the C_2H_2 auroral enhancement. If the C_2H_2 auroral enhancement is caused by the influx of charged particles, we might expect the abundance to vary with time, depending on the strength and size of the auroras, which in turn may vary depending on both solar activity and internal factors within the Jovian system (e.g., Bonfond et al., 2012; Nichols et al., 2017; Yao et al., 2022). The extent to which the C_2H_2 abundance varies with time may provide additional constraints on the chemical lifetimes and transport rates in the auroral region. Future studies may be able to examine the temporal variability of auroral C_2H_2 ; long-term ground-based infrared observations can be used to track the C_2H_2 emissions with time (Sinclair et al., 2018), and the next-generation UVS instrument on the JUICE mission (Jupiter Icy Moons Explorer, Grasset et al., 2013) is expected to make observations of Jupiter's high latitudes starting in 2031 and will allow a direct comparison with these Juno UVS observations from 2016 to 2022.

5. Conclusions

Reflected sunlight observations from the UVS instrument on the Juno spacecraft show enhanced C_2H_2 absorption within Jupiter's southern auroral oval. This builds on previous infrared observations which have shown higher C_2H_2 abundances within the northern auroral oval (Sinclair et al., 2017, 2018). Our ultraviolet observations both provide a confirmation for these previous results by making use of an independent spectral region and show that the same phenomenon exists at both poles. Future studies are required to study whether the C_2H_2 enhancement varies with time.

The localized enhancement of C_2H_2 is likely caused by the influx of charged particles within Jupiter's auroras, which leads to increased ion-neutral and electron recombination reactions. Ion-neutral photochemical models of Titan's atmosphere provide insight into possible pathways that would favor the production of C_2H_2 in Jupiter's

auroral regions. The development of ion-neutral photochemical models of Jupiter using the recent chemical reaction rates is an important next step in understanding the influence of the auroras on Jupiter's polar composition.

Data Availability Statement

The Juno UVS data used in this paper are archived in NASA's Planetary Data System Atmospheres Node: https://pds-atmospheres.nmsu.edu/PDS/data/jnouve_3001 (Trantham, 2014). The data used to produce the figures in this paper are available in Giles (2023). The NEMESIS radiative transfer and retrieval tool is available from Irwin (2020).

Acknowledgments

The authors are grateful to the NASA and contributing institutions, which have made the Juno mission possible. This work was funded by the NASA's New Frontiers Program for Juno via contract with the Southwest Research Institute. BB is a Research Associate of the Fonds de la Recherche Scientifique – FNRS.

References

- Bolton, S. J., Lunine, J., Stevenson, D., Connerney, J. E. P., Levin, S., Owen, T. C., et al. (2017). The Juno mission. *Space Science Reviews*, 213(1–4), 5–37. <https://doi.org/10.1007/s11214-017-0429-6>
- Bonfond, B., Grodent, D., Gérard, J.-C., Stallard, T., Clarke, J. T., Yoneda, M., et al. (2012). Auroral evidence of Io's control over the magnetosphere of Jupiter. *Geophysical Research Letters*, 39(1), L01105. <https://doi.org/10.1029/2011gl050253>
- Bonfond, B., Saur, J., Grodent, D., Badman, S. V., Bisikalo, D., Shematovich, V., et al. (2017). The tails of the satellite auroral footprints at Jupiter. *Journal of Geophysical Research: Space Physics*, 122(8), 7985–7996. <https://doi.org/10.1002/2017ja024370>
- Caldwell, J., Tokunaga, A. T., & Gillett, F. C. (1980). Possible infrared aurorae on Jupiter. *Icarus*, 44(3), 667–675. [https://doi.org/10.1016/0019-1035\(80\)90135-9](https://doi.org/10.1016/0019-1035(80)90135-9)
- Cavalié, T., Benmahi, B., Hue, V., Moreno, R., Lellouch, E., Fouchet, T., et al. (2021). First direct measurement of auroral and equatorial jets in the stratosphere of Jupiter. *Astronomy and Astrophysics*, 647, L8. <https://doi.org/10.1051/0004-6361/202140330>
- Chaufray, J.-Y., Greathouse, T. K., Gladstone, G. R., Waite, J. H., Maillard, J.-P., Majeed, T., et al. (2011). Spectro-imaging observations of Jupiter's 2 μm auroral emission. II: Thermospheric winds. *Icarus*, 211(2), 1233–1241. <https://doi.org/10.1016/j.icarus.2010.11.021>
- De La Haye, V., Waite, J. H., Jr., Cravens, T. E., Robertson, I. P., & Lebonnois, S. (2008). Coupled ion and neutral rotating model of Titan's upper atmosphere. *Icarus*, 197(1), 110–136. <https://doi.org/10.1016/j.icarus.2008.03.022>
- Dobrijevic, M., Loison, J. C., Hickson, K. M., & Gronoff, G. (2016). 1D-coupled photochemical model of neutrals, cations and anions in the atmosphere of Titan. *Icarus*, 268, 313–339. <https://doi.org/10.1016/j.icarus.2015.12.045>
- Drossart, P., Bézard, B., Atreya, S. K., Bishop, J., Waite, J., Jr., & Boice, D. (1993). Thermal profiles in the auroral regions of Jupiter. *Journal of Geophysical Research*, 98(E10), 18803–18811. <https://doi.org/10.1029/93je01801>
- Drossart, P., Bézard, B., Atreya, S. K., Lacy, J., Serabyn, E., Tokunaga, A., & Encenaz, T. (1986). Enhanced acetylene emission near the north pole of Jupiter. *Icarus*, 66(3), 610–618. [https://doi.org/10.1016/0019-1035\(86\)90094-1](https://doi.org/10.1016/0019-1035(86)90094-1)
- Fletcher, L. N., Greathouse, T. K., Orton, G. S., Sinclair, J. A., Giles, R. S., Irwin, P. G. J., & Encenaz, T. (2016). Mid-infrared mapping of Jupiter's temperatures, aerosol opacity and chemical distributions with IRTF/TEXES. *Icarus*, 278, 128–161. <https://doi.org/10.1016/j.icarus.2016.06.008>
- Giles, R. S. (2023). Enhanced C₂H₂ absorption within Jupiter's southern auroral oval from Juno UVS observations. Mendeley Data, V1. <https://doi.org/10.17632/tyx24ykcx.1>
- Giles, R. S., Greathouse, T. K., Hue, V., Gladstone, G. R., Melin, H., Fletcher, L. N., et al. (2021). Meridional variations of C₂H₂ in Jupiter's stratosphere from Juno UVS observations. *Journal of Geophysical Research: Planets*, 126(8), e2021JE006928. <https://doi.org/10.1029/2021je006928>
- Gladstone, G. R., Allen, M., & Yung, Y. L. (1996). Hydrocarbon photochemistry in the upper atmosphere of Jupiter. *Icarus*, 119(1), 1–52. <https://doi.org/10.1006/icar.1996.0001>
- Gladstone, G. R., Greathouse, T. K., Versteeg, M. H., Hue, V., Kammer, J. A., Davis, M. W., et al. (2019). Recent Juno-UVS observations of Jupiter's auroras. In *EPSC/DPS Joint Meeting Abstracts* (Vol. 13).
- Gladstone, G. R., Persyn, S. C., Eterno, J. S., Walther, B. C., Slater, D. C., Davis, M. W., et al. (2017). The ultraviolet spectrograph on NASA's Juno mission. *Space Science Reviews*, 213(1–4), 447–473. <https://doi.org/10.1007/s11214-014-0040-z>
- Grasset, O., Dougherty, M. K., Coustenis, A., Bunce, E. J., Erd, C., Titov, D., et al. (2013). JUPITER ICy moons Explorer (JUICE): An ESA mission to orbit Ganymede and to characterise the Jupiter system. *Planetary and Space Science*, 78, 1–21. <https://doi.org/10.1016/j.pss.2012.12.002>
- Greathouse, T. K., Gladstone, G. R., Davis, M. W., Slater, D. C., Versteeg, M. H., Persson, K. B., et al. (2013). Performance results from in-flight commissioning of the Juno ultraviolet spectrograph (Juno-UVS). In *UV, X-ray, and gamma-ray space instrumentation for astronomy XVIII* (Vol. 8859, p. 88590T).
- Grodent, D. (2015). A brief review of ultraviolet auroral emissions on giant planets. *Space Science Reviews*, 187(1), 23–50. <https://doi.org/10.1007/s11214-014-0052-8>
- Hue, V., Giles, R. S., Gladstone, G. R., Greathouse, T. K., Davis, M. W., Kammer, J. A., & Versteeg, M. H. (2021). Updated radiometric and wavelength calibration of the Juno ultraviolet spectrograph. *Journal of Astronomical Telescopes, Instruments, and Systems*, 7(4), 044003. <https://doi.org/10.1117/1.jatis.7.4.044003>
- Hue, V., Gladstone, G. R., Greathouse, T. K., Kammer, J. A., Davis, M. W., Bonfond, B., et al. (2019). In-flight characterization and calibration of the Juno-ultraviolet spectrograph (Juno-UVS). *The Astronomical Journal*, 157(2), 90. <https://doi.org/10.3847/1538-3881/aafb36>
- Hue, V., Hersant, F., Cavalié, T., Dobrijevic, M., & Sinclair, J. (2018). Photochemistry, mixing and transport in Jupiter's stratosphere constrained by Cassini. *Icarus*, 307, 106–123. <https://doi.org/10.1016/j.icarus.2018.02.018>
- Irwin, P. G. J. (2020). *NEMESIS/Radtrancode software* (Version 1.0). Zenodo. <https://doi.org/10.5281/zenodo.4303976>
- Irwin, P. G. J., Teanby, N. A., de Kok, R., Fletcher, L. N., Howett, C. J. A., Tsang, C. C. C., et al. (2008). The NEMESIS planetary atmosphere radiative transfer and retrieval tool. *Journal of Quantitative Spectroscopy and Radiative Transfer*, 109(6), 1136–1150. <https://doi.org/10.1016/j.jqsrt.2007.11.006>
- Kammer, J. A., Hue, V., Greathouse, T. K., Gladstone, G. R., Davis, M. W., & Versteeg, M. H. (2019). Planning operations in Jupiter's high-radiation environment: Optimization strategies from Juno-ultraviolet spectrograph. *Journal of Astronomical Telescopes, Instruments, and Systems*, 5(2), 027001. <https://doi.org/10.1117/1.jatis.5.2.027001>
- Keller-Rudek, H., Moortgat, G. K., Sander, R., & Sörensen, R. (2013). The MPI-Mainz UV/VIS spectral atlas of gaseous molecules of atmospheric interest. *Earth System Science Data*, 5(2), 365–373. <https://doi.org/10.5194/essd-5-365-2013>

- Kim, S. J., Caldwell, J., Rivolo, A. R., Wagener, R., & Orton, G. S. (1985). Infrared polar brightening on Jupiter: III. Spectrometry from the Voyager 1 IRIS experiment. *Icarus*, 64(2), 233–248. [https://doi.org/10.1016/0019-1035\(85\)90088-0](https://doi.org/10.1016/0019-1035(85)90088-0)
- Kim, Y. H., & Fox, J. L. (1994). The chemistry of hydrocarbon ions in the Jovian ionosphere. *Icarus*, 112(2), 310–325. <https://doi.org/10.1006/icar.1994.1186>
- Loison, J. C., Hébrard, E., Dobrijevic, M., Hickson, K. M., Caralp, F., Hue, V., et al. (2015). The neutral photochemistry of nitriles, amines and imines in the atmosphere of Titan. *Icarus*, 247, 218–247. <https://doi.org/10.1016/j.icarus.2014.09.039>
- Melin, H., Fletcher, L. N., Donnelly, P. T., Greathouse, T. K., Lacy, J. H., Orton, G. S., et al. (2018). Assessing the long-term variability of acetylene and ethane in the stratosphere of Jupiter. *Icarus*, 305(1), 301–313. <https://doi.org/10.1016/j.icarus.2017.12.041>
- Melin, H., Fletcher, L. N., Irwin, P. G. J., & Edgington, S. G. (2020). Jupiter in the ultraviolet: Acetylene and ethane abundances in the stratosphere of Jupiter from Cassini observations between 0.15 and 0.19 μm . *The Astronomical Journal*, 159(6), 291. <https://doi.org/10.3847/1538-3881/ab91a6>
- Moses, J. I., Fouchet, T., Bézard, B., Gladstone, G. R., Lellouch, E., & Feuchtgruber, H. (2005). Photochemistry and diffusion in Jupiter's stratosphere: Constraints from ISO observations and comparisons with other giant planets. *Journal of Geophysical Research*, 110(E8), E08001. <https://doi.org/10.1029/2005je002411>
- Nichols, J. D., Badman, S. V., Bagenal, F., Bolton, S. J., Bonfond, B., Bunce, E. J., et al. (2017). Response of Jupiter's auroras to conditions in the interplanetary medium as measured by the Hubble Space Telescope and Juno. *Geophysical Research Letters*, 44(15), 7643–7652. <https://doi.org/10.1002/2017gl073029>
- Nixon, C. A., Achterberg, R. K., Conrath, B. J., Irwin, P. G. J., Teanby, N. A., Fouchet, T., et al. (2007). Meridional variations of C_2H_2 and C_2H_6 in Jupiter's atmosphere from Cassini CIRS infrared spectra. *Icarus*, 188(1), 47–71. <https://doi.org/10.1016/j.icarus.2006.11.016>
- O'Donoghue, J., Moore, L., Bhakyaipabul, T., Melin, H., Stallard, T., Connerney, J., & Tao, C. (2021). Global upper-atmospheric heating on Jupiter by the polar aurorae. *Nature*, 596(7870), 54–57. <https://doi.org/10.1038/s41586-021-03706-w>
- Rego, D., Achilleos, N., Stallard, T., Miller, S., Prangé, R., Dougherty, M., & Joseph, R. D. (1999). Supersonic winds in Jupiter's aurorae. *Nature*, 399(6732), 121–124. <https://doi.org/10.1038/20121>
- Sinclair, J. A., Moses, J. I., Hue, V., Greathouse, T. K., Orton, G. S., Fletcher, L. N., & Irwin, P. G. J. (2019). Jupiter's auroral-related stratospheric heating and chemistry III: Abundances of C_2H_4 , $\text{CH}_3\text{C}_2\text{H}$, C_4H_2 and C_6H_6 from Voyager-IRIS and Cassini-CIRS. *Icarus*, 328, 176–193. <https://doi.org/10.1016/j.icarus.2019.03.012>
- Sinclair, J. A., Orton, G. S., Greathouse, T. K., Fletcher, L. N., Moses, J. I., Hue, V., & Irwin, P. G. J. (2017). Jupiter's auroral-related stratospheric heating and chemistry I: Analysis of Voyager-IRIS and Cassini-CIRS spectra. *Icarus*, 292, 182–207. <https://doi.org/10.1016/j.icarus.2016.12.033>
- Sinclair, J. A., Orton, G. S., Greathouse, T. K., Fletcher, L. N., Moses, J. I., Hue, V., & Irwin, P. G. J. (2018). Jupiter's auroral-related stratospheric heating and chemistry II: Analysis of IRTF-TEXES spectra measured in December 2014. *Icarus*, 300, 305–326. <https://doi.org/10.1016/j.icarus.2017.09.016>
- Trantham, B. (2014). Juno Jupiter UVS calibrated data archive V1.0. PDS Atmospheres (ATM) Node. <https://doi.org/10.17189/c32j-7r56>
- Waite, J. H., Cravens, T. E., Kozyra, J., Nagy, A. F., Atreya, S. K., & Chen, R. H. (1983). Electron precipitation and related aeronomy of the Jovian thermosphere and ionosphere. *Journal of Geophysical Research*, 88(A8), 6143–6163. <https://doi.org/10.1029/ja088ia08p06143>
- West, R. A., Baines, K. H., Friedson, A. J., Banfield, D., Regent, B., & Taylor, F. W. (2004). Jovian clouds and haze. In *Jupiter: The planet, satellites and magnetosphere* (pp. 79–104). Cambridge University Press.
- Wong, A.-S., Yung, Y. L., & Friedson, A. J. (2003). Benzene and haze formation in the polar atmosphere of Jupiter. *Geophysical Research Letters*, 30(8), 1447. <https://doi.org/10.1029/2002gl016661>
- Woods, T. N., Chamberlin, P. C., Harder, J. W., Hock, R. A., Snow, M., Eparvier, F. G., et al. (2009). Solar irradiance reference spectra (SIRS) for the 2008 whole heliosphere interval (WHI). *Geophysical Research Letters*, 36(1), L01101. <https://doi.org/10.1029/2008gl036373>
- Yao, Z. H., Bonfond, B., Grodent, D., Chané, E., Dunn, W. R., Kurth, W. S., et al. (2022). On the relation between auroral morphologies and compression conditions of Jupiter's magnetopause: Observations from Juno and the Hubble Space Telescope. *Journal of Geophysical Research: Space Physics*, 127(10), e2021JA029894. <https://doi.org/10.1029/2021ja029894>